

Offline

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

No. PWD-Dal/TA/Tender /2025-26 9005-07
To

Dated: - 18.02.26

The Executive Engineer (IT Cell)
Nigam Bihar Shimla-2

Subject: - Publishing of Tender Notice.

Dear Sir,

Enclosed please find herewith the tender Notice of work as given in the Notice inviting Tender for uploading on department website as per notification Principal Secretary (PW) to the Govt. of Himachal Pradesh letter No. PBW-(B) A9 (3)1/2020 dated Shimla-2 the 16th July 2021 as the work mentioned in the tender notice are urgent in nature and public interest.

DA/ As above.


Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie.


Copy forwarded to the Superintending Engineer, 7th Circle, HPPWD, Dalhousie for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer, (IT Cell) Nigam Bihar Shimla-2 for information and further necessary action.


Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie

Certificate

Certified that the tenders called vide this office letter No. PWD-
/TA/Tender /2025-26:- 9005-07 dated. 18.02.26 is emergent nature and in Public
interest.

 Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie.

Certificate

Certified that the tenders called vide this office letter No. PWD-
/TA/Tender /2025-26:- 9005-07 dated. 18.02.26 is emergent nature and in Public
interest.

 Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

"NOTICE INVITING TENDERS"

Sealed Item rate tender(s) on PWD from No 6 & 7/8 are hereby invited by the Executive Engineer, Dalhousie Division, HPPWD, Dalhousie on behalf of the Governor of HP for the following works from the approved and eligible contractor/firm of appropriate Class enlisted in HPPWD as per the latest instructions so as to reach in this office as per time schedule given below. The offer of the tender will be kept open for 90 days from the date of opening of the tender. The undersigned reserves the right to reject any or all the tender without assigning any reasons:-

1. Date of receipt of application for the tender Form a /w requisite documents:- 24.02.2026 onward (between 2:00 p.m.to 4:30.p.m.)

2. Date of issue/sale of tender form against Cash payment (non refundable). 24.02.2026

The tender shall be received up to 3:00 PM on 26.02.2026 and will be opened on the same day at 3:30 PM in the presence of intending Contractor or their authorized representative who may like to be present. The tender will be sold by this office against cash payment as shown below (Non refundable) during the working hours on 24.02.2026


The Earnest Money in the shape of National Saving Certificate/FDR of any Bank in HP duly pledged in favour of Executive Engineer, Dalhousie Division, HPPWD, Dalhousie must accompany with each application. Conditional tender and the tender received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 90 days. The XEN reserve the right to accept or reject the tender without assigning any reasons:-

S. No.	Name of work	Estimated cost	Earnest Money	Cost of tender	Time Limit	Class
1.	Restoration of Rain damage on Khairi to Bhunad road Km. 0/0 to 9/230 (SH:- Hiring of JCB for removal of Slips in Km. 6/00 to 9/230).	99910.00	2000.00	350.00	One Month	D & C
2.	Restoration of Rain damage on Brangal Wangal Mandoh road Km. 0/0 to 39/600 (SH:- Hiring of JCB for removal of Slips in Km. 15/00 to 20/00).	98880.00	2000.00	350.00	One Month	D&C
3.	A/R & M/O Jandrigat to Pukhri road Km.0/0 to 2/100 (SH: - Construction of Breast wall at RD. 0/889.60 to 0/893.30)	96216.00	2000.00	350.00	Two Months	D&C
4.	Restoration of Rain damage on Salla to Bhalei road Km. 0/0 to 1/00 0 (SH:- Hiring of JCB for Removal of Slips in Km. 0/0 to 1/00).	98880.00	2000.00	350.00	One Month	D&C
5	Restoration of Rain damage on Khairi to Bhunad road Km. 0/0 to 9/230 (SH:- Hiring of JCB for removal of Slips in Km. 4/00 to 6/00).	97850.00	2000.00	350.00	One Month	D & C
6.	Restoration of Rain damage on Brangal Wangal Mandoh road Km. 0/0 to 39/600 (SH:- Construction of Retaining wall in Wire crate at RD. 2/760 to 2/770).	94978.00	2000.00	350.00	Two Months	D&C
7.	A/R & M/O Jandrigat to Pukhri road Km.0/0 to 2/100 (SH: - Construction of Breast wall at RD. 0/897 to 0/900.70)	96549.00	2000.00	350.00	Two Months	D&C
8.	Restoration of Rain damage on Khairi to Bhunad road Km. 0/0 to 9/230 (SH:- Hiring of JCB for removal of Slips in Km. 2/00 to 4/00).	98880.00	2000.00	350.00	One Month	D&C

9	Restoration of Rain damage on Banikhet Dalhousie Khajjar road Km. 0/0 to 27/00 (SH:- Hiring of JCB for removal of Slips in Km. 0/00 to 27/00).	467250.00	9500.00	350.00	One Month	D&C
10	Restoration of Rain damage on Brangal Wangel Mandoh road Km. 0/0 to 39/600 (SH:- Construction of Retaining wall in Wire crate at RD. 2/750 to 2/760).	95305.00	2000.00	350.00	Two Months	D&C
11	Restoration of Rain damage on Khairi to Bhunad road Km. 0/0 to 9/230 (SH:- Hiring of JCB for removal of Slips in Km 0/0 to 2/00).	97850.00	2000.00	350.00	One Month	D&C
12	Restoration of Rain damage on Brangal Wangel Mandoh road Km. 0/0 to 39/600 (SH:- Hiring of JCB for removal of Slips in Km. 16/00 to 24/00).	99910.00	2000.00	350.00	One Month	D&C
13	A/R & M/O Jandrightat to Pukhri road Km.0/0 to 2/100 (SH:- Construction of Breast wall at RD. 0/885.90 to 0/889.60)	96045.00	2000.00	350.00	Two Months	D&C
14	Restoration of Rain damage on Link road to village Goli Km. 0/0 to 0/500 (SH:- Repair of Bridge and Slab Culvert at various RD's).	149510.00	3000.00	350.00	Two Months	D&C
15	Restoration of Rain damage on Brangal Wangel Mandoh road Km. 0/0 to 39/600 (SH:- Construction of Breast wall in Wire crate at RD. 35/830 to 35/840).	99997.00	2000.00	350.00	Two Months	D&C
16	Restoration of Rain damage on Brangal Wangel Mandoh road Km. 0/0 to 39/600 (SH:- Hiring of JCB for removal of Slips between Km. 32/00 to 39/600)	98880.00	2000.00	350.00	One Month	D&C
17	Annual Surfacing on various roads under Dalhousie Division HP PWD Dalhousie Under AMP 2025-26 (Village Road) (SH:- Providing and laying road Marking with Hot applied Thermoplastic Compound with Reflectorsing Glass beads on Bituminous Surface on Bounkharimour to Dhunera road Km. 1/00 to 2/00 & Link road to village Goli Km. 0/0 to 0/500).	91665.00	2000.00	350.00	Two Months	D&C
18	A/R & M/O Jandrightat to Pukhri road Km.0/0 to 2/100 (SH:- Construction of Breast wall at RD. 0/882.20 to 0/885.90)	96282.00	2000.00	350.00	Two Months	D&C
19	Restoration of Rain damage on Brangal Wangel Mandoh road Km. 0/0 to 39/600 (SH:- Construction of Retaining wall in Wire crate at RD. 35/835 to 35/840).	99850.00	2000.00	350.00	Two Months	D&C
20	Annual Surfacing on various roads under Dalhousie Division HP PWD Dalhousie Under AMP 2025-26 (Village Road) (SH:- Providing and laying road Hot Thermoplastic road making on Khoikuffar to Rikhnalli road Km. 3/00 to	77000.00	1600.00	350.00	Two Months	D&C

	4/00 & Link road to HP PWD Circuit House at Dalhousie Km.0/0 to 0/130)					
21	A/R & M/O Jandrighat to Pukhri road Km.0/0 to 2/100 (SH: - Construction of Breast wall at RD. 0/893.30 to 0/897.00)	96353.00	2000.00	350.00	Two Months	D&C
22	Restoration of Rain damage on Brangal Wangal Mandoh road Km. 0/0 to 39/600 (SH:- Hiring of JCB for removal of Slips between Km. 24/00 to 32/00)	99910.00	2000.00	350.00	One Month	D&C
23	Restoration of Rain damage on Dalhousie Jandrighat Chamba via Kohlari road Km. 0/0 to 11/040 (SH:- Hiring of JCB for removal of Slips in Km. 0/00 to 6/00)	98880.00	2000.00	350.00	One Month	D&C
24	Restoration of Rain on Dalhousie Jandrighat Chamba via Kohlari road Km. 0/0 to 11/040 (SH: - Hiring of JCB for removal of Slips in Km. to 6/00 to 11/040).	99910.00	2000.00	350.00	One Month	D&C
25	A/R & M/O Jandrighat to Pukhri road Km.0/0 to 2/100 (SH: - Construction of Breast wall at RD. 0/900.70 to 0/904.40)	96792.00	2000.00	350.00	Two Months	D&C
26	Running and Maintenance of Machinery under Dalhousie Sub Division (SH:- Replacement of various defective Machinery part of Bobcat/Excavator No. HP 47A- 0755 Under Dalhousie Sub Division)	36235.00	800.00	350.00	One Month	D&C
27	Restoration of Rain on Banikhet Dalhousie Khajjiar road Km. 15/600 to 27/00 (SH: - Hiring of Excavator com loader for removal of Slips/Snow in Km. 15/600 to 27/00).	98880.00	2000.00	350.00	One Month	D&C
28	Restoration of Rain on Link road to village Ruliyani Km. 0/0 to 3/020 (SH: - Hiring of Excavator com loader for removal of Slips/Snow in Km. 0/0 to 3/020).	99910.00	2000.00	350.00	One Month	D&C

1. The tender forms will not be issued to those Contractors whose performance is not found satisfactory.
2. GST No, Earnest Money, Tender Form cost, copy of enlistment should be accompanied with application.
3. Application without all documents will not be entertained.
4. Proxy application will not be entertained.


 Executive Engineer,
 Dalhousie Division,
 HPPWD, Dalhousie.

No. PWD/TA/Tender /2025-26 9008 - 9058

Dated:- 18-02-26

Copy forwarded to the following for information and necessary action please:-

- 1 Engineer-in-Chief, HPPWD, Shimla.
- 2 All the Chief Engineer in HPPWD.
- 3 All SEs/EE in HPPWD.
- 4 All AEs/Contractor under this Division.
- 5 Deputy Commissioner, Chamba
- 6 BDO Bhattiyat.
- 7 Sub Divisional Magistrate/Tehsildar Dalhousie.
- 8 Notice Board of this office.


Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie

Schedule of Qty.

Estimated Cost: - Rs. 99910.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month


Name of work: -Restoration of Rain damage on Khairi to Bhunad road Km. 0/0 to 9/230 (SII: - Hiring of JCB for removal of Slips in Km. 6/00 to 9/230).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB / Excavator cum loader for cutting / widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts upto any heights and depth as per direction and entire satisfactions of Engineer-in-charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period /execution shall be the absolute responsibility of the JCB / Excavator Owner which shall have to be fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare, watch and ward of machine also be borne by the Contractor / Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	97.00			Per Hour	
					G. Total:-	0.00

Note - 1) The physical progress of machine will also be measured while submitting the bill for payment. It is ensured that working progress of machine should be not be less than the amount to

Note - 2) No deviation shall be allowed in any case.

Note -3) Subject of availbity of funds


Executive Engineer
Dalhousie Division,
HPPWD Dalhousie

Schedule of Qty.

Estimated Cost: - Rs. 98880.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month


Name of work: -Restoration of Rain damage on Brangal Wangal Mandoh road Km. 0/0 to 39/600 (SIH: - Hiring of JCB for removal of Slips in Km. 15/00 to 20/00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB / Excavator cum loader for cutting / widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts upto any heights and depth as per direction and entire satisfactions of Engineer-in-charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period /execution shall be the absolute responsibility of the JCB / Excavator Owner which shall have to be fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare, watch and ward of machine also be borne by the Contractor / Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	96.00			Per Hour	
					G. Total:-	

Note - 1) The physical progress of machine will also be measured while submitting the bill for payment. It is ensured that working progress of machine should be not be less than the amount to be paid.

Note - 2) No deviation shall be allowed in any case.

Note -3) Subject of availbity of funds


 Executive Engineer
 Dalhousie Division,
 HPPWD, Dalhousie

Schedule of Qty.

Estimated Cost: - Rs. 96217.00

Earnest Money :- Rs. 2000.00

Time Limit :- Two Month

Name of work: -A/R & M/O Jandrigat to Pukhri road Km. 0/0 to 2/100 (SI: - Construction of Breast wall at RD. 0/889.60 to 0/893.30.

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 300 and 1600 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal un-useful materials upto any lead and lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. Carriage of surplus muck generated from cutting/excavation work to the disposable/dumping site to be selected by the contractor in private lands. The is rate including the octroi, royalty, Malkana, toll tax, sales tax GST or any other taxes imposed by the Government.	15.50			Per Cubic Metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete nominal mix 1:4:8 (one cement isto four sand isto eight graded stone agreegate 20 mm (twenty millimetre) nominal size) on ground or under water and curing complete for 14 (fourteen days), in open foundation for all type structure including pumping or bailing out water, (surface and sub soil water) dewatering, for all depths and any quantum of water including removal of slush which may arise at time of laying concrete completed for all heights/depths including the cost of form work complete as per drawing and MORD technical specification clause 800,900 and 1200 or as directed by the Engineer-In-Charge including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana toll tax ,sale tax GST or other taxes imposed by the Government.	1.22			Per Cubic Metre	
3	Random rubble masonry (first short) with hard stones of approved quality in sub-structure, Retaining wall wing walls, abutment, toe walls etcetra. in cement mortar 1:6 (one cement isto six sand) curing complete including pumping or bailing out water, dewatering, removal of slush which may arise at the time of masonry work, complete as per MORD technical specification clause 702,704,1202 and 1204 including carriage of materials upto all leads and lifts and other incidental as per entire satisfaction and direction of Engineer-in-charge.The rate is including octroi, royalty, Malkana, toll tax sale tax GST or other taxes imposed by the Government.	9.54			Per Cubic Metre	
4	Construction of dry rubble masonry with hard stone of approved quality for structure like retaining wall, breast wall, revetment wall, and parapets etcetra for sub structure and super structure complete as per MORD techincal specifications section 700 and 1300 and asper direction of Engineer-in-charge including carriage of materials upto all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax sale tax GST or other taxes imposed by the Government.	10.80			Per Cubic Metre	
					Total: -	

Schedule of Qty.

Estimated Cost: - Rs. 98880.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month

Name of work: -Restoration of Rain damage on Salla to Bhali road Km. 0/0 to 1/00 (SH: - Hiring of JCB for removal of Slips in Km. 0/00 to 1/00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB / Excavator cum loader for cutting / widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts upto any heights and depth as per direction and entire satisfactions of Engineer-in-charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period /execution shall be the absolute responsibility of the JCB / Excavator Owner which shall have to be fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare, watch and ward of machine also be borne by the Contractor / Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	96.00			Per Hour	
					G. Total:-	

Note - 1) The physical progress of machine will also be measured while submitting the bill for payment. It is ensured that working progress of machine should be not be less than the amount to be paid.

Note - 2) No deviation shall be allowed in any case.

Note -3) Subject of availbity of funds


Executive Engineer
Dalhousie Division,
HPPWD Dalhousie

Schedule of Qty.

Estimated Cost: - Rs. 97850.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month


Name of work: -Restoration of Rain damage on Khairi to Bhunad road Km. 0/0 to 9/230 (SH: - Hiring of JCB for removal of Slips in Km. 4/00 to 6/00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB / Excavator cum loader for cutting / widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts upto any heights and depth as per direction and entire satisfactions of Engineer-in-charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period /execution shall be the absolute responsibility of the JCB / Excavator Owner which shall have to be fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare, watch and ward of machine also be borne by the Contractor / Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	95.00			Per Hour	
					G. Total:-	

Note - 1) The physical progress of machine will also be measured while submitting the bill for payment. It is ensured that working progress of machine should be not be less than the amount to be paid.

Note - 2) No deviation shall be allowed in any case.

Note -3) Subject of availbity of funds


Executive Engineer
Dalhousie Division,
HPPWD Dalhousie

Schedule of Qty.


Estimated Cost: - Rs. 94978.00

Earnest Money :- Rs. 2000.00

Time Limit :- Two Month

Name of work: -Restoration of Rain damage on Brangal Wangal Mandoh road Km. 0/0 to 39/600 (SII: - Construction of Retaining wall in wire crate at RD. 2/760 to 2/770).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including octroi royalty Malkhana Toll tax sale tax, GST or other taxes imposed by the Government.	10.70			Per Cubic Metre	
2	Providing and laying of boulder apron laid in wire crates with 4 mm (four millimetre) dia G.I wire conforming to IS: 280 and IS: 4826 in 100 mm x 100 mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulders weighting not less than 40 Kg (forty kilograme) each as per drawing technical specifications Clause 1301 and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	31.26			Per Cubic Metre	
					Total: -	


Executive Engineer
Dalhousie Division,
HPPWD Dalhousie

Schedule of Qty.

Estimated Cost: - Rs. 96550.00

Earnest Money :- Rs. 2000.00

Time Limit :- Two Month

Name of work: -A/R & M/O Jandrigat to Pukhri road Km. 0/0 to 2/100 (SH: - Construction of Breast wall at RD. 0/897.00 to 0/900.70.

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 300 and 1600 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal un-useful materials upto any lead and lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. Carriage of surplus muck generated from cutting/excavation work to the disposable/dumping site to be selected by the contractor in private lands. The is rate including the octroi, royalty, Malkana toll tax, sales tax GST or any other taxes imposed by the Government.	16.06			Per Cubic Metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete nominal mix 1:4:8 (one cement isto four sand isto eight graded stone aggregate 20 mm (twenty millimetre) nominal size) on ground or under water and curing complete for 14 (fourteen days), in open foundation for all type structure including pumping or bailing out water, (surface and sub soil water) dewatering, for all depths and any quantum of water including removal of slush which may arise at time of laying concrete completed for all heights/depths including the cost of form work complete as per drawing and MORD technical specification clause 800,900 and 1200 or as directed by the Engineer-In-Charge including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana toll tax ,sale tax GST or other taxes imposed by the Government.	1.22			Per Cubic Metre	
3	Random rubble masonry (first short) with hard stones of approved quality in sub-structure, Retaining wall wing walls, abutment, toe walls etcetra. in cement mortar 1:6 (one cement isto six sand) curing complete including pumping or bailing out water, dewatering, removal of slush which may arise at the time of masonry work, complete as per MORD technical specification clause 702,704,1202 and 1204 including carriage of materials upto all leads and lifts and other incidental as per entire satisfaction and direction of Engineer-in-charge.The rate is including octroi, royalty, Malkana, toll tax sale tax GST or other taxes imposed by the Government.	9.54			Per Cubic Metre	
4	Construction of dry rubble masonry with hard stone of approved quality for structure like retaining wall, breast wall, revetment wall, and parapets etcetra for sub structure and super structure complete as per MORD technical specifications section 700 and 1300 and asper direction of Engineer-in-charge including carriage of materials upto all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax sale tax GST or other taxes imposed by the Government.	10.80			Per Cubic Metre	
					Total: -	

Executive Engineer
Dalhousie Division,
HPPW & Dalhousie

Schedule of Qty.

Estimated Cost: - Rs. 98880.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month


Name of work: -Restoration of Rain damage on Khairi to Bhunad road Km. 0/0 to 9/230 (SH: - Hiring of JCB for removal of Slips in Km. 2/00 to 4/00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB / Excavator cum loader for cutting / widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts upto any heights and depth as per direction and entire satisfactions of Engineer-in-charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period /execution shall be the absolute respoonsibility of the JCB / Excavator Owner which shall have to be fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare, watch and ward of machine also be borne by the Contractor / Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge including carriage of materails with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	96.00			Per Hour	
					G. Total:-	

Note - 1) The physical progress of machine will also be measured while submitting the bill for payment. It is ensured that working progress of machine should be not be less than the amount to be paid.

Note - 2) No deviation shall be allowed in any case.

Note -3) Subject of availbity of funds


Executive Engineer
Dalhousie Division,
HPPWD, Dalhousie

Schedule of Qty.

Estimated Cost: - Rs. 467250.00

Earnest Money :- Rs. 9500.00

Time Limit :- One Month

Name of work: -Restoration of Rain damage on Banikhet Dalhousie Khajjiar road Km. 0/00 to 27/00 (SI: - Removal of Slips/Snow in Km. 0/00 to 27/00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB / Excavator cum loader for cutting / widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts upto any heights and depth as per direction and entire satisfactions of Engineer-in-charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period /execution shall be the absolute responsibility of the JCB / Excavator Owner which shall have to be fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare, watch and ward of machine also be borne by the Contractor / Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	445.00			Per Hour	
					G. Total:-	

Note - 1) The physical progress of machine will also be measured while submitting the bill for payment. It is ensured that working progress of machine should be not be less than the amount to be paid.

Note - 2) No deviation shall be allowed in any case.

Note -3) Subject of availbity of funds


 Executive Engineer
 Dalhousie Division,
 HPPWD, Dalhousie

Schedule of Qty.

Estimated Cost: - Rs. 95305.00

Earnest Money :- Rs. 2000.00

Time Limit :- Two Month

Name of work: -Restoration of Rain damage on Brangal Wangal Mandoh road Km. 0/0 to 39/600 (SIH: - Construction of Retaining wall in wire crate at RD. 2/750 to 2/760).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including octroi royalty Malkhana Toll tax sale tax, GST or other taxes imposed by the Government.	11.25			Per Cubic Metre	
2	Providing and laying of boulder apron laid in wire crates with 4 mm (four milimetre) dia G.I wire conforming to IS: 280 and IS: 4826 in 100 mm x 100 mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulders weighting not less than 40 Kg (forty kilograme) each as per drawing technical specifications Clause 1301 and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana. toll tax, sales tax, GST or any other taxes imposed by the Government.	31.26			Per Cubic Metre	
					Total: -	


Executive Engineer
Dalhousie Division,
HPPWD Dalhousie

Schedule of Qty.

Estimated Cost: - Rs. 97850.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month

Name of work: -Restoration of Rain damage on Khairi to Bhunad road Km. 0/0 to 9/230 (SH: - Hiring of JCB for removal of Slips in Km. 0/00 to 2/00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB / Excavator cum loader for cutting / widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts upto any heights and depth as per direction and entire satisfactions of Engineer-in-charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period /execution shall be the absolute responsibility of the JCB / Excavator Owner which shall have to be fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare, watch and ward of machine also be borne by the Contractor / Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	95.00			Per Hour	
					G. Total:-	

Note - 1) The physical progress of machine will also be measured while submitting the bill for payment. It is ensured that working progress of machine should be not be less than the amount to be paid.

Note - 2) No deviation shall be allowed in any case.

Note -3) Subject of availbity of funds

Executive Engineer
Dalhousie Division.
HPPWD Dalhousie

Schedule of Qty.

Estimated Cost: - Rs. 99910.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month

Name of work: -Restoration of Rain damage on Brangal Wangal Mandoh road Km. 0/0 to 39/600 (SI: - Hiring of JCB for removal of Slips in Km. 16/00 to 24/00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB / Excavator cum loader for cutting / widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts upto any heights and depth as per direction and entire satisfactions of Engineer-in-charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period /execution shall be the absolute respoonsibility of the JCB / Excavator Owner which shall have to be fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare, watch and ward of machine also be borne by the Contractor / Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge including carriage of materails with in all leads, lifts and other incidentals. The rates are inclusive of the octori, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	97.00			Per Hour	
					G. Total:-	

Note - 1) The physical progress of machine will also be measured while submitting the bill for payment. It is ensured that working progress of machine should be not be less than the amount to be paid.

Note - 2) No deviation shall be allowed in any case.

Note -3) Subject of availbity of funds


Executive Engineer
Dalhousie Division,
HPPWD, Dalhousie

Schedule of Qty.

Job No. 13 TS 193

Estimated Cost :- Rs. 96045.00
Earnest Money :- Rs. 2000.00
Time Limit :- Two Month

Name of work: -A/R & M/O Jandrighat to Pukhri road Km. 0/0 to 2/100 (SII: - Construction of Breast wall at RD. 0/885.90 to 0/889.60.

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 300 and 1600 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal un-useful materials upto any lead and lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. Carriage of surplus muck generated from cutting/excavation work to the disposable/dumping site to be selected by the contractor in private lands. The is rate including the octroi, royalty, Malkana, toll tax, sales tax GST or any other taxes imposed by the Government.	15.21			Per Cubic Metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete nominal mix 1:4:8 (one cement isto four sand isto eight graded stone aggregate 20 mm (twenty millimetre) nominal size) on ground or under water and curing complete for 14 (fourteen days), in open foundation for all type structure including pumping or bailing out water, (surface and sub soil water) dewatering, for all depths and any quantum of water including removal of slush which may arise at time of laying concrete completed for all heights/depths including the cost of form work complete as per drawing and MORD technical specification clause 800.900 and 1200 or as directed by the Engineer-In-Charge including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana toll tax, sale tax GST or other taxes imposed by the Government.	1.22			Per Cubic Metre	
3	Random rubble masonry (first short) with hard stones of approved quality in sub-structure, Retaining wall wing walls, abutment, toe walls etcetra, in cement mortar 1:6 (one cement isto six sand) curing complete including pumping or bailing out water, dewatering, removal of slush which may arise at the time of masonary work, complete as per MORD technical specification clause 702,704,1202 and 1204 including carriage of materials upto all leads and lifts and other incidental as per entire satisfaction and direction of Engineer-in-charge. The rate is including octroi, royalty, Malkana, toll tax sale tax GST or other taxes imposed by the Government.	9.54			Per Cubic Metre	
4	Construction of dry rubble masonry with hard stone of approved quality for structure like retaining wall, breast wall, revetment wall, and parapets etcetra for sub structure and super structure complete as per MORD technical specifications section 700 and 1300 and asper direction of Engineer-in-charge including carriage of materials upto all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax sale tax GST or other taxes imposed by the Government.	10.80			Per Cubic Metre	
					Total: -	

Executive Engineer
Dalhousie Division,
HPPW/Dalhouis

Schedule of Qty.

Job No. 14 TS 198

Estimated Cost: - Rs. 149507.00

Earnest Money :- Rs. 3000.00

Time Limit :- Two Month

Name of work: -Restoration of Rain damage on Link road to village Goli Km. 0/0 to 0/500 (SI: - Repair of Bridge and Slab Culvert at various RD's).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORID technical specification clause 300 and 1600 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal un-useful materials upto any lead and lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. Carriage of surplus muck genrated from cutting/excavation work to the disposable/dumping site to be selected by the contractor in private lands. The is rate including the octroi, royalty, Malkana, toll tax, sales tax GST or any other taxes imposed by the Government.	10.58			Per Cubic Metre	
2	Providing and Laying Plain / reinforced cement concrete M-15 in substructure complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 & 1204 nominal mix 1:2.5:5 (One is to two point five isto five) and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax GST or any other taxes imposed by the Government.	21.53			Per Cubic Metre	
					Total: -	

Executive Engineer
Dalhousie Division,
HPPWD Dalhousie

Schedule of Qty.

Estimated Cost: - Rs. 99997.00

Earnest Money :- Rs. 2000.00

Time Limit :- Two Month

Name of work: -Restoration of Rain damage on Brangal Wangal Mandoh road Km. 0/0 to 39/600 (SI: - Construction of Breast wall in wire crate at RD. 35/830 to 35/840).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable & approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including octroi royalty Malkhana Toll tax sale tax, GST or other taxes imposed by the Government.	19.15			Per Cubic Metre	
2	Providing and laying of boulder apron laid in wire crates with 4 mm (four milimetre) dia G.I wire conforming to IS: 280 and IS: 4826 in 100 mm x 100 mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulders weighting not less than 25 Kg (Twenty five kilograme) each as per drawing technical specifications Clause 1301 and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	31.26			Per Cubic Metre	
					Total: -	

Executive Engineer
Dalhousie Division.
HPPWD Dalhousie

Schedule of Qty.

Estimated Cost: - Rs. 98880.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month

Name of work: -Restoration of Rain damage on Brangal Wangal Mandoh road Km. 0/0 to 39/600 (SIH: - Hiring of JCB for removal of Slips in Km. 32/00 to 39/00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB / Excavator cum loader for cutting / widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts upto any heights and depth as per direction and entire satisfactions of Engineer-in-charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period /execution shall be the absolute responsibility of the JCB / Excavator Owner which shall have to be fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare, watch and ward of machine also be borne by the Contractor / Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	96.00			Per Hour	
					G. Total:-	

Note - 1) The physical progress of machine will also be measured while submitting the bill for payment. It is ensured that working progress of machine should be not be less than the amount to be paid.

Note - 2) No deviation shall be allowed in any case.

Note -3) Subject of availbity of funds

Executive Engineer
Dalhousie Division,
HPPWD Dalhousie

Schedule of Qty.

Job No. 17 TS 200

Estimated Cost: - Rs. 91665.00

Earnest Money :- Rs. 2000.00

Time Limit :- Two Month

Name of work: -Annual Surfacing on various roads under Dalhousie Division HPP PWD Dalhousie Under AMP 2025-26 (Village Road) (SI:- Providing and laying road Marking with Hot applied Thermoplastic Compound with Reflectorising Glass beads on Bituminous Surface on Bounkharimour to Dhunera road Km. 1/00 to 2/00 & Link road to village Goli Km. 0/0 to 0/500).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Providing and laying Hot plastic road marking paint of approved manufacture 2.5 mm (two decimal five millimetre) thick with reflectorising glass beads at the rate 250 (two hundred fifty gram) gram per square metre area. thickness of 2.5 mm (two point five millimetre) is exclusive of surface applied glass beads as per specification and with strips of 0.10 (zero decimal one) metre width in centre lines or edge lines of the road as per MORTH specification Clause No.803 or as per directions of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate is inclusive of octroi, royalty ,Malkana. toll tax.GST or any other taxes imposed by the Government.	150.00			Per Square Metre	
					G. Total:-	

Executive Engineer
Dalhousie Division.
HPPWD Dalhousie

Schedule of Qty.

Job No. 18 TS 195

Estimated Cost: - Rs. 96282.00
Earnest Money :- Rs. 2000.00

Name of work: -A/R & M/O Jandrigat to Pukhri road Km. 0/0 to 2/100 (SH: - Construction of Breast wall at RD. 0/882.20 to 0/885.90).

Time Limit :- Two Month

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 300 and 1600 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal un-useful materials upto any lead and lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. Carriage of surplus muck generated from cutting/excavation work to the disposable/dumping site to be selected by the contractor in private lands. The is rate including the octroi, royalty, Malkana, toll tax, sales tax GST or any other taxes imposed by the Government.	15.61			Per Cubic Metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete nominal mix 1:4:8 (one cement isto four sand isto eight graded stone aggregate 20 mm (twenty millimetre) nominal size) on ground or under water and curing complete for 14 (fourteen days), in open foundation for all type structure including pumping or bailing out water, (surface and sub soil water) dewatering, for all depths and any quantum of water including removal of slush which may arise at time of laying concrete completed for all heights/depths including the cost of form work complete as per drawing and MORD technical specification clause 800,900 and 1200 or as directed by the Engineer-In-Charge including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana toll tax ,sale tax GST or other taxes imposed by the Government.	1.22			Per Cubic Metre	
3	Random rubble masonry (first short) with hard stones of approved quality in sub-structure, Retaining wall wing walls, abutment, toe walls etcetra, in cement mortar 1:6 (one cement isto six sand) curing complete including pumping or bailing out water, dewatering, removal of slush which may arise at the time of masonary work, complete as per MORD technical specification clause 702,704,1202 and 1204 including carriage of materials upto all leads and lifts and other incidental as per entire satisfaction and direction of Engineer-in-charge.The rate is including octroi, royalty, Malkana, toll tax sale tax GST or other taxes imposed by the Government.	9.54			Per Cubic Metre	
4	Construction of dry rubble masonry with hard stone of approved quality for structure like retaining wall, breast wall, revetment wall, and parapets etcetra for sub structure and super structure complete as per MORD techincal specifications section 700 and 1300 and asper direction of Engineer-in-charge including carriage of materials upto all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax sale tax GST or other taxes imposed by the Government.	10.80			Per Cubic Metre	
					Total: -	

Executive Engineer
Dalhousie Division,
MORD/TS/195

Schedule of Qty.


Estimated Cost: - Rs. 99851.00

Earnest Money :- Rs. 2000.00

Time Limit :- Two Month

Name of work: -Restoration of Rain damage on Brangal Wangal Mandoh road Km. 0/0 to 39/600 (SH: - Construction of Retaining wall in wire crate at RD. 35/835 to 35/840).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including octroi royalty Malkhana Toll tax sale tax, GST or other taxes imposed by the Government.	19.00			Per Cubic Metre	
2	Providing and laying of boulder apron laid in wire crates with 4 mm (four milimetre) dia G.I wire conforming to IS: 280 and IS: 4826 in 100 mm x 100 mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulders weighting not less than 25 Kg (Twenty five kilograme) each as per drawing technical specifications Clause 1301 and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	31.24			Per Cubic Metre	
					Total: -	


 Executive Engineer
 Dalhousie Division,
 HPPWD Dalhousie

Schedule of Qty.

Estimated Cost: - Rs. 76999.00

Earnest Money :- Rs. 1600.00

Time Limit :- Two Month

Name of work: -Annual Surfacing on various roads under Dalhousie Division HP PWD Dalhousie Under AMP 2025-26 (Village Road) (SH:- Providing and laying road Hot Thermoplastic road makring on Kholkuffar to Rikhnalli road Km. 3/00 to 4/00 & Link road to HP PWD Circuit House at Dalhousie Km.0/0 to 0/130)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Providing and laying Hot plastic road marking paint of approved manufacture 2.5 mm (two decimal five millimetre) thick with reflectorising glass beads at the rate 250 (two hundred fifty gram) gram per square metre area. thickness of 2.5 mm (two point five millimetre) is exclusive of surface applied glass beads as per specification and with strips of 0.10 (zero decimal one) metre width in centre lines or edge lines of the road as per MORTH specification Clause No.803 or as per directions of Engineer-in-Charge. including carriage of materials within all leads, lifts and other incidental.The rate is inclusive of octroi, royalty ,Malkana, toll tax,GST or any other taxes imposed by the Government.	126.00			Per Square Metre	
					G. Total:-	

Executive Engineer
Dalhousie Division,
HPPWD Dalhousie

Schedule of Qty.

Estimated Cost :- Rs. 96354.00

Earnest Money :- Rs. 2000.00

Time Limit :- Two Month

Name of work: -A/R & M/O Jandrighat to Pukhri road Km. 0/0 to 2/100 (SH: - Construction of Breast wall at RD. 0/893.30 to 0/897.00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 300 and 1600 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal un-useful materials upto any lead and lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. Carriage of surplus muck generated from cutting/excavation work to the disposable/dumping site to be selected by the contractor in private lands. The is rate including the octroi, royalty, Malkana, toll tax, sales tax GST or any other taxes imposed by the Government.	15.73			Per Cubic Metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete nominal mix 1:4:8 (one cement isto four sand isto eight graded stone agreegate 20 mm (twenty millimetre) nominal size) on ground or under water and curing complete for 14 (fourteen days), in open foundation for all type structure including pumping or bailing out water, (surface and sub soil water) dewatering, for all depths and any quantum of water including removal of slush which may arise at time of laying concrete completed for all heights/depths including the cost of form work complete as per drawing and MORD technical specification clause 800,900 and 1200 or as directed by the Engineer-In-Charge including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana toll tax, sale tax GST or other taxes imposed by the Government.	1.22			Per Cubic Metre	
3	Random rubble masonry (first short) with hard stones of approved quality in sub-structure, Retaining wall wing walls, abutment, toe walls etcetra, in cement mortar 1:6 (one cement isto six sand) curing complete including pumping or bailing out water, dewatering, removal of slush which may arise at the time of masonry work, complete as per MORD technical specification clause 702,704,1202 and 1204 including carriage of materials upto all leads and lifts and other incidental as per entire satisfaction and direction of Engineer-in-charge. The rate is including octroi, royalty, Malkana, toll tax sale tax GST or other taxes imposed by the Government.	9.54			Per Cubic Metre	
4	Construction of dry rubble masonry with hard stone of approved quality for structure like retaining wall, breast wall, revetment wall, and parapets etcetra for sub structure and super structure complete as per MORD technical specifications section 700 and 1300 and asper direction of Engineer-in-charge including carriage of materials upto all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax sale tax GST or other taxes imposed by the Government.	10.80			Per Cubic Metre	
					Total:-	

Executive Engineer
Dalhousie Division,
HPPWD Dalhousie

Schedule of Qty.

Estimated Cost: - Rs. 99910.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month


Name of work: -Restoration of Rain damage on Brangal Wangal Mandoh road Km. 0/0 to 39/600 (SIH: - Hiring of JCB for removal of Slips in Km. 24/00 to 32/00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB / Excavator cum loader for cutting / widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts upto any heights and depth as per direction and entire satisfactions of Engineer-in-charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period /execution shall be the absolute respoonsibility of the JCB / Excavator Owner which shall have to be fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare, watch and ward of machine also be borne by the Contractor / Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge including carriage of materails with in all leads, lifts and other incidentals. The rates are inclusive of the octori, royalty. Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	97.00			Per Hour	
					G. Total:-	

Note - 1) The physical progress of machine will also be measured while submitting the bill for payment. It is ensured that working progress of machine should be not be less than the amount to be paid.

Note - 2) No deviation shall be allowed in any case.

Note -3) Subject of availbity of funds


Executive Engineer
Dalhousie Division.
HPPWD, Dalhousie

Schedule of Qty.

Estimated Cost: - Rs. 98880.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month


Name of work: -Restoration of Rain on Dalhousie Jandrihat Chamba via Kohlari road Km. 0/0 to 11/040 (SH: - Hiring of JCB for removal of Slips in Km. 0/00 to 6/00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB / Excavator cum loader for cutting / widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-servicable materials from the road surface upto any leads and lifts upto any heights and depth as per direction and entire satisfactions of Engineer-in-charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period /execution shall be the absolute respoonsibility of the JCB / Excavator Owner which shall have to be fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare, watch and ward of machine also be borne by the Contractor / Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge including carriage of materails with in all leads, lifts and other incidentals. The rates are inclusive of the octori, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	96.00			Per Hour	
					G. Total:-	

Note - 1) The physical progress of machine will also be measured while submitting the bill for payment. It is ensured that working progress of machine should be not be less than the amount to be paid.

Note - 2) No deviation shall be allowed in any case.

Note -3) Subject of availbity of funds


Executive Engineer
Dalhousie Division,
HPPWD, Dalhousie

Schedule of Qty.

Estimated Cost: - Rs. 99910.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month

Name of work: -Restoration of Rain on Dalhousie Jandrigat Chamba via Kohlari road Km. 0/0 to 11/040 (SH: - Hiring of JCB for removal of Slips in Km. to 6/00 to 11/040).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB / Excavator cum loader for cutting / widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts upto any heights and depth as per direction and entire satisfactions of Engineer-in-charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period /execution shall be the absolute responsibility of the JCB / Excavator Owner which shall have to be fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare, watch and ward of machine also be borne by the Contractor / Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	97.00			Per Hour	
					G. Total:-	

Note - 1) The physical progress of machine will also be measured while submitting the bill for payment. It is ensured that working progress of machine should be not be less than the amount to be paid.

Note - 2) No deviation shall be allowed in any case.

Note -3) Subject of availbity of funds


Executive Engineer
Dalhousie Division,
HPPWD Dalhousie

Schedule of Qty.

Estimated Cost: - Rs.

Earnest Money :- Rs.

Time Limit :-

Two Month

Name of work: -A/R & M/O Jandrigat to Pukhri road Km. 0/0 to 2/100 (SI: - Construction of Breast wall at RD. 0/900.70 to 0/904.40).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 300 and 1600 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal un-useful materials upto any lead and lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. Carriage of surplus muck generated from cutting/excavation work to the disposable/dumping site to be selected by the contractor in private lands. The rate including the octroi, royalty, Malkana toll tax, sales tax GST or any other taxes imposed by the Government.	16.47			Per Cubic Metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete nominal mix 1:4:8 (one cement isto four sand isto eight graded stone aggregate 20 mm (twenty millimetre) nominal size) on ground or under water and curing complete for 14 (fourteen days), in open foundation for all type structure including pumping or bailing out water, (surface and sub soil water) dewatering, for all depths and any quantum of water including removal of slush which may arise at time of laying concrete completed for all heights/depths including the cost of form work complete as per drawing and MORD technical specification clause 800.900 and 1200 or as directed by the Engineer-In-Charge including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana toll tax, sale tax GST or other taxes imposed by the Government.	1.22			Per Cubic Metre	
3	Random rubble masonry (first sort) with hard stones of approved quality in sub-structure, Retaining wall wing walls, abutment, toe walls etcetra, in cement mortar 1:6 (one cement isto six sand) curing complete including pumping or bailing out water, dewatering, removal of slush which may arise at the time of masonry work, complete as per MORD technical specification clause 702,704,1202 and 1204 including carriage of materials upto all leads and lifts and other incidental as per entire satisfaction and direction of Engineer-in-charge. The rate is including octroi, royalty, Malkana, toll tax sale tax GST or other taxes imposed by the Government.	9.54			Per Cubic Metre	
4	Construction of dry rubble masonry with hard stone of approved quality for structure like retaining wall, breast wall, revetment wall, and parapets etcetra for sub structure and super structure complete as per MORD technical specifications section 700 and 1300 and asper direction of Engineer-in-charge including carriage of materials upto all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax sale tax GST or other taxes imposed by the Government.	10.80			Per Cubic Metre	
Total: -						

Executive Engineer
Dalhousie Division,
HPPW Dalhousie

Schedule of Qty.

Estimated Cost :- Rs. 36235.00

Earnest Money :- Rs. 800.00

Time Limit :- One Month

Name of work: -Running and Maintenance of Machinery under Dalhousie Sub Division (SH:- Replacement of various defective Machinery part of Bobcat/Excavator No. IIP 47A- 0755 Under Dalhousie Sub Division)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Replacement of defective Hand primer pump for fuel system of diesel engine operated excavator of approved make and specification. including removal of old unserviceable part. The rate including the octroi. royalty, malkana. till tax, sale tax excluding GST or any other taxes imposed by the Government.	1.00			Each	
2	Replacement of Outer Air filter Element of air cleaner assembly of excavator. including removal of old unserviceable part. The rate including the octroi, royalty, malkana, till tax, sale tax excluding GST or any other taxes imposed by the Government.	1.00			Each	
					Total: -	


Executive Engineer
 Dalhousie Division,
 HPPWD, Dalhousie

Schedule of Qty.

Estimated Cost: - Rs. 98880.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month


Name of work: -Restoration of Rain on Banikhet Dalhousie Khajjiar road Km. 15/600 to 27/00 (SH: - Hiring of Excavator cum loader for removal of Slips/Snow in Km. 15/600 to 27/00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB / Excavator cum loader for cutting / widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts upto any heights and depth as per direction and entire satisfactions of Engineer-in-charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period /execution shall be the absolute responsibility of the JCB / Excavator Owner which shall have to be fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare, watch and ward of machine also be borne by the Contractor / Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	96.00			Per Hour	
					G. Total:-	

Note - 1) The physical progress of machine will also be measured while submitting the bill for payment. It is ensured that working progress of machine should be not be less than the amount to be paid.

Note - 2) No deviation shall be allowed in any case.

Note -3) Subject of availbity of funds


Executive Engineer
Dalhousie Division,
HPPWD, Dalhousie

Schedule of Qty.

Job No. 28 TS 204

Estimated Cost: - Rs. 99910.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month

Name of work: -Restoration of Rain on Link road to village Ruliyani Km. 0/0 to 3/020 (SI: - Hiring of Excavator com loader for removal of Slips/Snow in Km. 0/0 to 3/020).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB / Excavator cum loader for cutting / widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts upto any heights and depth as per direction and entire satisfactions of Engineer-in-charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period /execution shall be the absolute respoonsibility of the JCB / Excavator Owner which shall have to be fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare, watch and ward of machine also be borne by the Contractor / Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge including carriage of materails with in all leads, lifts and other incidentals. The rates are inclusive of the octori, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	97.00			Per Hour	
					G. Total:-	

Note - 1) The physical progress of machine will also be measured while submitting the bill for payment. It is ensured that working progress of machine should be not be less than the amount to be paid.

Note - 2) No deviation shall be allowed in any case.

Note -3) Subject of availbity of funds


Executive Engineer
Dalhousie Division,
HPPWD Dalhousie