Himachal Pradesh
Public Works Department

No.PW/ESDH/E-8-Tender/2026 535-40 Dated:- 09/02/2026

To,

The Executive Engineer (IT Cell),
Nigam Vihar, Shimla-2

Subject:- Publication of tender Notice.

Jai Hind

Enclosed please find herewith the Tender Notice of works as given in the Notice Invited tender along with Schedule of Quantities for uploading on department website as per Notification Pr. Sec (PW) to the Govt. of HP letter No. PBW (B)A (3)1/2020 dated Shimla 26th July, 2021.

It is certified that the work mentioned in the Notice Invited tenders are urgent in nature and in public interest.

DA/NIT, SQs.

Assistant Engineer,
Electrical Sub-Division
HP.PWD. Hamirpur.

Copy forwarded to the following for information and necessary action please.

1. The Superintending Engineer,2nd Electrical Circle .
2. The Executive Engineer Electrical Division HP.PWD.Una.
3. The Assistant Engineer, Electrical Sub Division, HPPWD, Una and Bilaspur.
4. The Notice Board in this office.

Assistant Engineer,
Electrical Sub-Division
HP.PWD. Hamirpur

Office of the
Assistant Engineer
Electrical Sub-Division, HP.PWD., Hamirpur
Tel: +911972222439

NOTICE INVITING TENDER

Sealed percentage rate tenders are hereby invited by the Assistant Engineer, Electrical Sub-Division HP.PWD., Hamirpur, in form No.6 & 8 on behalf of Governor of H.P. for the following works from the contractors of appropriate class enlisted with HP.PWD. (Electrical) or authorized firm for specialized jobs. The tenders shall be opened on dated **23/02/2026** in the presence of contractors/firms or their authorized representative who wish to be present.

The copy of **Valid enlistment,** renewal certificate and Authorization letter along with GST No., Pan No., and EPF No. shall be attached with application form. The offer of the tender shall remain open **75 days** from the date of opening of the tenders. The undersigned reserves the right to reject/cancel the tenders without assigning any reason. The tender form will be issued to only those contractors who qualify the criteria after the scrutiny of application forms by the committee constituted for the purpose.

TIME SCHEDULE OF TENDER

1.	Last date of receipt of application	:-	21/02/2026 up to 01.00 P.M.
2.	Date of sale of tenders	:-	21/02/2026 up to 05.00 P.M.
3.	Last date of receipt of bids	: -	23/02/2026 up to 11.30 A.M.
4.	Date of bid opening	: -	23/02/2026 up to 01.00 P.M.

Sr. No.	Name of work	Estimated Cost (In Rs.)	Earnest Money (In Rs.)	Time limit	Cost of form (In Rs.)	Eligible Class of Contractor
1	Providing, Installation Testing and Commissioning Split type Air Conditioner in Rest House Bohni, Set No.1 District Hamirpur (HP)	66397/-	1300/-	Three Months	350/-	Class-D,C
2	Providing, Installation Testing and Commissioning Split type Air Conditioner in Rest House Bohni, Set No. 2 District Hamirpur (HP)	66397	1300/-	Three Months	350/-	Class-D,C
3.	Providing, Installation Testing and Commissioning Split type Air Conditioner in Rest House Bohni, Set No.3 District Hamirpur (HP)	69897/-	1400/-	Three Months	350/-	Class-D,C
4.	Providing, Rewiring in the office of State Intelligence unit Hamirpur, Room No. 7 and 8, District Hamirpur (HP)	64,899/-	1,300/-	One year	350/-	Class-D,C

GENERAL TERMS AND CONDITIONS:-

1. The earnest money in the shape of NATIONAL Saving Certificate time deposit account in any of the post office in HP/FDR or any bank duly pledged in favour of Assistant Engineer, HPPWD., Electrical Sub-Division Hamirpur accompanied with the application for receipt of tender form along with cost of form.
2. The Contractor/Firm should be submitted the all above-mentioned documents (photocopy to be self-attested) with the application for obtaining the tender documents.
3. In case office happens to be closed on any of the above mentioned dates, the bids will be opened on the next working day at same time and venue.
4. The contractors/firms are required to quote their rates clearly both in words as well as in figures, failing which tenders are likely to be rejected.
5. No Person/persons shall be allowed to give the documents with regard to tender unless he/they hold/holds the power of attorney duly registered under law.
6. The tender of those contractors who are registered under H.P. Central Sales Tax Act 1969, GST and who have been cleared all the dues on account of tax will be entertained.
7. The competent authority on behalf of Governor of H.P. reserves the right to reject any or all the tenders received without assigning any reason.
8. The eligible Contractors/Firm should performance certificate for specialized jobs as required.
9. The tendered amount should be within the limit of (+) 5% to (-) 30% as per notification No. PBW(B)A(3)1/2020-1 dated 07.10.2021 shall be applicable for Bid price lower than-10% and more than + 5%. If the Contractors/Firms has quoted bid price lower than 10% the performance guarantee will be deposited before the award of work as per terms & condition of above said notification.

Assistant Engineer,
Electrical Sub-Division
HPPWD, Hamirpur

No. PW/ESDH/NIT/Tender/2026- 541-48 Dated 09/02/2026

Copy along with its enclosures is forwarded to the following for favour of information please:-

1. The Superintending Engineer 2nd Electrical Circle, HP.PWD.Dharmshala.
2. The Executive Engineer, HP.PWD., Electrical Division Una .
3. The Assistant Engineer, Electrical Sub Division, HPPWD, Una and Bilaspur.
4. All the JE's under this Sub-Divn.
5. All the Contractors/Firms working under the control of this Division/Sub-Division
6. All the Head of Branches in this office
7. Notice Board.

Assistant Engineer,
Electrical Sub-Division
HPPWD, Hamirpur

Certificate

It is certified that the tender for above work is emergent nature and urgently required in public interest.

Assistant Engineer,
Electrical Sub-Division
HPPWD, Hamirpur

DRAFT SCHEDULE OF QUANTITY

Estimated cost: Rs. 66,397/-
Earnest money: Rs.1,300/-
Time Limit:- Three Months.

Name of work:-Providing, Installation testing and Commissioning Split type Air Conditioner in Rest House Bohni ,Set NO - 1 Distt Hamirpur (H.P)

S. No.	Description of Items	Quantity	Rate In Fig.	In Words.	Unit	Amount
1	Supplying and fixing 1.5 ton invertor split type air conditioner Hot and Cold with five year warranty , advanced filter ,E saver mode , quit mode, dual display ,auto clean ,anti bacteria filter jet Cool on/off timer sleep mode compressor cord less remote complete in all respect as per comprising to ISI with latest amendment suitable to operate on 230 volt /240 volt +_ 10 % AC supply capable to perform the function of cooling dehumidification air circulation ventilation and fitting in size of nominal cooling capacity and drain pipe 20 mm dia approximately 3mtrs long 2 nos copper pipe with Insulator for inlet and outlet approximatey 3 mtrs long Including carrigae of material with in all leads and lift. Make -Daikin (Model:FTHT50)/ O General/ Mitsubishi/ Voltas as approved by the Engineer-In-Charge.Warranty on product one year,on PCB five year & on compressor 10 year.	1	54000	Rupees Fifty four thousand only.	Each	54000
2	Supplying and fixing of voltage stabilizer upto 4 KVA having specification Digital display, led indicator & audible alarm, Input voltage range 130-300V, & built in protection ,over voltage ,Under volltage , overload, short circuits high temperature,and low oil levels and also have bypass switchin ,efficiency 98%,torodial core including connections, testing and commissioning as required: Make: Microtek /V Guard /Voltas as approved by Engineer-In-charge(Warranty Three year)	1	4666	Rupees Four thousand six hundred sixty six only.	each	4666
3	Supplying and fixing of DLP 105x50 mm PVC adaptable trunking on the exiting wall at required height from lower level for power connection, light connection and net working connection including partition chip flexible cover end cap Make:-Legrand /MK as required complete in all respect .	3.00	1517	Rupees One thousand five hundred seventeen only.	mtr	4551
4	Supply, Installation, testing and commissioning including vacuumization and Nitrogen testing of following nominal sizes of soft/hard drawn copper refrigerant piping for VRV/VRF system, complete with fittings, with suitable adjustable ring type hanger supports, jointing/brazing including accessories, insulated with XPLE Class-O tubular insulation/with Class-O closed cell elastomeric nitrile rubber tubular sleeves sections of specified thickness as given below for Suction and Liquid lines, all accessories as per specifications etc. as required. Copper pipe Make: Godrej/ Mehta/ Mandev/ Rajco/ Nippon/ Totaline/ Met Tube & Insulation Make:- Supreme/A-Flex/K-Flex including Gas charging.	2.00	1400	Rupees One thousand four hundred only.	meter	2800
5	Supplying & installation of flexible drain pipe. Make: Polypack/ Supreme/ Prince/ Finolex/ Diplast as approved by Engineer-in-charge	2.00	190	Rupees One hundred ninety only.	meter	380
	TOTAL					66397

This work is emergent, Nature and sequesed Immediate Execution at site in Public Hoat. St is certified that DWIT of above will be recommended for approval.

Assistant Engineer
Electrical Sub Division
H.P.P.W.D. Hamirpur

Executive Engineer
Electrical Division
H.P.P.W.D.Una-174303

DRAFT SCHEDULE OF QUANTITY

Estimated cost:- Rs. 66,397/-
Earnest money:- Rs.1,300/-
Time Limit:- Three Months.

Name of work:-Providing, Installation testing and Commissioning Split type Air Conditioner in Rest House Bohni ,Set NO - 2 Distt Hamirpur (H.P)

S. No.	Description of Items	Quantity	Rate In Fig.	In Words.	Unit	Amount
1	Supplying and fixing 1.5 ton invertor split type air conditioner Hot and Cold with five year warranty , advanced filter ,E saver mode , quit mode, dual display ,auto clean ,anti bacteria filter jet Cool on/off timer sleep mode compressor cord less remote complete in all respect as per comprising to ISI with latest amendment suitable to operate on 230 volt /240 volt +_ 10 % AC supply capable to perform the function of cooling dehumidification air circulation ventilation and fitting in size of nominal cooling capacity and drain pipe 20 mm dia approximately 3mtrs long 2 nos copper pipe with insulator for inlet and outlet approximatey 3 mtrs long including carrigae of material with in all leads and lift. Make - Daikin (Model:FTHT50)/ O General/ Mitsubishi/ Voltas as approved by the Engineer-in-Charge.Warranty on product one year,on PCB five year & on compressor 10 year.	1	54000	Rupees Fifty four thousand only.	Each	54000
2	Supplying and fixing of voltage stabilizer upto 4 KVA having specification Digital display, led indicator & audible alarm, Input voltage range 130-300V, & built in protection ,over voltage ,Under volltage , overload, short circuits high temperature,and low oil levels and also have bypass switchin ,efficiency 98%,torodial core including connections, testing and commissioning as required: Make:- Microtek /V Guard /Voltas as approved by Engineer-in-charge(Warranty Three year)	1	4666	Rupees Four thousand six hundred sixty six only.	each	4666
3	Supplying and fixing of DLP 105x50 mm PVC adaptable trunking on the exiting wall at required height from lower level for power connection, light connection and net working connection including partition chip flexible cover end cap Make:- Legrand /MK as required complete in all respect .	3.00	1517	Rupees One thousand five hundred seventeen only.	mtr	4551
4	Supply, Installation, testing and commissioning including vacuumization and Nitrogen testing of following nominal sizes of soft/hard drawn copper refrigerant piping for VRV/VRF system, complete with fittings, with suitable adjustable ring type hanger supports, jointing/brazing including accessories, insulated with XPLE Class-O tubular insulation/with Class-O closed cell elastomeric nitrile rubber tubular sleeves sections of specified thickness as given below for Suction and Liquid lines, all accessories as per specifications etc. as required. Copper pipe Make: Godrej/ Mehta/ Mandev/ Rajco/ Nippon/ Totaline/ Met Tube & Insulation Make:- Supreme/A-Flex/K-Flex including Gas charging.	2.00	1400	Rupees One thousand four hundred only.	meter	2800
5	Supplying & installation of flexible drain pipe. Make: Polypack/ Supreme/ Prince/ Finolex/ Diplast as approved by Engineer-in-charge	2.00	190	Rupees One hundred ninety only.	meter	380
	TOTAL					66397

for approval. The said work is of emergent nature and it is certified that DNIT of above work recommended required immediate execution in Public Interest.

Assistant Engineer
Electrical Sub Division
H P P W.D Hamirpur

DNIT checked and approved for amounting to Rs 66,397/- (Rs Sixty Six thousand three hundred Ninety seven only)

Executive Engineer
Electrical Division
H.P.P.W.D.Una-174303

Electrical Division

DRAFT SCHEDULE OF QUANTITY

Estimated cost:- Rs. 69,897/-
Earnest money:- Rs.1,400/-
Time Limit:- Three Months.

Name of work:-Providing, Installation testing and Commissioning Split type Air Conditioner in Rest House Bohni ,Set NO - 3 Distt Hamirpur (H.P)

S. No.	Description of Items	Quantity	Rate In Fig.	In Words.	Unit	Amount
1	Supplying and fixing 1.5 ton invertor split type air conditioner Hot and Cold with five year warranty , advanced filter ,E saver mode , quit mode, dual display ,auto clean ,anti bacteria filter jet Cool on/off timer sleep mode compressor cord less remote complete in all respect as per comprising to ISI with latest amendment suitable to operate on 230 volt /240 volt +_ 10 % AC supply capable to perform the function of cooling dehumidification air circulation ventilation and fitting in size of nominal cooling capacity and drain pipe 20 mm dia approximately 3mtrs long 2 nos copper pipe with insulator for inlet and outlet approximatey 3 mtrs long including carrigae of material with in all leads and lift. Make -Daikin (Model:FTHT50)/ O General/ Mitsubishi/ Voltas as approved by the Engineer-in-Charge.Warranty on product one year,on PCB five year & on compressor 10 year.	1	54000	Rupees Fifty four thousand only.	Each	54000
2	Supplying and fixing of voltage stabilizer upto 4 KVA having specification Digital display, led indicator & audible alarm, Input voltage range 130-300V, & built in protection ,over voltage ,Under volttage , overload, short circuits high temperature,and low oil levels and also have bypass switchin ,efficiency 98%,torodial core including connections, testing and commissioning as required: Make:- Microtek /V Guard /Voltas as approved by Engineer-in-charge(Warranty Three year)	1	4666	Rupees Four thousand six hundred sixty six only.	each	4666
3	Dismantling and Installation of New split type Air conditioner 1.5 ton and 1.8 AC at same place including Outdoor unit complete in all respect as required to the best satisfaction of Engineer-in-Charge.	1	3500	Rupees Three thousand five hundred only	EACH	3500
4	Supplying and fixing of DLP 105x50 mm PVC adaptable trunking on the exiting wall at required height from lower level for power connection, light connection and net working connection including partition chip flexible cover end cap Make:-Legrand /MK as required complete in all respect .	3.00	1517	Rupees One thousand five hundred seventeen only.	mtr	4551
5	Supply, Installation, testing and commissioning including vacuumization and Nitrogen testing of following nominal sizes of soft/hard drawn copper refrigerant piping for VRV/VRF system, complete with fittings, with suitable adjustable ring type hanger supports, jointing/brazing including accessories, insulated with XPLE Class-O tubular insulation/with Class-O closed cell elastomeric nitrile rubber tubular sleeves sections of specified thickness as given below for Suction and Liquid lines, all accessories as per specifications etc. as required. Copper pipe Make: Godrej/ Mehta/ Mandev/ Rajco/ Nippon/ Totaline/ Met Tube & Insulation Make:- Supreme/A-Flex/K-Flex including Gas charging.	2.00	1400	Rupees One thousand four hundred only.	meter	2800
6	Supplying & installation of flexible drain pipe. Make: Polypack/ Supreme/ Prince/ Finolex/ Diplast as approved by Engineer-in-charge	2.00	190	Rupees One hundred ninety only.	meter	380
	TOTAL					69897

work is emergent nature and required execution in Public interest. It is certified that DNIT of above work recommended to approval. The said DNIT cheque of final approval for amounting to Rs 69897/- only (Rs Sixty Nine thousand Eight hundred Ninety seven only)

Assistant Engineer
Electrical Sub Division
H.P.P.W.D Hamirpur

Executive Engineer
Electrical Division

DRAFT SCHEDULE OF QUANTITY

Estimated cost:- Rs. 64,899/-

Earnest money:- Rs. 1,300/-

Time Limit:- One year.

Name of Work:- Providing Rewiring in the office of state intelligence unit Hamirpur, Room No-7 and 8, Distt. Hamirpur H.P.

S. No.	Description of Items	Quantity	Rate In Figure	In Words.	Unit	Amount
1	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed Heavy class PVC Conduit having wall thickness minimum 2.0 mm , with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc as required. (Make:- Legrand Lyncus/ L&T Entice/ Anchor Roma Classic/ Panasonic Akina/ Crabtree Athena/ ABB Adiva/ Schneider Electric Clipsal & WIres Make: Finolex/Anchor/ Polycab/ Plaza.					
1.01	Group - C	11	1257	Rupees One thousand two hundred fifty seven only.	each	13827
2	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required. Make:- Legrand Lyncus/ L&T Entice/ Anchor Roma Classic/ Panasonic Akina/ Crabtree Athena.					0
2.01	5/6 amp Modular switch	2	98	Rupees Ninety eight only.	Each	196
2.02	5 pin 5/6 amp socket outlet	2	141	Rupees One hundred forty one only.	each	282
3	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 3 pin 5/6 amps modular socket outlet and 5/6 amps modular switch, connection etc. as required. Make:- Legrand Lyncus/ L&T Entice/ Anchor Roma Classic/ Panasonic Akina/ Crabtree Athena	1	492	Rupees Four hundred ninety two only.	each	492
4	Supplying and fixing two module stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modularplate etc. as required. Make:- Legrand Lyncus/ L&T Entice/ Anchor Roma Classic/ Panasonic Akina/ Crabtree Athena.	1	438	Rupees Four hundred thirty eight only.	each	438

5	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providng and fixing 2 nos. 3 pin 5/6 amps modular socket outlets and 2 nos 5/6 amps modular switches, connection etc. as required. (For light plugs to be used in non residential buildings). Make:- Legrand Lyncus/ L&T Entice/ Anchor Roma Classic/ Panasonic Akina/ Crabtree Athena.	2	739	Rupees Seven hundred thirty nine only.	each	1478
6	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 6 pin 5/6 & 15/16 amps modular socket outlet and 15/16 amps modular switch, connection etc. as required. Make:- Legrand Lyncus/ L&T Entice/ Anchor Roma Classic/ Panasonic Akina/ Crabtree Athena.	3	650	Rupees Six hundred fifty only.	each	1950
7	Supplying & fixing suitable size GI box wih modular plate and cover in front on surface or in recess i/c providing and fixing 25 amp modular socket outlet and 25 Amps modular SP MCB, "C" curve including connection, painting etc. as required. Make:- Legrand Lyncus/ L&T Entice/ Anchor Roma Classic/ Panasonic Akina/ Crabtree Athena.	1	737	Rupees Seven hundred thirty seven only.	each	737
8	Supplying and fixing Computer board comprising 3 nos 5 amp modular switches & Sockets , G.I box 2 module for jack box and G.I Box 12 module for 5 amp switchs and 5 amp sockets comprising sheet cover for each 2 module metal box , one no computer jack (RJ-45)with shutter including connections etc as required. Make:- Legrand Lyncus/ L&T Entice/ Anchor Roma Classic/ Panasonic Akina/ Crabtree Athena.	1	1871	Rupees One thousand eight hundred seventy one only.	each	1871
9	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required. Make:- Finolex/Anchor/Polycab/Plaza as approved by Engineer-in-Charge.					0
9.01	3 x 1.5 sq. mm	40	101	Rupees One hundred one only.	meter	4040
9.02	3 x 4 sq. mm	48	221	Rupees Two hundred twenty one only.	meter	10608
10	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed heavy class PVC conduit as required. Make:-Finolex/Anchor/Polycab/Plaza as approved by Engineer-in-Charge.					0
10.01	2 X 10 sq. mm + 1 X 6 sq. mm earth wire	2	576	Rupees Five hundred seventy six only.	meter	1152
11	Supplying and fixing of following sizes of Heavy class FRLS PVC Conduit having wall thickness minimum 2.0 mm along with accessories in surface/recess including cutting the wall and making good as required. MAKE:-Diplast/ BEC/Polyfit /AKG as approved by Engineer-in-Charge.					0

11.01	25 mm	5	102	Rupees One hundred two only.	meter	510
12	Supplying and fixing Ding Dong bell suitable for single phase, 230 volts, complete as required.					0
12.01	Ding dong bell	1	247	Rupees Two hundred forty seven only.	each	247
13	Providing, Installation, testing and commissioning of ceiling fan,including wiring the down rods of standard length (up to 45 cm) with 16/0.20 mmtwin twisted flexible, cotton braided, copper cable, including providing and fixing phenolic laminated sheet cover on the fan box and earthing etc. as required. (Make: Usha Technix Plus ISI/ Orient Echotech Prime/ Havells Efficiencia/ Bajaj Energos 26/ Anchor Ecobreez Urban 3 Blades/ Crompton Energion HS Groove Hyperjet only) .five year warranty					0
13.01	Ceiling Fan 1200 mm sweep	1	3677	Rupees Three thousand six hundred seventy seven only.	each	3677
14	Supplying and fixing batten/ angle holder including connection etc. as required.	3	90	Rupees Ninety only.	each	270
15	Supply and fixing of surface SQUARE/ROUND 24 W (+/- 5%)watts with minimum system lumen efficacy of 110 lm/W and total luminous flux 1320 with Pressure Die cast Aluminium heat sink with and HET diffuser and polycarbonate mounting box P.F.>0.95 ,THD<10% ,CCT 6500K/4000K, CRI > 80, UGR<23,IP20 protection.The LED with Useful life of 50000 Hrs at L70.. The Input voltage range shall be 150V to 270V .Fixture have Surge Protection 4 kV and inbuilt short circuit protection .Isolated Driver including ,cutting arrangement ,complete in all respect. Make:- Philips/Wipro/jaquar/panasonic or as approved by Engineer-in-Charge.(five year warranty)	4	1404	Rupees One thousand four hundred four only.	each	5616
16	Supplying and fixing LED batten 25 watt (+/- 5%)Watts, with clear glass cover with steel housing optical material polystyrene and optical cover material polycarbonate having efficacy 120lm/W and luminious flux 2000 lumens having P.F.>0.95 with THD<10%. The LED with Useful life of 50000 Hrs at L70. The LEDs used in the luminaire shall have CCT of 6500 K with CRI of minimum > 80. The Input voltage range shall be 150V to 270V . Fixture have Surge Protection 4kV complete with all accessories, connections, testing and commissioning etc. Make:- wipro /Philips/Jaquar/panasonic as approved by Engineer-in-Charge. (Five YEAR WARRANTY)	1.00	524	Rupees Five hundred twenty four only.	each	524
17	Providing and installation of following type of LED retrofit Lamp 9 watt , B-22 holder base with polycarbomate diffuser and aluminium heat sink including connections, testing and commissioning etc. as required. Make:- JAQUAR/ Wipro/Philips/ Panasonic as approved by Engineer-in-Charge.	3	125	Rupees One hundred twenty five only.	each	375

18	Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, 10 kA, "C" curve,miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Make:- L&T /Legrand/Hager / Schenider as approved by Engineer-in -charge. (five year warranty)					0
18.01	Single pole	7	316	Rupees Three hundred sixteen only.	each	2212
19	Supplying and erection of 40/50/63 amps rating, 10 KA breaking capacity, 240 volts, 'C' curves, miniature circuit breaker of double poles in the existing MCB DB complete with connections etc. as required. Make:- L&T/Legrand/ Hager/ABB as approved by Engineer-in-Charge. (five year warranty).	1	1435	Rupees One thousand four hundred thirty five only.	Each	1435
20	Supplying and fixing following rating, double pole, (single phase and neutral), 240 volts,10 KA residual current circuit breaker (RCCB), having a sensitivity current 30 milli amperes in the existing MCB DB complete with connections, testing and commissioning etc. as required. Make:- L&T /Legrand/Hager / Schinder as approved by Engineer-in -charge. (five year warranty)					0
20.01	63 AMP	1	4198	Rupees Four thousand one hundred ninety eight only.	Each	4198
21	Supplying and fixing following way, single pole and neutral,sheet steel, MCB distribution board, 240 V, on surface/recess, complete with tinned copper bus bar, neutral busbar, earth bar,din bar, detachable gland plate, interconnections, with appropriate rating copper lugs, gland , powder painted including earthing etc. as required. (But withoutMCB/RCCB/Isolator). Make:- L&T / Legrand/Hager / Schneider as approved by Engineer-in -charge. (five year warranty)					0
21.01	MCBDB-12 way , Double Door	1	2993	Rupees Two thousand nine hundred ninety three only.	Each	2993
22	Supplying and fixing true power make advanced earthing system having GI pipe 3 meter long 50 mm dia with terminal size 50x6 mm ,internal strip size 25x3 with 50 Kg compound including exvation of pit and refiling the same and making earthing pit cover 12 inch dia as required complete in all respect. Make :-True power /Earth plus/ Ashloka as per best satisfaction of Engineer-in -charge.	1	5171	Rupees Five thousand one hundred seventy one only.	set	5171
23	Providing and fixing 6swg G.I wire on surface or in recess for loop earthing as required.	10	60	Rupees Sixty only.	meter	600
	TOTAL					64899

This work is emergent nature and required immediate execution in public interest, 9% 13.5 Certified that DWT of above work recommended for approval

Assistant Engineer
Electrical Sub Division
H.P.P.W.D Hamirpur

DWT checked and approved for Rs. 65555/- (Rs Sixty-five thousand five hundred ninety nine only)

Executive Engineer
Electrical Division
H.P.P.W.D. Una-174303