

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NO.PW- GHD-EA-I- /Tender/2026-
To

13542-44 Dated:- 16-02-2026

The Executive Engineer (IT-Cell),
Nirman Bhawan Nigam Vihar Shimla-2
Himachal Pradesh Shimla -2.
Email:-ee-pwd-hp@nic.in


SUBJECT: - Publication of Tender Notice.

Sir,

Jai Hind

Enclosed please find herewith the Tender Notice for the work as given in the Notice Inviting Tender for uploading on department website as per Notification Secretary(PW) to the GOVT of HP vide No. PBW(B)A(3)1/2024 Dated 03/01/2025 as the matter is of urgent nature and in public interest, you are requested to kindly get it published on departmental website before 16.02.2026.

DA:-As above.


Executive Engineer,
Ghumarwin, Division.
HP.PWD. Ghumarwin.
On behalf of Governor of Himachal Pradesh

Copy along with copy of e-Procurement Notice forwarded to the following for information please: -

1. The Superintending Engineer, 10th Circle, HP.PWD., Bilaspur.
2. All the Assistant Engineer, working under this Division
3. Notice Board of this office.

DA:- One No.


Executive Engineer,
Ghumarwin, Division.
HP.PWD. Ghumarwin.
On behalf of Governor of Himachal Pradesh

CHACHAL PRADESH
PUBLIC WORKS DEPARTMENT
 Mail Id- ee-ghu-hp@nic.in
 Phone No.01978-255281

***NOTICE INVITING TENDER**

Sealed percentage rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Ghumarwin Division HP.PWD. Ghumarwin on behalf of the Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **24-02-2026 up to 11.00 AM(if holiday then next working day)**. and the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender form/documents can be had from his office against cash payment (Non refundable) on 23-02-2026 up to 4.00 P.M and the application for issue of tender form shall be **received on 23-02-2026 up to 11.30 AM(if holiday then next working day)**. The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons. The offer of the tender shall be kept open for 75 days.

The draft NIT, other specifications and conditions of the tender can be seen by the contractors in the office of the undersigned on any working day during the office hours.

S. No.	Name of work	Estimated of cost	Earnest Money	Cost of form	Time limit
1.	C/o Link road to Village Makri GP Saloun (SH: Providing and laying cement concrete pavement at various damage reaches VKVNY (Deposit works).	Rs. 68992/-	Rs.1400/-	Rs.350/-	One Month
2.	Balance work for C/o link road to village Dara GP Dakri (SH: C/o Hume pipe culvert at RD 0/220 under MMGSY).	Rs. 98133/-	Rs.2000/-	Rs.350/-	One Month
3.	Balance work for construction of science Block at SVN Govt. Degree College Ghumarwin Distt Bilaspur HP	Rs.38000/-	Rs.800/-	Rs.350/-	One Month
4.	Balance work for construction of Auditorium Building at SVN Govt.Degree College Ghumarwin Distt Bilaspur	Rs.40000/-	Rs.800/-	Rs.350/-	One Month
5.	Restoration of rain damages on link road Dadhol to Jarora km 0/00 to 2/060 (SH: Repair of pot hole on various damaged reaches under PDNA year 2023	Rs.494552/-	Rs.9900/-	Rs.350/-	One Month
6.	Restoration of rain damages on Nihari to berthin road km 0/00 to 10/00 (SH: Repair of pot hole on various damaged reaches under PDNA year 2023.	Rs.465520/-	Rs.9400/-	Rs.350/-	One Month
7.	Restoration of rain damages on Badhaghat to Kassar road km 0/00 to 1/500 (SH: Removal of slip,maintenance of earthen shoulder and Repair of Pot holes at various RD's SDF/2025/410 (Deposit Work).	Rs.89820/-	Rs.1800/-	Rs.350/-	One Month
8.	A/R & M/O to HPPWD Rest House at Ghumarwin Distt.Bilaspur HP(SH: Balance work of Additional Accomdation to Rest House 1 st and 2 nd floor finishing work & one NO. Toilet for suit No. Ten.	Rs.45000/-	Rs.900/-	Rs.350/-	One Month

Certificate:- Certified that tenders are being called for due to exigencies of works (landslide and road singking etc.) in the public interest.

Terms and Conditions:-

1. The Contractor should produce a copy of enlistment/renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason.
3. The Contractor/firm must have his registration and GST No. The copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer, Ghumarwin Division , HP.PWD, Ghumarwin and cost of tender form for the above works should be submitted with the application for the purchase of tender forms. The application received without earnest money and cost of tender form shall be rejected straight way.
5. The contractor/ Firms are requested to insert the rate in percentage only both in words and in figures failing which XEN reserves the rights to accept/reject any tender without assigning any reason at any stage.

Executive Engineer,
 Ghumarwin Division,
 HP.PWD, Ghumarwin

Draft Schedule of Quantity

Estimated Cost:- Rs. 68,992.00

Earnest Money:- Rs. 1,400.00

Time :- One month

Name of Work:- Construction of link road to village Makri G.P. Saloun (SH:- Providing and laying cement concrete pavement at various damage reaches).(VKVNY Deposit work).

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 150 mm (One Hundred fifty millimetre) spread thickness (finished work including materials and labour) as per direction of Engineer-In-Charge including carriage of material with in all leads and lifts and other incidentals as directed by the Engineer-In-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	9.24	Per cubic metre	1550.00	Rupees One Thousand Five Hundred Fifty Only	14322.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level. 1:1.5:3 (One cement is to one point five coarse sand is to three crushed graded stone aggregate 20 mm (twenty millimetre) nominal size as per direction of Engineer-In-Charge including carriage of material with in all leads and lifts and other incidentals as directed by the Engineer-In-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.70	Per cubic metre	7100.00	Rupees Seven Thousand One Hundred Only	54670.00
Total						68992

Draft Schedule of Quantity at Sr. No 445 for
the year 2025-26 approved for Rs 68,992/- only

Executive Engineer,
Ghumarwin Division,
H.P. PWD, Ghumarwin.

Draft Schedule of Quantity

Estimated Cost:- Rs. 98,133.00

Earnest Money:- Rs. 2,000.00

Time :- One Month

Name of Work:- Balance work for Construction of link road to village Dara G.P. Dakri (SH:- C/o Hume Pipe Culvert at RD 0/220).(Under MMGSY).

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas upto a all depth and width including getting out and disposal of excavated earth upto a all lead and lift as directed by Engineer-in-charge. in Ordinary rock as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other constrction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	28.64	Per cubic metre	250.00	Rupees Two Hundred Fifty Only	7160.00
2	Providing and Laying cement concrete 1:5:10 nominal mix (One Cement is to five Sand is to Ten graded crushed stone aggregate) 40mm (forty millimetre) nominal size with minimum cement contents 130 kg (One hundred thirty kilogram) per cubic metre and curring complete including cost of form work for plain /reinforce concrete in retaining walls, breast wall as per drawing and MORD tecnical specification 2014 Clause 800 and 1200 including carriage of material with in all leads and lifts ,shoring and shuttering and curring complete including pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering and carriage of machinery, material ,tools equipment safety measures and other incidentals as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other constrction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.19	Per cubic metre	4500.00	Rupees Four Thousand Five Hundred Only	27855.00
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level : (C.C. 1:3:6)(One cement is to three Coarse sand is to six graded stone aggregate) 20 mm (twenty millimeter) nominal size.The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other constrction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8.17	Per cubic metre	5400.00	Rupees Five Thousand Four Hundred Only	44118
4	Providing and laying reinforced cement concrete hume pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (One Cement: two Sand) but excluding cost of excavation, protection work, back filling ,concrete and masonary work in head walls and parapet as per MORD Technical Specification 2014 Clause 1108. 900mm dia (Nine hundred millimetre) dia including entire carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-charge. The rate includes octroi, royalty, Malkana toll tax, Goods Service Tax, building and other constrction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.00	Per running metre	3800.00	Rupees Three Thousand Eight Hundred Only	19000
Total						98133

Draft Schedule of Quantity at sn no 434 for the year 2025-26 approved for Rs 98133/- only

Executive Engineer,
Ghumarwin Division,
J.P. PWD, Ghumarwin.

Draft Schedule of Quantity

Draft Schedule of Quantity						
Name of Work:- Balance work for constuction of Science Block at SVN Govt. Degree College Ghumarwin. Distt. Bilaspur.		Estimated Cost:- Rs.		38,000.00		
		Earnest Money:- Rs.		800.00		
		Time :-		One Month		
Sr. No.	Description Item	Quantity	Unit	Rates		Amount
1	Preparation and Supplying working estimate as per Drawings. issued by Architect on detailed Analysis of Rate based on H.P.S.R 2020 with latest market rates and as per guidelines issued by HP.PWD and CPWD in duplicates and also got it approved from competent authority complete in all respect and entire satisfaction of Engineer in Charge.The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	Job	In figure 38000.00	In words Rupees Thirty Eight Thousand Only	38000
Total:-						38,000.00

Draft Schedule of Quantity No. 305 for
the year 2025-26 approved for Rs. 38,000/- only

Executive Engineer,
Ghumarwin Division,
HP, PWD, Ghumarwin,


Draft Schedule of Quantity

Draft Schedule of Quantity				Estimated Cost:- Rs. 40,000.00		
				Earnest Money:- Rs. 800.00		
				Time :- One Month		
Name of Work:- Balance work for constuction of Auditorium Building at SVN Govt. Degree Colleg Ghumarwin. Distt. Bilaspur.						
Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Preparation and Supplying working estimate as per Drawings. Issued by Architect on detailed Analysis of Rate based on H.P.S.R 2020 with latest market rates and as per guidelines issued by HP.PWD and CPWD in duplicates and also got it approved from competent authority complete in all respect and entire satisfaction of Engineer in Charge. The rate includes; octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	Job	40000.00	Rupees Forty Thousand Only	40000
Total:-						40,000.00

Draft Schedule of Quantity No. 306 for the year 2025-26 approved for Rs. 40,000/- only.

Executive Engineer,
Ghumarwin Division,
J.P. PWD, Ghumarwin.



Draft Schedule of Quantity

Estimated Cost:- Rs.	4,94,552.00
Earnest Money:- Rs.	9,900.00
Time :-	One Month

Item of Work:- Restoration of rain damages on link road Dadhol to Jarora km 0/00 to 2/060 (SH:- Repair of Pot hole on various damaged reaches) under PDNA Year 2023).

Description Item	Quantity	Unit	Rates		Amount
			In figure	In words	
1. Providing and applying tack coat with bitumen emulsion(RS-1) using emulsion distributor at the rate of 0.25 to 0.30 kg (Zero point two five to zero point three zero kilogram) per Square metre as per table 500.2 of MORD technical specification 2014, on the prepared bituminous surface cleaned with hydraulic broom as per technical specification clause 503. of MORD technical specification 2014, as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1247.63	Per square metre	20.00	Rupees Twenty Only	24953
2. Providing and laying bituminous macadam for correction layer and pot hole with hot mix plant using crushed aggregates of grading as per Table 500.4 premixed with bituminous binder, transported to site upto all lead laid over a previously prepared surface with paver finisher to the required grade, level and alignment and rolled to achieve the desired compaction as per Technical Specification MORD 2014 Clause 504 with 100-120 TPH batch type hot mix plant producing an average output of 75 tonnes (seventy five tonnes) per hour using crushed aggregates of specified grading, premixed with bituminous binder @ minimum 3.3 (three Point Three) per cent VG-30 (Viscosity grade thirty) of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per IRC-29-1988 complete in all respects as per direction of Engineer-In-Charge including carriage of material with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.67	Per Cubic metre	9000.00	Rupees Nine Thousand Only	51030
3. Providing and laying 30 mm (thirty millimetre) thick bituminous concrete with 100-120 (one hundred into one hundred twenty) TPH batch type hot mix plant producing an average output of 75 tonnes (seventy five tonnes) per hour using crushed aggregates of specified grading, premixed with bituminous binder @ minimum 5.4 to 5.6 (five point four to five point six) per cent VG-30 (Viscosity grade thirty) of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per IRC-29-1988 complete in all respects as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	34.03	Per Cubic metre	12300.00	Rupees Twelve Thousand Three Hundred Only	418569
Total :-					494552

Draft Schedule of Quantity No 547 for
the year 2025-26 approved for Rs 4,94,552/- only
Four lakh Ninety four Thousand five hundred fifty Two only

Executive Engineer,
Ghumarwin Division,
MP PWD, Ghumarwin.

Draft Schedule of Quantity

Estimated Cost:- Rs. 4,65,520.00

Earnest Money:- Rs. 9,400.00

Time :- One Month

Name of Work:- Restoration of rain damages on Nihari to Berthin road km 0/00 to 10/00 (SH:- Repair of Pot hole on various damaged reaches) (Under PDNA Year 2023).

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Providing and applying tack coat with bitumen emulsion(RS-1) using emulsion distributor at the rate of 0.25 to 0.30 kg (Zero point two five to zero point three zero kilogram) per Square metre as per table 500.2 of MORD technical specification 2014, on the prepared bitumenious surface cleaned with hydraulic broom as per technical specification clause 503. of MORD technical specification 2014, as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other constrction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1174.57	Per square metre	20.00	Rupees Twenty Only	23491
2	Providing and laying bituminous macadam for correction layer and pot hole with hot mix plant using crushed aggregates of grading as per Table 500.4 premixed with bituminous binder, transported to site upto all lead laid over a previously prepared surface with paver finisher to the required grade, level and alignment and rolled to achieve the desired compaction as per Technical Specification MORD 2014 Clause 504 with 100-120 TPH batch type hot mix plant producing an average output of 75 tonnes (seventy five tonnes) per hour using crushed aggregates of specified grading, premixed with bituminous binder @ minimum 3.3 (three Point Three) per cent VG-30 (Viscosity grade thirty) of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per IRC-29-1988 complete in all respects as per direction of Engineer-In-Charge including carriage of material with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.34	Per Cubic metre	9000.00	Rupees Nine Thousand Only	48060
3	Providing and laying 30 mm (thirty millimetre) thick bituminous concrete with 100-120 (one hundred into one hundred twenty) TPH batch type hot mix plant producing an average output of 75 tonnes (seventy five tonnes) per hour using crushed aggregates of specified grading, premixed with bituminous binder @ minimum 5.4 to 5.6 (five point four to five point six) per cent VG-30 (Viscosity grade thirty) of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per IRC-29-1988 complete in all respects as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other constrction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	32.03	Per Cubic metre	12300.00	Rupees Twelve Thousand Three Hundred Only	393969
Total :-						465520

Draft Schedule of Quantity at sr. no. 448 for the year 2025-26 approved for Rs 4,65,520/- only

Executive Engineer,
Ghumarwin Division,
HP, PWD, Ghumarwin.

Draft Schedule of Quantity

				Estimated Cost:- Rs.	89,820.00
				Earnest Money:- Rs.	1,800.00
				Time :-	One Month
Name of Work:- Restoration of rain damages on Badhaghat to Kassaru road Km 0/00 to 1/500 (SH:- Removal of slip, Maintenance of earthen shoulder & Repair of Pot holes at various RD's) (Mohal:- Badhaghat to Kassaru). (SDE/2025/410 Deposit work).					
Sr. No.	Description Item	Quantity	Unit	Rates	Amount
				In figure In words	
1	Providing and applying tack coat with bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.25 to 0.30 kg (Zero point two five to zero point three zero kilogram) per Square metre as per table 500.2 of MORD technical specification 2014, on the prepared bituminous surface cleaned with hydraulic broom as per technical specification clause 503. of MORD technical specification 2014, as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	226.78	Per square metre	20.00 Rupees Twenty Only	4536
2	Providing and laying bituminous macadam for correction layer and pot hole with hot mix plant using crushed aggregates of grading as per Table 500.4 premixed with bituminous binder, transported to site upto all lead laid over a previously prepared surface with paver finisher to the required grade, level and alignment and rolled to achieve the desired compaction as per Technical Specification MORD 2014 Clause 504 with 100-120 TPH batch type hot mix plant producing an average output of 75 tonnes (seventy five tonnes) per hour using crushed aggregates of specified grading, premixed with bituminous binder @ minimum 3.3 (three Point Three) per cent VG-30 (Viscosity grade thirty) of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per IRC-29-1988 complete in all respects as per direction of Engineer-In-Charge including carriage of material with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.03	Per Cubic metre	9000.00 Rupees Nine Thousand Only	9270
3	Providing and laying 30 mm (thirty millimetre) thick bituminous concrete with 100-120 TPH batch type hot mix plant producing an average output of 75 tonnes (seventy five tonnes) per hour using crushed aggregates of specified grading, premixed with bituminous binder @ minimum 5.4 to 5.6 (five point four to five point six) per cent VG-30 (Viscosity grade thirty) of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per IRC-29-1988 complete in all respects as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.18	Per Cubic metre	12300.00 Rupees Twelve Thousand Three Hundred Only	76014
Total					89820

Draft Schedule of Quantity at Sr. No 408 for
the year 2025-26 approved for Rs 89820/- only

Executive Engineer,
Ghumarwin Division,
J.P.W.D., Ghumarwin.

[Signature]

Draft Schedule of Quantity

Work:- A/R & M/O to HPPWD Rest House at Ghumanwin Distt. Bilaspur HP (SH:- Balance work of Additional Accommodation to Rest House 1st and finishing Work & One No. Toilet for Suit No. Ten).

Description Item	Quantity	Unit	Rates		Amount
			In figure	In words	
Reparation and Supplying working estimate as per Drawings. Issued by Architect on detailed Analysis of Rate as per guidelines issued by HP.PWD and CPWD in duplicates on H.P.S.R 2020 with latest market rates and as per guidelines issued by HP.PWD and CPWD in duplicates also got it approved from competent authority complete in all respect and entire satisfaction of Engineer in Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	Job	45000.00	Rupees Forty Five Thousand Only	45000
Total:-					45,000.00

Draft Schedule of Quantity No. 307 - for the year 2025-26 approved for Rs. 45,000/- only.

Executive Engineer,
Ghumanwin Division,
HP, PWD, Ghumanwin.