

Office of the Executive Engineer, HPPWD., Division Kangra
Himachal Pradesh Public works Department Kangra-176001
Phone No. & Fax No. 01892.265028 e-mail:- ee-kun-hp@nic.in

NOTICE INVITING TENDER


Sealed percentage rate tenders on form 6 & 8 are invited by the Executive Engineer, Division, HP; PWD, Kangra on behalf of the Governor of Himachal Pradesh for the following work from the approved and eligible contractors/firms enlisted in HPPWD in the appropriate class for the work mentioned below on **24.02.2026 up to 11-00 A.M.** and will be opened on the same day at **11-30 A.M.** in the presence of intending contractors or their authorized representatives who may wish to be present. The tender forms can be obtained from this office on cash payment (non refundable) on **23.02.2026 up to 4.30 P.M.** The tender applications for issue of tender forms will be received in this office on **23.02.2026 up to 11.30 A.M.** The earnest money in shape FDR National Saving certificate/Saving Account/Time Deposit Account in any of the Post Office/National Bank in H.P. duly pledged in favour of Executive Engineer, HPPWD., Division, Kangra. The conditional tenders and the tenders received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 75 days.

Sr. No.	Name of work	Estimated cost	Earnest Money	Cost of tender form	Time Limit
1.	C/O approach road to Degree College Matour km. 0/00 to 0/270(SH- C/O 900MM & 300 MM Dia Hume Pipe Culvert at RD 0/195 and 0/255 Respectively)(Deposit work)	99858/-	2000/-	350/-	Two Month
2.	C/O approach road to Degree College Matour km. 0/00 to 0/270(SH- C/O 1000MM ,900MM Dia Hume Pipe Culvert at RD 0/045 and 0/075)(Deposit work)	96540/-	2000/-	350/-	Two Month

Certified that tender of above works are being called of urgent nature in public interest.

TERMS & CONDITIONS:-

1. The contractors/firms should be produce the attested copy of latest enlistment and renewal enlisted in HPPWD, GST No. and EPF No. with the application failing which their application will not be entertained.
2. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
3. The Earnest Money for the above works should be required at the time of sale of tender forms.
4. The contractor/firms should be quoted percentage rate in the tender both in figures and in words failing which tender is likely to be rejected.
5. The Executive Engineer reserves the right to accept/reject any tender/application or all tenders without assigning any reason


Executive Engineer,
HPPWD, Division, Kangra,
Distt. Kangra (H.P.)

(On behalf of Governor of Himachal Pradesh)

Endst:- No.PW/KD/CB/Tenders/2025-26-
Copy is forwarded to:-

7598-7620

Date:- 16/2/26

1. The Computer Cell Office of the Engineer-in-Chief, HPPWD., Shimla for uploading the NIT on the Department website.
2. The Chief Engineer (KZ) HPPWD., Dharamshala for information please.
3. The Superintending Engineer, 5th Circle, HPPWD., Palampur for information please.
4. All the Assistant Engineer's working under Kangra Division.
5. NIT Register.
6. All Head of Branches.
7. Notice Board.


Executive Engineer,
HPPWD, Division, Kangra,
Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

NAME OF WORK :- CONSTRUCTION OF APPROACH ROAD TO DEGREE COLLEGE MATOUR KM. 0.06 TO 0.270					Estimated Cost :-	96540.00
(SH)- CONSTRUCTION OF 1000MM, 900 MM DIA HUME PIPE CULVERT AT RD. 0.045 AND 0.075) (DEPOSIT WORK)					Earnest Money:-	2000.-
					Time Limit:-	Two Months
					AMOUNT	
Description of work					Rate	
					In Figures	In Words
					Qty	Unit
Excavation of foundations, arches etc. in earth work in all kind of specification of soil such as pick work, jumper work, pick jumper work, blasting work, soft and hard blasting and doing work in saturated soil, including chiselling or wedging out rocks where blasting work is prohibited or any other mixed variety of soil including shoring, strutting, de-watering and pumping or bailing out water (surface and sub soil water) upto any depths any quantum of water including slush which may arise during de-watering or removal of slush, lift upto any height stacking the excavated soil not more than 3 metres (Three metres) clear from the edge of excavation and then returning the stacked soil in 15cm (Fifteen centimetre) layers, when required into plinths, sides of foundation etc. extra consolidating each deposited layer by ramming, watering and then disposing of all surplus excavated earth as per specification, approved drawing design as per the entire satisfaction and direction of the Engineer-in-Charge including carriage of material within leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkhana, toll tax, GST or any other taxes imposed by the Government.					6.75	Per Cubic metres
Providing & laying mechanically mixed and vibrated for plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-Ten) nominal mix 1:3:6 (one cement: three sand: six graded crushed stone aggregate) 40mm (forty millimetre) nominal size with minimum cement contents 220 kg/cum (two hundred twenty kilogram per cubic metre) in or under water and during complete including pumping or bailing out water, de-watering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including the cost of form work as per drawings and MORD technical specifications section 800, 900, and 1200 as per the direction of the Engineer-in-Charge including carriage of material with in all leads, lifts and other incidentals. The rate including of octroi, royalty, Malkhana, toll tax, GST or other taxes imposed by the government.					2.54	Per Cubic metres
					5714.60	Rupees Five Thousand Seven Hundred & Fourteen - Paise Sixty Only
					14515.00	

3	Providing and laying cement concrete for plain/ reinforced concrete work of grade M-15 in sub structure complete as per drawing and technical specification clauses 802.803, 1202, 1205 PCC in 1:2.5:5 (one cement : two part five sand : five graded crushed stone aggregate) 20 mm (twenty millimetre) nominal size with minimum cement contents 275 kg/cum (two hundred seventy five kilogram per cubic metre) and as per the direction of Engineer-in-charge including carriage of material with in all loads and lifts and other incidental. The rate including of octroi, maffiana, toll tax, sale tax or other taxes imposed by the government.	5.51	Per Cubic metres	6010.00	Rupees Six Thousand & Ten Only	33115.00
4	Providing and laying (to level or slope) 1000 mm dia (Ten Hundred millimetre) diameter reinforced cement concrete non pressure pipes IS Class NP-3 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (One cement to Two Sand) but excluding the cost of excavation, protection works, back filling, concrete and masonry work in head walls and parapets as per drawing and MORD technical specifications clause 1101 and as per direction of Engineer-in-Charge including carriage of material within all loads and lifts and other incidental. The rate is including octroi, royalty, Maffiana, toll tax, sale tax GST or any other taxes imposed by the Government.	5.00	Per Running metres	9121.00	Rupees Nine Thousand One Hundred & Twenty One - Paise Sixty Only	45608.00
Total:						96540.00

EXCESS = %

LESS = %


Executive Engineer,
HPPWD Kangra
Division Kangra

SCHEDULE OF QUANTITY

NAME OF WORK :- CONSTRUCTION OF APPROACH ROAD TO DEGREE COLLEGE MATOUR KM. 0/00 TO 0/270 (SH:- CONSTRUCTION OF 900MM. & 300 MM DIA HUME PIPE CULVERT AT RD. 0/195 AND 0/255 RESPECTIVELY) (DEPOSIT WORK)						
Sr. No	Description of work	Qty	Unit	Rates		Amount
				In Figures	In Words	
1	Excavation in foundation, trenches etcetra in earth work in all kind of classification of soil such as pick work, jumper work, pick jumper work, blasting work, soft and hard blasting and doing work in saturated soil, including chiselling or wedging out rocks where blasting work is prohibited or any other mixed variety of soil including shoring, strutting, de-watering and pumping or bailing out water (surface and sub soil water) upto any depths any quantum of water including slush which may arise during de-watering or removal of slush, lift upto any height sticking the excavated soil not more than 3 metres (Three metres) clear from the edge of excavation and then returning the stacked soil in 15cm (Fifteen centimetre) layers, when required into plinths, sides of foundation etcetra consolidating each deposited layer by ramming, watering and then disposing of all surplus excavated earth as per specification, approved drawing design as per the entire satisfaction and direction of the Engineer-in-Charge including carriage of material within leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikana, toll tax, GST or any other taxes imposed by the Government.	23.04	Per Cubic metres	489.20	Rupees Four Hundred & Eighty Nine - Paise Twenty Only	11271.00
2	Providing & laying mechanically mixed and vibrated for plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-Ten) nominal mix 1:3:6 (one cement: three sand: six graded crushed stone aggregate) 40mm(forty millimetre) nominal size with minimum cement contents 220 kg/cum (two hundred twenty kilogram per cubic metre) in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including the cost of form work as per drawings and MORE technical specifications section 800, 900, and 1200 as per the direction of the Engineer -in-Charge including carriage of material with in all leads, lifts and other incidentals. The rate including of octroi, royalty, Malikhana, toll tax, GST or other taxes imposed by the government.	3.62	Per Cubic metres	5714.60	Rupees Five Thousand Seven Hundred & Fourteen - Paise Sixty Only	20687.00

3	Providing and Laying cement concrete for plain/ reinforced concrete work of grade M-15 in sub structure complete as per drawing and technical specification clauses 802,803,1202,1203 PCC in 1:2.5:5(one cement : two point five sand : five graded crushed stone aggregate 120 mm (twenty millimetre) nominal size with minimum cement contents 275 kg/cum (two hundred seventy five kilogram per cubic metre)and as per the direction of Engineer- in -charge including carriage of material with in all leads and lifts and other incidentals. The rate including of octroi, malkhana, tolltax, sale Tax or other taxes imposed by the government.	4.99	Per Cubic metres	6010.00	Rupees Six Thousand & Ten Only	29990.00
4	Providing and laying (to level or slope) 900 mm dia (Nine Hundred millimetre) diameter reinforced cement concrete non pressure pipes IS Class NP-3 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (One cement isto Two Sand) but excluding the cost of excavation, protection works, back filling, concrete and masonry work in head walls and parapets as per drawing and MORD technical specifications clause 1108 and as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	2.50	Per Running metres	6559.00	Rupees Six Thousand Five Hundred & Fifty Nine Only	16398.00
5	Providing and laying (to level or slope) 300 mm dia (ThreeHundred millimetre) diameter reinforced cement concrete non pressure pipes IS Class NP-3 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (One cement isto Two Sand) but excluding the cost of excavation, protection works, back filling, concrete and masonry work in head walls and parapets as per drawing and MORD technical specifications clause 1108 and as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	15.00	Per Running metres	1434.10	Rupees One Thousand Four Hundred & Thirty Four - Paise Ten Only	21512.00
Total:						99858.00

EXCESS = %

LESS = %


HPPWD Kangra
Division Kangra.
HPPWD Kangra