

OFFICE OF
EXECUTIVE ENGINEER, SALOONI DIVISION HPPWD SALOONI
HIMACHAL PRADESH, PUBLIC WORKS DEPARTMENT SALOONI
Phone No. 01899-233287 Email: ee-slo-hp@nic.in
NOTING INVITING TENDER

Sealed item rate tender on form 6&8 are hereby invited by the Executive Engineer, Salooni Division HPPWD Salooni on behalf of the Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HPPWD. So as to reach in his office on or before **25.02.2026 to 11:00 AM** and the same shall be opened on the same day at **11:30 AM**, in the presence of the intending Contractor or their authorized representatives if any. The tender form can be obtained from his office on cash payment (Non refundable) on **24.02.2026 upto 03.00 PM** and the application for issue of tender form shall be received on **24.02.2026 upto 04.00 P.M.** The earnest money in the form of FDR from nationalized bank in HP duly pledged in favour of the Executive Engineer, Salooni Division HPPWD Salooni must be accompanied with each tender. The tender form will be issued to contractor who giving proof of enlistment, GST, Conditional tenders and the tenders received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer, reserves the right to reject the tender without assigning any reason. Special care should be taken to write the rates both in figure and in words.

Sr. No.	Name of work	Estimated Cost	Earnest money	Cost of form	Time limit	Eligible Class
1.	Restoration of rain damages on Kund Siula road K.M. 0/0 to 6/255 (SH: Removal of snow/slips at various RD's)	96,820/-	2000/-	350/-	90 Days	D & C
2.	Restoration of rain damages on Lachori to Seri road K.M. 0/0 to 8/500 (SH: Construction of wire crate Retaining wall at R.D. 2/865 to 2/872.50)	98,023/-	2000/-	350/-	90 Days	D & C
3.	Restoration of rain damages on Sundla to Girjindoo road K.M. 0/0 to 36/500 (SH: Removal of slips between K.M. 18/0 to 27/0)	99,910/-	2000/-	350/-	90 Days	D & C
4.	Restoration of rain damages on Bihali Bachuni Chamber Katara road K.M. 0/0 to 11/100 (SH: Removal of slips at R.D. 2/120 to 2/150, 4/500 to 4/530 and 6/795 to 6/835)	99,889/-	2000/-	350/-	90 Days	D & C
5.	Restoration of rain damages on Bhadela Andwas road K.M. 0/0 to 6/300 (SH: Removal of snow/slips at various RD's)	97,850/-	2000/-	350/-	90 Days	D & C
6.	Restoration of rain damages on Bathri Sundla Langer J&K Boundary road K.M. 13/130 to 28/0 (SH: Construction of PCC Retaining wall at R.D. 18/897.33 to 18/899.82)	99,234/-	2000/-	350/-	90 Days	D & C
7.	Restoration of rain damages on Bihali Bachuni Chamber Katara road K.M. 0/0 to 11/100 (SH: Removal of slips at R.D. 0/350 to 0/380, 3/620 to 3/650 and 9/0 to 9/040)	99,833/-	2000/-	350/-	90 Days	D & C
8.	Restoration of rain damages on Sundla to Girjindoo road K.M. 0/0 to 36/500 (SH: Construction of wire crate Retaining walls at R.D. 26/550 to 26/560)	93,360/-	2000/-	350/-	90 Days	D & C
9.	Restoration of rain damages on Bathri Sundla Langer J & Boundary road K.M. 28/0 to 93/400 (SH: Removal of snow/slips at K.M. 57/0 to 80/0)	99,910/-	2000/-	350/-	90 Days	D & C
10.	Restoration of rain damages on link road to village Ranjni K.M. 0/0 to 1/0 (SH: Construction of crate work Retaining wall at R.D. 0/710 to 0/720)	93,721/-	2000/-	350/-	90 Days	D & C
11.	Restoration of rain damages on Sundla to Girjindoo road K.M. 0/0 to 36/500 (SH: Removal of slips between K.M. 27/0 to 36/500)	98,880/-	2000/-	350/-	90 Days	D & C


12.	Restoration of rain damages on link road Pukhri to Bhatoli K.M. 0/0 to 3/090 (SH: Removal of slips at R.D. 0/550 to 0/600, 1/300 to 1/340 and 1/920 to 1/950)	99,878/-	2000/-	350/-	90 Days	D & C
13.	Restoration of rain damages on Hutta Ligga Ladwah road K.M. 0/0 to 7/040 (SH: Removal of slips between K.M. 0/0 to 7/040)	99,910/-	2000/-	350/-	90 Days	D & C
14.	Restoration of rain damages on Bathri Sundla Langer J & Boundary road K.M. 13/130 to 28/0 (SH: Removal of slips at R.D. 26/700 to 26/730, 27/580 to 27/610, 27/760 to 27/810 and 27/850 to 27/900)	99,619/-	2000/-	350/-	90 Days	D & C
15.	Restoration of rain damages on Kainthly Bhidro road K.M. 0/0 to 6/700 (SH: Removal of snow/slips at various RD's)	97,850/-	2000/-	350/-	90 Days	D & C
16.	Restoration of rain damages on Bathri Sundla Langer J & K Boundary road K.M. 28/0 to 93/400 (SH: Construction of crate work Breast wall at R.D. 82/460 to 82/470)	95,536/-	2000/-	350/-	90 Days	D & C
17.	Restoration of rain damages on Maira Jakhral road K.M. 0/0 to 11/900 (SH: Removal of snow/slips at various RD's)	98,161/-	2000/-	350/-	90 Days	D & C
18.	Restoration of rain damages on Bathri Sundla Langer J & Boundary road K.M. 28/0 to 93/400 (SH: Removal of snow/slips at various RD,s)	97,983/-	2000/-	350/-	90 Days	D & C
19.	Restoration of rain damages on Bhalei Matta Temple to village Athed road K.M. 0/0 to 6/0 (SH: Construction of PCC Retaining wall at R.D. 2/341.25 to 2/345)	97,615/-	2000/-	350/-	90 Days	D & C
20.	Restoration of rain damages on Bathri Sundla Langer J & Boundary road K.M. 28/0 to 93/400 (SH: Removal of snow/slips at K.M. 80/0 to 93/400)	98,880/-	2000/-	350/-	90 Days	D & C
21.	Restoration of rain damages on Lachori to Seri road K.M. 0/0 to 8/500 (SH: Construction of wire crate Retaining wall at R.D. 2/850 to 2/857.50)	99,208/-	2000/-	350/-	90 Days	D & C
22.	Restoration of rain damages on Bathri Sundla Langer J & Boundary road K.M. 28/0 to 93/400 (SH: Removal of snow/slips at various RD,s)	99,205/-	2000/-	350/-	90 Days	D & C
23.	Restoration of rain damages on link road to village Dind K.M. 0/0 to 3/830 (SH: Removal of slips at R.D. 0/750 to 0/780, 1/030 to 1/060, 1/780 to 1/810 and 2/300 to 2/320)	99,799/-	2000/-	350/-	90 Days	D & C
24.	Restoration of rain damages on Ani near Salooni (Portion Drekri to Sarar) road K.M. 0/0 to 4/900 (SH: Removal of slips between K.M. 0/0 to 4/900)	98,880/-	2000/-	350/-	90 Days	D & C
25.	Restoration of rain damages on Bathri Sundla Langer J&K Boundary road K.M. 13/130 to 28/0 (SH: Construction of PCC Retaining wall at R.D. 18/892.40 to 18/894.90)	99,910/-	2000/-	350/-	90 Days	D & C
26.	Restoration of rain damages on Salooni Ghal road K.M. 0/0 to 7/500 (SH: Removal of snow/slips at various RD's)	99,910/-	2000/-	350/-	90 Days	D & C
27.	Restoration of rain damages on Bathri Sundla Langer J & K Boundary road K.M. 13/130 to 28/0 (SH: Construction of wire crate Breast wall at R.D. 21/940 to 21/950 i.e. 1 st Raw 1No. crate & 2 nd Raw)	94,574/-	2000/-	350/-	90 Days	D & C
28.	Restoration of rain damages on Kandhwara Bhadela road K.M. 0/0 to 4/100 (SH: Removal of snow/slips at various RD's)	98,880/-	2000/-	350/-	90 Days	D & C

29.	Restoration of rain damages on Lachori to Seri road K.M. 0/0 to 8/500 (SH: Construction of PCC Retaining wall at R.D. 7/415 to 7/418.75)	98,276/-	2000/-	350/-	90 Days	D & C
30.	Restoration of rain damages on Bathri Sundla Langera J & Boundary road K.M. 28/0 to 93/400 (SH: Removal of snow/slips at various RD,s)	99,830/-	2000/-	350/-	90 Days	D & C
31.	Restoration of rain damages on Maira Jakhral road K.M. 0/0 to 11/900 (SH: Removal of snow/slips at various RD's)	96,820/-	2000/-	350/-	90 Days	D & C
32.	Restoration of rain damages on Bathri Sundla Langera J & Boundary road K.M. 28/0 to 93/400 (SH: Removal of snow/slips at various RD,s)	99,988/-	2000/-	350/-	90 Days	D & C
33.	Restoration of rain damages on Bhalei Matta Temple to village Athed road K.M. 0/0 to 6/0 (SH: Construction of PCC Retaining wall at R.D. 2/333.75 to 2/337.50)	97,737/-	2000/-	350/-	90 Days	D & C
34.	Restoration of rain damages on Bathri Sundla Langera J & Boundary road K.M. 28/0 to 93/400 (SH: Removal of snow/slips at various RD,s)	99,363/-	2000/-	350/-	90 Days	D & C
35.	Restoration of rain damages on Bhalei Matta Temple to village Athed road K.M. 0/0 to 6/0 (SH: Construction of 600mm dia hume pipe culvert at R.D. 1/465)	99,614/-	2000/-	350/-	90 Days	D & C
36.	Restoration of rain damages on Bathri Sundla Langera J & Boundary road K.M. 28/0 to 93/400 (SH: Removal of snow/slips at various RD,s)	97,358/-	2000/-	350/-	90 Days	D & C
37.	Restoration of rain damages on Chowga to Khal road K.M. 0/0 to 13/705 (SH: Removal of slips at R.D. 3/300 to 3/350, 5/650 to 5/680, 7/450 to 7/480 and 7/840 to 7/860)	99,810/-	2000/-	350/-	90 Days	D & C
38.	Restoration of rain damages on Bindhokhi to Khundi Baag road K.M. 0/0 to 3/700 (SH: Construction of wire crate Breast wall at R.D. 1/625 to 1/635)	90,377/-	2000/-	350/-	90 Days	D & C
39.	Restoration of rain damages on Sundla to Girjindoo road K.M. 0/0 to 36/500 (SH: Removal of slips between K.M. 27/0 to 36/500)	98,880/-	2000/-	350/-	90 Days	D & C
40.	Restoration of rain damages on Bathri Sundla Langera J & K boundary road K.M. 13/130 to 28/0 (SH: Removal of slips at R.D. 14/720 to 14/750, 17/740 to 17/760, 20/860 to 20/900 and 21/620 to 21/640)	99,675/-	2000/-	350/-	90 Days	D & C
41.	Restoration of rain damages on Lachori to Seri road K.M. 0/0 to 8/500 (SH: Removal of slips at R.D. 0/900 to 0/940, 3/120 to 3/170 and 5/680 to 5/720)	99,788/-	2000/-	350/-	90 Days	D & C
42.	Restoration of rain damages on Chhudra to Tuhien road K.M. 0/0 to 2/225 (SH: Removal of slips between K.M. 0/0 to 2/225)	97,850/-	2000/-	350/-	90 Days	D & C
43.	Restoration of rain damages on Bassa to Chhudra road K.M. 0/0 to 3/0 (SH: Removal of slips at R.D. 0/860 to 0/900, 1/220 to 1/260 and 2/600 to 2/630)	99,731/-	2000/-	350/-	90 Days	D & C
44.	Restoration of rain damages on Bathri Sundla Langera J & Boundary road K.M. 28/0 to 93/400 (SH: Removal of snow/slips at various RD,s)	99,826/-	2000/-	350/-	90 Days	D & C
45.	Restoration of rain damages on Kandi to Athed road K.M. 0/0 to 12/0 (SH: Removal of slips at R.D. 5/180 to 5/230, 7/120 to 7/140, 7/330 to 7/360 and 9/630 to 9/650)	99,675/-	2000/-	350/-	90 Days	D & C

46.	Restoration of rain damages on Sundla to Girjindoo road K.M. 0/0 to 36/500 (SH: Construction of wire crate Retaining walls at R.D. 26/540 to 26/550)	93,727/-	2000/-	350/-	90 Days	D & C
47.	Restoration of rain damages on Bathri Sundla Langer J & Boundary road K.M. 28/0 to 93/400 (SH: Removal of snow/slips at various RD,s)	99,880/-	2000/-	350/-	90 Days	D & C
48.	Restoration of rain damages on Bindhokhi to Khundi Baag road K.M. 0/0 to 3/700 (SH: Construction of wire crate Retaining wall at R.D. 1/570 to 1/590)	93,221/-	2000/-	350/-	90 Days	D & C
49.	Restoration of rain damages on Sundla to Girjindoo road K.M. 0/0 to 36/500 (SH: Removal of slips between K.M. 18/0 to 27/0)	99,910/-	2000/-	350/-	90 Days	D & C
50.	Restoration of rain damages on Kandi to Athed road K.M. 0/0 to 12/0 (SH: Removal of slips at R.D. 1/580 to 1/620, 2/200 to 2/240 and 5/180 to 5/210)	99,867/-	2000/-	350/-	90 Days	D & C
51.	Restoration of rain damages on Bathri Sundla Langer J & Boundary road K.M. 13/130 to 28/0 (SH: Removal of slips at R.D. 17/170 to 17/210, 23/960 to 24/0, and 27/265 to 27/300)	99,765/-	2000/-	350/-	90 Days	D & C
52.	Restoration of rain damages on Maira Jakhral road K.M. 0/0 to 11/900 (SH: Removal of snow/slips at various RD's)	98,897/-	2000/-	350/-	90 Days	D & C
53.	Improvement of Black spot on link road Bhalei Matta temple to village Saphan K.M. 0/0 to 4/825 (SH: Improvement of curve at R.D. 3/015 to 3/073)	99,808/-	2000/-	350/-	90 Days	D & C
54.	Restoration of rain damages on Bassa to Chhudra road K.M. 0/0 to 3/0 (SH: Removal of slips between K.M. 0/0 to 3/0)	98,880/-	2000/-	350/-	90 Days	D & C
55.	Restoration of rain damages on Kandi to Athed road K.M. 0/0 to 12/0 (SH: Removal of slips at R.D. 0/880 to 0/920, 1/240 to 1/280 and 1/425 to 1/455)	99,563/-	2000/-	350/-	90 Days	D & C
56.	Improvement of Black spot on link road Bhalei Matta temple to village Saphan K.M. 0/0 to 4/825 (SH: Improvement of curve at R.D. 2/970 to 3/015)	99,734/-	2000/-	350/-	90 Days	D & C
57.	Restoration of rain damages on Bathri Sundla Langer J & Boundary road to village Lamni K.M. 0/0 to 2/500 (SH: Removal of slips at R.D. 0/030 to 0/060, 0/110 to 0/140, 1/650 to 1/680 and 1/800 to 1/820)	99,360/-	2000/-	350/-	90 Days	D & C
58.	Restoration of rain damages on link road Surella to Pukhi Part-2 K.M. 0/0 to 0/480 (SH: Removal of slips at R.D. 0/170 to 0/190, 0/200 to 0/235 and 0/300 to 0/370)	99,900/-	2000/-	350/-	90 Days	D & C
59.	Restoration of rain damages on Bathri Sundla Langer J & Boundary road K.M. 28/0 to 93/400 (SH: Removal of snow/slips at various RD,s)	99,072/-	2000/-	350/-	90 Days	D & C
60.	Restoration of rain damages on Bhalei Matta Temple to village Saphan road K.M. 0/0 to 4/825 (SH: Removal of slips at R.D. 1/270 to 1/290, 2/220 to 2/250, 2/400 to 2/420 and 2/750 to 2/800)	99,855/-	2000/-	350/-	90 Days	D & C
61.	Restoration of rain damages on Lachori to Seri road K.M. 0/0 to 8/500 (SH: Construction of PCC Retaining wall at R.D. 7/410 to 7/413.75)	99,448/-	2000/-	350/-	90 Days	D & C
62.	Restoration of rain damages on Bathri Sundla Langer J & Boundary road K.M. 28/0 to 93/400 (SH: Removal of snow/slips at various RD,s)	98,418/-	2000/-	350/-	90 Days	D & C

TERMS AND CONDITIONS:-

1. The contractor should produce a copy of enlistment /renewal at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor /firm have his registration and GST No., the copy of Pan Number same be attached with the application.
4. The earnest Money shall be deposited duly pledged in favour of Executive Engineer, Salooni Division HPPWD Salooni and cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
5. The contractor /firms are requested to insert the rate of each item in works as well as in figures failing which XEN reserves the right to accept/reject any tender without assigning any reasons at any stage.



Executive Engineer,
Salooni Division
HPPWD Salooni.

No. PW/SD/GA/Contract/Tender/2025-2026- 14968-15017

Dated: -18 /02/2026

Copy forwarded to:-



1. The F.C-Cum-Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information, please.
2. The Engineer-in-Chief, HPPWD, Shimla.
3. The Chief Engineer (Kangra Zone) HPPWD Dharamshala.
4. The Superintending Engineer, 7th Circle HPPWD Dalhousie.
5. The Executive Engineer (IT Cell) office of Engineer-in-Chief HPPWD Shimla for uploading the NIT on the Departmental website.
6. All the Assistant Engineers under Salooni Division.
7. All the Contractor working under this Division.
8. H.D.M./Supdt./Acctt. of this office.
9. Notice Board.


Executive Engineer,
Salooni Division
HPPWD Salooni.

OFFICE OF
EXECUTIVE ENGINEER, SALOONI DIVISION HPPWD SALOONI
HIMACHAL PRADESH, PUBLIC WORKS DEPARTMENT SALOONI
Phone No. 01899-233287 Email: ee-slo-hp@nic.in

CERTIFICATE

Certified that tender of works, as called vide this office letter No.
PW/SD/GA/Contract/tender/2025-2026- 14968-15017 Dated: 18/2/2026 are emergent
nature in exigency of public interest.


Executive Engineer,
Salooni Division
HPPWD Salooni.


DNIT						Estimated cost
Name of work:- Restoration of rain damages on link road to village Ranjini K.M. 0/0 to 1/0 (SH: Construction of crate work Retaining wall at R.D. 0/710 to 0/720)						Earnest money
S. N.						Time limit
Description of item						90 days
Quantity						Unit
Rate						In Words
Amount						
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals.	19.30	564.55	Per Cubic Metre	Rupees Five Hundred Sixty Four And Paise Fifty Five Only	10896.00
3	Providing and laying boulder apron laid in wire crate with 4mm dia G.I. wire confirming to IS 280 and IS 4826 in 100 mm x100mm (hundred millimeters into hundred millimeters) mesh(woven diagonally) including 10%for laps & joints laid with stone boulders weighing not less than 40kg (forty kilogram) each in toe walls as per drawing and MORD technical specifications clause 2503 and as per direction of the Engineer - in -Charge including carriage of materials within all leads and lifts and other incidental. The rate also includes octroi,royalty, malkana, toll tax sale tax or other taxes imposed by the Government.	31.25	2650.40	Per Cubic Metre	Rupees Two Thousand Six Hundred Fifty And Paise Forty Only	82825.00
Total						93721.00

Rupees Ninety Three Thousand Seven Hundred Twenty One Only

Executive Engineer
Salooni Division
HPPWD Salooni

DNIT

Name of work:- Restoration of rain damages on Bathri Sundia Langera J & K Boundary road K.M. 28/0 to 93/400 (SH: 2000.00)
Construction of crate work Breast wall at R.D. 82/460 to 82/470)

Section of Rate Work Breast wall at meter 02/100 to 02/150							
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes to level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of un-useful material for filling in road ways, camber, embankments for grade improvements and disposal of all useful material to acquired width of the road or on approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures.. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases., including carriage of materials with in all leads and lifts. The rate is including octroi, royalty, Malkana,Tol tax, sale tax, GST or other taxes imposed by the Government. The land for dumping sites shall be arranged by the contractor himself and nothing extra shall be paid on this account.	49.10	194.50	Per Cubic Metre	Rupees One Hundred Ninety Four And Paise Fifty Only	9550.00	
2	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals.	5.60	564.55	Per Cubic Metre	Rupees Five Hundred Sixty Four And Paise Fifty Five Only	3161.00	
3	Providing and laying boulder apron laid in wire crate with 4mm dia G.I. wire confirming to IS 280 and IS 4826 in 100 mm x100mm (hundred millimeters into hundred millimeters) mesh(woven diagonally) including 10%for laps & joints laid with stone boulders weighing not less than 40kg (forty kilogram) each in toe walls as per drawing and MORD technical specifications clause 2503 and as per direction of the Engineer - in -Charge including carriage of materials within all leads and lifts and other incidental. The rate also includes octroi,royalty, malkana, toll tax sale tax or other taxes imposed by the Government.	31.25	2650.40	Per Cubic Metre	Rupees Two Thousand Six Hundred Fifty And Paise Forty Only	82825.00	
Total						95536.00	

Rupees Ninety Five Thousand Five Hundred Thirty Six Only

Executive Engineer
Salooni Division
HPPWD Salooni

DNIT						Estimated cost
Name of work:- Restoration of rain damages on Bathri Sundla Langera J & K Boundary road K.M. 13/130 to 28/0 (SH: 1)						94574.00
Construction of wire crate Breast wall at R.D. 21/940 to 21/950 i.e. 1st Raw 1No. crate & 2nd Raw)						2000.00
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Providing and laying boulder apron laid in wire crate with 4mm dia G.I. wire confirming to IS 280 and IS 4826 in 100 mm x100mm (hundred millimeters) mesh(woven diagonally) including 10%for laps & joints laid with stone boulders weighing not less than 40kg (forty kilogram) each in toe walls as per drawing and MORD technical specifications clause 2503 and as per direction of the Engineer - in -Charge including carriage of materials within all leads and lifts and other incidental. The rate also includes octroi,royalty, maikana, toll tax sale tax or other taxes imposed by the Government.	35.21	2686.00	Per Cubic Metre	Rupees Thousand Six Hundred Eighty Six Only	94574.00
Total						94574.00
Rupees Ninety Four Thousand Five Hundred Seventy Four Only						

Executive Engineer
Salooni Division
HPPWD Salooni

1

DNIT

Name of work:- Restoration of rain damages on Bathri Sundia Langera J&K Boundary road K.M. 13/130 to 28/0 (SH: 1)
Construction of PCC Retaining wall at R.D. 18/897.38 to 18/899.82)

S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals.	10.38	564.50	Per Cubic Metre	Rupees Five Hundred Sixty Four And Paise Fifty Only	5860.00
2	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concrete nominal mix 1:5:10 (one cement is to five sand is to ten graded crushed stone aggregate 40 millimeter (forty millimeter) nominal size in or under water and curing complete for 14 (fourteen) days, in open foundations for all type of structures and the like drain etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 or as directed by the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate includes octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	18.08	4961.10	Per Cubic Metre	Rupees Four Thousand Hundred Sixty One And Paise Ten Only	89697.00
3	Backfilling behind retaining wall/breast wall complete as per drawing and technical specification clause 1204.3.8 in granular material within all leads and lift of material as per direction of Engineer-in-Charge and other incidentals. The rate is including royalty, Malkana,Toll tax, GST or other taxes imposed by the Government.	2.24	991.15	Per Cubic Metre	Rupees Nine Hundred Ninety One And Paise Fifteen Only	2220.00
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe (Finolex/ Vertex) with slope of 1 (v): 20(H) towards drainage face complete as per drawing and MORD technical specification section 700 and 1200 including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect and as per the direction of Engineer-in-Charge. The rate is including royalty, Malkana,Toll tax, GST or other taxes imposed by the Government.	5.00	291.40	Each	Rupees Two Hundred Ninety One And Paise Forty Only	1457.00
Total						99234.00

Rupees Ninety Nine Thousand Two Hundred Thirty Four Only

Rupees Ninety Nine Thousand Two Hundred Thirty Four Only

K. S.
Executive Engineer
Salooni Division
HPPWD Salooni

8

DNI

Name of work:- Restoration of rain damages on Bathri Sundia Langera J&K Boundary road K.M. 13/130 to 28/0 (SH: Construction of PCC Retaining wall at R.D. 18/892.40 to 18/894.90)

Estimated cost 99910.00
Earnest money 2000.00
Time limit 90 days

S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling/wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals.	10.43	564.50	Per Cubic Metre	Rupees Five Hundred Sixty Four And Paise Fifty Only	5888.00
2	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concrete nominal mix 1:5:10 (one cement is to five sand is to ten graded crushed stone aggregate 40 millimeter (forty millimeter) nominal size in or under water and curing complete for 14 (fourteen) days, in open foundations for all type of structures and the like drain etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802.803, 1202 and 1203 or as directed by the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate includes octroi, royalty, Malkana, Toll tax, GST or any other taxes imposed by the Government.	18.15	4961.10	Per Cubic Metre	Rupees Four Thousand Nine Hundred Sixty One And Paise Ten Only	90044.00
3	Backfilling behind retaining wall/breast wall complete as per drawing and technical specification clause 1204.3.8 in granular material within all leads and lift of material as per direction of Engineer-in-Charge and other incidentals. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	2.25	991.15	Per Cubic Metre	Rupees Nine Hundred Ninety One And Paise Fifteen Only	2230.00
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe (Finolux/ Vertex) with slope of 1 (v): 20(H) towards drainage face complete as per drawing and MORD technical specification section 700 and 1200 including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect and as per the direction of Engineer-in-Charge. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	6.00	291.40	Each	Rupees Two Hundred Ninety One And Paise Forty Only	1748.00
Total						99910.00

Rupees Ninety Nine Thousand Nine Hundred Ten Only

RSC
Executive Engineer

Salooni Division

HPPWD Salooni

3

DNIT

Name of work:- Restoration of rain damages on Bhalei Matta Temple to village Athed road K.M. 0/0 to 6/0 (SH: Construction of PCC Retaining wall at R.D. 2/333.75 to 2/337.50)	Estimated cost	97737.00
S. N.	Earnest money	2000.00
	Time limit	90 days

S. N.	Description of item	Quantity	Rate	Unit	In Words	Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORO technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals.	10.29	564.50	Per Cubic Metre	Rupees Five Hundred Sixty Four And Paise Fifty Only	5809.00
2	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concrete nominal mix 1:5:10 (one cement is to five sand is to ten graded crushed stone aggregate 40 millimeter (forty millimeter) nominal size in or under water and curing complete for 14 (fourteen) days, in open foundations for all type of structures and the like drain etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 or as directed by the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate includes octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	17.48	4969.90	Per Cubic Metre	Rupees Thousand Hundred Sixty Nine And Paise Ninety Only	86874.00
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe (Finolex/ Vertex) with slope of 1 (V): 20(H) towards drainage face complete as per drawing and MORO technical specification section 700 and 1200 including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect and as per the direction of Engineer-in-Charge. The rate is including royalty, Malkana,Toll tax, GST or other taxes imposed by the Government.	8.00	291.40	Each	Rupees Two Hundred Ninety One And Paise Forty Only	2331.00
4	Backfilling behind retaining wall/breast wall complete as per drawing and technical specification clause 1204.3.8 in granular material within all leads and lift of material as per direction of Engineer-in-Charge and other incidentals. The rate is including royalty, Malkana,Toll tax, GST or other taxes imposed by the Government.	2.36	1153.70	Per Cubic Metre	Rupees One Thousand One Hundred Fifty Three And Paise Seventy Only	2723.00
Total						97737.00

Rupees Ninety Seven Thousand Seven Hundred Thirty Seven Only


Executive Engineer
Salooni Division
HPPWD Salooni

DNIT

Name of work:- Restoration of rain damages on Bhalei Matta Temple to village Athed road K.M. 0/0 to 6/0 (SH: Construction of PCC Retaining wall at R.D. 2/341.25 to 2/345)

S. N.	Description of Item	Quantity	Rate	Estimated cost	
				Earnest money	97615.00
		Unit	In Words	Time limit	2000.00
				90 days	
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals.	10.99	564.50	Per Cubic Metre Rupees Five Hundred Sixty Four And Paise Fifty Only	6204.00
2	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concrete nominal mix 1:5:10 (one cement is to five sand is to ten graded crushed stone aggregate 40 millimeter (forty millimeter) nominal size in or under water and curing complete for 14 (fourteen) days, in open foundations for all type of structures and the like drain etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 or as directed by the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate includes octroi, royalty, Malkana, Toll tax, GST or any other taxes imposed by the Government.	17.48	4970.00	Per Cubic Metre Rupees Thousand Nine Hundred Seventy Only	86876.00
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe (Finolex/ Verrex) with slope of 1 (v): 20(H) towards drainage face complete as per drawing and MORD technical specification section 700 and 1200 including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect and as per the direction of Engineer-in-Charge. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	8.00	291.40	Each Rupees Two Hundred Ninety One And Paise Forty Only	2331.00
4	Backfilling behind retaining wall/breast wall complete as per drawing and technical specification clause 1204.3.8 in granular material within all leads and lift of material as per direction of Engineer-in-Charge and other incidentals. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1.91	1153.70	Per Cubic Metre Rupees One Thousand One Hundred Fifty Three And Paise Seventy Only	2204.00
Total					97615.00

Rupees Ninety Seven Thousand Six Hundred Fifteen Only


Executive Engineer
Salooni Division
HPPWD Salooni

DNIT						Estimated cost	93221.00
Name of work:- Restoration of rain damages on Bindhokhi to Khundi Baag road K.M. 0/0 to 3/700 (SH: Construction of wire crate Back wall at R.D. 1/570 to 1/590)						Earnest money	2000.00
						Time limit	90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount	
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals.	15.60	564.50	Per Cubic Metre	Rupees Five Hundred Sixty Four And Paise Fifty Only	8806.00	
3	Providing and laying boulder apron laid in wire crate with 4mm dia G.I. wire conforming to IS 280 and IS 4826 in 100 mm x 100mm (hundred millimeters into hundred millimeters) mesh(woven diagonally) including 10% for laps & joints laid with stone boulders weighing not less than 40kg (forty kilogram) each in toe walls as per drawing and MORD technical specifications clause 2503 and as per direction of the Engineer - in -Charge including carriage of materials within all leads and lifts and other incidental. The rate also includes octroi, royalty, makana, toll tax sale tax or other taxes imposed by the Government.	31.20	2705.60	Per Cubic Metre	Rupees Two Thousand Seven Hundred Five And Paise Sixty Only	84415.00	
						Total	93221.00
Rupees Ninety Three Thousand Two Hundred Twenty One Only							

Executive Engineer
 Salooni Division
 HPPWD Salooni

DNIT

Name of work:- Restoration of rain damages on Bindhokhi to Khundi Baag road K.M. 0/0 to 3/700 (SH: Construction of wire crate Retaining wall at R.D. 1/625 to 1/635)		Estimated cost	2000.00
		Earnest money	90 days

S.N.	Description of item	Quantity	Rate	Unit	In Words	Amount
1	Excavation in soil in hilly area in all heights and depths in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes to level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of un-useful material for filling in road ways, camber, embankments for grade improvements and disposal of all useful material to acquired width of the road or on approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases., including carriage of materials with in all leads and lifts. The rate is including octroi, royalty, Malkana, Tol tax, sale tax, GST or other taxes imposed by the Government. The land for dumping sites shall be arranged by the contractor himself and nothing extra shall be paid on this account.	14.40	194.50	Per Cubic Metre	Rupees One Hundred Ninety Four And Paise Fifty Only	2801.00
2	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals.	5.60	564.50	Per Cubic Metre	Rupees Five Hundred Sixty Four And Paise Fifty Only	3161.00
3	Providing and laying boulder apron laid in wire crate with 4mm dia G.I. wire confirming to IS 280 and IS 4826 in 100 mm x100mm (hundred millimeters into hundred millimeters) mesh(woven diagonally) including 10%for laps & joints laid with stone boulders weighing not less than 40kg (forty kilogram) each in toe walls as per drawing and MORD technical specifications clause 2503 and as per direction of the Engineer - in -Charge including carriage of materials within all leads and lifts and other incidental. The rate also includes octroi,royalty, malkana, toll tax sale tax or other taxes imposed by the Government.	31.20	2705.60	Per Cubic Metre	Rupees Two Thousand Seven Hundred Five And Paise Sixty Only	84415.00
Total						90377.00

Rupees Ninety Thousand Three Hundred Seventy Seven Only

Executive Engineer
Salooni Division
HPPWD Salooni

DNIT							Estimated cost
Name of work:- Restoration of rain damages on Bhadela Andwas road K.M. 0/0 to 6/300 (SH: Removal of snow/slips at various RD's)							97850.00
S. N.	Description of item	Quantity	Rate	Unit	In Words	Amount	Earnest money
							Time limit
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire statification of Engineer- in Charge any loss to the public/provate property or any accident etc. happened during the course of hiring period/execution shall by the absolute resonsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less then 17.00 cum per hours to be lifted and snow not less then 15.00 cum per hour to be lifted with in a lead of 200 metre.	95.00	1030.00	Per Hours	Rupees Thousand Only	One Thirty	2000.00
Total							90 days
Rupees Ninety Seven Thousand Eight Hundred Fifty Only							97850.00


 Executive Engineer
 Salooni Division
 HPPWD Salooni




DNIT						Estimated cost	96820.00
Name of work:- Restoration of rain damages on Kund Siula road K.M. 0/0 to 6/255 (SH: Removal of snow/slips at various RD's)						Earnest money	2000.00
						Time limit	90 days
S. N.	Description of item	Quantity	Rate	Unit	In Words	Amount	
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire statification of Engineer- in Charge any loss to the public/provate property or any accident etc. happened during the course of hiring period/execution shall by the absolute reosninsility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less then 17.00 cum per hours to be lifted and snow not less then 15.00 cum per hour to be lifted with in a lead of 200 metre.	94.00	1030.00	Per Hours	Rupees Thousand Only	One Thirty 96820.00	
Total						96820.00	
Rupees Ninety Six Thousand Eight Hundred Twenty Only							


 Executive Engineer
 Salooni Division
 HPPWD Salooni



DNIT						Estimated cost
Name of work:- Restoration of rain damages on Salooni Ghal road K.M. 0/0 to 7/500 (SH: Removal of snow/slips at various RD's)						99910.00
						Earnest money 2000.00
						Time limit 90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire statification of Engineer- in Charge any loss to the public/provate property or any accident etc. happened during the course of hiring period/execution shall by the absolute resonsinility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less then 17.00 cum per hours to be lifted and snow not less then 15.00 cum per hour to be lifted with in a lead of 200 metre.	97.00	1030.00	Per Hours	Rupees Thousand Only	One Thirty 99910.00
Total						99910.00
Rupees Ninety Nine Thousand Nine Hundred Ten Only						



 Executive Engineer
 Salooni Division
 HPPWD Salooni



DNIIT						Estimated cost
Name of work:- Restoration of rain damages on Kandhwara Bhadela road K.M. 0/0 to 4/100 (SH: Removal of snow/slips at various RD's)						Earnest money
S. N.	Description of item	Quantity	Rate	Unit	In Words	90 days
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire statification of Engineer- in Charge any loss to the public/provate property or any accident etc. happened during the course of hiring period/execution shall by the absolute resonsinility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less then 17.00 cum per hours to be lifted and snow not less then 15.00 cum per hour to be lifted with in a lead of 200 metre.	96.00	1030.00	Per Hours	Rupees Thousand Only	98880.00
Total						98880.00
Rupees Ninety Eight Thousand Eight Hundred Eighty Only						

Executive Engineer
 Salooni Division
 HPPWD Salooni

DNIT							Estimated cost	99910.00
Name of work:-Restoration of rain damages on Bathri Sundla Langera J & Boundary road K.M. 28/0 to 93/400 (SH: Removal of snow/slips at K.M. 57/0 to 80/0)							Earnest money	2000.00
							Time limit	90 days
S. N.	Description of item	Quantity	Rate	Unit	In Words	Amount		
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all rxcavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire statification of Engineer- in Charge any loss to the public/provate property or any accident etc. happened during the course of hiring period/execution shall by the absolute resonsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less then 17.00 cum per hours to be lifted and snow not less then 15.00 cum per hour to be lifted with in a lead of 200 metre.	97.00	1030.00	Per Hours	Rupees Thousand Only	One Thirty 99910.00		
Total							99910.00	
Rupees Ninety Nine Thousand Nine Hundred Ten Only								


 Executive Engineer
 Salooni Division
 HPPWD Salooni




DNIT					
Name of work:-Restoration of rain damages on Bathri Sundla Langera J & Boundary road K.M. 28/0 to 93/400 (SH: Removal of snow/slips at K.M. 80/0 to 93/400)					
S. N.	Description of item	Quantity	Rate	Estimated cost	
				Earnest money	2000.00
				Time limit	90 days
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire statification of Engineer- in Charge any loss to the public/provate property or any accident etc. happened during the course of hiring period/execution shall by the absolute resonsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less then 17.00 cum per hours to be lifted and snow not less then 15.00 cum per hour to be lifted with in a lead of 200 metre.	96.00	1030.00	Unit Per Hours	Rupees Thousand Only
				In Words	One Thirty
				Amount	98880.00
Total					98880.00
Rupees Ninety Eight Thousand Eight Hundred Eighty Only					


 Executive Engineer
 Salooni Division
 HPPWD Salooni



DNIT						Estimated cost
Name of work:- Restoration of rain damages on Maira Jakhral road K.M. 0/0 to 11/900 (SH: Removal of snow/slips at various RD's)						96820.00
						Earnest money
						2000.00
						Time limit
						90 days
S. N.	Description of item	Quantity	Rate	Unit	In Words	Amount
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire statification of Engineer- in Charge any loss to the public/provate property or any accident etc. happened during the course of hiring period/execution shall by the absolute resonsinility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less then 17.00 cum per hours to be lifted and snow not less then 15.00 cum per hour to be lifted with in a lead of 200 metre.	94.00	1030.00	Per Hours	Rupees Thousand Only	One Thirty 96820.00
Total						96820.00
Rupees Ninety Six Thousand Eight Hundred Twenty Only						


 Executive Engineer
 Salooni Division
 HPPWD Salooni



DNIT							Estimated cost
Name of work:- Restoration of rain damages on Kainthly Bhidroh road K.M. 0/0 to 6/700 (SH: Removal of snow/slips at various RD's)							2000.00
S. N.	Description of item	Quantity	Rate	Unit	In Words	Amount	90 days
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire statification of Engineer- in Charge any loss to the public/provate property or any accident etc. happened during the course of hiring period/execution shall by the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less than 17.00 cum per hours to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	95.00	1030.00	Per Hours	Rupees Thousand Only	One Thirty	97850.00
Total							97850.00
Rupees Ninety Seven Thousand Eight Hundred Fifty Only							


 Executive Engineer
 Salooni Division
 HPPWD Salooni




DNIT

Name of work:- Restoration of rain damages on Lachori to Seri road K.M. 0/0 to 8/500 (SH: Construction of wire crate Retaining wall at R.D. 2/850 to 2/857.50)


Estimated cost						99208.00
Earnest money						2000.00
Time limit						90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals.	15.71	564.50	Per Cubic Metre	Rupees Five Hundred Sixty Four And Paise Fifty Only	8868.00
3	Providing and laying boulder apron laid in wire crate with 4mm dia G.I. wire conforming to IS 280 and IS 4826 in 100 mm x100mm (hundred millimeters into hundred millimeters) mesh(woven diagonally) including 10%for laps & joints laid with stone boulders weighing not less than 40kg (forty kilogram) each in toe walls as per drawing and MORD technical specifications clause 2503 and as per direction of the Engineer - in -Charge including carriage of materials within all leads and lifts and other incidental. The rate also includes octroi,royalty, maikana, toll tax sale tax or other taxes imposed by the Government.	35.10	2573.80	Per Cubic Metre	Rupees Two Thousand Five Hundred Seventy Three And Paise Eighty Only	90340.00
Total						99208.00

Rupees Ninety Nine Thousand Two Hundred Eight Only


Executive Engineer
Salooni Division
HPPWD Salooni



DNIT							Estimated cost
Name of work:- Restoration of rain damages on Lachori to Seri road K.M. 0/0 to 8/500 (SH: Construction of wire crate Retaining wall at R.D. 2/865 to 2/872.50)							2000.00
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount	90 days
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals.	13.61	564.50	Per Cubic Metre	Rupees Five Hundred Sixty Four And Paise Fifty Only	7683.00	
3	Providing and laying boulder apron laid in wire crate with 4mm dia G.I. wire conforming to IS 280 and IS 4826 in 100 mm x100mm (hundred millimeters into hundred millimeters) mesh(woven diagonally) including 10%for laps & joints laid with stone boulders weighing not less than 40kg (forty kilogram) each in toe walls as per drawing and MORD technical specifications clause 2503 and as per direction of the Engineer - in -Charge including carriage of materials within all leads and lifts and other incidental. The rate also includes octroi,royalty, maikana, toll tax sale tax or other taxes imposed by the Government.	35.10	2573.80	Per Cubic Metre	Rupees Two Thousand Five Hundred Seventy Three And Paise Eighty Only	90340.00	
Total						98023.00	
Rupees Ninety Eight Thousand Twenty Three Only							


 Executive Engineer
 Salooni Division
 HPPWD Salooni




DNIT

Name of work:- Restoration of rain damages on Lachori to Seri road K.M. 0/0 to 8/500 (SH: Construction of PCC Retaining wall at R.D. 7/410 to 7/413.75)

Name of work:- Restoration of rain damages on Lachori to Seri road K.M. 0/0 to 8/500 (SH: Construction of PCC Retaining wall at R.D. 7/410 to 7/413.75)						DNIT		Estimated cost	99448.00
						Earnest money	2000.00		
						Time limit	90 days		
S. N.	Description of item	Quantity	Rate	Unit	In Words	Amount			
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals.	8.93	564.50	Per Cubic Metre	Rupees Five Hundred Sixty Four And Paise Fifty Only	5041.00			
2	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concrete nominal mix 1:5:10 (one cement is to five sand is to ten graded crushed stone aggregate 40 millimeter (forty millimeter) nominal size in or under water and curing complete for 14 (fourteen) days, in open foundations for all type of structures and the like drain etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 or as directed by the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate includes octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	17.48	5090.40	Per Cubic Metre	Rupees Five Thousand Niney And Paise Forty Only	88980.00			
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe (Finolex/ Vertex) with slope of 1 (V): 20(H) towards drainage face complete as per drawing and MORD technical specification section 700 and 1200 including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect and as per the direction of Engineer-in-Charge. The rate is including royalty, Malkana,Toll tax, GST or other taxes imposed by the Government.	8.00	291.40	Each	Rupees Two Hundred Ninety One And Paise Forty Only	2331.00			
4	Backfilling behind retaining wall/breast wall complete as per drawing and technical specification clause 1204.3.8 in granular material within all leads and lift of material as per direction of Engineer-in-Charge and other incidentals. The rate is including royalty, Malkana,Toll tax, GST or other taxes imposed by the Government.	2.93	1056.80	Per Cubic Metre	Rupees One Thousand Fifty Six And Paise Eighty Only	3096.00			
Total						99448.00			

Rupees Ninety Nine Thousand Four Hundred Forty Eight Only

Rupees Ninety Nine Thousand Four Hundred Forty Eight Only


Executive Engineer
Salooni Division
HPPWD Salooni

5

Name of work:- Restoration of rain damages on Lachori to Seri road K.M. 0/0 to 8/500 (SH: Construction of PCC Retaining wall at R.D. 7/415 to 7/418.75)


DNIT

S. N.		Description of item		Estimated cost	
				Earnest money	90 days
		Quantity	Rate	Unit	In Words
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals.	8.93	564.50	Per Cubic Metre	Rupees Five Hundred Sixty Four And Paise Fifty Only
2	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concrete nominal mix 1:5:10 (or under water and curing complete for 14 (fourteen) days, in open foundations for all type of structures and the like quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 or as directed by the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate includes octroi, royalty, Malkana, Toll tax, GST or any other taxes imposed by the Government.	17.48	5090.50	Per Cubic Metre	Rupees Five Thousand Niney And Paise Fifty Only
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe (Finolex/ Vertex) with slope of 1 (V): 20(H) towards drainage face complete as per drawing and MORD technical specification section 700 and 1200 including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect and as per the direction of Engineer-In-Charge. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	7.00	291.40	Each	Rupees Two Hundred Niney One And Paise Forty Only
4	Backfilling behind retaining wall/breast wall complete as per drawing and technical specification clause 1204.3.8 in granular material within all leads and lift of material as per direction of Engineer-in-Charge and other incidentals. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	3.04	1056.80	Per Cubic Metre	Rupees One Thousand Fifty Six And Paise Eighty Only
Total					
					99276.00

Rupees Ninety Nine Thousand Two Hundred Seventy Six Only

Executive Engineer
Salooni Division
HPPWD Salooni

DNIT						Estimated cost
Name of work:- Restoration of rain damages on link road to village Dind K.M. 0/0 to 3/830 (SH: Removal of slips at R.D. 0/750 to 0/780, 1/030 to 1/060, 1/780 to 1/810 and 2/300 to 2/320)						Earnest money
S. N.	Description of item	Quantity	Rate	Unit	In Words	90 days
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1108.88	90.00	Per Cubic Metre	Rupees Ninety Only	99799.00
Total						99799.00
Rupees Ninety Nine Thousand Seven Hundred Ninety Nine Only						


 Executive Engineer
 Salooni Division
 HPPWD Salooni



DNIT						Estimated cost
Name of work:- Restoration of rain damages on Bathri Sundla Langera J & K boundary road K.M. 13/130 to 28/0 (SH: Removal of slips at R.D. 14/720 to 14/750, 17/740 to 17/760, 20/860 to 20/900 and 21/620 to 21/640)						2000.00
S. N.	Description of item	Quantity	Rate	Unit	In Words	Amount
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1107.50	90.00	Per Cubic Metre	Rupees Ninety Only	99675.00
Total						99675.00

Rupees Ninety Nine Thousand Six Hundred Seventy Five Only

Executive Engineer
Salooni Division
HPPWD Salooni



DNIT						Estimated cost
Name of work:- Restoration of rain damages on Bihali Bachuni Chamber Katara road K.M. 0/0 to 11/100 (SH: Removal of slips at R.D. 0/350 to 0/380, 3/620 to 3/650 and 9/0 to 9/040)						Earnest money
						2000.00
S. N.	Description of Item	Quantity	Rate	Unit	In Words	90 days
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1109.25	90.00	Per Cubic Metre	Rupees Ninety Only	99833.00
Total						99833.00
Rupees Ninety Nine Thousand Eight Hundred Thirty Three Only						


 Executive Engineer
 Salooni Division
 HPPWD Salooni




DNIT		1/629		Estimated cost	
Name of work:- Restoration of rain damages on Kandi to Athed road K.M. 0/0 to 12/0 (SH: Removal of slips at R.D. 1/580 to 1/60, 2/200 to 2/240 and 5/180 to 5/210)		Earnest money		99867.00	
S. N.		Time limit		2000.00	
Description of Item		Unit		90 days	
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	Quantity	Rate	In Words	Amount
		1109.63	90.00	Per Cubic Metre	99867.00
Total					99867.00
Rupees Ninety Nine Thousand Eight Hundred Sixty Seven Only					

Executive Engineer
Salooni Division
HPPWD Salooni

1

DNIT						
Name of work:- Restoration of rain damages on Maira Jakhral road K.M. 0/0 to 11/900 (SH: Removal of snow/slips at various RD's)						
S. N.	Description of item	Quantity	Rate	Unit	In Words	Estimated cost
						Earnest money
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1098.85	90.00	Per Cubic Metre	Rupees Ninety Only	2000.00
Total						90 days
Rupees Ninety Eight Thousand Eight Hundred Ninety Seven Only						98897.00


 Executive Engineer
 Salooni Division
 HPPWD Salooni



DNIT							Estimated cost	98161.00
Name of work:- Restoration of rain damages on Maira lakhral road K.M. 0/0 to 11/900 (SH: Removal of snow/slips at various RD's)							Earnest money	2000.00
							Time limit	90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount		
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana,Toll tax, GST or other taxes imposed by the Government.	1090.68	90.00	Per Cubic Metre	Rupees Ninety Only	98161.00		
Total						98161.00		
Rupees Ninety Eight Thousand One Hundred Sixty One Only								

Executive Engineer
Salooni Division
HPPWD Salooni


8/

DNIIT					
Name of work:- Restoration of rain damages on Bathri Sundla Langer a J & Boundary road K.M. 28/0 to 93/400 (SH: Removal of snow/slips at various RD,s)					
S. N.	Description of item	Quantity	Rate	Estimated cost Earnest money Time limit	99072.00 2000.00 90 days
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1100.81	90.00	Unit Per Cubic Metre	In Words Rupees Ninety Only Amount 99073.00
Total					99073.00
Rupees Ninety Nine Thousand Seventy Three Only					


 Executive Engineer
 Salooni Division
 HPPWD Salooni



DNIT						
Name of work:- Restoration of rain damages on Bathri Sundla Langera J & Boundary road K.M. 28/0 to 93/400 (SH: Removal of snow/slips at various RD,s)						Estimated cost
						Earnest money
						Time limit
						90 days
S. N.	Description of item	Quantity	Rate	Unit	In Words	Amount
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana,Toll tax, GST or other taxes imposed by the Government.	1104.03	90.00	Per Cubic Metre	Rupees Ninety Only	99363.00
Total						99363.00
Rupees Ninety Nine Thousand Three Hundred Sixty Three Only						


 Executive Engineer
 Salooni Division
 HPPWD Salooni

Name of work:- Restoration of rain damages on Bathri Sundla Langer J & Boundary road K.M. 28/0 to 93/400 (SH: Removal of snow/slips at various RD,s)						DNI		Estimated cost	99826.00
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Time limit	Earnest money	2000.00	90 days
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1109.18	90.00	Per Cubic Metre	Rupees Ninety Only			99826.00	
Total								99826.00	
Rupees Ninety Nine Thousand Eight Hundred Twenty Six Only									

Executive Engineer
Salooni Division
HPPWD Salooni

Name of work:- Restoration of rain damages on Bathri Sundla Langer J & Boundary road K.M. 28/0 to 93/400 (SH: Removal of snow/slips at various RD,s)					
DNIT					
S. N.	Description of Item	Quantity	Rate	Unit	Estimated cost Earnest money
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1109.78	90.00	Per Cubic Metre	2000.00
Total					99880.00
Rupees Ninety Nine Thousand Eight Hundred Eighty Only					

Executive Engineer
Salooni Division
HPPWD Salooni

1

Name of work:- Restoration of rain damages on Bathri Sundia Langera J & Boundary road K.M. 28/0 to 93/400 (SH: Removal of snow/slips at various RD,s)					
DNIT					
S. N.	Description of Item	Quantity	Rate	Unit	Estimated cost
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana,Toll tax, GST or other taxes imposed by the Government.	1088.70	90.00	Per Cubic Metre	97983.00
Total					97983.00
Rupees Ninety Seven Thousand Nine Hundred Eighty Three Only					


 Executive Engineer
 Salooni Division
 HPPWD Salooni


 B

DNIT						
Name of work:- Restoration of rain damages on Bathri Sundia Langera J & Boundary road K.M. 28/0 to 93/400 (SH: Removal of snow/slips at various RD,s)						
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Estimated cost Earnest money
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1102.28	90.00	Per Cubic Metre	Rupees Ninety Only	99205.00
Total						99205.00
Rupees Ninety Nine Thousand Two Hundred Five Only						


 Executive Engineer
 Salooni Division
 HPPWD Salooni


 8/

Name of work:- Restoration of rain damages on Bathri Sundla Langera J & Boundary road K.M. 28/0 to 93/400 (SH: Removal of snow/slips at various RD,s)						DNIT		Estimated cost	97358.00
S. N.	Description of item	Quantity	Rate	Unit	In Words	Amount	Earnest money	2000.00	
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana,Toll tax, GST or other taxes imposed by the Government.	1081.76	90.00	Per Cubic Metre	Rupees Ninety Only	97358.00	Time limit	90 days	
Total						97358.00			
Rupees Ninety Seven Thousand Three Hundred Fifty Eight Only									

Rupees Ninety Seven Thousand Three Hundred Fifty Eight Only

Executive Engineer
Salooni Division
HPPWD Salooni

8

DNIT					
Name of work:- Restoration of rain damages on Bathri Sundla Langera J & Boundary road K.M. 28/0 to 93/400 (SH: Removal of snow/slips at various RD,s)					
S. N.	Description of Item	Quantity	Rate	Unit	Estimated cost
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1093.53	90.00	Per Cubic Metre	98418.00
Total					98418.00
Rupees Ninety Eight Thousand Four Hundred Eighteen Only					


 Executive Engineer
 Salooni Division
 HPPWD Salooni



Name of work:- Restoration of rain damages on Bathri Sundla Langer a J & Boundary road K.M. 28/0 to 93/400 (SH: Removal of snow/slips at various RD,s)							DNIT	
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount	Estimated cost	99831.00
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana,Toll tax, GST or other taxes imposed by the Government.	1109.23	90.00	Per Cubic Metre	Rupees Ninety Only	99831.00	Earnest money	2000.00
							Time limit	90 days
Total						99831.00		
Rupees Ninety Nine Thousand Eight Hundred Thirty One Only								

Executive Engineer
Salooni Division
HPPWD Salooni

8

Name of work:- Restoration of rain damages on Bathri Sundia Langeri J & Boundary road K.M. 28/0 to 93/400 (SH: Removal of snow/slips at various RD,s)		DNIT		Estimated cost	
S. N.	Description of Item	Quantity	Rate	Unit	Amount
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1110.98	90.00	Per Cubic Metre	99988.00
Total					99988.00
Rupees Ninety Nine Thousand Nine Hundred Eighty Eight Only					

Executive Engineer
Salooni Division
HPPWD Salooni

81


DNIT

Name of work:- Restoration of rain damages on Bhalei Matta Temple to village Athed road K.M. 0/0 to 6/0 (SH: Construction of 600mm dia hume pipe culvert at R.D. 1/465)

Estimated cost 99614.00
Earnest money 2000.00

S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals.	14.37	564.55	Per Cubic Metre	Rupees Five Hundred Sixty Four And Paise Fifty Five Only	8113.00
2	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concrete nominal mix 1:4:8 (one cement is to four sand is to eight graded crushed stone aggregate 40 millimeter (forty millimeter) nominal size in or under water and curing complete for 14 (fourteen) days, in open foundations for all type of structures including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 or as directed by the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate includes octroi, royalty, Malkana, Tol tax, sale tax or any other taxes imposed by the Government.	1.25	5290.10	Per Cubic Metre	Rupees Five Thousand Two Hundred Ninety And Paise Ten Only	6613.00
3	Providing and laying mechanically mixed and vibrated concrete for plain/ cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M ten) per cubic metre nominal mix 1:3:6 (one cement is to three sand is to six crushed stone aggregate 40mm(forty millimeter) nominal size) in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and to the entire satisfaction and direction of Engineer - in-Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, Malkana, Tol tax, sale tax, GST or other taxes imposed by the Government.	9.73	6519.70	Each	Rupees Six Thousand Five Hundred Nineteen And Paise Seventy Only	63437.00
4	Providing and laying mechanically mixed and vibrated concrete in sub-structure for grade M15 (M-fifteen) design mix with cement contents not less than 275 kg (two hundred seventy five kilogram) per cubic metre and using graded/ crushed stone aggregate 40 mm (forty millimeter) nominal size and curing complete including cost of form work for plain concrete work in abutment as per drawings and M.O.R.D. technical specification section 800,900, 1200 as directed by the Engineer-in-Charge including hauling/carriage of materials to various location through all modes of transportation in all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, Tol tax, sale tax, GST or other taxes imposed by the Government.	0.60	6986.90	Per Cubic Metre	Rupees Six Thousand Nine Hundred Eighty Six And Paise Ninety Only	4192.00
5	Providing and laying (to level or slope) 600mm dia (Six thousand millimeters) diameter reinforced cement concrete heavy duty non pressure pipes (IS Class NP-2 for culverts in single row including fixing collar with cement mortar 1 : 2 (One cement : two sand) but excluding the cost of excavation, protection works, back filling, bedding concrete or first class bedding and masonry work in head walls and parapets as per drawing and MORD technical specifications section 1100, including hauling/carriage of materials in all leads and lifts and other incidental. The rate including Octroi, Royalty, Malkana, Tol Tax, Sale Tax, GST or other taxes imposed by the Government.	6.00	2876.5	Per Running metre	Rupees Two Thousand Eight Hundred Seventy Six And Paise Fifty Only	17259.00
Total						99614.00

Rupees Ninety Nine Thousand Six Hundred Fourteen Only


Executive Engineer
Salooni Division
HPPWD Salooni



Name of work:- Restoration of rain damages on Kandl to Athedroad K.M. 0/0 to 12/0 (SH: Removal of slips at R.D. 0/880 to 0/920, 1/240 to 1/280 and 1/425 to 1/455)							DNIT	
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount	Estimated cost	Earnest money
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1106.25	90.00	Per Cubic Metre	Rupees Ninety Only	99563.00	99563.00	2000.00
Total						99563.00		90 days
Rupees Ninety Nine Thousand Five Hundred Sixty Three Only								

Rupees Ninety Nine Thousand Five Hundred Sixty Three Only

Executive Engineer
Salooni Division
HPPWD Salooni

(Signature)

DNIT

Name of work:- Restoration of rain damages on Bihali Bachuni Chamber Katara road K.M. 0/0 to 11/100 (SH: Removal of slips at R.D. 2/120 to 2/150, 4/500 to 4/530 and 6/795 to 6/835)

Name of work:- Restoration of rain damages on Bihali Bachuni Chamber Katara road K.M. 0/0 to 11/100 (SH: Removal of slips at R.D.									
S. N.									
Description of item									
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	Quantity	Rate	Unit	In Words	Amount	Estimated cost	Earnest money	90 days
		1109.88	90.00	Per Cubic Metre	Rupees Ninety Only	99889.00	99889.00	2000.00	
Total						99889.00			
Rupees Ninety Nine Thousand Eight Hundred Eighty Nine Only									

Rupees Ninety Nine Thousand Eight Hundred Eighty Nine Only


 Executive Engineer
 Salooni Division
 HPPWD Salooni



DNIT					
Name of work:- Restoration of rain damages on Bathri Sundia Langera J & Boundary road to village Lamni K.M. 0/0 to 2/500 (SH: Removal of slips at R.D. 0/030 to 0/060, 0/110 to 0/140, 1/650 to 1/680 and 1/800 to 1/820)					
S. N.	Description of Item	Quantity	Rate	Unit	Estimated cost
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1104.00	90.00	Per Cubic Metre	99360.00
Total					99360.00
Rupees Ninety Nine Thousand Three Hundred Sixty Only					


Executive Engineer
Salooni Division
HPPWD Salooni

DNIIT						
Name of work:- Restoration of rain damages on Bathri Sundia Langer J & Boundary road K.M. 13/130 to 28/0 (SH: Removal of slips at R.D. 26/700 to 26/730, 27/580 to 27/610, 27/760 to 27/810 and 27/850 to 27/900)						
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1106.88	90.00	Per Cubic Metre	Rupees Ninety Only	99619.00
Total						99619.00
Rupees Ninety Nine Thousand Six Hundred Nineteen Only						

Executive Engineer
Salooni Division
HPPWD Salooni

8

Name of work:- Restoration of rain damages on Kandi to Athed road K.M. 0/0 to 12/0 (SH: Removal of slips at R.D. 5/180 to 5/230, 7/120 to 7/140, 7/330 to 7/360 and 9/630 to 9/650)						DNIT		Estimated cost	99675.00
S. N.	Description of item	Quantity	Rate	Unit	In Words	Amount	Time limit	Earnest money	2000.00
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1107.50	90.00	Per Cubic Metre	Rupees Ninety Only	99675.00	90 days		
Total						99675.00			
Rupees Ninety Nine Thousand Six Hundred Seventy Five Only									



 Executive Engineer
 Salooni Division
 HPPWD Salooni



DNIT

Name of work:- Restoration of rain damages on link road Pukhri to Bhatoli K.M. 0/0 to 3/090 (SH: Removal of slips at R.D. 0/550 to 0/600, 1/300 to 1/340 and 1/920 to 1/950)

DNIT						
Name of work:- Restoration of rain damages on link road Pukhri to Bhatoli K.M. 0/0 to 3/090 (SH: Removal of slips at R.D. 0/550 to 0/600, 1/300 to 1/340 and 1/920 to 1/950)						
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1109.75	90.00	Per Cubic Metre	Rupees Ninety Only	99878.00
Total						99878.00
Rupees Ninety Nine Thousand Eight Hundred Seventy Eight Only						


 Executive Engineer
 Salooni Division
 HPPWD Salooni




DNIT

Name of work:- Restoration of rain damages on Bathri Sundla Langer J & Boundary road K.M. 13/130 to 28/0 (SH: Removal of slips at R.D. 17/170 to 17/210, 23/960 to 24/0, and 27/265 to 27/300)


S. N.	Description of item	Quantity	Rate	Unit	In Words	Estimated cost
						Earnest money
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1108.50	90.00	Per Cubic Metre	Rupees Ninety Only	99765.00
Total						99765.00

Rupees Ninety Nine Thousand Seven Hundred Sixty Five Only


Executive Engineer
Salooni Division
HPPWD Salooni


 1

DNT					
Name of work:- Restoration of rain damages on link road Surella to Pukhi Part-2 K.M. 0/0 to 0/480 (SH: Removal of slips at R.D. 0/170 to 0/190, 0/200 to 0/235 and 0/300 to 0/370)					
S. N.	Description of Item	Quantity	Rate	Unit	In Words
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1110.00	90.00	Per Cubic Metre	Rupees Ninety Only
Total					99900.00
Rupees Ninety Nine Thousand Nine Hundred Only					


 Executive Engineer
 Salooni Division
 HPPWD Salooni




DNIIT

Name of work:- Restoration of rain damages on Chowga to Khal road K.M. 0/0 to 13/705 (SH: Removal of slips at R.D. 3/300 to 3/350, 5/650 to 5/680, 7/450 to 7/480 and 7/840 to 7/860)

S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1109.00	90.00	Per Cubic Metre	Rupees Ninety Only	99810.00
Total						99810.00

Rupees Ninety Nine Thousand Eight Hundred Ten Only


 Executive Engineer
 Salooni Division
 HPPWD Salooni

81

DNIT						
Name of work:- Restoration of rain damages on Bhalei Matta Temple to village Saphan road K.M. 0/0 to 4/825 (SH: Removal of slips at R.D. 1/270 to 1/290, 2/220 to 2/250, 2/400 to 2/420 and 2/750 to 2/800)						
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1109.50	90.00	Per Cubic Metre	Rupees Ninety Only	99855.00
Total						99855.00
Rupees Ninety Nine Thousand Eight Hundred Fifty Five Only						

Executive Engineer
Salooni Division
HPPWD Salooni


DNIT

Name of work:- Restoration of rain damages on Bassa to Chhudra road K.M. 0/0 to 3/0 (SH: Removal of slips at R.D. 0/860 to 0/900, 1/220 to 1/260 and 2/600 to 2/630)

Estimated cost	99732.00
Earnest money	2000.00
90 days	

S. N.	Description of item	Quantity	Rate	Unit	In Words	Amount
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1108.13	90.00	Per Cubic Metre	Rupees Ninety Only	99732.00
Total						99732.00

Rupees Ninety Nine Thousand Seven Hundred Thirty Two Only



Executive Engineer
 Salooni Division
 HPPWD Salooni



DNIT

Name of work:- Restoration of rain damages on Lachori to Seri road K.M. 0/0 to 8/500 (SH: Removal of slips at R.D. 0/900 to 0/940, 3/120 to 3/170 and 5/680 to 5/720)

S. N.	Description of Item	Quantity	Rate	Estimated cost	
				Earnest money	99788.00
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1108.75	90.00	Time limit	2000.00
				Unit	90 days
				Per Cubic Metre	
				In Words	Amount
				Rupees Ninety Only	99788.00
Total					99788.00
Rupees Ninety Nine Thousand Seven Hundred Eighty Eight Only					


 Executive Engineer
 Salooni Division
 HPPWD Salooni


1

DNIT

Name of work:- Restoration of rain damages on Chhudra to Tuhien road K.M. 0/0 to 2/225 (SH: Removal of slips between K.M. 0/0 to 2/225)

S. N.	Description of item	Estimated cost		Earnest money		Time limit	90 days
		Quantity	Rate	Unit	In Words		
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfaction of Engineer- in Charge any loss to the public/probate property or any accident etc. happened during the course of hiring period/execution shall by the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less than 17.00 cum per hours to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	95.00	1030.00	Per Hours	Rupees Thousand Only	One Thirty	97850.00
Total							97850.00

Rupees Ninety Seven Thousand Eight Hundred Fifty Only


 Executive Engineer
 Salooni Division
 HPPWD Salooni



Name of work:- Restoration of rain damages on Bassa to Chhudra road K.M. 0/0 to 3/0 (CU. Restored 1.50 m³).

S. N.	3/0)
	carriages on Bassa to Chhudra road K.M. 0/0 to 3/0 (SH: Removal of slips between K.M. 0/0 to

3/0)		Estimated cost		98880.00	
S. N.		Earnest money		2000.00	
Description of Item		Time limit		90 days	
1		Quantity	Rate	Unit	In Words
Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire statisfication of Engineer- in Charge any loss to the public/provate property or any accident etc. happened during the course of hiring period/execution shall by the absolute resonsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less then 17.00 cum per hours to be lifted and snow not less then 15.00 cum per hour to be lifted with in a lead of 200 metre.	96.00	1030.00	Per Hours	Rupees Thousand Only	One Thirty
Total					98880.00


Rupees Ninety Eight Thousand Eight Hundred Eighty Only

Executive Engineer
Salooni Division
HPPWD Salooni

DNIT

Name of work:- Restoration of rain damages on Sundla to Girjindoo road K.M. 0/0 to 36/500 (SH: Removal of slips between K.M. 18/0 to 27/0)

S. N.	Description of item	Quantity	Rate	Estimated cost	
				Time limit	Earnest money
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire statification of Engineer- in Charge any loss to the public/provate property or any accident etc. happened during the course of hiring period/execution shall by the absolute resonsinility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less then 17.00 cum per hours to be lifted and snow not less then 15.00 cum per hour to be lifted with in a lead of 200 metre.	97.00	1030.00	Unit Per Hours	In Words Rupees Thousand Only
				One Thirty	Amount 99910.00
Total					99910.00
Rupees Ninety Nine Thousand Nine Hundred Ten Only					


Executive Engineer
Salooni Division
HPPWD Salooni




DNIT

Name of work:- Restoration of rain damages on Ani near Salooni (Portion Drekri to Sarar) road K.M. 0/0 to 4/900 (SH: Removal of slips between K.M. 0/0 to 4/900)

S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfaction of Engineer- in Charge any loss to the public/provate property or any accident etc. happened during the course of hiring period/execution shall by the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less than 17.00 cum per hours to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	96.00	1030.00	Per Hours	Rupees Thousand Only	98880.00
Total						98880.00

Rupees Ninety Eight Thousand Eight Hundred Eighty Only


 Executive Engineer
 Salooni Division
 HPPWD Salooni




DNIT

Name of work:- Restoration of rain damages on Sundla to Girjindoo road K.M. 0/0 to 36/500 (SH: Removal of slips between K.M. 27/0 to 36/500)

		Estimated cost	
		Earnest money	98880.00
		Time limit	2000.00
			90 days
S. N.	Description of item	Unit	In Words
1		Per	One
		Hours	Thousand
			Only
			Thirty
			Amount
			98880.00
		Total	98880.00

Rupees Ninety Eight Thousand Eight Hundred Eighty Only


Executive Engineer
Salooni Division
HPPWD Salooni



DNI

Name of work:- Restoration of rain damages on Sundla to Girjindoo road K.M. 0/0 to 36/500 (SH: Removal of slips between K.M. 18/0 to 27/0)

S. N.	Description of item	Quantity	Rate	Unit	In Words	Estimated cost
						Earnest money
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfaction of Engineer- in Charge any loss to the public/provate property or any accident etc. happened during the course of hiring period/execution shall by the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less than 17.00 cum per hours to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	97.00	1030.00	Per Hours	Rupees Thousand Only	99910.00
					One Thirty	2000.00
						90 days
Total						99910.00

Rupees Ninety Nine Thousand Nine Hundred Ten Only


Executive Engineer
Salooni Division
HPPWD Salooni




DNIT

Name of work:- Restoration of rain damages on Hutta Ligga Ladwah road K.M. 0/0 to 7/040 (SH: Removal of slips between K.M. 0/0 to 7/040)

Name of work:- Restoration of rain damages on Hurta Ligga Ladwah road K.M. 0/0 to 7/040 (SH: Removal of slips between K.M. 0/0 to 7/040)					DNIT		Estimated cost
S. N.					Earnest money	2000.00	
					Time limit	90 days	
1	Description of item	Quantity	Rate	Unit	In Words	Amount	
	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire statisfication of Engineer- in Charge any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall by the absolute reponsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less then 17.00 cum per hours to be lifted and snow not less then 15.00 cum per hour to be lifted with in a lead of 200 metre.	97.00	1030.00	Per Hours	Rupees Thousand Only One Thirty	99910.00	
Total						99910.00	
Rupees Ninety Nine Thousand Nine Hundred Ten Only							

Rupees Ninety Nine Thousand Nine Hundred Ten Only


Executive Engineer
 Salooni Division
 HPPWD Salooni



DNIT						
Name of work:- Restoration of rain damages on Sundla to Girjindoo road K.M. 0/0 to 36/500 (SH: Removal of slips between K.M. 27/0 to 36/500)						
S. N.	Description of item	Quantity	Rate	Unit	In Words	Amount
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire statification of Engineer- in Charge any loss to the public/provate property or any accident etc. happened during the course of hiring period/execution shall by the absolute resonsinility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less then 17.00 cum per hours to be lifted and snow not less then 15.00 cum per hour to be lifted with in a lead of 200 metre.	96.00	1030.00	Per Hours	Rupees Thousand Only	One 98880.00
Total						98880.00
Rupees Ninety Eight Thousand Eight Hundred Eighty Only						



 Executive Engineer
 Salooni Division
 HPPWD Salooni



DNIT

Name of work:- Restoration of rain damages on Sundla to Girjindoo road K.M. 0/0 to 36/500 (SH: Construction of wire crate Retaining walls at R.D. 26/550 to 26/560)		Estimated cost	93721.00
		Earnest money	2000.00
		Time limit	90 days

S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals.	14.05	564.50	Per Cubic Metre	Rupees Five Hundred Sixty Four And Paise Fifty Only	7931.00
3	Providing and laying boulder apron laid in wire crate with 4mm dia G.I. wire confirming to IS 280 and IS 4826 in 100 mm x100mm (hundred millimeters into hundred millimeters) mesh(woven diagonally) including 10%for laps & joints laid with stone boulders weighing not less than 40Kg (forty kilogram) each in toe walls as per drawing and MORD technical specifications clause 2503 and as per direction of the Engineer - in -Charge including carriage of materials within all leads and lifts and other incidental. The rate also includes octroi,royalty, malkana, toll tax sale tax or other taxes imposed by the Government.	31.20	2738.10	Per Cubic Metre	Rupees Two Thousand Seven Hundred Thirty Eight And Paise Ten Only	85429.00
Total						93360.00
Rupees Ninety Three Thousand Three Hundred Sixty Only						


Executive Engineer
Salooni Division
HPPWD Salooni

Name of work:- Restoration of rain damages on Sundla to Girjindoo road K.M. 0/0 to 36/500 (SH: Construction of wire crate Retaining walls at R.D. 26/540 to 26/550)						Estimated cost
DNIT						93727.00
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals.	14.70	564.50	Per Cubic Metre	Rupees Five Hundred Sixty Four And Paise Fifty Only	8298.00
3	Providing and laying boulder apron laid in wire crate with 4mm dia G.I. wire confirming to IS 280 and IS 4826 in 100 mm x100mm (hundred millimeters into hundred millimeters) mesh(woven diagonally) including 10%for laps & joints laid with stone boulders weighing not less than 40kg (forty kilogram) each in toe walls as per drawing and MORD technical specifications clause 2503 and as per direction of the Engineer - in -Charge including carriage of materials within all leads and lifts and other incidental. The rate also includes octroi,royalty, maikana, toll tax sale tax or other taxes imposed by the Government.	31.20	2738.10	Per Cubic Metre	Rupees Two Thousand Seven Hundred Thirty Eight And Paise Ten Only	85429.00
Total						93727.00
Rupees Ninety Three Thousand Seven Hundred Twenty Seven Only						

Executive Engineer
Salooni Division
HPPWD Salooni

DNIT

Name of work:- Improvement of Black spot on link road Bhalel Matta temple to village Saphan K.M. 0/0 to 4/825 (SH: Improvement of curve at R.D. 2/970 to 3/015)

S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes to level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of un-useful material for filling in road ways, camber, embankments for grade improvements and disposal of all useful material to acquired width of the road or on approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures.. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases. , including carriage of materials with in all leads and lifts. The rate is including octroi, royalty, Malkana,Tol tax, sale tax, GST or other taxes imposed by the Government. The land for dumping sites shall be arranged by the contractor himself and nothing extra shall be paid on this account.	401.26	248.551	Per Cubic Metre	Rupees Two Hundred Forty Eight And Paise Fifty Five Only	99734.00
Total						99734.00

Rupees Ninety Nine Thousand Seven Hundred Thirty Four Only

Executive Engineer
Salooni Division
HPPWD Salooni


DNIT

Name of work:- Improvement of Black spot on link road Bhaiei Matta temple to village Saphan K.M. 0/0 to 4/825 (SH: 1)

Improvement of curve at R.D. 3/015 to 3/073)

S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes to level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of un-useful material for filling in road ways, camber, embankments for grade improvements and disposal of all useful material to acquired width of the road or on approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures.. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases. including carriage of materials with in all leads and lifts. The rate is including octroi, royalty, Malkana, Tol tax, sale tax, GST or other taxes imposed by the Government. The land for dumping sites shall be arranged by the contractor himself and nothing extra shall be paid on this account.	401.56	248.551	Per Cubic Metre	Rupees Two Hundred Forty Eight And Paise Fifty Five Only	99808.00
Total						99808.00

Rupees Ninety Nine Thousand Eight Hundred Eight Only


Executive Engineer
Salooni Division
HPPWD Salooni

81