

Himachal Pradesh
Public Works Department
HP.PWD Division Shahpur Distt. Kangra (H.P)-176206
e-mail id: ee-shahpur-pwd@hp.gov.in
"NOTICE INVITING TENDERS"

Sealed percentage rate tenders on form 6 & 8 are hereby invited by the Executive Engineer Shahpur Division HP.PWD Shahpur on behalf of Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD (B&R) whose registration stood renewed as per revised rules and also registered under in H.P General Sales Tax Act 1968 so as to reach in his office on or before **12-02-2026 up to 11:00 AM.** and the same shall be opened on the same day at **11:30 AM.** in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable on **10-02-2026 to 11-02-2026 up to 4:00 P.M** and the application for issue of tender form shall be received on **10-02-2026 up to 2.00 PM.**

The earnest money in the shape of NSC/FDR/Saving account of the Post office/ Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/incomplete tenders & tenders without earnest money will be summarily rejected. The offer of tender shall be kept open for 75 days.

Sr. No.	Name of work	Estimated Cost	Earnest Money	Time limit	Cost of tender form
1	C/o Retaining wall Gaggal Airport West End to NH-154 Road slope stabilization Vill. Kuthman Tehsil Shahpur (Under Head (SDRF).(S.H:-Removal of slips.)	98900.00	2000.00	One Month	350/-
2	Restoration of Rain Damages on Kutharana to Kareri Road KM 0/00 to 8/720. (S.H:- C/o R/Wall at RD 1/415 to 417.50)	95626.00	2000.00	One Month	350/-
3	Restoration of Rain damage on Harnera to Harnera Bag Road KM 0/00 to 1/500.(S.H:-C/o R/wall at RD 0/800 to 0/806.80)	98205.00	2000.00	One Month	350/-
4	Special Repair of Non Residential Building S.E Office N.H. HP.PWD Circle Shahpur Distt Kangra(H.P).(S.H:- Providing and Laying Floor Tile in 1st floor.)	94530.00	2000.00	One Month	350/-
5	Restoration of Rain Damages on Kutharana to Kareri Road KM 0/00 to 8/720. (S.H:- C/o R/Wall at RD 1/501 to 1/503.50.)	95626.00	2000.00	One Month	350/-
6	Restoration of Rain damage on Harnera to Harnera Bag Road KM 0/00 to 1/500.(S.H:-C/o R/wall at RD 0/810 to 0/816.80)	98205.00	2000.00	One Month	350/-
7	Special Repair of Non Residential Building S.E Office N.H. HP.PWD Circle Shahpur Distt Kangra(H.P).(S.H:- Providing and Laying Floor Tile in Ground floor).	95178.00	2000.00	One Month	350/-
8	C/o Chowari to Bhanala via Machretta road KM 0/00 to 2/750.(S.H:- C/o Brest wall at RD 2/270 to 2/276.50).	96208.00	2000.00	One Month	350/-
9	A/R & M/O Kutharna to Kareri road KM 0/00 to 8/720.(Maintenance of earthen shoulder, cutting of grass & weeds and C/o Unlied Darin etc in between Km 0/000 to 4/00,)	98987.00	2000.00	One Month	350/-
10	A/R & M/O Rulehar to Lam road KM 0/00 to 3/825.(Maintenance of earthen shoulder, cutting of grass & weeds and C/o Unlied Darin etc.)	97517.00	2000.00	One Month	350/-
11	Repair and Restoration of Shahpur Kiari Chatter Road KM 0/00 to 9/00. (S.H:- C/O Unlined Darin surface etc in KM 3/00 to 6/00.)	98538.00	2000.00	One Month	350/-
12	Repair of community Hall near Matti Ward No-04 G.P. in Gharoh.(Deposit work). (S.H:- Providing and Laying Brick masonry and flooring work etc.)	95821.00	1950.00	Two Months	350/-
13	Restoration of Rain Damage on Harnera Mohad Chattari Road Km 0/00 to 9/100 in Tehsil Shahpur, Distt. Kangra (HP) .(S.H:- C/o P.C.C R /Wall at RD 4/391 to 4/395.50)	90249.00	2000.00	Two Months	350/-
14	Recovery and Reconstruction on Bhanalla Pucca Tiala Road KM 0/00 to 3/700.(Under PDNA).(S.H:-C/o C.C. Pavement at RD 2/985 to 3/000)	99160.00	2000.00	Two Months	350/-
15	Repair and Restoration of Shahpur Kiari Chatter Road KM 0/00 to 9/00. (S.H:- C/O Unlined Darin surface etc in KM 0/00 to 3/00.)	98538.00	2000.00	One Month	350/-
16	Repair of community Hall near Matti Ward No-04 G.P. in Gharoh.(Deposit work). (S.H:- Providing and Laying frame work for door & plastering, flooring work etc.)	95701.00	1950.00	Two Months	350/-

17	Restoration of Rain Damage on Harnera Mohad Chattari Road Km 0/00 to 9/100 in Tehsil Shahpur, Distt. Kangra (HP) .(S.H:- C/o R /Wall at RD 4/396.30 to 4/401.60.)	90684.00	1850.00	Two Months	350/-
18	C/o Link road Lam to Roun KM 0/00 to 2/100.(S.H:-Formation cutting at Rd 0/136 to 0/255)	99112.00	2000.00	One Month	350/-
19	Restoration of Rain Damages on Kutharana to Kareri Road KM 0/00 to 8/720. (S.H:- C/o R/Wall at RD 1/418.50 to 1/421.)	95626.00	2000.00	One Month	350/-
20	Restoration of Rain Damage on Harnera Mohad Chattari Road Km 0/00 to 9/100 in Tehsil Shahpur, Distt. Kangra (HP) .(S.H:- C/o P.C.C R /Wall at RD 4/385 to 4/390.30.)	91337.00	2000.00	Two Months	350/-
21	Recovery and Reconstruction on Bhanalla Pucca Tiala Road KM 0/00 to 3/700.(Under PDNA).C/o Irrigation drain at Rd 2/995, P/L WBM G-III from Rd 2/985 to 3/000 and Rd 2/916.30 to 2/930, C/o Double row 300 MM Dia NP3 hume pipe culvert at Rd 2/920 and C/o Single Row 450 MM Dia Np3 hume pipe culvert at Rd 2/850)	95875.00	1950.00	Two Months	350/-
22	C/o Link road Lam to Roun KM 0/00 to 2/100.(S.H:-Formation cutting at Rd 0/061 to 0/135	91281.00	2000.00	One Month	350/-
23	C/o Breast wall Near the Land of Karan Parmar R/O Rehlu Village Skow(Deposit work)S.H:- C/o Breast wall at RDd 0/00 to 0/035).	95557.00	2000.00	One Month	350/-
24	Restoration of Rain Damages on Kutharana to Kareri Road KM 0/00 to 8/720. (S.H:- C/o R/Wall at RD 1/415 to 417.50)	95626.00	2000.00	One Month	350/-
25	C/o Retaining wall Gaggal Airport West End to NH-154 Road slope stabilization Vill. Kuthman Tehsil Shahpur (Under Head (SDRF).(S.H:-Haring of tractor with Trolley).	99000.00	2000.00	One Month	350/-
26	C/o Link road Lam to Roun KM 0/00 to 2/100.(S.H:-Formation cutting at Rd 0/00 to 0/060).	99432.00	2000.00	One Month	350/-
27	Restoration of Rain Damages on Kutharana to Kareri Road KM 0/00 to 8/720. (S.H:- Providing and Laying Kharanja Soling at Various Reaches).	99484.00	2000.00	One Month	350/-
28	A/R & M/O Rulehar to Lam road KM 0/00 to 3/825.(S.H:- Maintenance of earthen shoulder, cutting of grass & weeds and C/o Unlined Darin between portion KM 0/00 to 2/00).	97292.00	2000.00	One Month	350/-
29	A/R & M/O Rulehar to Lam road KM 0/00 to 3/825.(S.H:- Maintenance of earthen shoulder, cutting of grass & weeds and C/o Unlined Darin between portion KM 2/00 to 3/825).	96844.00	2000.00	One Month	350/-
30	C/o Kut to Chamiyara road KM 0/00 to 2/500.(S.H:- C/o unlined Darin surface etc in KM 0/00 TO 1/530).	95550.00	2000.00	One Month	350/-
31	Restoration of Rain damages on Various roads under Darini Sub Division.(S.H:-Hiring of Excavator cum loader under Darini Section.)	99000.00	2000.00	One Month	350/-
32	Restoration of Rain Damage on Harnera Mohad Chattari Road Km 0/00 to 9/100 in Tehsil Shahpur, Distt. Kangra (HP) .(S.H:- C/o R /Wall at RD 4/615 to 4/624)	93809.00	2000.00	Two Months	350/-
33	Restoration of Rain Damage on Harnera Mohad Chattari Road Km 0/00 to 9/100 in Tehsil Shahpur, Distt. Kangra (HP) .(S.H:- C/o R /Wall at RD 4/640 to 4/648.85)	92260.00	2000.00	Two Months	350/-
34	A/R & M/O Salli to Khri bhei road KM 0/00 to 9/525.(S.H:- Maintenance of earthen shoulder, cutting of grass & weeds and C/o Unlined Darin between portion KM 3/00 to 5/00 etc.)	97517.00	2000.00	One Month	350/-
35	C/o Link road Harnera Mohad CHAMDERA kiari Shapur Road Km 0/00 to 13/900 in Tehsil Shahpur, Distt. Kangra (HP)(under MNP).(S.H:-C/o of B/Wall from RD 7/006 to 7/011) .	99104.00	2000.00	Two Months	350/-
36	Restoration of Rain Damage on Harnera Mohad Chattari Road Km 0/00 to 9/100 in Tehsil Shahpur, Distt. Kangra (HP) .(S.H:- C/o R /Wall at RD 4/630 to 4/638.90).	92774.00	2000.00	Two Months	350/-
37	C/o Harnera Mohad Chamdera Kiari Shahpur road KM 0/00 to 13/900 in Tehsil Shahpur Distt Kangra (H.P).S.H:- C/o B/wall at RD 6/695 to 7/005).	99820.00	2000.00	Two Months	350/-
38	A/R & M/O Salli to Khri bhei road KM 0/00 to 9/525.(S.H:- Maintenance of earthen shoulder, cutting of grass & weeds and C/o Unlined Darin between portion KM 1/00 to 2/00 etc).	97517.00	2000.00	One Month	350/-
39	C/o Link road from Martroti to Bharun including vridge over Chambi khad KM 0/00 to 4/800(Under NABARD).(S.H:- Providing , fixing aand Painting of kilometre stone ,Writing letters etc),	99485.00	2000.00	Two Months	350/-
40	Special repair of Vetnary Hospital Gohju in Tehsil Shahpur at Distt. Kangra Himachal Pradesh.(S.H:-C/o Boundary wall.)	99786.00	2000.00	Two Months	350/-

41	A/R & M/O Salli to Khri bhei road KM 0/00 to 9/525.(S.H:- Maintenance of earthen shoulder, cutting of grass & weeds and C/o Unlined Darin between portion KM 6/00 to 8/00 etc).	97068.00	2000.00	One Month	350/-
42	Restoration of Rain Damages on Kutharana to Kareri Road KM 0/00 to 8/720. (S.H:- C/o R/Wall at RD 1/495 to 1/497.50.)	95626.00	2000.00	One Month	350/-
43	C/o Harnera Mohod Chamdera Kiari Shahpur road KM 0/00 to 13/900 in Tehsil Shahpur Distt Kangra (H.P).under MNP)S.H:- C/o B/wall at RD 7/012 to 7/019.20).	97046.00	2000.00	Two Months	350/-
44	C/o Kut to Chamiyara road KM 0/00 to 2/500.(S.H:- C/o unlined Darin surface etc in KM 0/00 TO 1/535).	98493.00	2000.00	One Month	350/-
45	C/o Harnera Mohod Chamdera Kiari Shahpur road KM 0/00 to 13/900 in Tehsil Shahpur Distt Kangra (H.P).under MNP)S.H:- C/o B/wall at RD 7/021 to 7/026).	99220.00	2000.00	Two Months	350/-
46	C/o Link road Bair Dramman to Yol Macchial KM 0/00 TO 1/00.(S.H:- Formation cutting in KM 0/200 to 0/400).	97150.00	2000.00	One Month	350/-
47	C/o Link road Harnera Mohar Chamdera Chattri Pehad Km 0/00 to 9/100 in Tehsil Shahpur, Distt. Kangra (HP).(under MNP) (S.H:- C/o of B/Wall from Rd 7/027to 7/034.15).	98154.00	2000.00	Two Months	350/-
48	Special Repair of Non Residential Building S.E Office N.H. HP.PWD Circle Shahpur Distt Kangra(H.P).(S.H:- Providing and Laying Floor Tile in 1st floor)	94286.00	2000.00	One Month	350/-
49	Recovery and Reconstruction on Bhanalla Pucca Tiala Road KM 0/00 to 3/700.(Under PDNA).(S.H:- C/o C.C. Pavement at RD 2/916.30 to 2/930).	99458.00	2000.00	Two Months	350/-
50	Restoration of Rain Damages on Kutharana to Kareri Road KM 0/00 to 8/720. (S.H:- C/o R/Wall at RD 1/422 to 1/424.50.)	95626.00	2000.00	One Month	350/-
51	C/o Link road Bair Dramman to Yol Macchial KM 0/00 TO 1/00.(S.H:- Formation cutting in KM 0/00 to 0/200).	98600.00	2000.00	One Month	350/-
52	Restoration of Rain damages on Various roads under Shahpur Sub Division.(S.H:-Hiring of Excavator cum loader under Shahpur Section).	99000.00	2000.00	One Month	350/-
53	Restoration of Rain Damages on Kutharana to Kareri Road KM 0/00 to 8/720. (S.H:- C/o R/Wall at RD 1/425 to 1/429.50.)	95626.00	2000.00	One Month	350/-
54	A/R & M/O Various road under Gaggal Sub Division.(S.H:- Painting and writing letters, figures Kilometres stone etc.)	99470.00	2000.00	One Month	350/-
55	C/o Chowari to Bhanala via Machretta road KM 0/00 to 2/750.(S.H:- C/o Brest wall at RD 2/277.60 to 2/285).	97503.00	2000.00	One Month	350/-
56	C/o Link road Harnera Mohar Chamdera Chattri Pehad Km 0/00 to 9/100 in Tehsil Shahpur, Distt. Kangra (HP).(under MNP) (S.H:- C/o of B/Wall from Rd 7/130 to 7/137.50 on R/ side of gully)	97188.00	2000.00	Two Months	350/-
57	C/o Link road Bair Dramman to Yol Macchial KM 0/00 TO 1/00.(S.H:- Formation cutting in KM 0/400 to 0/600).	95700.00	2000.00	One Month	350/-
58	Special Repair to the office Cum Residence Junior Engineer in HP.PWD Darini.(S.H:-Painting and Destempering)	97949.00	2000.00	One Month	350/-
59	C/o Link road Harnera Mohar Chamdera Chattri Pehad Km 0/00 to 9/100 in Tehsil Shahpur, Distt. Kangra (HP).(under MNP) (S.H:- C/o of B/Wall from Rd 7/120 to 7/128 on R/ side of gully)	98222.00	2000.00	Two Months	350/-
60	Restoration of Rain Damage on Rajol Ansuie Charri Road KM 0/00 to 4/235.(S.H:-C/o Wire create at RD 4/020 to 4/025)	85290.00	2000.00	Two Months	350/-
61	Restoration of Rain damages on Shahpur Chakban Lapiyana road KM 0/00 to 20/500 (S.H:-Hiring of Excavator cum loader)	99000.00	2000.00	One Month	350/-
62	C/o Retaining wall Gaggal Airport West End to NH-154 Road slope stabilization Vill. Kuthman Tehsil Shahpur (Under Head (SDRF).(S.H:-Removal of Debris in the Banoi Khad).	98860.00	2000.00	One Month	350/-
63	Restoration of Rain Damage on Rajol Ansuie Charri Road KM 0/00 to 4/235.(S.H:-C/o Wire create at RD 4/026 to 4/030).	88751.00	2000.00	Two Months	350/-
64	A/R & M/O Rulehar to Lam Road km 0/000 to 3/880.(S.H:- Maintenance of earthen shoulder, cutting of grass & weeds and C/o Unlined Drain etc)	97517.00	2000.00	One Month	350/-
65	Restoration of Rain Damage on Rajol Ansuie Charri Road KM 0/00 to 4/235.(S.H:-C/o Wire create at RD 4/036 to 4/040)	87139.00	2000.00	Two Months	350/-

66	A/R & M/O Kutharna to Kareri Road km 0/000 to 8/720.(S.H:-Maintenance of earthen shoulder, cutting of grass & weeds and C/o Unlined Drain at KM 0/00 TO 4/000)	97517.00	2000.00	One Month	350/-
67	C/o Shahpur Majiar Road KM 0/00 to 1/500.(S.H:-C/o R/Wall at Rd 1/106.10 to 1/111.20).	97119.00	2000.00	One Month	350/-
68	C/o Retaining wall Gaggal Airport West End to NH-154 Road slope stabilization Vill. Kuthman Tehsil Shahpur (Under Head (SDRF).(S.H:-Removal of Debris in the Banoi Khad).	98750.00	2000.00	One Month	350/-
69	Landslide Disaster Realed Mitigation work on Salli to Khari Behi Road KM 0/00 to 9/570.(S.H:-C/o Edge Wall at Rd 2/816 to 2/828.)	89261.00	2000.00	One Month	350/-
70	Restoration of Rain Damage on Rajol Ansuie Charri Road KM 0/00 to 4/235.(S.H:-C/o Wire create at RD 4/031 to 4/035).	88114.00	2000.00	Two Months	350/-
71	Construction of Darini to Jhaniyana road KM 0/00 to 2/00.(S.H:- Construction of R/wall in G.I. Wire crete at RD 0/092 to 0/102).	99933.00	2000.00	Two Months	350/-
72	C/o Shahpur Majiar Road KM 0/00 to 1/500.(S.H:-C/o R/Wall at Rd 1/100 to 1/105.10).	97119.00	2000.00	One Month	350/-
73	Construction of Darini to Jhaniyana road KM 0/00 to 2/00.(S.H:- Construction of R/wall in G.I. Wire crete at RD 0/080 to 0/090).	99916.00	2000.00	Two Months	350/-

Certified that tender of above works are being called of urgent nature in public interest.

Terms & Conditions: -

1. The contractor/firm should be produce the attested copy of latest enlistment and renewal enlistment in HP.PWD. GST No. and EPF No. with the application falling which their application will not be entertained.
2. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
3. The Earnest Money for the above works should be required at the time of sale of tender forms.
4. The Contractor/Firms should be quoted percentage rate in the tender both in figures and in words failing which tender is likely to be rejected.
5. The Executive Engineer reserves the right to accept/reject any tender/application or all tender without assigning any reason.

Executive Engineer
Shahpur Division
HP.PWD Shahpur.

(on behalf of Governor of Himachal Pradesh)

Dated: 05/02/2026

No.PWD/SD/Tender/NIT/2025-26/- 1968 - 77

Copy to following for information and necessary action:-

1. The Superintending Engineer 5th Circle HP.PWD Palampur.
2. The Executive Engineer (IT) Nigam Vihar Shimla. He is requested to upload the same on the department website.
3. All the Assistant Engineer under this Division.
4. The Drawing/Accounts Branch in this office.
5. Notice Board

Executive Engineer
Shahpur Division
HP.PWD Shahpur.

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 98900.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT :- One Month

NAME OF WORK :- C/o Retaining wall Gaggaal Airport West End to NH-154 Road slope stabilization Vill. Kuthman Tehsil Shahpur (Under Head (SDRF))

SUB-HEAD :- Removal of slips.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In Fig	In words		
1	Removal of sand slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and turning of slips and disposal of cut material with in lift upto 1.5m and lead upto 1000m as per technical specification 302.5 and 1611 as per direction of Engineer in Charge including carriage of materials with in all loads, lifts and other incidental. The rate is including octroi, royalty, Malkana toll tax, Sale tax, on any type of taxes imposed by the Government.	3	1536.06	60.45 Rupees Sixty And Paise Forty Five Only	Per Cubic Metre	98900.00
		TOTAL :-		98900.00		
		Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)		
		Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)		

HPWD
Executive Engineer,
Shahpur Division,
HPWD Shahpur

SCHEDULE OF QUANTITY

NAME OF WORK :-
SUB-HEAD :-

Restoration of Rain damages on Kutharana to Kareeri road KM 0/00 to 18.720.
C/o R/Wall at RD 1/497 to 1/500.)

ESTIMATED COST :- ₹ 95626.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : One Month

(2)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 1-805.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3	4	5	6	7
		4.98	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	1743.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-Charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	18.20	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	86450.00
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials within all leads, lifts and other incidentals. The rates including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	5.45	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	4633.00

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1		3	4	5	6	7
4	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	8.00	350.00	Rupees Three Hundred Fifty Only	Each	2800.00
TOTAL :-						95626.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shajapur

SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 98205.00
EARNEST MONEY:- ₹ 2000.00
TIME LIMIT : One Month

NAME OF WORK :- Restoration of Rain damages on Harnera to Harnera Bag road KM 0/00 to 1/500.
SUB-HEAD :- C/o Retaining wall at RD 0/800 to 0/806.80.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	13.50	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	4725.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	17.81	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	84598.00
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	5.92	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	5032.00

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1		3	4	5	6	7
4	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope 1(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	11.00	350.00	Rupees Three Hundred Fifty Only	Each	3850.00
TOTAL :-						98205.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

NAME OF WORK :-

Special Repair of Non Residential Building S.E. Office N.H. HP. PWD Circle Shahpur Dist Kangra (H.P.).
SUB-HEAD :- Providing and Laying Floor Tile in 1st floor.

ESTIMATED COST :- ₹ 94530.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT :- One Month

(4)

S. No.	Description of Items	Quantity	RATES			Unit	Amount
			In fig	In words			
1	1	3	4	5	6	7	
1	Dismantelling Plain cement concrete manually/ mechanically including disposal of rubbish within all lead and lift as per direction of Engineer in charge. as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of toll tax, GST and any other taxes imposed by the government.	37.60	950.00	Rupees Nine Hundred Fifty Only	Per cubic metre	35720.00	
2	Providing and laying Size of (600x 600mm) Double charged/Ultra charged vetrified tiles of Restile/Nitco /Rak/Kajaria / Orient -Bell/AGL/Simplo /Johnson/Somany/ Orient & Bell as per approved shade and design of the office in flooring (thickness to be specified by the manufacturer) with water absorption less than 0.08% (zero decimal zero eight percentage) and conforming to IS: 15622, of approved make, In all colours and shades, laid on 20mm (twenty millimetres) thick cement mortar 1:4 (one cement isto four coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm (three decimal three kilogram per squaremetre) including grouting the joints with white cement and matching pigments etc., complete as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material withineall leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government	32.10	1570.50	Rupees One Thousand Five Hundred Seventy And Paise Fifty Only	Per Square metre	50413.00	
3	Providing and laying Size of (600x 600mm) Double charged/Ultra charged vetrified tiles of Restile/Nitco /Rak/Kajaria / Orient -Bell/AGL/Simplo /Johnson/Somany/ Orient & Bell as per approved shade and design of the office in skirting (thickness to be specified by the manufacturer) with water absorption less than 0.08% (zero decimal zero eight percentage) and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm (twenty millimetres) thick cement mortar 1:3 (one cement isto three coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm (three decimal three kilogram per squaremetre) including grouting the joints with white cement and matching pigments etc., complete as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material withineall leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	5.56	1510.20	Rupees One Thousand Five Hundred Ten And Paise Twenty Only	Per Square metre	8397.00	
TOTAL :-							94530.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)					
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)					

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY


NAME OF WORK :-
SUB-HEAD :-

Restoration of Rain damages on Kuthuraga to Kareri road KM 0/00 to 18.720.
C/o R/Wall at RD 1/501 to 1/503.50.)

ESTIMATED COST:- ₹ 95626.00
EARNEST MONEY:- ₹ 2000.00
TIME LIMIT :- One Month

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3	4.98	Rupees Three Hundred Fifty Only	Per cubic metre	1743.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	18.20	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	86450.00
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	5.45	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	4633.00

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1		3	4	5	6	7
4	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORR technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	8.00	350.00	Rupees Three Hundred Fifty Only	Each	2800.00
TOTAL :-						95626.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 98205.00
EARNEST MONEY:- ₹ 2000.00
TIME LIMIT : One Month

NAME OF WORK :- Restoration of Rain damages on Harnera to Harnera Bag road KM 0/90 to 1/500.
SUB-HEAD :- C/o Retaining wall at RD 0/810 to 0/816.80.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3	4	5	6	7
1		13.50	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	4725.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement :sto Four sand :sto Eight Graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	17.81	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	84598.00
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	5.92	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	5032.00

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
4	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain /, reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	3	11.00	Rupees Three Hundred Fifty Only	Each	3850.00
TOTAL :-						98205.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				



 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 95178.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : One Month

NAME OF WORK :- Special Repair of Non Residential Building S.E. Office N.H. HP.PWD Circle Shahpur Distt Kangra(H.P.).
SUB-HEAD :- Providing and Laying Floor Tile in Ground floor.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Dismantelling Plain cement concrete manually/ mechanically including disposal of rubbish within all lead and lift as per direction of Engineer in charge. as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of toll tax, GST and any other taxes imposed by the government.	37.72	950.00	Rupees Nine Hundred Fifty Only	Per cubic metre	35834.00
2	Providing and laying Size of (600x 600mm) Double charged/Ultra charged vetrified tiles of Restile/Nitco /Rak/Kajaria / Orient -Bell/AGL/Simplo /Johnson/Somany/ Orient & Bell as per approved shade and design of the office in flooring (thickness to be specified by the manufacturer) with water absorption less than 0.08% (zero decimal zero eight percentage) and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm (twenty millimetres) thick cement mortar 1:4 (one cement isto four coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm (three decimal three kilogram per squaremetre) including grouting the joints with white cement and matching pigments etc., complete as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government	32.44	1570.50	Rupees One Thousand Five Hundred Seventy And Paise Fifty Only	Per Squire metre	50947.00
3	Providing and laying Size of (600x 600mm) Double charged/Ultra charged vetrified tiles of Restile/Nitco /Rak/Kajaria / Orient -Bell/AGL/Simplo /Johnson/Somany/ Orient & Bell as per approved shade and design of the office in skirting (thickness to be specified by the manufacturer) with water absorption less than 0.08% (zero decimal zero eight percentage) and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm (twenty millimetres) thick cement mortar 1:3 (one cement isto three coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm (three decimal three kilogram per squaremetre) including grouting the joints with white cement and matching pigments etc., complete as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	5.56	1510.20	Rupees One Thousand Five Hundred Ten And Paise Twenty Only	Per Squire metre	8397.00
TOTAL :-						95178.00
	Quoted Rate in Figure (%)			(Amount to be quoted by the contractor in Figure)		
	Quoted Rate in Words (%)			(Amount to be quoted by the contractor in words)		


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 96208.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- 1 Pre Month

NAME OF WORK :-

C/o Chowari to Bhanala via Machhreta road KM 0/00 to 2/750.

SUB-HEAD :-

C/o Breast wall at RD 2/270 to 2/276.50.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORO technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	16.45	350.00	Rupees Three Hundred Fifty Only	Per cubic Metre	5758.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORO technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-Charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	18.60	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic Metre	88350.00
3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORO technical specification section 700 and 1200 and as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	6.00	350.00	Rupees Three Hundred Fifty Only	Each	2100.00
TOTAL :-						96208.00
	Quoted Rate in Figure (%)	0	(Amount to be quoted by the contractor in Figure)			
	Quoted Rate in Words (%)	0	(Amount to be quoted by the contractor in words)			

Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 98987.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : One Month

NAME OF WORK :- A/R & M/O Kuthama to Kareel Road km 0/000 to 8/720

SUB-HEAD :- Maintenance of earthen shoulder, cutting of grass & weeds and C/o Unlined Drain etc in between km 0/000 to 4/00.

S No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Clearing and grubbing road land including uprooting wild vegetation, grass, bushes, strubs, saplings and trees of girth upto 300mm removal of stumps of such trees cut earlier and disposal of unserviceable material and stacking of serviceable material to be used or auctioned upto a lead of 1000 meters including removal and disposal of top organic soil not exceeding 150 mm in thickness as per technical specification clause 201 and as per direction of Engineer in charge with in all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	0.52	22440.10	Rupees Twenty Two Thousand Four Hundred Forty And Paise Ten Only	Per Hecor	11669.00
2	C/O Shoulder (filling with fresh soil) Making up loss of material/ irregularities on shoulder to the design level by adding fresh approved soil and compacting it with appropriate equipment. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	4680.00	7.35	Rupees Seven And Paise Thirty Five Only	Per square metre	34398.00
3	GST or any other taxes imposed by the Government. Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307.. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	1800.00	29.40	Rupees Twenty Nine And Paise Forty Only	Per Running metre	52920.00
TOTAL :-						98987.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

(9)

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 97517.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT :- One Month

NAME OF WORK :-
SUB-HEAD :-

A/R & M/O Rulehar to Lam Road km 0/000 to 3/825.
Maintenance of earthen shoulder, cutting of grass & weeds and C/O Unlined Drain etc.

S No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	12 Cleaning and grubbing road land including uprooting wild vegetation, grass, bushes, strubs, saplings and trees of girth upto 300mm removal of stumps of such trees cut earlier and disposal of unserviceable material and stacking of serviceable material to be used or auctioned upto a lead of 1000 meters including removal and disposal of top organic soil not exceeding 150 mm in thickness as per technical specification clause 201 and as per direction of Engineer in charge with in all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	3 0.52	4 22440 10	5 Rupees Twenty Two Thousand Four Hundred Forty And Paise Ten Only	6 Per Hector	7 1669.00
2	C/O Shoulder (filling with fresh soil) Making up loss of material/ irregularities on shoulder to the design level by adding fresh approved soil and compacting it with appropriate equipment. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	4680.00	7.35	Rupees Seven And Paise Thirty Five Only	Per square metre	34398.00
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307.. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	1750.00	29.40	Rupees Twenty Nine And Paise Forty Only	Per Running metre	51450.00
TOTAL :-						97517.00
	Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)			
	Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)			

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 98538.00
EARNEST MONEY :- ₹ 2000.00
One Month
TIME LIMIT

NAME OF WORK :- Repair and Restoration of Shahpur Kiarl Chattrer Road km 0/000 to 9/00.

SUB-HEAD :- C/o Unlined Drain surface etc in km 3/00 to 6/00.

S No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Clearing and grubbing road land including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm removal of stumps of such trees cut earlier and disposal of unserviceable material and stacking of serviceable material to be used or auctioned upto a lead of 1000 meters including removal and disposal of top organic soil not exceeding 150 mm in thickness as per technical specification clause 201 and as per direction of Engineer in charge with in all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	0.50	22440.10	Rupees Twenty Two Thousand Four Hundred Forty And Paise Ten Only	Per Hector	11220.00
2	C/O Shoulder (filling with fresh soil) Making up loss of material/irregularities on shoulder to the design level by adding fresh approved soil and compacting it with appropriate equipment. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	4680.00	7.35	Rupees Seven And Paise Thirty Five Only	Per square metre	34398.00
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	1800.00	29.40	Rupees Twenty Nine And Paise Forty Only	Per Running metre	52920.00
TOTAL :-						98538.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

[Signature]
Executive Engineer,
Shahpur Division,
HPPWD Shahpur

DRAFT-SCHEDULE OF QUANTITY

NAME OF WORK :-

Repair of community Hall near Matti ward No-04 In G.P Charoh. (Deposit work).

SUB-HEAD :-

Providing and laying Brick masonry and flooring work etc.

ESTIMATED COST: - ₹ 95821.00
EARNEST MONEY: - ₹ 1950.00
TIME LIMIT : Two Months

(12)

343

(1)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Second class brick work using common burnt clay building bricks in super-structure upto all floor level in cement mortar 1:6 (One cement isto six sand) and curing complete within all leads, lifts of materials and other incidentals, as per approved specification, drawing, design and as directed by the Engineer-In-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	12.30	6850.00	Rupees Six Thousand Eight Hundred Fifty Only	Per cubic metre	84255.00
2	Providing and laying Size of (600x 600mm) verified tiles of Restile/Nitco /Rak/Kajania / Orient -Bell/G/L/Simplo /Johnson/Somanyas per approved shade and design of the office (thickness to be specified by the manufacturer) with water absorption less than 0.08% (zero decimal zero eight percentage) and conforming to IS- 15622, of approved make, in all colours and shades, laid on 20mm (twenty millimetres) thick cement mortar 1:4 (one cement isto four coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm (three decimal three kilogram per squaremetre) including grouting the joints with white cement and matching pigments etc., complete as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-In-Charge including cartage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	8.50	1360.70	Rupees One Thousand Three Hundred Sixty And Paise Seventy Only	Per square metre	11566.00
TOTAL :-						95821.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

[Signature]

SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 90249.00
EARNEST MONEY:- ₹ 1850.00
TIME LIMIT Two Months

(13)

NAME OF WORK :- Restoration of Rain Damage on Harnera Mohad Chattrai Road Km 0/00 to 9/100 In Tehsil Shahpur, Distt. Kangra (HP).
SUB-HEAD :- C/o P.C.C. R /Wall at RD 4/391 to 4/395.50.

S No.	Description of Items	Quantity	RATES			Unit	Amount
			In fig	In words			
1	2	3	4	5	6	7	
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	6.74	350.00	Rupees Three Hundred Fifty Only	Pcf cubic metre	2359.00	
2	Providing and laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:5:10 (One cement isto five sand isto ten graded/crushed stone aggregate) 40mm (forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	19.40	4350.00	Rupees Four Thousand Three Hundred Fifty Only	Pcf cubic metre	84390.00	
3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope 1(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	10.00	350.00	Rupees Three Hundred Fifty Only	Each	3500.00	
TOTAL :-							90249.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)					
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)					

Executive Engineer,
Shahpur Division,
Shahpur


SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99150.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- Two Months

NAME OF WORK :- Recovery and Reconstruction on Bhanalla Pucca Tiala Road KM 0/00 to 3/700.(Under PDNA).

SUB-HEAD :- C/o C.C. Pavement at RD 2/985 to 3/000.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Construction of panel concrete plain cement concrete pavement, thickness as per design, over a prepared sub-base with 43 Grade cement or any other type as per clause 1501.2.2 M30 Grade course and fine aggregate conforming to IS: 383. Maximum size of coarse aggregate not exceeding 25mm, mixed in a concrete mixer of not less than 0.2 Cum capacity and appropriate weight batcher using approved mix design, laid in approved fixed side framework (Steel channel , laying and fixing of 125 micron thick Polythene film, wedges steel plates including levelling form work as per drawing), spreading the concrete with shovels/rakes, compacting using roller, screed and plate vibrators and finishing continuous operation including provision of contraction and expansion, construction joints, applying debonding strips , primer, sealant ,dowel bars, nera approaches to bridge/culverts and construction joints, admixtures as approved, curing of slab for 14 days, Curing compound (Where specified) and water specified to lines and grade as per drawing and technical specifications clause 1501.PCC Grade M-30 Each panels (1.25x1.25) Thickness 160mm. as per the entire satisfaction and directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, and any other taxes imposed by the Government but excluding GST.	13.31	7450.00	Rupees Seven Thousand Four Hundred Fifty Only	Per cubic metre	99150.00
TOTAL :-						99150.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD, Shahpur

15

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 98538.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT One Month

NAME OF WORK :- Repair and Restoration of Shabpur Kiari Chattrer Road km 0/000 to 9/00.
SUB-HEAD :- C/o Unlined Drain surface etc in km 0/00 to 3/00.

S No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Clearing and grubbing road land including uprooting wild vegetation, grass, bushes, strubs, saplings and trees of growth upto 300mm removal of stumps of such trees cut earlier and disposal of unserviceable material and stacking of serviceable material to be used or auctioned upto a lead of 1000 meters including removal and disposal of top organic soil not exceeding 150 mm in thickness as per technical specification clause 201 and as per direction of Engineer in charge with in all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	0.50	22440.10	Rupees Twenty Two Thousand Four Hundred Forty And Paise Ten Only	Per Hectar	11220.00
2	C/O Shoulder (filling with fresh soil) Making up loss of material irregularities on shoulder to the design level by adding fresh approved soil and compacting it with appropriate equipment. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	1800.00	29.40	Rupees Twenty Nine And Paise Forty Only	Per Running metre	52920.00
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307.. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.					
TOTAL :-						98538.00
Quoted Rate in Figure (%)						
Quoted Rate in Words (%)						

Executive Engineer,
Shabpur Division,
HPPWD Shabpur

SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 95701.00
EARNEST MONEY:- ₹ 1950.00
TIME LIMIT : Two Months

NAME OF WORK :-

Repair of community Hall near Matti ward No-04 in G.P Gharoh.(Deposit work).

SUB-HEAD :-

Providing and laying frame work for door & plastering, flooring work etc.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	15 mm (Fifteen millimeter) thick cement plaster in single coat on rough side of brick/concretes/ stone walls for interior plastering up to all floor levels including arises, internal angles, chamfers and rounded angles not exceeding 80mm (Eighty millimeter) in girth and finished even and smooth with cement mortar 1:5 (One cement isto six sand) as per specifications, approved drawing, design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	139.61	230.50	Rupees Two Hundred Thirty And Paise Fifty Only	Per cubic metre	32180.00
2	Providing and laying Size of (600x 600mm) vetrified tiles of Restile/Nitco /Rak/Kajaria / Orient -Bell/AGUSimplo (Johnson/Somanyas per approved shade and design of the office (thickness to be specified by the manufacturer) with water absorption less than 0.08% (zero decimal zero eight percentage) and conforming to IS- 15622, of approved make, in all colours and shades, laid on 20mm (twenty millimetres) thick cement mortar 1:4 (one cement isto four coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm (three decimal three kilogram per squaremetre) including grouting the joints with white cement and matching pigments etc., complete as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	27.67	1360.70	Rupees One Thousand Three Hundred Sixty And Paise Seventy Only	Per square metre	37651.00
3	Providing 2nd class Decdar wood wood work in frames of doors,windows,clerestory,windows and other frames wrought,framed and fixed in position. within all leads, lifts of materials and other incidentals, as per approved specification, drawing, design and as directed by the Engineer-In-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	0.26	99500.00	Rupees Ninety Nine Thousand Five Hundred Only	Per cubic metre	25870.00
TOTAL :-						95701.00
(Amount to be quoted by the contractor in Figure)						
(Amount to be quoted by the contractor in words)						
Quoted Rate in Figure (%)						
Quoted Rate in Words (%)						

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

[Signature]

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 90684.00
EARNEST MONEY :- ₹ 1850.00
TIME LIMIT Two Months

NAME OF WORK :- Restoration of Rain Damage on Harnera Mohad Chaitani Road Km 0/00 to 9/100 In Tehsil Shahpur, Distt. Kangra (HP).

SUB-HEAD :- C/O P.C.C R/Well at RD 4/396.30 to 4/401.60.

SUB-HEAD :-		C/o P.C.C. R/Wall at RD 4/396.30 to 4/401.60.				
Description of items		Quantity	RATES	Unit	Amount	
S. No.			In fig	In words		
1	2	3	4	5	6	
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	6.74	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	2359.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:5:10 (One cement isto five sand isto ten graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	19.50	4350.00	Rupees Four Thousand Three Hundred Fifty Only	Per cubic metre	84825.00
3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope 1(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	10.00	350.00	Rupees Three Hundred Fifty Only	Each	3500.00
		TOTAL :-				90684.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Kiran Khandelwal
Executive Engineer,
Shahpur Division,
Himachal Pradesh

SCHEDULE OF QUANTITY

(18)

ESTIMATED COST:- ₹ 99112.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : One Month


NAME OF WORK :-

C/o Link road Lam to Roun KM 0/00 to 2/100.

SUB-HEAD :-

Formation cutting at Rd 0/136 to 0/255.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1		3	4	5	6	7
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock, chiseling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required lines, grades, cutting and trimming of side slopes and level as shown in the drawing and as directed by engineer-in-charge at site according to the MORD technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to the approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour if required. All useful material such as stones shingle, aggregate and slates etcetra shall be sorted out and stacked in proper stack. Any loss to the public, private / property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be compensated by him in all cases including carriage of materials within all leads and lifts and other incidentals The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	381.20	260.00	Rupees Two Hundred Sixty Only	Per cubic metre	99112.00
TOTAL :-						99112.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahnur Division,
 HPPWD Sharnur

SCHEDULE OF QUANTITY

(19)

NAME OF WORK :-
SUB-HEAD :-

Restoration of Rain damages on Kutharana to Kareri road KM 0/00 to 18.720.
C/o R/Wall at RD 1/418.50 to 1/421.

ESTIMATED COST:- ₹ 95626.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : One Month

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm, one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3	4	5	6	7
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	18.20	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	86450.00
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	5.45	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	4633.00

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
4	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope 1(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	8.00	350.00	Rupees Three Hundred Fifty Only	Each	2800.00
TOTAL :-						95626.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 91337.00
EARNEST MONEY :- ₹ 1850.00
TIME LIMIT Two Months

(20)

NAME OF WORK :- Restoration of Rain Damage on Harnera Mohad Chattrari Road Km 0/00 to 9/100 in Tehsil Shahpur, Distt. Kangra (HP).
SUB-HEAD :- C/o P.C.C. R/Wall at RD 4/385 to 4/390.30.

5. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	6.74	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	2359.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:5:10 (One cement isto five sand isto ten graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	19.65	4350.00	Rupees Four Thousand Three Hundred Fifty Only	Per cubic metre	85478.00
3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	10.00	350.00	Rupees Three Hundred Fifty Only	Each	3500.00
TOTAL :-						91337.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
Dehra Shahpur

SCHEDULE OF QUANTITY

21

ESTIMATED COST :- ₹ 95875.00
EARNEST MONEY :- ₹ 1950.00
TIME LIMIT : Two Months

NAME OF WORK :-

Recovery and Reconstruction on Bhanalla Pucca Tiala Road KM 0/00 to 3/700, (Under PDNA).

SUB-HEAD :-

C/o Irrigation drain at Rd 2/995, P/L WBM G-II from Rd 2/985 to 3/000 and Rd 2/916.30 to 2/930, C/o Doublr row 300 MM Dia NP3 hume pipe culvert at Rd 2/920 and C/o Single Row 450 MM Dia NP3 hume pipe culvert at Rd 2/850.

S. No.	Description of Items	Quantity	RATES			Unit	Amount
			In fig	In words			
1	2	3	4	5	6	7	
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	10.35	350.00	Rupees Three Hundred Fifty Only	Per cubic Metre	3623.00	
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-Charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	1.54	4850.00	Rupees Four Thousand Eight Hundred Fifty Only	Per cubic Metre	7469.00	
3	Providing and laying (to level or slope) 300 mm dia (Four hundred fifty millimetres) diameter reinforced cement concrete heavy duty non pressure pipes IS Class NP3 for culverts on first class bedding of granular material in single row including providing and fixing collar with cement mortar 1 : 2 (One cement : two sand) but excluding the cost of excavation, protection works, back filling, concrete bedding and masonry work in head walls and parapets as per drawing and M.O.R.D. technical specifications section 1102 and as per direction of Engineer - in- Charge including carriage of materials within all leads, lifts and other incidental . The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government (labour Rate).	5.00	450.00	Rupees Four Hundred Fifty Only	Per Running Metre	2250.00	

4	Providing and laying (to level or slope) 450 mm dia (Four hundred fifty millimetres) diameter reinforced cement concrete heavy duty non pressure pipes IS Class NP3 for culverts on first class bedding of granular material in single row including providing and fixing collar with cement mortar 1 : 2 (One cement : two sand) but excluding the cost of excavation, protection works, back filling, concrete bedding and masonry work in head walls and parapets as per drawing and M.O.R.D. technical specifications section 1102, and as per direction of Engineer – in- Charge including carriage of materials within all leads, lifts and other incidental . The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government (labour Rate).	10.00 M	225.50	Rupees Two Hundred Twenty Five And Paise Fifty Only	Per Running Metre	2255.00
5	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall ectetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	5.28 M	5400.00	Rupees Five Thousand Four Hundred Only	Per cubic Metre	28512.00
6	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-all size (75mm) seventy five millimeters) compacted thickness to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	10.16 M	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic Metre	22860.00
7	Construction of panel concrete plain cement concrete pavement, thickness as per design, over a prepared sub-base with 43 Grade cement or any other type as per clause 1501.2.2 M30 Grade course and fine aggregate conforming to IS: 383. Maximum size of coarse aggregate not exceeding 25mm, mixed in a concrete mixer of not less than 0.2 Cum capacity and appropriate weight batcher using approved mix design, laid in approved fixed side framework (Steel channel), laying and fixing of 125 micron thick Polythene film, wedges steel plates including levelling form work as per drawing), spreading the concrete with shovelstrakes, compacting using neel, screed and plate vibrators and finishing continuous operation including provision of contraction and expansion, construction joints, admixtures as approved, curing, primer, sealant, dowel bars, nera approaches to bridge/culverts and construction joints, applying debonding strips of slab for 14 days, Curing compound (Where specified) and water specified to lines and grade as per drawing and technical specifications clause 1501.PCC Grade M-30 Each panel(1.25x1.25) Thickness 160mm. as per the entire satisfaction and directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, and any other taxes imposed by the Government but excluding GST.	3.88 M	7450.00	Rupees Seven Thousand Four Hundred Fifty Only	Per cubic Metre	28906.00
		87	TOTAL :-			
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				
		95875.00				

Executive Engineer,
Shanpur Division,
HPPWD Shanpur

SCHEDULE OF QUANTITY

22

ESTIMATED COST:- ₹ 91281.00
 EARNEST MONEY:- ₹ 2000.00
 TIME LIMIT : One Month

NAME OF WORK :-

C/o Link road Lam to Roun KM 0/00 to 2/100.

SUB-HEAD :-

Formation cutting at Rd 0/061 to 0/135

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock, chiseling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required lines, grades, cutting and trimming of side slopes and level as shown in the drawing and as directed by engineer-in-charge at site according to the MORD technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to the approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour if required. All useful material such as stones shingle, aggregate and slates etcetra shall be sorted out and stacked in proper stack. Any loss to the public, private / property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be compensated by him in all cases including carriage of materials within all leadsl and lifts and other incidentals The rate is including octrol, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	351.08	260.00	Rupees Two Hundred Sixty Only	Per cubic metre	91281.00
TOTAL :-						91281.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Shahour
 Executive Engineer,
 Shahour Division,
 HPPWD Shahpur


SCHEDULE OF QUANTITY

23

NAME OF WORK :- C/o Breast wall Near the Land of Karan Parmar R/O Rehlu Village Skow(Deposit work)
SUB-HEAD :- C/o Breast wall at Rdd 0/00 to 0/035).

ESTIMATED COST :- ₹ 95557.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT :- One Month

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	4.02	350.00	Rupees Three Hundred Fifty Only	Per cubic Metre	1407.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement : two sand : six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800/900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	17.50	5380.00	Rupees Five Thousand Three Hundred Eighty Only	Per cubic Metre	94150.00
TOTAL :-						95557.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shapur Division,
 HPWD Shapur

SCHEDULE OF QUANTITY

24

NAME OF WORK :-

Restoration of Rain damages on Kutharana to Kareri road KM 0/00 to 18.720.

SUB-HEAD :-

C/o R/Wall at RD 1/415 to 417.50

ESTIMATED COST :- ₹ 95626.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT :- One Month

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3	4	5	6	7
1		4.98	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	1743.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	18.20	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	86450.00
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	5.45	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	4633.00

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1		3	4	5	6	7
4	Providing and laying 100mm (one Hundred millimeter) dia P.V.C. pipe weep holes in brick masonry/stone masonry, plain, / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope 1(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	8.00	350.00	Rupees Three Hundred Fifty Only	Each	2800.00
		TOTAL :-				95626.00
		(Amount to be quoted by the contractor in Figure)				
		(Amount to be quoted by the contractor in words)				
		Quoted Rate in Figure (%)				
		Quoted Rate in Words (%)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99000.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT :- One Month

NAME OF WORK :- C/o Retaining wall Gaggal Airport West End to NH-154 Road slope stabilization Vill. Kuthman Tehsil Shahpur (Under Head (SDRF)
SUB-HEAD :- Haring of tractor with Trolley

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Hiring of tractor with trolley 3 to 5 tonne (three to five tone) capacity trip. on through rate bases for transportation of material like mix material, granular sub base, river shingle etc. for filling in road formation, berms etc. complete in all respect as per direction of entire satisfaction of the Engineer-in-charge. The cost of lubricant, diesel oil, repair maintenance will be borne by the me contractoras per direction of Engineer-in-Charge including carriage of materials within all leads , lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax or any type of taxes imposed by the Government.	165.00	600.00	Rupees Six Hundred Only	Per Hours	99000.00
TOTAL :-						99000.00
	Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)			
	Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)			

Executive Engineer.
Shahpur Division,
HPPWD Shahpur

25

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99432.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT :- One Month

NAME OF WORK :-

C/o Link road Lam to Roun KM 0/00 to Z/100.

SUB-HEAD :-

Formation cutting at Rd 0/00 to 0/050.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock, chiseling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required lines, grades, cutting and trimming of side slopes and level as shown in the drawing and as directed by engineer-in-charge at site according to the MORD technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to the approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour if required. All useful material such as stones shingle, aggregate and slates etcetra shall be sorted out and stacked in proper stack. Any loss to the public, private / property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be compensated by him in all cases including carriage of materials within all leads and lifts and other incidentals The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	382.43	260.00	Rupees Two Hundred Sixty Only	Per cubic metre	99432.00
TOTAL :-						99432.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				

(Signature)
Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 99484.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : One Month

NAME OF WORK :- Restoration of Rain Damages on Kutharana to Kareri Road KM 0/00 to 8/720.

SUB-HEAD :- Providing and Laying Kharanja Soling at Various Reaches).

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and Laying Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour) as per drawing and technical specification. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax or any type of taxes imposed by the Government.	104.72	950.00	Rupees Nine Hundred Fifty Only	Per Cubic Metre	99484.00
TOTAL :-						99484.00
	Quoted Rate in Figure (%)	31	(Amount to be quoted by the contractor in Figure)			
	Quoted Rate in Words (%)	31	(Amount to be quoted by the contractor in words)			

14/Jan/20
 Executive Engineer,
 Shapur Division,
 HPPWD Shapur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 96844.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT :- One Month

NAME OF WORK :- AIR & M/O Rulehar to Lam Road km 0/000. to 3/825
SUB-HEAD :- Maintenance of earthen shoulder, cutting of grass & weeds and C/O Unlined Drain between Portion KM 2/00 to 3/825.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Clearing and grubbing road land including uprooting wild vegetation, grass, bushes, strubs, saplings and trees of girth upto 300mm removal of stumps of such trees cut earlier and disposal of unserviceable material and stacking of serviceable material to be used or auctioned upto a lead of 1000 meters including removal and disposal of top organic soil not exceeding 150 mm in thickness as per technical specification clause 201 and as per direction of Engineer in charge with in all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	0.49	22440.10	Rupees Twenty Two Thousand Four Hundred Forty And Paise Ten Only	Per Hector	10996.00
2	C/O Shoulder (filling with fresh soil) Making up loss of material/ irregularities on shoulder to the design level by adding fresh approved soil and compacting it with appropriate equipment. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	4680.00	7.35	Rupees Seven And Paise Thirty Five Only	Per square metre	34398.00
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307.. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	1750.00	29.40	Rupees Twenty Nine And Paise Forty Only	Per Running metre	51450.00
TOTAL :-						96844.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

[Signature]
Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 95550.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : One Month

NAME OF WORK :- C/o Kut to Chantiyara Road km 0/000 to 2/500
SUB-HEAD :- C/o Unlined Drain surface etc In km 0/00 to 1/530.

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307.. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	3250.00	29.40	Rupees Twenty Nine And Paise Forty Only	Per Running metre	95550.00
TOTAL :-						95550.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Ambar
 Executive Engineer,
 Shapur Division,
 HPPWD Shapur

21

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99000.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT :- One Month

NAME OF Restoration of Rain damages on various roads under Darini Sub-Division.
SUB-HEAD :- Hiring of Excavator cum loader under Darini Section.

S. No	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Hiring of Excavator cum loader required for removal of slips, clearing road opening of drains and catchpits etc, in all kind of soil like boulder, rocks done etc, completely as per instruction of engineer-in-charge. Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner of machinery. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	90.00	1100.00	Rupees one thousand and or hundred only	Per Hour	99000.00
TOTAL :-						99000.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

div/ am
Executive Engineer,
Shahpur Division,
HPPWD Shahpur

32

SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 93809.00
EARNEST MONEY:- ₹ 1900.00
TIME LIMIT : Two Months

NAME OF WORK :- Restoration of Rain Damage on Harnera Mohad Chhattari Road Km 0/00 to 9/100 in Tehsil Shahpur, Distt. Kangra (HP).

SUB-HEAD :- C/o R/Wall at RD 4/615 to 4/624

5. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORO technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	9.11	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	3189.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORO technical specifications section 800, 900, 1200 and 1600 nominal mix 1:5:10 (One cement isto five sand isto ten graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	19.45	4350.00	Rupees Four Thousand Three Hundred Fifty Only	Per cubic metre	84608.00
3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORO technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	7.00	350.00	Rupees Three Hundred Fifty Only	Each	2450.00

4	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	4.19	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	3562.00
TOTAL :- 93809.00						
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shashpur Division,
 H.P.W.D. Shashpur

SCHEDULE OF QUANTITY

NAME OF WORK :- Restoration of Rain Damage on Hamera Mohad Chhattari Road Km 0/00 to 9/100 in Tehsil Shahpur, Distt. Kangra (HP).
SUB-HEAD :- C/O R/Wall at RD 4/640 to 4/648.85.

ESTIMATED COST :- ₹ 92260.00
EARNEST MONEY :- ₹ 1850.00
TIME LIMIT : Two Months

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORO technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3	4	5	6	7
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORO technical specifications section 800, 900, 1200 and 1600 nominal mix 1:5:10 (One cement isto five sand isto ten graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	19.12	4350.00	Rupees Four Thousand Three Hundred Fifty Only	Per cubic metre	83172.00
3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORO technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	7.00	350.00	Rupees Three Hundred Fifty Only	Each	2450.00

4	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	4.12	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	3502.00
TOTAL :-						
	Quoted Rate in Figure (%)	(			(Amount to be quoted by the contractor in Figure)	
	Quoted Rate in Words (%)	(			(Amount to be quoted by the contractor in words)	
92260.00						


 Executive Engineer,
 Shahpur Division,
 HPWD Shahpur

SCHEDULE OF QUANTITY

NAME OF WORK :- A/R & M/O Sallit to Khri Bhei Road km 0/000 to 9/525.
SUB-HEAD :- Maintenance of earthen shoulder, cutting of grass & weeds and C/O Unlined Drain between Portion KM 3/00 to 5/00 etc.

ESTIMATED COST :- ₹ 97517.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT :- One Month

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	1	3	4	5	6	7
1	Clearing and grubbing road land including uprooting wild vegetation, grass, bushes, strubs, saplings and trees of girth upto 300mm removal of stumps of such trees cut earlier and disposal of unserviceable material and stacking of serviceable material to be used or auctioned upto a lead of 1000 meters including removal and disposal of top organic soil not exceeding 150 mm in thickness as per technical specification clause 201 and as per direction of Engineer in charge with in all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	0.52	2240.10	Rupees Twenty Two Thousand Four Hundred Forty And Paise Ten Only	Per Hecter	11669.00
2	C/O Shoulder (filling with fresh soil) Making up loss of material/ Irregularities on shoulder to the design level by adding fresh approved soil and compacting it with appropriate equipment. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	4680.00	7.35	Rupees Seven And Paise Thirty Five Only	Per square metre	34398.00
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307.. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	1750.00	29.40	Rupees Twenty Nine And Paise Forty Only	Per Running metre	51450.00
TOTAL :-						97517.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

[Signature]
 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99104.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : Two Months

NAME OF WORK :- C/o Harnera Mohan Chameera Kish Shahpur Road Km 0/00 to 13/900 in Tehsil Shahpur, Distt. Kangra (HP) (Under MNP).

SUB-HEAD :- C/o B/Wall at RD 7/006 to 7/011.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	9.31	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	3259.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	18.50	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	87875.00
3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope 1(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	9.00	350.00	Rupees Three Hundred Fifty Only	Each	3150.00

Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including cartage of materials with in all loads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	5.67	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	4820.00
Quoted Rate in Figure (%)	11				
Quoted Rate in Words (%)	11				
TOTAL :-					99104.00


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY


ESTIMATED COST :- ₹ 92774.00
EARNEST MONEY :- ₹ 1900.00
TIME LIMIT : Two Months.

NAME OF WORK :- Restoration of Rain Damage on Hamra Mohad Chatarf Road Km 0/00 to 9/100 in Tehsil Shahpur, Distt. Kangra (HP).
SUB-HEAD :- C/O R/Wall at RD 4/630 to 4/638.90.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	9.01	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	3154.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:5:10 (One cement isto five sand isto ten graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	19.23	4350.00	Rupees Four Thousand Three Hundred Fifty Only	Per cubic metre	83651.00
3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	7.00	350.00	Rupees Three Hundred Fifty Only	Each	2450.00

25

4	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	4.14	850.00	Ruppes Eight Hundred Fifty Only	Per cubic metre	3519.00
TOTAL :- 92774.00						
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shapur Division,
 HPWD Shapur

SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 99820.00
EARNEST MONEY:- ₹ 2000.00
TIME LIMIT : Two Months

NAME OF WORK :- C/o Harnera Mohad Chaudhara Kari Shahpur Road Km 0/00 to 13/900 In Tehsil Shahpur, Distt. Kangra (HP). (Under MHP).
SUB-HEAD :- C/o B/Wall at RD 6/695 to 7/005.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-In-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	8.82	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	3087.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-In-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	18.95	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	90013.00
3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	9.00	350.00	Rupees Three Hundred Fifty Only	Each	3150.00

4	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all loads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	4.20	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	3570.00
TOTAL :- 99820.00						
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 Haryana Sahasra

SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 97517.00
EARNEST MONEY:- ₹ 2000.00
TIME LIMIT : One Month

NAME OF WORK :- A/R & M/O Sall to Khri Bhel Road km 0/000 to 9/525.
SUB-HEAD :- Maintenance of earthen shoulder, cutting of grass & weeds and C/O Unlined Drain between Portion KM 1/00 to 2/00 etc.

S No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Clearing and grubbing road land including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm removal of stumps of such trees cut earlier and disposal of unserviceable material and stacking of serviceable material to be used or auctioned upto a lead of 1000 meters including removal and disposal of top organic soil not exceeding 150 mm in thickness as per technical specification clause 201 and as per direction of Engineer in charge with in all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	0.52	22440 10	Rupees Twenty Two Thousand Four Hundred Forty And Paise Ten Only	Per Hectore	11669.00
2	C/O Shoulder (filling with fresh soil) Making up loss of material/ irregularities on shoulder to the design level by adding fresh approved soil and compacting it with appropriate equipment. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	4680.00	7.35	Rupees Seven And Paise Thirty Five Only	Per square metre	34398.00
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307.. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	1750.00	29.40	Rupees Twenty Nine And Paise Forty Only	Per Running metre	51450.00
TOTAL :-						97517.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Nam Pathi
Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99485.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- Two Months

NAME OF WORK :- Construction of Link road from Mathroti to Bharun including Bridge over Chambh Khad Km 0/00 to 4/800(Under Nabard).

SUB-HEAD :- Providing, Fixing and Painting of Kilometre stone, Writing letters etc.)

5. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Painting two coats (excluding priming coat) on previously steel and other metal surfaces with enamel paint brushing to give an even shade including cleaning the surface to remove all dirt, dust and other foreign matter with enamel paint other than white including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	35.00 Squire metre	25.00	Rupees Twenty Five Only	Per square metre	875.00
2	Painting two or more coats of Nerolac/Asian paint/ Berger (excluding priming coat) on previously concrete based surface with enamel paint white to give an even shade including cleaning the surface of dirt, dust and other foreign matter, sand papering and stoping, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	30.00 Squire metre	54.00	Rupees Fifty Four Only	Per square metre	1620.00
3	Writing letters or figures on any surfaces with synthetic enamel paint (other than white) stops, commas, hyphens and the like not to be measured and paid separately, Block letters, Indian letters / figures etc. including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	36600.00 Per letter per centimetre hight	2.65	Rupees Two And Paise Sixty Five Only	Per letter per centimetre hight	96990.00
TOTAL :-						99485.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shapur Division,
 HPPWD Shapur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99786.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : Two Months

NAME OF WORK :- Special repair of Vethary Hospital Gohju in Tehsil Shahpur at Dist. Kangra Himachal Pradesh.
SUB-HEAD :- C/O Boundary wall.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	3.75	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	17813.00
2	Random rubble masonry/polygonal rubble masonry (uncoursed/brought to courses) with hard stone of approved quality in foundation and plinth including leveling up with cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 20mm (twenty) millimeter nominal size mechanical mixed in cement mortar 1:6 (one cement six sand) as per the entire satisfaction and direction of the Engineer-in-charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	16.90	4860.50	Rupees Four Thousand Eight Hundred Fifty And Paise Fifty Only	Per cubic metre	81973.00
TOTAL :-						99786.00
	Quoted Rate in Figure (%)	m	(Amount to be quoted by the contractor in Figure)			
	Quoted Rate in Words (%)	m	(Amount to be quoted by the contractor in words)			

29/10/23
Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

NAME OF WORK :-

A/R & M/O Sall to Khiri Bhel Road km 0/000 to 9/525.

SUB-HEAD :- Maintenance of earthen shoulder, cutting of grass & weeds and C/o Unlined Drain between Portion KM 6/00 to 8/00 etc.

ESTIMATED COST :- ₹ 97068.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : One Month

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Clearing and grubbing road land including uprooting wild vegetation, grass, bushes, strubs, saplings and trees of girth upto 300mm removal of stumps of such trees cut earlier and disposal of unserviceable material and stacking of serviceable material to be used or auctioned upto a lead of 1000 meters including removal and disposal of top organic soil not exceeding 150 mm in thickness as per technical specification clause 201 and as per direction of Engineer in charge with in all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	0.50	22440.10	Rupees Twenty Two Thousand Four Hundred Forty And Paise Ten Only	Per Hecdar	11220.00
2	C/O Shoulder (filling with fresh soil) Making up loss of material/ irregularities on shoulder to the design level by adding fresh approved soil and compacting it with appropriate equipment. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	4680.00	7.35	Rupees Seven And Paise Thirty Five Only	Per square metre	34398.00
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	1750.00	29.40	Rupees Twenty Nine And Paise Forty Only	Per Running metre	51450.00
TOTAL :-						97068.00
(Amount to be quoted by the contractor in Figure)						
Quoted Rate in Figure (%)						
Quoted Rate in Words (%)						

Executive Engineer,
Shapur Division,
HPPWD Shapur

SCHEDULE OF QUANTITY


NAME OF WORK :-

Restoration of Rain damages on Kutharana to Kareri road KM 0/00 to 18.720,
C/o R/Wall at RD 1/495 to 1/497.50.)

ESTIMATED COST :- ₹ 95626.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT :- One Month

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3 4.98	4 350.00	5 Rupees Three Hundred Fifty Only	6 Per cubic metre	7 1743.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-Charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	18.20	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	86450.00
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	5.45	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	4633.00

5. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1		3	4	5	6	7
4	Providing and laying 100mm (one Hundred millimeter) dia P.V.C. pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	8.00	350.00	Rupees Three Hundred Fifty Only	Each	2800.00
TOTAL :-						95626.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPRWD Shahpur

SCHEDULE OF QUANTITY


NAME OF WORK :- C/o Harnera Mohad Chamdera Kiarl Shahpur Road Km 0/00 to 13/900 in Tehsil Shahpur, Distt. Kangra (HP). (Under MNP).
SUB-HEAD :- C/o B/Wall at RD 7/012 to 7/019.20

ESTIMATED COST:- ₹ 97046.00
EARNST MONEY :- ₹ 2000.00
TIME LIMIT : Two Months

5. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3	4	5	6	7
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	18.40	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	87400.00
3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	10.00	350.00	Rupees Three Hundred Fifty Only	Each	3500.00

483

4	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	4.43	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	3766.00
TOTAL :-						
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				
						97046.00


 Executive Engineer,
 Shahpur Division,
 HRPWD Shahpur

SCHEDULE OF QUANTITY

NAME OF WORK :-

C/o Kut to Chantiyara Road km 0/000 to 2/500.

SUB-HEAD :-

C/o Unlined Drain between Portion KM 0/00 to 1/535.

ESTIMATED COST :- ₹ 98493.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : One Month

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1		3				
2		4				
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 95 m) as per Technical Specification Clause 307.. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	3350.10	29.40	Rupees Twenty Nine And Paise Forty Only	Per Running metre	98493.00
TOTAL :-						98493.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Signature
Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

NAME OF WORK :- C/o Harnera Mohad Chamdera Kian Shahpur Road Km 0/00 to 13/900 in Tehsil Shahpur, Distt. Kangra (HP), Under MNP.

SUB-HEAD :- C/o B/Wall at RD 7/021 to 7/026.

ESTIMATED COST :- ₹ 99220.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : Two Months

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiselling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3	4	5	6	7
2	Providing and laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	18.75	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	89063.00
3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	10.00	350.00	Rupees Three Hundred Fifty Only	Each	3500.00

4	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including cartage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	4.20	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	3570.00
TOTAL :-						
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				
						99220.00


 Executive Engineer,
 Shahpur Division,
 H.P.W.R. Shahpur

SCHEDULE OF QUANTITY

NAME OF WORK :- C/O link road Bair Dramman to Yol Macchial KM 0/00 to 1/00.
SUB-HEAD :- Formation cutting in km 0/200 to 0/400.

ESTIMATED COST :- ₹ 97150.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : One Month

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock, chiseling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required lines, grades, cutting and trimming of side slopes and level as shown in the drawing and as directed by engineer-in-charge at site according to the MORO technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to the approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour if required. Any loss to the public, private / property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be compensated by him in all cases including carriage of materials within all leads and lifts and other incidentals The rate is including octroi, royalty, Malkhana, toll tax, GST and any other taxes imposed by the Government.	3	290.00	Rupees two Hundred Ninety only	Per Cum	97150.00
TOTAL :-						97150.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Shahpur
 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur


SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 98154.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT :- Two Months

NAME OF WORK :- C/o Harnera Mohad Chamdera Kiari Shahpur Road Km 0/00 to 13/900 in Tehsil Shahpur, Distt. Kangra (HP). (Under MNP).
SUB-HEAD :- C/o B/Wall at RD 7/027 to 7/034.15.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	7.01	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	2454.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	18.70	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	88825.00
3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H) (One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	10.00	350.00	Rupees Three Hundred Fifty Only	Each	3500.00

4	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	3.97	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	3375.00
TOTAL :-						
	Quoted Rate in Figure (%)	10	(Amount to be quoted by the contractor in Figure)			
	Quoted Rate in Words (%)	10	(Amount to be quoted by the contractor in words)			
						98154.00


 Executive Engineer,
 Shahpur Division,
 H.P.W.D. Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 94286.00
EARNEST MONEY:- ₹ 2000.00
TIME LIMIT : One Month

NAME OF WORK :-

Special Repair of Non Residential Building S.E Office N.H. HP.PWD Circle Shapur Dist Kangra(H.P.).

SUB-HEAD :-

Providing and Laying Floor Tile in 1st floor.

5. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Dismantelling Plain cement concrete manually/ mechanically including disposal of rubbish within all lead and lift as per direction of Engineer in charge. as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of toll tax, GST and any other taxes imposed by the government.	37.60	950.00	Rupees Nine Hundred Fifty Only	Per cubic metre	35720.00
2	Providing and laying Size of (600x 600mm) Double charged/Ultra charged vetrified tiles of Restile/Nitco /Rak/Kajaria / Orient -Bell/AGL/Simplo /Johnson/Somany/ Orient & Bell as per approved shade and design of the office in flooring (thickness to be specified by the manufacturer) with water absorption less than 0.08% (zero decimal zero eight percentage) and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm (twenty millimetres) thick cement mortar 1:4 (one cement isto four coarse sand), joining with grey cement slurry @ 3.3 kg/ sqm (three decimal three kilogram per squaremetre) including grouting the joints with white cement and matching pigments etc., complete as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	32.05	1570.50	Rupees One Thousand Five Hundred Seventy And Paise Fifty Only	Per Squire metre	50335.00
3	Providing and laying Size of (600x 600mm) Double charged/Ultra charged vetrified tiles of Restile/Nitco /Rak/Kajaria / Orient -Bell/AGL/Simplo /Johnson/Somany/ Orient & Bell as per approved shade and design of the office in skirting (thickness to be specified by the manufacturer) with water absorption less than 0.08% (zero decimal zero eight percentage) and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm (twenty millimetres) thick cement mortar 1:3 (one cement isto three coarse sand), joining with grey cement slurry @ 3.3 kg/ sqm (three decimal three kilogram per squaremetre) including grouting the joints with white cement and matching pigments etc., complete as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	5.45	1510.20	Rupees One Thousand Five Hundred Ten And Paise Twenty Only	Per Squire metre	8231.00
TOTAL :-						94286.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

HPWD
Executive Engineer,
Shapur Division,
HPPWD Shapur

SCHEDULE OF QUANTITY

40

NAME OF WORK :-

SUB-HEAD :-

Recovery and Reconstruction on Bhanalla Pucca Tiala Road KM 0/00 to 3/700. (Under PDNA).
C/o C.C. Pavement at RD 2/916.30 to 2/930.

ESTIMATED COST :- ₹ 99458.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : Two Months

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Construction of panel concrete plain cement concrete pavement, thickness as per design, over a prepared sub-base with 43 Grade cement or any other type as per clause 1501.2.2 M30 Grade course and fine aggregate conforming to IS: 383. Maximum size of coarse aggregate not exceeding 25mm, mixed in a concrete mixer of not less than 0.2 Cum capacity and appropriate weight batcher using approved mix design, laid in approved fixed side framework (Steel channel), laying and fixing of 125 micron thick Polythene film, wedges steel plates including levelling form work as per drawing), spreading the concrete with shovels, rakes, compacting using needle, screed and plate vibrators and finishing continuous operation including provision of contraction and expansion, construction joints, applying debonding strips, primer, sealant, dowel bars, nera approaches to bridge/culverts and construction joints, admixtures as approved, curing of slab for 14 days. Curing compound (Where specified) and water specified to lines and grade as per drawing and technical specifications clause 1501. PCC Grade M-30 Each panels (1.25x1.25) Thickness 160mm. as per the entire satisfaction and directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, and any other taxes imposed by the Government but excluding GST.	13.35	7450.00	Rupees Seven Thousand Four Hundred Fifty Only	Per cubic metre	99458.00
TOTAL :-						99458.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 95626.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT :- One Month

NAME OF WORK :- Restoration of Rain damages on Kutharana to Kareri road KM 0/00 to 18.720.
SUB-HEAD :- C/O R/Wall at RD 1/422 to 1/424.50.)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	4.98	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	1743.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	18.20	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	86450.00
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	5.45	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	4633.00

Sl. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
40	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	8.00	350.00	Rupees Three Hundred Fifty Only	Each	2800.00
TOTAL :-						95626.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 98600.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : One Month

NAME OF WORK :-

C/O link road Bair Dramman to Yol Macchial KM 0/00 to 1/00.

SUB-HEAD :-

Formation cutting in km 0/00 to 0/200.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock, chiseling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required lines, grades, cutting and trimming of side slopes and level as shown in the drawing and as directed by engineer-In-Charge at site according to the MORD technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to the approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour if required. Any loss to the public, private / property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be compensated by him in all cases including carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkhana, toll tax, GST and any other taxes imposed by the Government.	340.00	290.00	Rupees two Hundred Ninety only	Per Cum	98600.00
TOTAL :-						98600.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Nur bany
 Executive Engineer,
 Shahpur Division,
 HP&WD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99000.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : One Month

NAME OF Restoration of Rain damages on various roads under Shahpur Sub-Division.
SUB-HEAD :- Hiring of Excavator cum loader under Shahpur Section.

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Hiring of Excavator cum loader required for removal of slips, clearing road opening of drains and catchpits etc, in all kind of soil like boulder, rocks done etc, completely as per instruction of engineer-in-charge. Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner of machinery. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer in-Charge. The rate is inclusive of octroi, royalty, Malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	90.00	1100.00	Rupees one thousand and or hundred only <i>one</i>	Per Hour	99000.00
TOTAL :-						99000.00
(Amount to be quoted by the contractor in Figure)						
(Amount to be quoted by the contractor in words)						
Quoted Rate in Figure (%)						
Quoted Rate in Words (%)						

[Signature]
Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 95626.00
EARNEST MONEY:- ₹ 2000.00
TIME LIMIT : One Month

NAME OF WORK :- Restoration of Rain damages on Kutharana to Kareri road KM 0/00 to 18.720.
SUB-HEAD :- C/o R/Wall at RD 1/425 to 1/429.50.)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	4.98	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	1743.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	18.20	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	86450.00
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	5.45	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	4633.00

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1		2				
4	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope 1(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	3	8.00	350.00 Rupees Three Hundred Fifty Only	Each	2800.00
TOTAL :-						95626.00
	Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)			
	Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)			


 Executive Engineer,
 Shajapur Division,
 HPPWD Shajapur

SCHEDULE OF QUANTITY

54

ESTIMATED COST:- ₹ 99470.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : One Month

NAME OF WORK :- A/R & M/O various roads of HPPWD Sub Division Gaggal.
SUB-HEAD :- Painting and writing letters , figures Kilometre Stone etc.

S. No	Description of items	Quantity	RATES			Unit	Amount
			In fig	In words			
1	Removing old paint from steel and other metal surfaces and making the surfaces even with paint remover of approved brand and manufacture including carriage of material with all leads lift and as per direction of Engineer-in-Charge. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	220.00	26.200	Rupees Twenty Six And Paise Twenty Only		Per Square meter	5764.00
2	Painting one coat excluding priming coat on previously painted steel and other metal surfaces of all dirt dust and other for matter with ready mixed paint including carriage of material with all leads lift and as per direction of Engineer-in-Charge. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	220.00	45.000	Rupees Forty Five Only		Per Square meter	9900.00
3	Painting two coats (excluding priming coat) on new steel and other metal surface with enamel paint brushing to give an even shade including cleaning the surface to remove all dirt, dust and other foreign matter with enamel paint other than white within all leads, lifts of material and other incidentals. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	210.00	89.900	Rupees Eighty Nine And Paise Ninety Only		Per Square meter	18879.00
4	Applying Birda white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete as per direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	80.00	55.000	Rupees Fifty Five Only		Per Square meter	4400.00
5	Finishing wall with weather proof exterior grade emulsion of approved design (Apexultima) or its equivalent on undecorated wall surface (two coats) to give an even shade and final after thoroughly cleaning the surface to remove all dirt, dust and other foreign matter etc including sand paper smooth complete as per direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	590.00	95.000	Rupees Ninety Five Only		Per Square meter	56050.00
6	Writing letters or figures on any surfaces with synthetic enamel paint (other than white) stops, commas, hyphens and the like not to be measured and paid separ The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government (Block letters, Indian letters/figures within all leads, lifts of materials and other incidentals. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	2035.00	2.200	Rupees Two And Paise Twenty Only		Per letter per cm. height	4477.00
TOTAL :-							99470.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)					
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)					

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- 97503.00
EARNEST MONEY :- 2000.00
TIME LIMIT :- One Month

NAME OF WORK :- C/o Chowari to Bhanala via Machhetta road KM 0/00 to 2/750.

SUB-HEAD :- C/o Breast wall at RD 2/277.60 to 2/285.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORO technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	16.40	350.00	Rupees Three Hundred Fifty Only	Per cubic Metre	5740.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORO technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	18.95	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic Metre	90013.00
3	Providing and laying 100mm (one hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (1V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORO technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	5.00	350.00	Rupees Three Hundred Fifty Only	Each	1750.00
TOTAL :-						97503.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer
 Shahpur Division
 HPPWD Shahpur

54

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 97188.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : Two Months

NAME OF WORK :- C/o Link road Hamera Mohar Chamdeera Chatra Pehad Km 0/00 to 9/100 in Tehsil Shahpur, Distt. Kangra (HP).

SUB-HEAD :- C/o of B/Wall from Rd 7/130 to 7/137.50 on R / side of Gully.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In Fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	58.57 Cubic metres	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	20500.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:5:10 (One cement isto five sand isto ten graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	17.55 Cubic metres	4250.00	Rupees Four Thousand Two Hundred Fifty Only	Per cubic metre	74588.00
3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (IV):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in- charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	6.00 Number	350.00	Rupees Three Hundred Fifty Only	Each	2100.00
TOTAL :-						97188.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPWD Shimla

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 95700.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : One Month

NAME OF WORK :-

C/O link road Bair Dramman to Yol Macchial KM 0/00 to 1/00.

SUB-HEAD :-

Formation cutting in km 0/400 to 0/600.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock, chiseling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required lines, grades, cutting and trimming of side slopes and level as shown in the drawing and as directed by engineer-In-Charge at site according to the MORD technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to the approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour if required. Any loss to the public, private / property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be compensated by him in all cases including carriage of materials within all leads and lifts and other incidentals The rate is including octroi, royalty, Malkhana, toll tax, GST and any other taxes imposed by the Government.	330.00	290.00	Rupees two Hundred Ninty only	Per Cum	95700.00
TOTAL :-						95700.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Narain
 Executive Engineer,
 Shahpur Division,
 HPFWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 96800.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : One Month

NAME OF Restoration of Rain damages on Shahpur Chakban Lapiyana road km 0/00 to 20/500

SUB-HEAD :- Hiring of Excavator cum Loader

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Hiring of Excavator cum loader required for removal of slips, clearing road opening of drains and catchpits etc, in all kind of soil like boulder, rocks done etc, completely as per instruction of engineer-in-charge. Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner of machinery. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	88.00	1100.00	Rupees one thousand and or hundred only <i>one</i>	Per Hour	96800.00
TOTAL :-						96800.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

[Signature]
 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

(56)

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 97949.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : One Month

NAME OF WORK :- Special Repair to the office Cum Residence Junior Engineer in HP.PWD Darini

SUB-HEAD :- Painting and Desteptering.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in- Charge. With cement mortar 1:4 (1 cement : 4 fine sand) within all leads, lifts of materials and other incidentals as per approved specification, drawing, design and as directed by the Engineer-in-Charge. The rate is including Royalty, Malkhana, Octroi, Toll Tax, Sale Tax, GST or any other taxes imposed by the Government.	15.12	264.35	Rupees Two Hundred Sixty Four And Paise Thirty Five Only	Per Square metre	3997.00
2	Removing dry or oil bound distemper by washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete. as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	794.12	11.15	Rupees Eleven And Paise Fifteen Only	Per Square metre	8854.00
3	Applying Birda / J.K. white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	119.12	85.10	Rupees Eighty Five And Paise Ten Only	Per Square metre	10137.00
4	Wall painting (Two coat) with plastic emulsion paint of approved brand and manufacture on undecorated wall surfaces to give an even shade including thoroughly bushing the surface free from mortar droppings and other foreign matter and sand papered smooth including applying of putty as required for marking the surface. as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	408.49	74.80	Rupees Seventy Four And Paise Eighty Only	Per Square metre	30555.00

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1		3	4	5	6	7
5	Painting two or more coats of Nerolac/Asian paint/ Berger (excluding priming coat) on new wood and wood based surface with enamel paint other than white to give an even shade including cleaning the surface of dirt, dust and other foreign matter, sand papering and stoping within all leads, lifts of materials and other incidentals. as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	113.30	53.85	Rupees Fifty Three And Paise Eighty Five Only	Per Square metre	6,101.00
6	Finishing walls with Acrylic Smooth exterior paint of required shade New work (Two or more coat applied @ 1.67 lit/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm) and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	291.61	128.75	Rupees One Hundred Twenty Eight And Paise Seventy Five Only	Per Square metre	37545.00
7	Providing and fixing 32mm (Thirty two millimetres) nominal size diametres PVC waste pipe for wash basin within all leads, lifts of materials and other incidentals. as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	4.00	190.00	Rupees One Hundred Ninety Only	Each	760.00
TOTAL :-						97949.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

NAME OF WORK :- C/o Link road Harnera Mohar Chamdara Chatra Pehad Km 0/00 to 9/100 in Tehsil Shahpur, Distt. Kangra (HP).

SUB-HEAD :- C/o of B/Wall from Rd 7/120 to 7/128 on R / side of gully.

ESTIMATED COST :- ₹ 98222.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT Two Months

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORO technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	47.32	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	15562.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORO technical specifications section 800, 900, 1200 and 1600 nominal mix 1:5:10 (One cement isto five sand isto ten graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	18.72	4250.00	Rupees Four Thousand Two Hundred Fifty Only	Per cubic metre	79560.00
3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (1V,20H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORO technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	6.00	350.00	Rupees Three Hundred Fifty Only	Each	2100.00
TOTAL :-						98222.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

NAME OF WORK :- Restoration of Rain Damage on Rajol Ansule Chatti Road KM 0/00 to 4/235.
SUB-HEAD :- C/o Wire create at RD 4/020 to 4/025.

ESTIMATED COST :- ₹ 85290.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT :- Two Months

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing and laying of boulder apron or gabion walls laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100mm x100mm (Hundred millimetre into hundred millimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone boulders weighing not less than 40 Kg (forty kilogram) each as per drawing and technical specification clause 1300, as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	23.43	3250.00	Rupees Three Thousand Two Hundred Fifty Only	Per cubic metre	76148.00
2	Construction of Embankment with approved material deposited at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of Table 300.1 and 300.2 as per technical specification Clause 301.5 as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	35.16	260.00	Rupees Two Hundred Sixty Only	Per cubic metre	9142.00
TOTAL :-						85290.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HIPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 98860.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : One Month

(62)

NAME OF WORK :- C/o Retaining wall Gaggal Airport West End to NH-154 Road slope stabilization Vill. Kuthman Tehsil Shahpur (Under Head (SDRF)
SUB-HEAD :- Removal of Debris in the Banoi Khad).

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.5m and lead upto 1000m as per technical specification 302.5 and 1611. as per direction of Engineer-in-Charge including carriage of materials within all leads , lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax or any type of taxes imposed by the Government.	1635.40	60.45	Rupees Sixty And Paise Forty Five Only	Per Cubic Metre	98860.00
TOTAL :-						98860.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				

[Signature]
 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

NAME OF WORK :- Restoration of Rain Damage on Rajol Ansuile Charri Road KM 0/00 to 4/235.
SUB-HEAD :- C/o Wire create at RD 4/026 to 4/030.

ESTIMATED COST: - ₹ 88751.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT Two Months

S. No.	Description of Items	Quantity	RATES			Unit	Amount
			In fig	In words			
1	2	3	4	5	6	7	
1	Providing and laying of boulder apron or gabion walls laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100mm x100mm (Hundred millimetre into hundred millimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone boulders weighing not less than 40 Kg (forty kilogram) each as per drawing and technical specification clause 1300, as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	24.50	3250.00	Rupees Three Thousand Two Hundred Fifty Only	Per cubic metre	79625.00	
2	Construction of Embankment with approved material deposited at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of Table 300.1 and 300.2 as per technical specification Clause 301.5 as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	35.10	260.00	Rupees Two Hundred Sixty Only	Per cubic metre	9126.00	
TOTAL :-							88751.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)					
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)					

N. V. Jyoti
 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 97517.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : One Month

NAME OF WORK :- A/R and M/O Rulehar to Lam km 0/00 to 3/880
SUB-HEAD :- Clearing and Grubbing road land, C/O Earthen shoulder and unlined drain etc.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Clearing and grubbing road land including uprooting wild vegetation, grass, bushes, strubs, saplings and trees of girth upto 300mm removal of stumps of such trees cut earlier and disposal of unserviceable material and stacking of serviceable material to be used or auctioned upto a lead of 1000 meters including removal and disposal of top organic soil not exceeding 150 mm in thickness as per technical specification clause 201 and as per direction of Engineer in charge with in all leads and lifts and other incidentals per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of toll tax, GST and any other taxes imposed by the Government	0.56	22440.10	Rupees Twenty Two Thousand Four Hundred Forty And Paise Ten Only	Per Hectar	12566.00
2	C/O Shoulder (filling with fresh soil) Making up loss of material/irregularities on shoulder to the design level by adding fresh approved soil and compacting it with appropriate equipments per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of toll tax, GST and any other taxes imposed by the Government	3800.00	7.35	Rupees Seven And Paise Thirty Five Only	Per Square metre	27930.00
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1939.50	29.40	Rupees Twenty Nine And Paise Forty Only	Per Running metre	57021.00
TOTAL :-						97517.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Shahpur
Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 87139.00

EARNEST MONEY :- ₹ 2000.00

TIME LIMIT :- Two Months

NAME OF WORK :- Restoration of Rain Damage on Rajol Ansule Chatti Road KM 0/00 to 4/235.

SUB-HEAD :- C/o Wire create at RD 4/036 to 4 /040.

S. No.	Description of Items	Quantity	RATES			Unit	Amount
			In fig	In words			
1	2	3	4	5	6	7	
1	Providing and laying of boulder apron or gabion walls laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100mm x100mm (hundred millimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone boulders weighing not less than 40 Kg (Forty kilogram) each as per drawing and technical specification clause 1300, as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	24.00	3250.00	Rupees Three Thousand Two Hundred Fifty Only	Per cubic metre	78000.00	
2	Construction of Embankment with approved material deposited at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of Table 300.1 and 300.2 as per technical specification Clause 301.5 as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	35.15	260.00	Rupees Two Hundred Sixty Only	Per cubic metre	9139.00	
TOTAL :-							87139.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)					
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)					

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

25

SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 97517.00
EARNEST MONEY:- ₹ 2000.00
TIME LIMIT : One Month

NAME OF WORK :-

A/R and M/O Kutharna to Karei km 0/00 to 8/720.

SUB-HEAD :-

Clearing and Grubbing road land, C/O Earthen shoulder and unlined-drain Between Km 0/00 to 4/00.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Clearing and grubbing road land including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm removal of stumps of such trees cut earlier and disposal of unserviceable material and stacking of serviceable material to be used or auctioned upto a lead of 1000 meters including removal and disposal of top organic soil not exceeding 150 mm in thickness as per technical specification clause 201 and as per direction of Engineer in charge with in all leads and lifts and other incidental's per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of toll tax, GST and any other taxes imposed by the government	0.56	22440.10	Rupees Twenty Two Thousand Four Hundred Forty And Paise Ten Only	Per Hector	12566.00
2	C/O Shoulder (filling with fresh soil) Making up loss of material/ irregularities on shoulder to the design level by adding fresh approved soil and compacting it with appropriate equipments per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of toll tax, GST and any other taxes imposed by the government	3800.00	7.35	Rupees Seven And Paise Thirty Five Only	Per Square metre	27930.00
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1939.50	29.40	Rupees Twenty Nine And Paise Forty Only	Per Running metre	57021.00
TOTAL :-						97517.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				

[Signature]
Executive Engineer,
Shapur Division,
HPPWD Shapur

SCHEDULE OF QUANTITY

NAME OF WORK :- C/o Shahpur Majar Road KM 0/00 to 1/500.
SUB-HEAD :- C/o R/Wall at Rd 1/106.10 to 1/111.20).

ESTIMATED COST :- ₹ 97119.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT :- One Month

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	6.16	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	2156.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	17.89	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	84978.00
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	5.57	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	4735.00

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1		3			6	7
4	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope 1(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	15.00	350.00	Rupees Three Hundred Fifty Only	Each	5250.00
		TOTAL :-				97119.00
		(Amount to be quoted by the contractor in Figure)				
		(Amount to be quoted by the contractor in words)				
		Quoted Rate in Figure (%)				
		Quoted Rate in Words (%)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 98750.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- One Month

NAME OF WORK :-

C/o Retaining wall Gaggal Airport West End to NH-154 Road slope stabilization Vill. Kuthman Tehsil Shajapur (Under Head (SDRF)

SUB-HEAD :-

Removal of Debris in the Banol Khad.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.5m and lead upto 1000m as per technical specification 302.5 and 1611. as per direction of Engineer-in-Charge including carriage of materials within all loads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax or any type of taxes imposed by the Government.	1633.58	60.45	Rupces Sixty And Paise Forty Five Only	Per Cubic Metre	98750.00
TOTAL :-						98750.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer,
 Shajapur Division,
 HPPWD Shajapur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 89261.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : One Month

NAME OF WORK :- Landslide Disaster Realed Mitigation work on Salli to Khari Behi Road KM 0/00 to 9/570.

SUB-HEAD :- C/o Edge Wall at Rd 2/816 to 2/828.)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	5.30	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	1855.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	16.47	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	78233.00
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	5.85	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	4973.00

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1		3	4	5	6	7
4	Providing and laying 100mm (one Hundred millimeter) dia P.V.C. pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope 1(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	12.00	350.00	Rupees Three Hundred Fifty Only	Each	4200.00
TOTAL :-						89261.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 88114.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- Two Months

NAME OF WORK :- Restoration of Rain Damage on Rajol Ansule Chatti Road KM 0/00 to 4/235.
SUB-HEAD :- C/o Wire create at RD 4/031 to 4 /035.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing and laying of boulder apron or gabion walls laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS:280 and 15.4826 in 100mm x100mm (Hundred millimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone boulders weighing not less than 40 Kg (forty kilogram) each as per drawing and technical specification clause 1300, as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	24.30	3250.00	Rupees Three Thousand Two Hundred Fifty Only	Per cubic metre	78975.00
2	Construction of Embankment with approved material deposited at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of Table 300.1 and 300.2 as per technical specification Clause 301.5 as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	35.15	260.00	Rupees Two Hundred Sixty Only	Per cubic metre	9139.00
TOTAL :-						88114.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				

*Shahpur Division,
 HPPWD Shahpur*

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99933.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : Two Months

NAME OF WORK :- Construction of Darini to Jhanlyana road KM 0/00 to 2/00.
SUB-HEAD :- Construction of R/wall in G.I wire crete at RD 0/092 to 0/102.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3 11.25	4 350.000	5 Rupees Three Hundred Fifty Only	6 Per cubic metre	7 3938.00
2	Providing and laying of boulder apron or gabion walls laid in wire crates with 5mm (Five millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100mm x100mm (Hundred millimetre into hundred millimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone boulders weighing not less than 40 Kg (Forty kilogram) each as per drawing and technical specification clause 1300, as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	27.34	3250.000	Rupees Three Thousand Two Hundred Fifty Only	Per cubic metre	88855.00
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	8.40	850.000	Rupees Eight Hundred Fifty Only	Per cubic metre	7140.00
TOTAL :-						99933.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 97119.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT :- One Month

NAME OF WORK :- C/o Shahpur Majiar Road KM 0/00 to 1/500.

SUB-HEAD :- C/o R/Wall at Rd 1/100 to 1/105.10.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	6.16	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	2156.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	17.89	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	84978.00
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	5.57	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	4735.00

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
4	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope 1(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	15.00	350.00	Rupees Three Hundred Fifty Only	Each	5250.00
TOTAL :-						97119.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shapuri Division,
 HPPWD Shapur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99916.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : Two Months

NAME OF WORK :- Construction of Darini to Jhanviana road KM 0/00 to 2/00.

SUB-HEAD :- Construction of R/wall in G.I wire crete at RD 0/080 to 0/090.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3	12.66	Rupees Three Hundred Fifty Only	Per cubic metre	4437.00
2	Providing and laying of boulder apron or gabion walls laid in wire crates with 5mm (Five millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100mm x100mm (Hundred millimetre into hundred millimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone boulders weighing not less than 40 Kg (Forty kilogram) each as per drawing and technical specification clause 1300, as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	27.34	3250.000	Rupees Three Thousand Two Hundred Fifty Only	Per cubic metre	88855.00
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	7.80	850.000	Rupees Eight Hundred Fifty Only	Per cubic metre	6630.00
TOTAL :-						99916.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur