

**Himachal Pradesh  
Public works Department  
Notice inviting Tender**

Sealed percentage rate tenders on form 6 & 8 are invited by the Executive Engineer, Gohar Division, H.P.PWD Gohar for the following works from the approved and eligible contractors enlisted in H.P.PWD so as to reach in his office on or before **12-02-2026 up to 11.00 A.M.** and will be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The D.N.I.T. tender documents can be had from this office against cash payment (Non-refundable) up to 5.00 P.M. on **11-02-2026**. The applications for issue of tender forms will be received **up to 2.00 P.M. on 10-02-2026**.

The earnest money in the shape of National Saving Certificate/ Time deposit accounts/Saving account/F.D. Rs. in any of the Post Office/Nationalized Banks in Himachal Pradesh duly pledged in favour of the Executive Engineer must accompany the request for issue of tender form for each work. Conditional tenders and the tenders received without earnest money will summarily be rejected. The Executive Engineer reserves the right to reject the tenders without assigning any reason. It is further added that the rates be quoted both in words and figures for proper checking to avoid any complications. If the date of opening will be holiday, the tenders will be opened on the next working day at the same time.

Sr. No.	Name of road/work	Estimated Cost	Earnest Money	Time limit
1	Repair of Restoration of rain Damages on Chambi Kangar road km. 0/00 to 5/500(SH:- Maintenance of earthen shoulder, Bush cutting, removal of slips and clearing of drain) SDF/2025/328	97551	2000	Two Months
2	RRD on Dhanotu Rohangaloo road km. 0/00 to 32/400 (SH:- C/o PCC R/wall at RD 13/832 to 13/839) Under PDNA	456931	9200	Two Months
3	RRD on Dhanotu to Rohangaloo road km. 0/00 to 32/400 (SH:- C/o RCC Causeway at RD 7/353 and Steel Panelling on Drain Between RD 11/669 to 11/681) Under PDNA	482092	9700	Two Months
4	RRD on Various roads under Dhanotu Sub-Division (SH:- Herring of Tipper for carriage of debris/muck in various roads under Bharjwanoo section)	99200	2000	One Month
5	RRD on various roads under Dhanotu sub division (SH:- Herring of JCB for removal of slips/debris, dressing of berms, clearance of drain etc. in various roads under Bharjawanoo section)	99000	2000	One Month
6	RRD on various roads under Dhanotu sub division (SH:- Herring of JCB for removal of slips/debris, dressing of berms, clearance of drain etc. in various roads under Dhanotu section)	99000	2000	One Month

Certified that tender of above works are being called for emergent nature in exigency of public interest.

**GENERAL CONDITIONS:-**

1. The Contractors are required to submit the valid Enlistment/GST registration and latest ITR alongwith application form.
2. The Contractors should quote the percentage rates in the tenders both in figures and words.
3. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
4. An undertaking will have to be given by the contractor that he has not more than two works in hand at the time of opening of this tender.
5. Contractors will have to submit appropriate Earnest Money in the shape of F.D.R along with the application form for getting issued the tender forms. Applications with out EMD shall be summarily rejected.
6. As per Govt. Notification No.PBW(B)A(3)1/2020-I dated 07-10-2021 the tenders above 5% of estimated cost will be summarily rejected. The tender offered below 30 % will also be accepted as per the office letter No. Engineer-in- Chief office letter No. PW-CTR/32-20/Genl Inst. CPWD-2020-37996-38096 dated 13.03.2023 and further ex- post-facto approval has been granted by the Principal Secretary (PW) to the Govt. of H.P. letter No. PBW (B) A(3)1/2020-I dated 10.05.2023. Beside this the additional performance security will have to borne by the bidders as per the said notifications.
7. Conditional and incomplete tenders shall be rejected.
8. The Executive Engineer reserves the right to accept or reject the tender without any reason.

Executive Engineer,  
Gohar Division (B&R),  
HPPWD Gohar.  
Dated 02-02-2026

No. PW-GHR-Tender/NIT/2025 9295-9309

Copy along with Tender inviting Notice forwarded for information:-

- 1 The Deputy Commissioner, Mandi H.P.
- 2 The Engineer-in-Chief HP.PWD.Shimla.
- 3 The Superintending Engineer 1<sup>st</sup>Circle, HP.PWD Mandi.
- 4 **The Executive Engineer (IT Cell) O/O Engineer-in-Chief, HPPWD Nirman Bhawan, Nigam Vihar, Shimla-2 for uploading the NIT on departmental website please.**
- 5 The Sub- Divisional Officer (Civil) Chachiot at Gohar.
- 6 The Block Development Officer Gohar.
- 7 The Assistant Engineer HPPWD Sub- Division Gohar/Dhanotu.
- 8 Various contractors.
- 9 Notice Board/DB/AB.


Executive Engineer,  
Gohar Division (B&R),  
HPPWD.,Gohar.



### BILL OF QUANTITY

Name of work :- Repiar of Restoration of rain Damages on Chambi Kangar road km 0/00 to 5/500 (SH:- Maintenance of earthen shoulder, Bush cutting, removal of slips and clearing of drain ) SDF/2025/328						Estimated cost Rs. - 97,551/-
						Earnest Money cost Rs.2,000/-
						Time - Two Month
SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Maintenance of earthen shoulder (Filling with fesh selected soil) Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	1044.00	per square metre	30.20		
2	Maintenance of earthen shoulder (stripping of excess soil) Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 within all leads , lifts and carriage of materials and other incidentals .	1026.00	per square metre	15.10		
3	The maintenance of drains include erosion, repair, clearing, cleaning, reshaping, regrading, deepening of side drains as well as catch water drains as per technical specification Clause 1907as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals in all leads and lifts and as per direction of Engineer in charge.	3840.00	per Running metre	4.70		
4	Cutting of branches of trees shrubs and trimming of grass and weeds cutting of branches of trees and shrubs from the road way or with in R.O.W including disposal of wood and leaves to suitable location as per technical specification Clause 1914.as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	3570.00	per square metre	5.90		
5	Removal of landslide/slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in any lift and lead upto 1.5 m and land upto 1000 meter as per technical specification 302.3.5 and 1611 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	108.64	per Cubic metre	105.10		
Total:-						
Percentage rate Quoted in figure						
Percentage rate Quoted in words						

BILL OF QUANTITY						
Name of Work:- RRD on Dhanotu Rohangaloo road km. 0/00 to 32/400 ( SH:- C/o PCC R/wall at RD. 13/832 to 13/839) . Under PDNA				Estimated cost Rs. - 456931.00		
				Earnest Money cost Rs. -9200.00		
				Time - Two Month		
Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	14.49	Per Cubic metre	230.00		
2	Providing and Laying concrete for plain/reinforced concrete in open foundations P.C.C nominal mix 1:5:10 (one cement :five sand : ten graded stone aggregate 40 mm fourty millimetre aggregates) complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge.	99.05	Per cubic metre	4350.20		
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	15.82	Per cubic metre	1050.60		
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 with in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	16.00	Each	380.70		
Total						
Percentage rate Quoted in figure						
Percentage rate Quoted in words						

  
 Executive Engineer  
 Gohar Division  
 H.P.P.W.D. Gohar

# **BILL OF QUANTITY**

Name of work :- RRD on Dhanotu to Rohangaloo road km 0/00 to 32/400 (SH:- Construction of RCC Causeway at RD 7/353 and Steel Panelling on Drain Between RD 11/669 to 11/681) Under PDNA


Estimated cost Rs. - 4,82,092/-

Earnest Money cost Rs. 9700/-

Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	18.40	Per Cubic meter	230.00		
2	Providing and Laying concrete 1:4:8 (one cement : four sand : eight graded crushed stone aggregate 40mm (forty millimeter) nominal size for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 within all leads , lifts and carriage of materials and other incidentals as directed by Engineer-incharge.	26.45	Per Cubic meter	4820.10		
3	Supplying, fitting and placing TMT bar reinforcement (Fe 415) in substructure complete as per drawings and technical specification Clauses 1002, 1005, 1010 & 1202 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	1.05	Per Tonne	93500.00		
4	Providing and laying reinforced cement concrete in nominal mix 1:1.5:3 upto 5 m height in superstructure as per drawing and technical specifications Clauses 800, 1205.4 and 1205.5 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	26.45	Per Cubic meter	6160.10		
5	Providing steel R.S.Js/built-up steel sections including cutting, welding/rivetting, hoisting, fixing in position for composite girders with shear connectors complete with painting as per drawing and technical specifications Clause 1205.6 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	8.82	Per Quintle	10120.00		
<b>Total:-</b>						
Percentage rate Quoted in figure						
Percentage rate Quoted in words						

107


  
 Executive Engineer  
 Gohar Division  
 H.P.P.W.D. Gohar



BILL OF QUANTITY						
Name of work :- RRD on various roads under Dhanotu Sub Division (SH:- Hiring of Tipper for carriage of debris/muck in various roads under Bharjwanoo section ).					Estimated cost Rs. -	96100.00
					Earnest Money cost Rs. -	2000.00
Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Time - One Month	
1	Hiring of Tipper for carriage/ disposal of debris to dumping site of work with lift to suitable place with in all leads and lifts to the entire satisfaction of the Engineer-in Charge . The Tipper should work minimum 9.00 AM to 5.00 PM daily any loss to the public/ private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the Tipper owner which shall have to be fully compensated by him in all cases the fuel and Tipper driver and lodging & boarding of operational staff will be provided by the Tipper owner the repair and spare including watch and ward of Tipper also borne by the contractor /owner. The daily log book will be maintained at site which should be dully verified by the Engineer-in charge.	31.00	Days	3100.00	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					


**Terms and conditions:-**

- 1 The daily logbook will be maintained at site which should be daily verified by the Engineer-in-Charge
- 2 During working hours any type of accident or loss of private/Govt. property the owner is responsible.
- 3 Driver and POL will be provided by the owner.

  
 Executive Engineer  
 Gohar Division  
 H.P.P.W.D. Gohar

BILL OF QUANTITY						
Name of work :- RRD on various roads under Dhanotu Sub Division (SH:- Hiring of JCB for removal of slips/debris, dressing of berms, clearance of drain etc. in various roads under Bharjawanoo Section )				Estimated cost Rs. -	99000.00	
				Earnest Money cost Rs. -2000.00		
				Time - One Month		
SL No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Hiring of JCB/Excavator for removal of slips/ debris in all kind of soil and saturated soil, dressing of road surface, filling of depressions and disposing of all excavated slips / earth or unserviceable materials from the road surfaces up to any leads and lift as per direction and entire satisfaction of Engineer in Charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of JCB/excavator owner which shall have to be duly compensated by him in all cases.The fuel and operational staff for excavator will be provided by the owner, The repair and spare, watch and ward of excavator also be borne by the contractor/owner.The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	90.00	Per Hour	1100.00		
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					
Terms and conditions:-						

- 1 The daily logbook will be maintained at site which should be daily verified by the Engineer-in-Charge
- 2 During working hours any type of accident or loss of private/Govt. property the owner is responsible.
- 3 Driver and POL will be provided by the owner.


  
 Executive Engineer  
 Gohar Division  
 H.P.W.D. Gohar

# **BILL OF QUANTITY**

Name of work :- RRD on various roads under Dhanotu Sub Division (SH:- Hiring of JCB for removal of slips/debris, dressing of berms, clearance of drain etc. in various roads under Dhanotu Section )							Estimated cost Rs. -	99000.00
							Earnest Money cost Rs. -2000.00	
							Time - One Month	
Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words		
1	Hiring of JCB/Excavator for removal of slips/ debris in all kind of soil and saturated soil, dressing of road surface, filling of depressions and disposing of all excavated slips / earth or un-serviseable materials from the road surfaces up to any leads and lift as per direction and entire satisfaction of Engineer in Charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of JCB/excavator owner which shall have to be duly compensated by him in all cases.The fuel and operational staff for excavator will be provided by the owner, The repair and spare, watch and ward of excavator also be borne by the contractor/owner.The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	90.00	Per Hour	1100.00				
	Percentage rate Quoted in figure							
	Percentage rate Quoted in words							

Terms and conditions:-

- 1 The daily logbook will be maintained at site which should be daily verified by the Engineer-in-Charge
- 2 During working hours any type of accident or loss of private/Govt. property the owner is responsible.
- 3 Driver and POL will be provided by the owner.

  
 Executive Engineer  
 Gohar Division  
 H.P.P.W.D. Gohar