

OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG

PH: 01907-222229 Fax: 222229 , e-mail : ee-kar-hp@nic.in

No.PW-KSG-E-Tenders/2024-

12803.

Dated:- 2-2-2026

To

The Executive Engineer (IT) Cell,
HPPWD, Nirman Bhawan, Nigam Vihar,
Shimla-2.


Subject :-

Regarding publication of Tender on departmental site.

With reference to the notification issued by the Secretary(PW) to the Government of Himachal Pradesh No. P BW(B)A(3)1/2024 dated 03.01.2024 and PBW-B-F0(2)/3/2024-284016 dated 18.07.2025, enclosed please find herewith the copy of Notice Inviting Tender for the loading on departmental web-site as

Certified that the works mentioned in the Tender Notice are urgent in nature and in coordination with the Disaster Management Act, 2005 Section 24 (i).

Encl:- As above.


Executive Engineer,
B&R Division,
HP PWD Karsog

**OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG
PH: 01907-222229 Fax: 222229 , E-mail : ee-kar-hp@nic.in**

Notice inviting tender

Sealed item rates tender on form 6 & 8 are hereby invited by the Executive Engineer, B&R Division HPPWD Karsog on behalf of Governor of Himachal Pradesh from the approved/eligible contractors enlisted in HP,PWD for the following works so as to reach in this office on or before **11.02.2026 upto 11.00 AM** and shall be opened on the same day at **12.00 AM** in presence of the contractor or their authorized representatives who may like to be present. The tender form can be obtained from this office against cash payment (Non refundable) **upto 4.00 PM on 10.02.2026** for which the application should reach in this office **upto 1.00 PM 10.02.2026**.

The earnest money in shape of National saving certificate/time deposit account/saving account in any Nationalized Bank in H.P duly pledged in favour of the Executive Engineer Karsog Division HPPWD Karsog will be received alongwith application for obtaining tenders form. The conditional tenders will summarily be rejected. The offer of the tenders shall be kept open for 51 days from the date of opening of tender. The Executive Engineer, HP PWD, Karsog reserves the right to reject any or all tenders without assigning any reason. The contractors should append their enlistment/renewed certificates/sale Tax registration Numbers with the application for issue of tender form. If any of the date mentioned above happens to be holiday the same shall be processed on next working day.

Sr. No.	Name of work	Estimated cost	Earnest money	Time allowed	Cost of Form
1	R/R damages on link road to village Dachhain Km. 0/00 to 2/500 (SH:- Providing work for abutment of slab culvert at RD 1/435) Job No. 2	98,964/-	2,000/-	One Month	350/-
2	R/R damages on Kahnool to Prangan road Km. 0/00 to 9/500 (SH:- Hiring of JCB/Excavator cum loader on daily wages basis for removal of snow/slips)	98,900/-	2,000/-	One Month	350/-
3	A/R & M/O Type-II residential building of HPPWD at Baral Tehsil Karsog Distt. Mandi H.P. (SH:- Providing and applying Putty,painting etc in the room in Set No. 1 &2)	92,642/-	1,900/-	One Month	350/-
4	R/R damages on Shahog to Majhas road in GP Lower Karsog Km. 0/00 to 2/00 (SH:- removal of slips, maintenance of berms & C/o unlined drain in Km. 0/00 to 2/00)	99,615/-	2,000/-	One Month	350/-
5	R/R damages on Rikki to Bahan Gadhiman road (SH:- removal of slips, maintenance of berms & C/o unlined drain in Km. 0/00 to 5/00)	99,429/-	2,000/-	One Month	350/-
6	R/R damages on Sainj Sainjeli road Km. 0/00 to 5/500 (SH:- ROFD at various stretches in KM. 3/00 to 4/00 and removal of slips in various RDs in KM. 0/00 to 5/00) under PDNA	4,82,275/-	9,700/-	Two months	350/-

7	R/R damages on Seri shout road Km. 0/00 to 19/00 (SH:- Removal of slips in various RDs in Km. 10/00 to 19/00) under PDNA	4,98,907/-	10,000/-	One month	350/-
8	R/R damages on Katanda Mahog road Km. 0/00 to 10/500 (SH:- Removal of land slide slips & maintenance of earthen shoulders at various RDs in Km. 0/00 to 10/500)	99,704/-	2,000/-	One month	350/-
9	R/R damages on Katanda Mahog road Km. 0/00 to 10/500 (SH:- Hiring of JCB/Excavator cum loader on daily wages basis for removal of snow/slips between KM. 0/00 to 5/00)	99,900/-	2,000/-	One month	350/-
10	R/R damages on Jingal Mod to Ghanufri road Km. 0/00 to 1/300 (SH:-Removal of slips at various RDs in Km. 0/00 to 0/500)	99,468/-	2,000/-	One month	350/-
11	R/R damages on Jingal Mod to Ghanufri road Km. 0/00 to 1/300 (SH:-Removal of slips at various RDs in Km. 0/500 to 0/900)	99,900/-	2,000/-	One month	350/-

TERMS & CONDITIONS:-

1. No tender form will be issued to those contractors who are not registered under HPGST Act.
2. The Contractor/firm should be registered as or dealer GST NO.
3. ~~If any of the date mentioned above happened to be Gazetted holidays the same shall be processed on next working day.~~
4. The Executive Engineer reserves the right to accept/reject any tender/ application or all tenders without assigning any reason.
5. No tender form will be issued to those contractors who are not registered under EPF Act.
6. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
7. The earnest money for the above work should be attached with the application.
8. The intending contractors/firms shall have to produce the copy of latest enlistment and renewal enlisted in HP,PWD.
9. As per Govt. Notification PW/CTR/32-20Genl Inst-CPWD/2020-37996-3809+5 dated 13-03-2023 the tenders above 5% will be summarily rejected and tenders amounts below 30% of amount put to tender will also be accepted.

Executive Engineer
B&R Division
HPPWD Karsog

No. PW-E-Tender-NIT/2025-26-

12797-12802-

Dated:-


2-2-2026

1. All the Assistant Engineers, working under this Division.
2. Copy to Drawing & Account Branch.
3. Notice board of this office.

Executive Engineer,
B&R Division,
HP PWD Karsog

Percentage Schedule of Quantity

Name of Work:- R/R Damages on Link road to Village Dachhain Km. 0/00 to 2/500 (SH:- Protection work for abutment of slab culvert at RD 1/435) Job No.2					Estimated Cost Earnest Money Time	98964 2000 One Month
Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST	Toatal Amount with all taxes including GST In Words
1	Providing concrete for plain/reinforced concrete M-10 grade 1:3:6 (one cement : three course sand : six graded crushed stone aggregate) 40 mm (forty millimeter) nominal size for mechanically mixed and vibrated in open foundation and plinths or similar work complete as per drawing and technical specifications MORD Clause 802, 803, 1202 & 1203 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	15.54	Per Cubic Meter	6368.32	98964.00	Rupees Ninety Eight Thousand Nine Hundred Sixty Four and Paise Zero Only
Total in Figures					98964.00	
Quoted Rate in Figures						
Quoted Rate in Words						



Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 98900
Earnest Money 2000
Time One Month

Name of Work:- R/R Damages on Kahanoo to Prangan road Km. 0/00 to 9/500 (SH:- Hiring of JCB/Excavator cum loader on daily wages basis for removal of snow/slips)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Hiring of JCB/Excavator cum Loader for cutting in earth work/removal of snow/slips from road surface in all kind of soil such as pick work, jumper work, blasting work in soft and hard rock saturated soil and disposing of all excavated earth or un-serviceable materials from the road surface up to any leads and lifts and as per direction of Engineer-in-Charge. The machine/JCB should work 7 Hour daily. Any loss of public property and accident etc. the contractor is fully responsible during the execution of work. The POL and operation staff for the machine will be provided by the owner the repair charges of machinery will be provided by the owner. The repair charges of machinery during the excution of work will be borne by the contractor. The useful material shall be stacked along the road side as epr direction of Engineer-in-Charge.	86.00	Per Hours	1150.00	98900.00	Rupees Ninety Eight Thousand Nine Hundred and Paise Zero Only
Quoted Rate in Figures		Select			98900.00	
Quoted Rate in Words		Zero and Paise Zero Only				



Executive Engineer,
Karsog Division,
CHPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 92642
Earnest Money 1900
Time One Month

Name of Work:- A/R & M/O Type-II residential building of HPPWD at Baral Tehsil Karsog Distt. Mandi (H.P) (Sh:- Providing & Applying Putty, Painting Etc. in the Room in Set No. 1&2).

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including	Total Amount with all taxes including GST In Words
1	15 mm (Milli metre) cement plaster on rough side of single or half brick wall of mix: 1:6 (1 cement: 6 coarse sand).as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	11.64	Per Square Metre	301.00	3504.00	Rupees Three Thousand Five Hundred Four and Paise Zero Only
2	Providing and applying white cement based putty of average thickness 1mm, (Milli metre) of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	79.82	Per Square Metre	139.80	11159.00	Rupees Eleven Thousand One Hundred Fifty Nine and Paise Zero Only
3	Wall painting two coats with premium acrylic emulsion paint of interior grade, having VOC (Volatile Orgainc Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour.as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	427.78	Per Square Metre	118.40	50649.00	Rupees Fifty Thousand Six Hundred Forty Nine and Paise Zero Only
4	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture.as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	97.38	Per Square Metre	143.37	13961.00	Rupees Thirteen Thousand Nine Hundred Sixty One and Paise Zero Only
5	Finishing with deluxe multi surface paint system for interior and exterior using primer as per maufactures specification: Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/10 sqm of approved brand and manufacture.as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	15.74	Per Square Metre	152.55	2401.00	Rupees Two Thousand Four Hundred One and Paise Zero Only
6	Providing Wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately).as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	0.03	Per Cubic Metre	152637.60	4579.00	Rupees Four Thousand Five Hundred Seventy Nine and Paise Zero Only
7	Providing and fixing panelled & glazed shutters for doors, windows and clerestory windows, including ISI marked M.S. pressed butt hinges bright finished of required size with necessary screws, excluding panelling which will be paid for separately, all complete as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. (Note:- Butt hinges and necessary screws shall be paid separately).	1.62	Per Square Metre	3943.65	6389.00	Rupees Six Thousand Three Hundred Eighty Nine and Paise Zero Only
Total in Figures					92642.00	
Quoted Rate in Figures						
Quoted Rate in Words						



 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 99615
Earnest Money 2000
Time One Month

Name of Work:- R/R Damages on Shahog to Majhas road in GP Lower Karsog Km. 0/00 to 2/00(SH:- Removal of slips,Maintenance of Berms & C/O Unlined drain in Km 0/00 to 2/00)

	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST	Total Amount with all taxes Including GST In Words
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	372.15	Per Cubic Meter	120.00	44658.00	Rupees Forty Four Thousand Six Hundred Fifty Eight and Paise Zero Only
2	Construction of unlined surface drain of average cross-section area 0.20 sqm(zero point twenty square metre) in soil specified line grade, level and dimension. Excavated material to be used to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per directin of Engineer- in -charge with in all lead and lifts and other incidentals.	300.00	Per Running Meter	23.80	7140.00	Rupees Seven Thousand One Hundred Forty and Paise Zero Only
3	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto 1000m (one thousand metre) as per technical specification clause 1903 as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	2173.50	Per Square Meter	22.00	47817.00	Rupees Forty Seven Thousand Eight Hundred Seventeen and Paise Zero Only
Total in Figures					99615.00	
Quoted Rate in Figures						
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
HPPWD, Karsog.


Percentage Schedule of Quantity

**Estimated Cost
Earnest Money
Time**

**99429
2000
One Month**

Name of Work:- R/R Damages on Rikki to Bahan Gadhiman Road (SH:- Removal of slips,Maintenance of Berms & C/O Unlined drain in Km 0/00 to 5/00)

	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST	Total Amount with all taxes Including GST In Words
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	347.50	Per Cubic Meter	120.00	41700.00	Rupees Forty One Thousand Seven Hundred and Paise Zero Only
2	Construction of unlined surface drain of average cross-section area 0.20 sqm(zero point twenty square metre) in soil specified line grade, level and dimension . Excavated material to be used to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per directin of Engineer- in -charge with in all lead and lifts and other incidentals	300.00	Per Running Meter	23.80	7140.00	Rupees Seven Thousand One Hundred Forty and Paise Zero Only
3	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto 1000m (one thousand metre) as per technical specification clause 1903 as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	2299.50	Per Square Meter	22.00	50589.00	Rupees Fifty Thousand Five Hundred Eighty Nine and Paise Zero Only
Total in Figures					99429.00	
Quoted Rate in Figures						
Quoted Rate in Words						


**Executive Engineer,
Karsog Division,
HPPWD, Karsog.**

Percentage Schedule Of Quantity

Estimated Cost 482275.00
Earnest Money 9700
Time Two Months

Name of Work:- R/R Damages on Sainj Sainjali road Km. 0/00 to 5/500 (SH:- ROFD at various Stretches in Km 3/00 to 4/00 and removal of slips in various RD's in Km 0/00 to 5/00)
Under PDNA.

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blinding and finishing of the road to specified dimensions or as directed by the Engineer-in charge for smooth riding. The recovery of 25.00 cubic metre @ Rs. 300/- per cubic metre amounting to Rs.7500/- only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases. or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	833.25	Per Cubic Meter	236.61	197155.00	Rupees One Lakh Ninety Seven Thousand One Hundred Fifty Five and Paise Zero Only
2	Removal of land slide slip clearance Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material. with in all leads and lift upto 1.5 m (one point five metre) and lead upto 1000m (one thousand metre) as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	2376.00	Per Cubic Meter	120.00	285120.00	Rupees Two Lakhs Eighty Five Thousand One Hundred Twenty and Paise Zero Only
Total in Figures					482275.00	
Quoted Rate in Figures						
Quoted Rate in Words						



Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 498907
Earnest Money 10000
Time One Month

Name of Work:- R/R Damages on Seri Shout Road Km. 0/00 to 19/00 (SH:- Removal of slips in various RD's Km 10/00 to 19/00) Under PDNA.

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material. with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	4157.56	Per Cubic Metre	120.00	498907.00	Rupees Four Lakhs Ninety Eight Thousand Nine Hundred Seven and Paise Zero Only
Total in Figures					498907.00	
Quoted Rate in Figures					0	
Quoted Rate in Words						



Executive Engineer,
Karsog Division,
PPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 99704
Earnest Money 2000
Time One Month

Name of Work:- R/R Damages on Katanda Mahog Road Km. 0/00 to 10/500 (SH:- Removal of Land Slide Slips & Maintenance of Earthen Shoulders at various RD in km 0/00 to 10/500).

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with	Toatal Amount with all taxes including GST In
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	661.26	Per Cubic Metre	120.00	79351.00	Rupees Seventy Nine Thousand Three Hundred Fifty One and Paise Zero Only
2	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	931.50	Per Square Metre	21.85	20353.00	Rupees Twenty Thousand Three Hundred Fifty Three and Paise Zero Only
Total in Figures					99704.00	
Quoted Rate in Figures						
Quoted Rate in Words						



Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 98900
Earnest Money 2000
Time One Month

Name of Work:- R/R Damages on Katanda Mahog Km 0/00 to 10/500 (SH:- Hiring of JCB/Excavator cum loader on daily wages basis for removal of snow/slips between Km. 0/00 to 5/00)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Hiring of JCB/Excavator cum Loader for cutting in earth work/removal of snow/slips from road surface in all kind of soil such as pick work, jumper work, blasting work in soft and hard rock saturated soil and disposing of all excavated earth or un-serviceable materials from the road surface up to any leads and lifts and as per direction of Engineer-in-Charge. The machine/JCB should work 7 Hour daily. Any loss of public property and accident etc. the contractor is fully responsible during the execution of work. The POL and operation staff for the machine will be provided by the owner the repair charges of machinery will be provided by the owner. The repair charges of machinery during the execution of work will be borne by the contractor. The useful material shall be stacked along the road side as per direction of Engineer-in-Charge.	86.00	Per Hours	1150.00	98900.00	Rupees Ninety Eight Thousand Nine Hundred and Paise Zero Only
Quoted Rate in Figures			Select		98900.00	
Quoted Rate in Words		Zero and Paise Zero Only				



Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 99468
Earnest Money 2000
Time One Month

Name of Work:- R/R Damages on Jingal Mod to Ghanuphari road Km. 0/00 to 1/300 (SH:- Removal of slips at various RD's in Km 0/00 to 0/500).

	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST	Total Amount with all taxes Including GST In Words
1	Removal of land slide slip clearance Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lift upto 1.5 m (one point five metre) and lead upto 1000m (one thousand metre) as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	828.90	Per Cubic Meter	120.00	99468.00	Rupees Ninety Nine Thousand Four Hundred Sixty Eight and Paise Zero Only
Total in Figures					99468.00	
Quoted Rate in Figures						
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
HPPWD, Karsog.


Percentage Schedule of Quantity

Estimated Cost
Earnest Money
Time

99900
2000
One Month

Name of Work:- R/R Damages on Jingal Mod to Ghanuphari road Km. 0/00 to 1/300(SH:- Removal of slips at various RD's in Km 0/500 to 0/900).

Sub-Head and items of works.		No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST	Total Amount with all taxes Including GST In Words
1	Removal of land slide slip clearance Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lift upto 1.5 m (one point five metre) and lead upto 1000m (one thousand metre) as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	832.50	Per Cubic Meter	120.00	99900.00	Rupees Ninety Nine Thousand Nine Hundred and Paise Zero Only
Total in Figures					99900.00	
Quoted Rate in Figures						
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
HPPWD, Karsog.