

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No.PW-AD-EA-I-Tender-2025-26 14820-29

Dated:- 19/03/24


To

The Executive Engineer (IT Cell)
H.P.P.W.D. Nigam Vihar Shimla-2.

Subject:- Notice Inviting Tender for uploading the same on departmental website.


Enclosed please find herewith Notice Inviting Tender (NIT) of various works in respect of this office as per notification Secy.(PW) to the Govt. of Himachal Pradesh letter no. PBW(B)A0(3)8/2025-300858 dated shimla-2 the 09.10.2025 and letter No. PWD-B0(3)1/2024-241828 dated Shimla 2.02.2026 as the works mentioned in the tender notice are uploading the same on departmental website at the earliest please.

Encl:-Copy of NIT


Executive Engineer,
Arki Division
H.P.P.W.D. Arki.
Ph. 01796-220714

Copy forwarded for the following for information and necessary action to:-

1. The Engineer-in-Chief, HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-2
2. The Chief Engineer, (SZ) HPPWD., Nirman Bhawan, Nigam Vihar, Shimla.
3. The Superintending Engineer, 3rd Circle, HPPWD., Solan.
4. The Deputy Commissioner Solan, Distt. Solan.
5. The Sub Divisional Magistrate Arki.
6. All the Executive Engineers in HPPWD, (SZ).
7. All the Assistant Engineer, working under this division.
8. All the heads of the branches in this office.
9. Notice Board.


Executive Engineer,
Arki Division
H.P.P.W.D. Arki.
Ph. 01796-220714

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDER

Sealed percentage tenders on PWD Form 6 & 7/8 are hereby invited by the Executive Engineer Arki Division H.P.P.W.D. Arki on behalf of Governor of Himachal Pradesh for the followings works from the eligible contractors enlisted in H.P.PWD. (B&R) whose registration stood renewed as per revised rules and also registered under the Central Goods and Service Tax Act, 2017 so as to reach in this office on before **28.03.2026 up to 11:30 AM** and the same shall be opened on the same day at **12:00 A.N.** in the presence of intending contractors or their authorized representative who may like to be present. The Tenders documents can be had from this office against cash payment (Non-refundable) on **27.03.2026 up to 4:30 PM** and the application for issue of tender form shall be received on **27.03.2026 up to 5:00 PM.**

The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/Bank duly pledged in favour of Executive Engineer Arki Division HPPWD Arki must be accompanied with the application for tender documents. Please not no exemption order of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 75 days. The Executive Engineer reserve right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on next working day at the same time and venue.


Sr. No	Name of Work	Estimated Cost	Earnest Money	Time	Cost of Form
1	R/R damages on Chandi Khali road km 0/0 to 3/0(SH:-C/o R/wall at RD 0/0 to 0/135)DMFT Deposit	3,92,673/-	8,000/-	1 Month	350/-
2.	C/o Jablu Bhanot road km. 0/0 to 1/800(SH:-Formation cutting in km. 0/0 to 0/080)Under DMFT for the year 2025-26	99,361/-	2000/-	1 Month	350/-
3	Construction of link road to Jyalang in GP Mann Tehsil Arki Distt. Solan HP Km. 0/0 to 1/0 under DMFT for the year 2025-26(SH:-Providing and laying interlocking paver Block at RD 0/045 to 0/065	99,957/-	2000/-	1 Month	350/-
4	Construction of Sahid Ram Rattan link road to village Banli Brahmana km. 0/0 to 09/645(SH:-C/o RCC hume pipe culvert 900mm diameter NP2 at Rd 0/345 with wing walls both side)Under DMFT Deposit	1,63,289/-	4000/-	1 Month	350/-
5	Restoration of rain damanges on Loharghat Bhiunkhari road km. 0/00 to 15/0 under deposit work 2025-26(SH:-C/o wire crate at RD 0/180 to 0/185)Under Deposit work	96,877/-	2000/-	1 Month	350/-
6	Restoration of rain damanges on Loharghat Bhiunkhari road km. 0/00 to 15/0 under	96,877/-	2000/-	1 Month	350/-

	deposit work 2025-26(SH:-C/o wire crate at RD 0/190 to 0/195)Under Deposit work				
7	Restoration of rain damanges on Loharghat Bhiunkhari road km. 0/00 to 15/0 under deposit work 2025-26(SH:-C/o wire crate at RD 0/185 to 0/190)Under Deposit work	96,877/-	2000/-	1 Month	350/-
8.	Construction of Breast wall for the protection of Govt. Sr. Sec. School building at Loharghat Sub-Tehsil Loharghat Distt. Solan HP(SH:-C/o B/wall at Rd 0/018 to 0/027)Job No.3)Under Deposit work	97,492	2000/-	1 Month	350/-
9	Construction of Breast wall for the protection of Govt. Sr. Sec. School building at Loharghat Sub-Tehsil Loharghat Distt. Solan HP(SH:-C/o B/wall at Rd 0/009 to 0/018)Job No.2)Under deposit work)	97,492	2000/-	1Month	350/-
10	Construction of Breast wall for the protection of Govt. Sr. Sec. School building at Loharghat Sub-Tehsil Loharghat Distt. Solan HP(SH:-C/o B/wall at Rd 0/00 to 0/009)Job No.1)Under deposit work)	97,492	2000/-	1Month	350/-
11	Repair and Maintenance of A.E. Residence at Arki. (SH:- C/o Edge wall, Paver Block 60mm thick, Plaster, White Wash, Damp proof & other Minor repair) Under Head 2216)	99,981/-	2,000/-	15 Days	350/-
12	Repair and Maintenance of A.E. Residence at Arki. (SH:- Earth work in excavation CC work 1:5:10 for Paver Block) Under Head 2216)	99,511/-	2,000/-	15 Days	350/-
13	Repair and Maintenance of A.E. & EE Residence at Arki. (SH:- P/L C.C., Paver block in Lawans 60mm thick.) Under Head 2216)	99,294/-	2,000/-	15 Days	350/-
14	Repair and Maintenance of A.E. & EE Residence at Arki. (SH:- P/L C.C. 1:5:10 and 600mm thick C.C. interlocking paver block.) Under Head 2216)	98,658/-	2,000/-	15 Days	350/-
15	Repair and Maintenance of EE Residence at Arki (SH:- Providing Panelled or panlled and glazed shutter for door, corrugated G.S. sheet prepainted steel prepainted steel sheet, wash basin cera water closet with sheet and lid) (Under Head 2216)	99,733/-	2,000/-	15 Days	350/-
16	Repair and Maintenance of A.E. & EE Residence at Arki. (SH:- P/A Damp proof water proofing, steel work tiles work etc.) Under Head 2216	85,982/-	2,000/-	15 Days	350/-

Followings documents should be attached with the application for tenders:-

- (i) The Contractors are requested to be produced a copy of their PAN No. GST No. copy of enlistment renewed letter and EPF certificate alongwith FDR against earnest money.

- (ii) Special care would be taken to write the rates both in figures and in word failing which tender is likely to be rejected.



Executive Engineer
Arki Division,
H.P.P.W.D. Arki.

Dated:- 19/03/2024

No: PW-AD-EA-I-Tender-2025-26- 14820-29


Copy forwarded for the following for information and necessary action to:-

- 1.The Superintending Engineer 3rd Circle HPPWD Solan.
- 2.The all Assistant Engineer working under this division for information and necessary action.
- 3.All the heads of the branches in this office.
- 4.Notice Board.


Executive Engineer
Arki Division
H.P.P.W.D.Arki.

Certificate

Certified that the tenders called vide this notice inviting tender for 16(sixteen) jobs are due to exigencies/emergency of works in the larger public interest.


Executive Engineer
Arki Division
H.P.P.W.D. Arki.

SCHEDULE OF QUANTITY					Estimated Cost: -Rs3,92,673/- only	
Name of Work:-R/R Damages on Chandi Khali Road Km 0/00 to 3/00. (SH:- C/o R/wall at RD 0/00 to 0/135) (DMFT Deposit)					Earnest Money :-Rs8,000/-Only	
					Time :-One Month	
S No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4		5	6
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In-Charge	39.60	171.40	Rupees One hundred seventy one and paise forty only	P.Cum.	6787
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	78.30	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	343784
3	Backfilling Granular materials behind abutment, wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts and as per the direction of Engineer-In- Charge	26.10	1203.30	Rupees one thousand two hundred three and paise thirty only	P.Cum.	31406
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	39.00	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	10696
					Total	392673

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY

Name of work :-Construction of Jablu Bhanot road km 0/00 to 1/800.(Sh:- Formation Cutting in km 0/00 to 0/080) Under DMFT for the year 2025-2026

Estimated Cost :- Rs 99,361.00
 Earnest money :- Rs 2,000.00
 Time: One months

Sr.No.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
		3		In figure	In words	6	7
1.00	Excavation in earth work in hilly area all height and depths in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super elevation and level as shown on drawings or as directed by the Engineer-In-Charge, in conformity with the requirement of technical specification for rural Road, August, 2004 and clause 16.2 of General Conditions for Contract to achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blind age and finishing of the road to specified dimensions or as directed by the Engineer-IN-Charge for smooth riding. The recovery of useful stone that is 22.32 cum . In all cases, @ Rupees 300/- cum. shall be effected on pro rata basis. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	558.05	cum	178.05	Rupees One Hundred Seventy eight and Five paise only	Per cubic metre	99361.00
						Total	99361.00
Conditions:- (i) All the machinery etc. will be procured by the contractor himself							

Quoted Rate Percentage in Figures
 Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division (B&R)
 HP. PWD. Arki.

SCHEDULE OF QUANTITY

Name of work :-Construction of Link road to Jyalang in GP Mann Tehsil Arki Distt Solan HP. Km 0/00 to 1/00 UNDER DMFT
for the year 2025-2026 (SH:-Providing and laying Interlock Paver Block at Rd 0/045 to 0/065)

Estimated Cost :- Rs 99,957.00

Earnest money :- Rs 2,000.00


Time: One month

Sr.No.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
		3		In figure	In words		
1	2	3		4	5	6	7
1.00	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of slumps and other deleterious material and disposal up to a lead of 50 meters dressing of sides and bottom and back filling in trenches with excavated suitable materials. (I) Ordinary Rock (I) Up to 3 m. depth.	0.00	Cum	171.40	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	0.00
2.00	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clauses 802,803,1202 and 1203. P.C.C. 1:4:8 40 mm nominal size including carriage of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	6.05	Cum	4855.20	Rupees Four Thousand eight Hundred fifty five and twenty paise Only	Per cubic metre	29374.00
3.00	Providing concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specifications Clauses 802,803,1202 and 1203. (II) P.C.C. Grade M-10 (i) Nominal mix 1:3:6 (20 mm Nominal Size) including carriage of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	0.45	Cum	5294.95	Rupees Five Thousand Two HundredNinety four and Ninety five paise Only	Per cubic metre	2383.00
4.00	Providing and laying factory made Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape. made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-inCharge . 80 mm thick C.C. paver block of M-30 grade with approved color design and pattern including carriage of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	62.00	Sqm	1100.00	Rupees One Thausand one Hundred r and Twenty Zero paise Only	Per Square metre	68200.00
						Total	99957.00

Conditions:- (i) All the material will be procured by the contractor himself and bills will be submitted.(ii) The cement will be procured by the contractor from the nearest HP Civil Supply Depot.

Quoted Rate Percentage in Figures

Quoted Rate Percentage in Words


Executive Engineer
Arki Division (B&R)
HP. PWD. Arki.

DRAFT SCHEDULE OF QUANTITY

NAME OF WORK:- Construction of Sahid Ram Rattan Link road to Village Banli Brahmana km 0/00 to 0/645.(SH :- C/o RCC Hume Pipe Culvert 900 mm diameter NP2 at Rd 0/345 with wing walls both side.) Under DMFT Deposit.

Estimated Cost :- Rs 1,63,289.00

Earnest money :- Rs 4,000.00


Time: One months

Sr.No	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
		3		In figure	In words	6	7
1.00	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORD Specification and as per the direction of Engineer-In- Charge	49.40	Cum	171.40	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	8467.00
2.00	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clauses 802,803,1202 and 1203. P.C.C. 1:4:8 40 mm (One cement isto four fine sand isto eight graded stone aggregate forty milimeter) nominal size including carriage of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	3.53	Cum	4855.20	Rupees Four Thousand Eight Hundred Fifty Five and Twenty paise Only	Per cubic metre	17139.00
3.00	Providing concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specifications Clauses 802,803,1202 and 1203. (II) P.C.C. Grade M-10 (i) Nominal mix 1:3:6 (20 mm Nominal Size) including carriage of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	3.00	Cum	5294.95	Rupees Five Thousand Two Hundred Ninety four and Ninety Five paise Only	Per cubic metre	15885.00
4.00	Providing and laying Plain cement concrete 1:5:10 (one cement isto Five sand isto ten graded crushed stone aggregate 40 milimetre(forty milimetre) nominal size for plain /reinforced concrete in open foundation complete as per drawings and technical specifications clause 802,803,1202 & 1203 and curing complete including the cost of form work and carriage of materials in all leads lifts as per the direction of Engineer-In-Charge.	12.75	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Sixty paise Only	Per cubic metre	55980.00
5.00	Providing and laying reinforced concrete pipe NP2 for culverts on first class bedding of granular materials in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets Clause 1108.(C) 900 mm dia. including carriage of materials in all leads & lifts and as per entire stisfaction of Engineer-in -Charge.	15.00	Cum	3881.55	Rupees Three Thousand eight Hundred eighty one and fifty Five paise Only	Per cubic metre	58223.00
6.00	Back filling behind abutment ,wing wall and retaining wall of granular material complete as per drawings and technical specifications MORD clause 1204.3.8 including carriage of materials within all leads lifts and as per the direction of Engineer-In-Charge.	5.40	Cum	1203.30	Rupees One Thousand Two Hundred Three and Thirty paise Only	Per cubic metre	6498.00

7.00	Providing and laying weapholes in brick masonry /stone masonry /plain reinforced concrete abutment, wing wall return wall with 100mm (one hundred)milimetre dia PVC pipe extending through the full width of the structures with slop of 1(v);20 (H) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7 including carriage of materials within all leads and lifts as per the direction of Engineer-In-Charge.	4.00	Rmt	274.25	Rupees Two Hundred Seventy Four and Twenty Five paise Only	Per running metre	1097.00
						Total	163289.00

Conditions:- i) All the material will be procured by the contractor himself and bills will be submitted.(ii) The cement will be procured by the contractor from the nearest HP Civil Supply Depot.

Draft Schedule of Quantity duly Approved for Rs 1,63,289=00 /- only (Rupees One lac sixty three thousand two hundred eighty nine and paise zero) only for the year 2025-26. Entered at 6/1


Executive Engineer
Arki Division (B&R)
HP, PWD. Arki.

SCHEDULE OF QUANTITY

Name of work :-Restoration of Rain damages on Loharghat Bhuinkhary road km 0/00 to 15/00. UNDER Deposit work
 2025-26.(SH:-C/O Wire Crate at RD 0/180 to 0/185) Under Deposit work. For the year 2025-26

Estimated Cost :- Rs 96,877.00

Earnest money :- Rs 2,000.00

Time: One months

Sr.No.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
				In figure	In words		
1	2	3				6	7
1.00	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of slumps and other deleterious material and disposal up to a lead of 50meters dressing of sides and bottom and back filling in trenches with excavated suitable materials. (1) Ordinary Rock (1) Up to 3 m. depth.	17.50	cum	171.40	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	3000.00
2.00	Providing and laying of boulder apron laid in wire crates with 4mm dia G.I. wire conforming to IS:280 and IS:4826 in 100 mm x100mm mesh (woven diagonally) including 10 per cent extra for laps and joint laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301.	31.25	cum	3004.05	Rupees Four Thousand Three Hundred Ninety and Sixty paise Only	Per cubic metre	93877.00
						Total	96877.00

Conditions:- i) All the material will be procured by the contractor himself and bills will be submitted.(ii) The cement will be procured by the contractor from the nearest HP Civil Supply Depot.

Quoted Rate Percentage in Figures

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division (B&R)
 HP. PWD. Arki.

SCHEDULE OF QUANTITY

Name of work :-Restoration of Rain damages on Loharghat Bhuinkhary road km 0/00 to 15/00. UNDER Deposite work 2025-26.(SH:-C/O Wire Crate at RD 0/190 to 0/195) Under Deposit work. For the year 2025-26					Estimated Cost :- Rs 96,877.00		
					Earnest money :- Rs 2,000.00		
					Time: One months		
Sr.No.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
		1	2	In figure	In words		
1.00	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of slumps and other deleterious material and disposal up to a lead of 50meters dressing of sides and bottom and back filling in trenches with excavated suitable materials. (1) Ordinary Rock (1) Up to 3 m. depth.	17.50	cum	171.40	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	3000.00
2.00	Providing and laying of boulder apron laid in wire crates with 4mm dia G.I. wire conforming to IS:280 and IS:4826 in 100 mm x100mm mesh (woven diagonally) including 10 per cent extra for laps and joint laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301.	31.25	cum	3004.05	Rupees Four Thousand Three Hundred Ninety and Sixty paise Only	Per cubic metre	93877.00
						Total	96877.00

Conditions:- i) All the material will be procured by the contractor himself and bills will be submitted.(ii) The cement will be procured by the contractor from the nearest HP Civil Supply Depot.

Quoted Rate Percentage in Figures
Quoted Rate Percentage in Words


Executive Engineer
Arki Division (B&R)
HP, PWD. Arki.

SCHEDULE OF QUANTITY

Name of work :-Restoration of Rain damages on Loharghat Bhuinkhary road km 0/00 to 15/00. UNDER Deposit work
 2025-26.(SH:-C/O Wire Crate at RD 0/185 to 0/190) Under Deposit work. For the year 2025-26

Estimated Cost :- Rs 96,877.00
 Earnest money :- Rs 2,000.00
 Time: One months

Sr.No.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
				In figure	In words		
1	2	3				6	7
1.00	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of slumps and other deleterious material and disposal up to a lead of 50meters dressing of sides and bottom and back filling in trenches with excavated suitable materials. (I) Ordinary Rock (I) Up to 3 m. depth.	17.50	cum	171.40	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	3000.00
2.00	Providing and laying of boulder apron laid in wire crates with 4mm dia G.I. wire conforming to IS:280 and IS:4826 in 100 mm x100mm mesh (woven diagonally) including 10 per cent extra for laps and joint laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301.	31.25	cum	3004.05	Rupees Four Thousand Three Hundred Ninety and Sixty paise Only	Per cubic metre	93877.00
						Total	96877.00

Conditions:- i) All the material will be procured by the contractor himself and bills will be submitted.(ii) The cement will be procured by the contractor from the nearest HP Civil Supply Depot.

Quoted Rate Percentage in Figures
 Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division (B&R)
 HP. PWD. Arki.

SCHEDULE OF QUANTITY

Name of work :-Construction of Breast wall for the protection of Govt Sr. Sec. School building at Loharghat Sub Tehsil Loharghat Distt Solan HP.(SH :- (Sh:- Construction of breast wall at Rd 0/018 to 0/027) Job No.3) Under Deposit work.	Estimated Cost :- Rs 97,492.00 Earnest money :- Rs 2,000.00 Time: One months
--	--

Sr.No.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
		1	2	In figure	In words		
1.00	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORD Specification and as per the direction of Engineer-In- Charge	6.66	Cum	171.40	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	1142.00
2.00	Providing and laying Plain cement concrete 1:5:10 (one cement isto Five sand isto ten graded crushed stone aggregate 40 milimetre(forty milimetre) nominal size for plain /reinforced concrete in open foundation complete as per drawings and technical specifications clause 802,803,1202 &1203 and curing complete including the cost of form work and carriage of materials in all leads lifts as per the direction of Engineer-In-Charge.	21.24	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Sixty paise Only	Per cubic metre	93256.00
3.00	Back filling behind abutment ,wing wall and retaining wall of granular material complete as per drawings and technical specifications MORD clause 1204.3.8 including carriage of materials within all leads lifts and as per the direction of Engineer-In-Charge.	0.00	Cum	1203.30	Rupees One Thousand Two Hundred Three and Thirty paise Only	Per cubic metre	0.00
4.00	Providing and laying weapholes in brick masonry /stone masonry /plain reinforced concrete abutment, wing wall return wall with 100mm (one hundred)milimetre dia PVC pipe extending through the full width of the structures with slop of 1(v);20 (H) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7 including carriage of materials within all leads and lifts as per the direction of Engineer-In-Charge.	11.28	Rmt	274.25	Rupees Two Hundred Seventy Four and Twenty Five paise Only	Per running metre	3094.00
						Total	97492.00

Conditions:- i) All the material will be procured by the contractor himself and bills will be submitted.(ii) The cement will be procured by the contractor from the nearest HP Civil Supply Depot.

Quoted Rate Percentage in Figures
 Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division (B&R)
 HP. PWD Arki.

SCHEDULE OF QUANTITY

Name of work :- Construction of Breast wall for the protection of Govt Sr. Sec. School building at Loharghat Sub Tehsil Loharghat Distt Solan HP.(SH :- (SH:- Construction of breast wall at Rd 0/009 to 0/018) Job No.2) Under Deposit work.

Estimated Cost :- Rs 97,492.00


Earnest money :- Rs 2,000.00

Time: One months

Sr.No.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
				In figure	In words		
1	2	3				6	7
1.00	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORD Specification and as per the direction of Engineer-In- Charge	6.66	Cum	171.40	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	1142.00
2.00	Providing and laying Plain cement concrete 1:5:10 (one cement isto Five sand isto ten graded crushed stone aggregate 40 milimetre(forty milimetre) nominal size for plain /reinforced concrete in open foundation complete as per drawings and technical specifications clause 802,803,1202 &1203 and curing complete including the cost of form work and carriage of materials in all leads lifts as per the direction of Engineer-In-Charge.	21.24	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Sixty paise Only	Per cubic metre	93256.00
3.00	Back filling behind abutment ,wing wall and retaining wall of granular material complete as per drawings and technical specifications MORD clause 1204.3.8 including carriage of materials within all leads lifts and as per the direction of Engineer-In-Charge.	0.00	Cum	1203.30	Rupees One Thousand Two Hundred Three and Thirty paise Only	Per cubic metre	0.00
4.00	Providing and laying weapholes in brick masonry /stone masonry /plain reinforced concrete abutment, wing wall return wall with 100mm (one hundred)milimetre dia PVC pipe extending through the full width of the structures with slop of 1(v);20 (H) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7 including carriage of materials within all leads and lifts as per the direction of Engineer-In-Charge.	11.28	Rmt	274.25	Rupees Two Hundred Seventy Four and Twenty Five paise Only	Per running metre	3094.00
						Total	97492.00

Conditions:- i) All the material will be procured by the contractor himself and bills will be submitted.(ii) The cement will be procured by the contractor from the nearest HP Civil Supply Depot.

Quoted Rate Percentage in Figures
Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division (B&R)
 HP. PWD. Arki.

SCHEDULE OF QUANTITY

Name of work :- Construction of Breast wall for the protection of Govt Sr. Sec. School building at Loharghat Sub Tehsil Loharghat Distt Solan HP. (SH :- (Sh:- Construction of breast wall at Rd 0/00 to 0/009) Job No.1) Under Deposit work.		Estimated Cost :- Rs 97,492.00					
		Earnest money :- Rs 2,000.00					
		Time: One months					
Sr.No.	Sub Head and Items of Work	Qty.	Rate	Unit	Amount		
1	2	3	In figure	In words	6	7	
1.00	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORD Specification and as per the direction of Engineer-In- Charge	6.66	Cum	171.40	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	1142.00
2.00	Providing and laying Plain cement concrete 1:5:10 (one cement isto Five sand isto ten graded crushed stone aggregate 40 milimetre(forty milimetre) nominal size for plain /reinforced concrete in open foundation complete as per drawings and technical specifications clause 802,803,1202 &1203 and curing complete including the cost of form work and carriage of materials in all leads lifts as per the direction of Engineer-In-Charge.	21.24	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Sixty paise Only	Per cubic metre	93256.00
3.00	Back filling behind abutment ,wing wall and retaining wall of granular material complete as per drawings and technical specifications MORD clause 1204.3.8 including carriage of materials within all leads lifts and as per the direction of Engineer-In-Charge.	0.00	Cum	1203.30	Rupees One Thousand Two Hundred Three and Thirty paise Only	Per cubic metre	0.00
4.00	Providing and laying weapholes in brick masonry /stone masonry /plain reinforced concrete abutment, wing wall return wall with 100mm (one hundred)milimetre dia PVC pipe extending through the full width of the structures with slop of 1(v);20 (H) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7 including carriage of materials within all leads and lifts as per the direction of Engineer-In-Charge.	11.28	Rmt	274.25	Rupees Two Hundred Seventy Four and Twenty Five paise Only	Per running metre	3094.00
						Total	97492.00

Conditions:- i) All the material will be procured by the contractor himself and bills will be submitted.(ii) The cement will be procured by the contractor from the nearest HP Civil Supply Depot.

Quoted Rate Percentage in Figures
Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division (B&R)
 HP, PWD. Arki.

SCHEDULE OF QUANTITY

Estimated Cost: -Rs99,981/- only

Name of Work:-Repair and Maintenance of A.E. Residence at Arki.(SH:- C/o Edge wall, Paver Block 60mm thick, Plaster, White Wash, Damp proof & other Minor repair.) (Under Head 216)

Earnest Money :-Rs2,000/-Only

Time :-Fifteen Days

S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	15mm Cement plaster in single coat on the rough side and fair side of brick/ concrete/ stone walls for interior plastering upto floor two level including arrises,internal rounded angles, chamfers and/or rounded angles not exceeding 80mm in girth and finished even and smooth including all leads , lifts & carriage of material. (Cement Mortar 1:6 (1 Cement isto 6 Sand).	76.10	196.45	Rupees one hundred ninety six and paise forty five only	P.Sqm	14950
2	Providing and applying white cement based putty of average thickness 1mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	200.00	85.10	Rupees eighty five and paise ten only	P.Sqm.	17020
3	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications Two or more coats applied on walls @ 1.25 ltr/10 sqm over and including one coat of Special primer applied @ 0.75 ltr /10 sqm including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	500.00	106.25	Rupees one hundred six and paise twenty five only	P.Sqm.	53125
4	Providing and laying cement concrete work 1:2:4 (one cement : two sand : four graded stone aggregate40mm nominal size) mechanically mixed and compecting with vibrator and curing complete excluding cost of form work and reinforced concrete work including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge .	2.50	5954.35	Rupees five thousand nine hundred fifty four and paise thirty five only	P.Cum.	14886
					Total	99981

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY					Estimated Cost: -Rs99,511/- only	
Name of Work:-Repair and Maintenance of A.E. Residence at Arki.(SH:- Earth work in excavationand CC work1:5:10 for Paver Block) (Under Head 1216)					Earnest Money :-Rs2000/-Only	
					Time :-Fifteen Days	
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	28.55	171.40	Rupees One hundred seventy one and paise forty only	P.Cum.	4893
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	21.55	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	94617
					Total	99511

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY					Estimated Cost: -Rs99,294/- only	
Name of Work:-Repair and Maintenance of A.E. & E.E. Residence at Arki.(SH:-P/L C.C. ,Paver Block in Lawans 60mm thick, .) (Under Head 216)					Earnest Money :-Rs2,000/-Only	
					Time :-Fifteen Days	
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding /laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in-Charge. (60 mm) Sixty milimeter thick C.C. paver block of M-30 grade NTC brand with approved color design and pattern)	76.38	1300.00	Rupees one thousand three hundred and paise zero only	P.Sqm.	99294
					Total	99294

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY

Estimated Cost: -Rs98,658/- only

Name of Work:-Repair and Maintenance of A.E. & E.E. Residence at Arki.(SH:-P/L C.C.1:5:10 and 60mm thick C.C. Interlocking Paver Block .) (Under Head 216)


Earnest Money :-Rs2,000/-Only

Time :-Fifteen Days

S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	11.90	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	52248
2	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding /laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in-Charge. (60 mm) Sixty milimeter thick C.C. paver block of M-30 grade NTC brand with approved color design and pattern)	35.70	1300.00	Rupees one thousand three hundred and paise zero only	P.Sqm.	46410
					Total	98658

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY

Estimated Cost: -Rs99,733/- only


Earnest Money :-RS2,000/-Only

Time :-Fifteen Days

Name of work:- Repair of Maintenance of E.E. Residence at Arki (SH:- Providing Panelled or panlled and glazed shutter for door, corrugated G.S. sheet preapainted steel sheet, wash basin cera water closet with sheet and lid) Under Head 216

S. No	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, excluding panelling which will be paid for separately, all complete as per direction of Engineer-in-charge. 35mm thick shutters.	3.60	3122.60	Rupees Three Thousand One Hundred & Twenty Two - Paise Sixty Only	P.Sqm	11241
2	Providing corrugated G.S. sheet roofing including vertical/ curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. 0.63mm thick with zinc coating not less than 275gm/m2 all complete as per direction of Engineer-in-charge	8.28	837.30	Rupees Eight Hundred & Thirty Seven Paise Thirty Only	P.Sqm	6933
3	Providing and fixing 0.60mm thick preapainted steel sheet Tata/Reliance/Jundal sheets in roofing with not dipped metallic zinc coated sheet with top coat of regular midified polyster(RNP) orginc coating of 20 microns over 5 microns primer coating to back coat of polyster of 5 microns over 5 microns primer coating i/c fixing with preapainted iron J or I. hooks, bolts, and nuts 6mm dia metre with preapainted limpet and rubber washers complete with all accesiriees as required as per the direction of Engineer-in-charge.	10.15	1321.05	Rupees One Thousand Three Hundred & Twenty One - Paise Five Only	P.Sqm	13409
4	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever required: White Vitreous Cera Wash basin size 530x345 mm with a pair of 15 mm C.P. brass pillar tap.all complete as per direction of Engineer-in-charge	2.00	7000.00	Rupees Seven Thousand Only	Each	14000
5	Providing and fixing white viteous pedestal for wash basin competely recessed at the back for the reception of pipes and fittings.complete and as per direction of Engineer-in-charge	2.00	1420.15	Rupees One Thousand Four Hundred & Twenty - Paise Fifteen Only	Each	2840
6	Providing and fixing white vitreous Cera pedestal type water closet with seat and lid, 10 litre low level white vitreous china flushing cistern & C.P. flush bend with fittings 7 C.I. brackets, 40 mm flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required: W.C. pan with ISI marked white solid plastic seat and lid.complete and as per direction of Engineer-in-charge	2.00	15000.00	Rupees Fifteen Thousand Only	Each	30000
7	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.75 ltr / 10 sqm of approved brand and manufacture and as per direction of Engineer-in-charge	225.98	94.30	Rupees Ninety Four - Paise Thirty Only	P.Sqm	21310
Total						99733

Quoted Rate Percentage in Figure
Quoted Rate Percentage in Words


Executive Engineer
Arki Division, HPPWD
Arki

SCHEDULE OF QUANTITY

Estimated Cost: -Rs85,982/- only

Earnest Money :-RS2,000/-Only

Time :-Fifteen Days

Name of work:- Repair & Maintenance of A.E. & E.E. Residence at Arki (SH:- P/A Damp proof water proofing, steel work tiles work etc. Under Head 2216

S. No	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Providing and applying Damp Proof coating, two or more coat over and under coat of primer with approved brand and manufacture including cleaning the slab /concrete surface by removing all dirt and foreign material etc. complete and as per the direction of Engineer-in-Charge	4.62	305.00	Rupees Three Hundred & Five Only	P.Sqm.	1409
2	Providing and fixing cup board shutters 25 mm thick, with Pre-laminated flat pressed three layer particle board or graded wood particle board IS: 12823 marked, exterior grade, having one side decorative lamination and other siddebalancing lamination, including IInd class teak wood lipping of 25 mm wide x 12 mm thick with necessary screws and bright finished stainless steel piano hinges, complete as per direction of the Engineer-in-charge.	7.50	1765.95	Rupees One Thousand Seven Hundred & Sixty Five - Paise Ninety Five Only	P.Sqm.	13245
3	Steel work welded in built up sections/ framed work. A priming coat of approval steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder railings, brackets, gates and similar works.within all leads, lifts and as per the direction of Engineer-In-Charge	128.00	107.45	Rupees One Hundred & Seven - Paise Fourty Five Only	P.Kg	13754
4	Providing and laying vitrified floor tiles in different sizes with water absorption less then 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4, jointing with cement slurry @ 3.3 kg/sqm including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 600x600mm. within all leads, lifts and as per the direction of Engineer-In- Charge	5.04	1360.70	Rupees One Thousand Three Hundred & Sixty - Paise Seventy Only	P.Sqm.	6858
5	Providing and laying Ceramic glazed floor tiles of size 300x300 mm of 1st quality conforming to IS: 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20mm thick cement mortar 1:4, jointing with grey cement slurry @ 3.3 kg/sqm including pointing the joints with white cement and matching pigment etc. complete.within all leads, lifts and as per the direction of Engineer-In- Charge	29.52	787.05	Rupees Seven Hundred & Eighty Seven - Paise Five Only	P.Sqm.	23234
6	Providing and fixing C.P. brass long nose bib cock of approved quality conforming to IS standards and weighing not less than 810 gms. 15mm nominal bore as per the direction of Engineer-In- Charge	4.00	618.80	Rupees Six Hundred & Eighteen - Paise Eighty Only	Each	2475
7	Providing and laying cement concrete 1:2:4(1 cement 2 sand 4 graded stone aggregate 40mm nominal size) with curing complete in retaining wall/ Breast wall as per HP PWD specification.within all leads, lifts and as per the direction of Engineer-In- Charge	4.20	5954.35	Rupees Five Thousand Nine Hundred & Fifty Four - Paise Thirty Five Only	P.Cum	25008
Total						85982

Quoted Rate Percentage in Figure
Quoted Rate Percentage in Words


Executive Engineer
Arki Division, HPPWD
Arki