

HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT

No.PW-AD-EA-1-Tender-2025-26

14868-77

Dated:-23/03/26


To

The Executive Engineer (IT Cell)  
H.P.P.W.D. Nigam Vihar Shimla-2.

**Subject:- Notice Inviting Tender for uploading the same on departmental website.**

Enclosed please find herewith Notice Inviting Tender (NIT) of various works in respect of this office as per notification Secy.(PW) to the Govt. of Himachal Pradesh letter no. PBW(B)A0(3)8/2025-300858 dated shimla-2 the 09.10.2025 and letter No. PWD-B0(3)1/2024-241828 dated Shimla 2.02.2026 as the works mentioned in the tender notice are uploading the same on departmental website at the earliest please.

**Encl:-Copy of NIT**

  
Executive Engineer,  
Arki Division  
H.P.P.W.D. Arki.  
Ph. 01796-220714

Copy forwarded for the following for information and necessary action to:-

1. The Engineer-in-Chief, HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-2
2. The Chief Engineer, (SZ) HPPWD., Nirman Bhawan, Nigam Vihar, Shimla.
3. The Superintending Engineer, 3rd Circle, HPPWD., Solan.
4. The Deputy Commissioner Solan, Distt. Solan.
5. The Sub Divisional Magistrate Arki.
6. All the Executive Engineers in HPPWD, (SZ).
7. All the Assistant Engineer, working under this division.
8. All the heads of the branches in this office.
9. Notice Board.

  
Executive Engineer,  
Arki Division  
H.P.P.W.D. Arki.  
Ph. 01796-220714

HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDER

Sealed percentage tenders on PWD Form 6 & 7/8 are hereby invited by the Executive Engineer Arki Division H.P.P.W.D. Arki on behalf of Governor of Himachal Pradesh for the followings works from the eligible contractors enlisted in H.P.PWD. (B&R) whose registration stood renewed as per revised rules and also registered under the Central Goods and Service Tax Act, 2017 so as to reach in this office on before 31.03.2026 up to 11:30 AM and the same shall be opened on the same day at 12:00 A.N. in the presence of intending contractors or their authorized representative who may like to be present. The Tenders documents can be had from this office against cash payment (Non-refundable) on 30.03.2026 up to 4:30 PM and the application for issue of tender form shall be received on 30.03.2026 up to 5:00 PM.


The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/Bank duly pledged in favour of Executive Engineer Arki Division HPPWD Arki must be accompanied with the application for tender documents. Please not no exemption order of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 75 days. The Executive Engineer reserve right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on next working day at the same time and venue.

Sr. No	Name of Work	Estimated Cost	Earnest Money	Time	Cost of Form
1	C/o Ambulance road Sora Nala to House of Chandu Ram (Mingla Sora) (SH:- C/o R/wall at RD 0/105 to 0/123.50) DMFT	2,78,898/-	5,600/-	1 Month	350/-
2.	C/o Forest Rest house building at Kandar (SH:- Providing & Fixing PMKKKY Tripical informatory sign board.)	91,352/-	2000/-	1 Month	350/-
3	C/o link road Primary School Kashyalu to Kali Mata Mandir km. 0/00 to 1/075 (SH:- P/L C.C. Paver Block Kali Mata Mandir (Gaina)DMFT.	4,93,583/-	10,000/-	1 Month	350/-
4	C/o link road Primary School Kashyalu to Kali Mata Mandir km. 0/0 to 1/075) (SH:- C/o B/wall at RD 0/00 to 0/020, R/wall at RDs 0/00 to 0/025) DMFT	4,46,766/-	9,000/-	1 Month	350/-
5	C/o Ambulance road from H/o Sh. Narayanu to Pump House Kashyalu in km. 0/00 to 0/330.(Balance Work) (SH:- C/o Rwall at RD 0/265 to 0/269) DMFT Deposit	1,91,438/-	4,000/-	1 Month	350/-
6	C/o Ambulance road from H/o Sh. Narayanu to Pump House Kashyalu in km. 0/00 to 0/330 (SH:- C/o R/wall at RD 0/255 to 0/265) DMFT Deposit.	4,79,336/-	10,000/-	1 Month	350/-

	C/o Ambulance road Mangooghat Dharil Malawan km. 0/00 to 5/00 (SH:- P/L WBM G-1, C.C. 1:4:8, C.C. 1:2:4 and Kharanja Stone soling km. 0/00 to 0/090) DMFT	4,79,840/-	10,000/-	1 Month	350/-
8.	C/o Toon Padyar road km. 0/0 to 2/750. (SH:- C/o R/wall at RD 0/768 to 0/783) DMFT	1,65,179/-	3,500/-	1 Month	350/-
9	C/o Ambulance road Pansoda to Chamba km. 0/0 to 1/0 (SH:- C/o Hume Pipe culvert at RD 0/065 and 0/465) DMFT	3,76,139/-	7,600/-	1 Month	350/-
10	R/R damages on Kandar Samtyari Padyar road km. 0/0 to 4/500 (SH:- Hiring of JCB for reoval of slips) Job No. 1	99,000/-	2,000/-	15 Days	350/-
11	C/o Ambulance road Pansoda to Chamba km. 0/0 to 1/0 (SH:- Formation Cutting at RD's 0/00 to 0/585) DMFT Deposit.	3,12,000/-	6,500/-	1 Month	350/-
12	C/o Ambulance road Pansoda to Chamba km. 0/00 to 1/00 (SH:- Formation Cutting at RD's 0/585 to 0/975) DMFT Deposit	2,57,553/-	5,200/-	1 Month	350/-
13	C/o Retaining wall for Govt. High School Sehrol. (Under DMFT)	4,99,915/-	10,000/-	1 Month	350/-
14	R/R damages on Kandar Samtyari Padyar road km. 0/00 to 4/500 (SH:- Hiring of Tipper for removal of slips.) Job No.1	97,500/-	2,000/-	15 Days	350/-
15	C/o Boundary wall in Govt. High School Bagga, GP. Bagga, Tehsil Arki, Distt. Solan HP. (SH:- Providing and Fixing Fencing Gate, Plaster work and Painting.) DMFT Deposit.	2,29,672/-	5,000/-	1 Month	350/-

Followings documents should be attached with the application for tenders:-


- The Contractors are requested to be produced a copy of their PAN No. GST No. copy of enlistment renewed letter and EPF certificate alongwith FDR against earnest money.
- Special care would be taken to write the rates both in figures and in word failing which tender is likely to be rejected.

  
Executive Engineer  
Arki Division,  
H.P.P.W.D. Arki.

No: PW-AD-EA-I-Tender-2025-26- 14868-77  
Copy forwarded for the following for information and necessary action to:-


Dated:- 23/03/26

- The Superintending Engineer 3<sup>rd</sup> Circle HPPWD Solan.
- The all Assistant Engineer working under this division for information and necessary action.
- All the heads of the branches in this office.
- Notice Board.

  
Executive Engineer  
Arki Division  
H.P.P.W.D. Arki.

### Certificate


Certified that the tenders called vide this notice inviting tender for 15 (Fifteen) jobs are due to exigencies/emergency of works in the larger public interest.

  
Executive Engineer  
Arki Division  
H.P.P.W.D. Arki.

SCHEDULE OF QUANTITY					Estimated Cost: -Rs2,78,898/- only	
Name of Work:-C/o Ambulance Road Sora Nala to House of Chandu Ram ( Mingla Sora).					Earnest Money :-Rs5,600/-Only	
(SH:- C/o R/wall at RD 0/105 to 0/123.50 ) DMFT					Time :-One Month	
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	25.90	171.40	Rupees One hundred seventy one and paise forty only	P.Cum.	4439
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	55.69	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	244513
3	Backfilling Granular materials behind abutment, wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts.and as per the direction of Engineer-In- Charge	18.87	1203.30	Rupees one thousand two hundred three and paise thirty only	P.Cum.	22706
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	26.40	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	7240
					Total	278898

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words

  
Executive Engineer  
Arki Division HPPWD  
Arki

SCHEDULE OF QUANTITY						Estimated Cost: -Rs91,352/- only	
Name of Work:-C/o Forest Rest House Building at Kandar. (SH:-Providing & fixing PMKKKY Typical Informatory Sign Board.)						Earnest Money :-Rs2,000/-Only	
						Time :-One Month	
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount	
			Figure	Words			
1	Providing and fixing of PMKKY typical informatory sign board as per specifications and drawing. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted The rate is including octroi, royalty, Malkana, toll tax or any other taxes imposed by the Government but excluding GST. with primer and two coats of epoxy paint as per drawing & MORD Specification section 1700 and Annexure 1700.1 including hauling of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.The rate is including octroi, royalty, Malkana, toll tax or any other taxes imposed by the Government but excluding GST.	5.00	18270.30	Rupees eighteen thousand two hundred seventy and paise thirty only	Each	91352	
					Total	91352	

Quoted Rate Percentage in Figure


Quoted Rate Percentage in Words

  
 Executive Engineer  
 Arki Division HPPWD  
 Arki

SCHEDULE OF QUANTITY					Estimated Cost: -Rs4,93,583/- only	
Name of Work:-C/o Link Road Primary School Kashyalu to Kali Mata Mandir Km 0/00 to1/075. (SH:- P/L C.C. Paver Block Kali Mata Mandir (Gaina)) DMFT					Earnest Money :-Rs10,000/-Only	
					Time :-One Month	
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Surface dressing of Ground including removing of Vegetation and in-equalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5 m. all kinds of soil and as directed by Engineer-In- Charge	300.00	14.00	Rupees fourteen and paise zero only	P.Sqm.	4200
2	WBM Grading -I :- Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, stone screening /binding material to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading-1 as per Technical Specification Clause 405. by mechanically means using stone aggregate 90mm to 40mm (Ninety to forty millimeter size) including carriage of material with in all leads, lifts and as per the direction of Engineer-In-Charge.	30.00	1969.80	Rupees one thousand nine hundred sixty nine and paise eighty only	P.Cum.	59094
3	Providing and Laying concrete for plain/reinforced concrete 1:4:8 (one cement : four sand: eight graded stone aggregate 20mm (Twenty millimeter) nominal size in open foundations and curing complete including cost of form work plain/ reinforced concrete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials within all leads and lifts. The rate including octroi, royalty, and other taxes imposed by the Government.	22.50	4955.20	Rupees four thousand nine hundred fifty five and paise twenty only	P.Cum.	111492
4	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding /laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, complete all as per direction of Engineer-in- Charge. <b>(60 mm) Sixty millimeter thick C.C. paver block of M-30 grade with approved color design and pattern )</b>	300.00	1050.00	Rupees one thousand fifty and paise zero only	P.Sqm.	315000
5	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803,1202 &1203 including carriage of materials in all leads and lifts. a)P.C.C 1:3:6.(1 Cement :3 sand : 6 Agg. 20mm nominal Size) i/c carriage of material within all leads & lifts As per the direcion of Engineer In-Charge.	0.70	5424.85	Rupees five thousand four hundred twenty four and paise eighty five only	P.Cum.	3797
					Total	493583

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words

  
 Executive Engineer  
 Arki Division HPPWD  
 Arki

## SCHEDULE OF QUANTITY

Estimated Cost: -Rs4,46,766/- only

Name of Work:-C/o Link Road Primary School Kashyalu to Kali Mata Mandir Km 0/00 to 1/075. (SH:- C/o B/wall at RD 0/00 to 0/020,R/wall at Rds 0/00 to 0/025) DMFT

Earnest Money :-Rs9,000/-Only

Time :-One Month

S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4		5	6
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	52.80	171.40	Rupees One hundred seventy one and paise forty only	P.Cum.	9050
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	91.75	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	402838
3	Backfilling Granular materials behind abutment, wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts.and as per the direction of Engineer-In- Charge	18.00	1203.30	Rupees one thousand two hundred three and paise thirty only	P.Cum.	21659
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	48.20	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	13219
					Total	446766

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words

  
 Executive Engineer  
 Arki Division HPPWD  
 Arki

## SCHEDULE OF QUANTITY

Estimated Cost: -Rs1,91,438/- only

Name of Work:-C/O Ambulance Road from H/O Sh.Narayanu to Pump House Kashyalu in Km 0/00 to 0/330.(Balance work) (SH:- C/o R/wall at RD 0/265 to 0/269) DMFT Deposit

Earnest Money :-Rs4,000/-Only

Time :-One Month

S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	19.60	171.40	Rupees One hundred seventy one and paise forty only	P.Cum.	3359
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	39.72	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	174395
3	Backfilling Granular materials behind abutment, wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts.and as per the direction of Engineer-In- Charge	7.68	1203.30	Rupees one thousand two hundred three and paise thirty only	P.Cum.	9241
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	16.20	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	4443
					Total	191438

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words

  
 Executive Engineer  
 Arki Division HPPWD  
 Arki

SCHEDULE OF QUANTITY					Estimated Cost: -Rs4,79,336/- only	
Name of Work:-C/O Ambulance Road from H/O Sh.Narayanu to Pump House Kashyalu in Km 0/00 to 0/330. (SH:- C/o R/wall at RD 0/255 to 0/265) DMFT Deposit					Earnest Money :-Rs10,000/-Only	
					Time :-One Month	
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4		5	6
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	49.00	171.40	Rupees One hundred seventy one and paise forty only	P.Cum.	8399
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	99.30	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	435987
3	Backfilling Granular materials behind abutment, wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts.and as per the direction of Engineer-In- Charge	19.20	1203.30	Rupees one thousand two hundred three and paise thirty only	P.Cum.	23103
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	43.20	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	11848
					Total	479336

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words

  
 Executive Engineer  
 Arki Division HPPWD  
 Arki

## SCHEDULE OF QUANTITY

Estimated Cost: -Rs4,79,840/- only

Name of Work:-C/o Ambulance Road Mangoohat Dhrrail Malawan Km 0/00 to 5/00. (SH:- P/L WBM G-I, C.C.1:4:8,C.C.1:2:4 and Kharanja Stone Soling Km 0/00 to 0/090) DMFT

Earnest Money :-Rs10,000/-Only

Time :-One Month

S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	WBM Grading -I :- Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, stone screening /binding material to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading-1 as per Technical Specification Clause 405. by mechanically means using stone aggregate 90mm to 40mm (Ninety to forty millimeter size) including carriage of material with in all leads, lifts and as per the direction of Engineer-In-Charge.	45.00	1969.80	Rupees one thousand nine hundred sixty nine and paise eighty only	P.Cum.	88641
2	Providing and Laying concrete for plain/reinforced concrete 1:4:8 (one cement : four sand: eight graded stone aggregate 40mm (Fourty millimeter) nominal size in open foundations and curing complete including cost of form work plain/ reinforced concrete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials within all leads and lifts . The rate including octroi, royalty, and other taxes imposed by the Government.	40.50	4955.20	Rupees four thousand nine hundred fifty five and paise twenty only	P.Cum.	200686
3	Providing and laying cement concrete work 1:2:4 ( one cement : two sand : four graded stone aggregate 20mm nominal size ) mechanically mixed and compecting with vibrator and curing complete excluding cost of form work and reinforced concrete work including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge .	30.38	5954.35	Rupees five thousand nine hundred fifty four and paise thirty five only	P.Cum.	180893
4	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour) and as directed by Engineer-In- Charge	6.75	1425.25	Rupees one thousand four hundred twenty five and paise twenty five only	P.Cum.	9620
					Total	479840

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words

  
 Executive Engineer  
 Arki Division HPPWD  
 Arki

SCHEDULE OF QUANTITY					Estimated Cost: -Rs1,65,179/- only	
Name of Work:-C/o Toon Padyar Road Km 0/00 to2/750. (SH:- C/o R/wall at RD 0/768 to 0/783) DMFT					Earnest Money :-Rs3.500/-Only	
					Time :-One Month	
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	10.50	171.40	Rupees One hundred seventy one and paise forty only	P.Cum.	1800
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	31.80	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	139621
3	Backfilling Granular materials behind abutment, wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts.and as per the direction of Engineer-In- Charge	15.30	1203.30	Rupees one thousand two hundred three and paise thirty only	P.Cum.	18410
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	19.50	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	5348
					Total	165179

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words

  
Executive Engineer  
Arki Division HPPWD  
Arki

<b>DRAFT SCHEDULE OF QUANTITY</b>	Estimated Cost: -Rs99000/- only
Name of Work:-Restoration of Rain Damages on Kandar Samtvari Padvar Road Km 0/00 to 4/500	Earnest Money: -Rs2000/- only

SCHEDULE OF QUANTITY						Estimated Cost: -Rs3,76,139/- only	
Name of Work:- C/o Ambulance Road Pansoda to Chamba Km 0/00 to 1/00. (SH:- C/o Hume Pipe Culvert at Rd,0/065 and 0/465 ) DMFT						Earnest Money :-Rs7,600/-Only	
						Time :-One Month	
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount	
			Figure	Words			
1	2	3	4	5	6	7	
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	81.96	171.40	Rupees One hundred seventy one and paise forty only	P.Cum.	14048	
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803,1202 &1203 including carriage of materials in all leads and lifts. a)P.C.C 1:3:6.(1 Cement :3 sand : 6 Agg. 40mm nominal Size) i/c carriage of material within all leads & lifts As per the direcion of Engineer In-Charge.	21.66	5291.95	Rupees five thousand two hundred ninety one and paise ninety five only	P.Cum.	114624	
3	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	38.40	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	168599	
4	Backfilling Granular materials behind abutment, wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts.and as per the direction of Engineer-In- Charge	13.68	1203.30	Rupees one thousand two hundred three and paise thirty only	P.Cum.	16461	
5	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation protection work, back filling concrete and masonry work in head walls and parapets clause 1108. 900 mm dia pipe.including carriage of materials in all leads and lifts. and as per the direction of Engineer-In-Charge	15.00	3882.55	Rupees three thousand eight hundred eighty two and paise fifty five only	P.Rmt	58238	
6	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	15.20	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	4169	
					<b>Total</b>	<b>376139</b>	

unt  
00  
00

Quoted Rate Percentage in Figure  
Quoted Rate Percentage in Words

  
Executive Engineer  
Arki Division HPPWD  
Arki

**SCHEDULE OF QUANTITY**


Name of Work:-Restoration of Rain Damages on Kandar Samtyari Padyar Road Km 0/00 to 4/500 .  
 (SH:-Hiring of JCB for removal of slips.) Job No-1

Estimated Cost :-Rs99000/- only  
 Earnest Money :-Rs2000/-Only  
 Time :-Fifteen Days

S. No.	Sub head and items of work	Qty.		Rate In		Unit	Amount
				Figure	Words		
1	2	3		4	5	6	
1	Hiring of JCB Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 1611.)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	99.00	Hour	1000.00	Rupees One Thousand and paise nil only	P.Hour.	99000
						<b>Total</b>	<b>99000</b>

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words

  
 Executive Engineer  
 Arki Division HPPWD  
 Arki

### SCHEDULE OF QUANTITY

Name of Work:- C/o Ambulance Road Pansoda to Chamba Km 0/00 to 1/00. (SH:- Formation Cutting at Rd,s 0/00 to 0/585.)DMFT Deposit

Estimated Cost: -Rs 3,12,000/- only



Earnest Money :-Rs6,500/-Only

Time :- One Month

S.No	Sub head and items of work	Qty.	Unit	Rate		Amount
				Figure	Words	
1	Excavation in earthwork in hilly area by mechanical means all hights and depth, in all kind of soil including saturated soil comprising of mixed soil , ordinaryrock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side,water pollution , etc. and to protect stabality of hill side . Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting / excavation , including rock excavation shall be carried out true to lines grades , side slopes, width, chamber, super elevation and level as shown on the drawings or as directed by the Engineer-in - Charges, in conformity with the requirement of technical specification for Rural Road, August 2004 and clause 16.2 of General Conditions for Contract to achieve designed formation wothd including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut matererial inspecified manner,tremming, filling of unevenness, blindage and finishing of the road to specified dimensions or as dirrected by the Engineer-in -Charge for smooth riding. The recovery of useful stone that is <b>82.64</b> cubic meter in all cases falling which recovery @ Rupees <b>300/-</b> only (Rupees three hundered only) per cubic metre shall be effected on prorata basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	1676.70	Per. Cum.	186.08	Rupees One hundred eighty six and paise eight only .	312000
					Total	312000

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words

  
 Executive Engineer  
 B&R Division HPPWD  
 Arki 

### SCHEDULE OF QUANTITY

Name of Work:- C/o Ambulance Road Pansoda to Chamba Km 0/00 to 1/00. (SH:- Formation Cutting at Rd,s 0/585 to 0/975.)DMFT Deposit

Estimated Cost: -Rs 2,57,553/- only

Earnest Money :-Rs5,200/-Only

Time :- One Month

S.No	Sub head and items of work	Qty.	Unit	Rate		Amount
				Figure	Words	
1	Excavation in earthwork in hilly area by mechanical means all hights and depth, in all kind of soil including saturated soil comprising of mixed soil , ordinaryrock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side,water pollution , etc. and to protect stabality of hill side . Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting / excavation , including rock excavation shall be carried out true to lines grades , side slopes, width, chamber, super elevation and level as shown on the drawings or as directed by the Engineer-in -Charges, in conformity with the requirement of techanical specification for Rural Road, August 2004 and clause 16.2 of General Conditions for Contract to achieve designed formation wodth including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut matereial inspecified manner,tremming, filling of unevenness, blindage and finishing of the road to specified dimensions or as dirrected by the Engineer-in -Charge for smooth riding. The recovery of useful stone that is <b>74.80</b> cubic meter in all cases falling which recovery @ Rupees <b>300/-</b> only (Rupees three hundereed only) per cubic metre shall be effected on prorata basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	1376.70	Per. Cum.	187.08	Rupees One hundred eighty seven and paise eight only .	257553
					Total	257553

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words

  
 Executive Engineer  
 B&R Division HPPWD  
 Arki

SCHEDULE OF QUANTITY					Estimated Cost -Rs4,99,915/- only	
Name of Work -C/o Retaining wall for Govt. High School Sehrol.(Under DMFT)					Earnest Money -Rs10,000/-Only	
					Time :-One Month	
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In-Charge	31.68	171.40	Rupees One hundred seventy one and paise forty only	P.Cum.	5430
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts and as per the direction of Engineer-In- Charge	108.90	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	478136
3	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	20.00	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	5485
4	Backfilling Granular materials behind abutment, wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts and as per the direction of Engineer-In- Charge	9.24	1175.80	Rupees one thousand one hundred seventy five and paise eighty only	P.Cum.	10864
					Total	499915

Quoted Rate Percentage in Figure  
Quoted Rate Percentage in Words

  
Executive Engineer  
Arki Division HPPWD  
Arki

## SCHEDULE OF QUANTITY

Name of Work:-Restoration of Rain Damages on Kandar Samtyari Padyar Road Km 0/00 to 4/500 .  
(SH:-Hiring of Tipper for removal of slips.) Job No- 1

Estimated Cost: -Rs97,500/- only

Earnest Money :-Rs2000/-Only

Time :-Fifteen Days

S. No.	Sub head and items of work	Qty.		Rate In		Unit	Amount
				Figure	Words		
1	2	3		4	5	6	
1	Hiring of Tipper for removal of slips and debris with minimum capacity of 5.5 cum per trip and minimum working 6(six)hours per day. The contractor /owner of the tipper shall bear the expansion of P.O.L. charges , repair of machineries . Any accident and other damages to be the private and govt. property occur durring the working hours is the responsibility of contractor and debris disposed with in all leads and lifts as per the direction of Engineer-In- Charge.	150.00	Hour	650.00	Rupees six hundred fifty and paise nil only	P.Hour.	97500
						Total	97500

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words

  
 Executive Engineer  
 Arki Division HPPWD  
 Arki

### SCHEDULE OF QUANTITY

Estimated Cost: -Rs2,29,672/- only

Earnest Money :-Rs5,000/-Only

Time :-One Month

Name of Work:-C/o Boundary wall in Govt. High School Bagga, G.P. Bagga, Tehsil Arki Distt. Solan  
H.P. ( SH:- Providing and Fixing Fencing ,Gate, Plaster work and Painting.)DMFT Deposit

S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	1.11	171.40	Rupees One hundred seventy one and paise forty only	P.Cum.	190
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802, 803 , 1202 &1203 including carriage of materials in all leads and lifts. a)P.C.C 1:3:6.(1 Cement :3 sand : 6 Agg. 20mm nominal Size) i/c carriage of material within all leads & lifts As per the direcion of Engineer In-Charge.	1.11	5424.85	Rupees five thousand four hundred twenty four and paise eighty five only	P.Cum.	6022
3	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including carriage of materials in all leads,lifts and as per the direction of Engineer-In- Charge	497.55	107.45	Rupees one hundred seven and paise forty five only	P.Kg	53462
4	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer-in-charge upto all leads and lifts. Made of G.I. wire of dia 4 mm.	58.80	658.60	Rupees six hundred fifty eight and paise sixty only	P.Sqm	38726
5	Providing and fixing M.S. B.P. sheet 1.66 to 2 mm thick in eaves board / facia / soffits / ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete (Base members of steel paid separately) as per HP, PWD. Specifications of 1990 vplume-I including carriage of materials, labour, tool and plant through all modes of transportation within all leads and lifts and as per direction of Engineer-in- Charge.	0.90	1851.20	Rupees One thousand eight hundred fifty one and paisa twenty only	P.Sqm	1666
6	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture including carriage of materials in all leads and lifts and as per the direction of Engineer-in-Charge	58.80	89.90	Rupees eighty nine and paise ninty only	P.Sqm	5286
7	20mm cement plaster in single coat on fair rough side of brick/concrete/stone walls for interior plastering upto floor two level including arrises,internal rounded angles, chamfers and/or rounded angles not exceeding 80mm in girth and finished even and smooth. Cement Mortar 1:4 (1 cement:4 sand)in all leads and lifts. and as per the direction of Engineer-In- Charge	480.28	241.40	Rupees two hundred forty one and paise forty only	P.Sqm	115940

S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2		3	4	5	6
8	White washing with lime to give an even shade in New work (three or more coats) complete and as per direction of Engineer-in- Charge.	480.28	17.45	Rupees seventeen and paise fourty five only	P.Sqm	8381
					Total	229672

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words

  
 Executive Engineer  
 Arki Division HPPWD  
 Arki