



OFFICE OF THE EXECUTIVE ENGINEER
BANGANA DIVISION HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT BANGANA

No:- PW-BGN-CB/T-1/2025-26-
To

15/49-58

Dated:- 23-03-26


The Executive Engineer (IT Cell),
Nigam Vihar, HP Shimla-2,
cc-pwd-hp@nic.in.

Subject:- Publication of Tender Notice.

Sir,


Enclosed please find herewith the Tender Notice of various works as given in the Notice Inviting Tender. As per Notification Pr. Secy (PW) to the Govt. of Himachal Pradesh letter No. PBW(B)A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the works mentioned in the tender Notice are of urgent nature and in public interest, the same may be uploaded on the departmental website.

**DA/- Notice Inviting Tender/Scheduled of Quantity
And "A" Certificate.**


Executive Engineer
Bangana Division
HPPWD Bangana

Copy forwarded with its enclosures for information to:-


1. The Engineer-in-Chief, H.P.P.W.D., Shimla-2.
2. The Chief Engineer (HZ), H.P.P.W.D., Hamirpur.
3. The Superintending Engineer, 15th Circle, HPPWD, Una.
4. The Assistant Engineer, Sub Division, HPPWD Bangana and Basal.
5. Drawing Branch in this office.
6. Accounts Branch in this office.
7. Supdt of C Branch in this office.
8. Notice Board.


Executive Engineer
Bangana Division
HPPWD Bangana.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

CERTIFICATE.

Certified that the works are of **urgent** in nature and for larger public interest so there is exigencies/emergency in calling these tenders without press vide this office letter No. PW-BGN/CB/T-1/2025-26-
15149-58 dated 23-03-26.


Executive Engineer
Bangana Division
HPPWD Bangana.


**OFFICE OF THE EXECUTIVE ENGINEER BANGANA DIVISION HIMACHAL PRADESH PUBLIC WORKS
DEPARTMENT BANGANA**

NOTICE INVITING TENDER.

Sealed percentage rate tender on form 6 & 8 are hereby invited by the Executive Engineer Bangana Division HPPWD Bangana on behalf of Governor of HP. from the approved eligible contractors enlisted in HPPWD. for the following works: so as to reach this office on **28.03.2026 up to 10.30 A.M** and same will be opened on the same day at **11.00 AM** in presence of the interested contractors or their authorized representative. The application will be received in this office on at **25.03.2026 upto 03.00 PM**. The tender form can be had from the office of Executive Engineer Bangana Division HPPWD Bangana on cash payment (Non-refundable) on **27.03.2026** during office Hours **up to 4.00 P.M.** The application must be accompanied with earnest money in shape of NSD/FDR/Time deposit etc. of any post office of HP. or Nationalized Bank duly pledged in the name of Executive Engineer Bangana Division HPPWD Bangana cash order will not be entertained, it may be ensure that the earnest money shall have to be prepared work wise otherwise forms will not be issued. The tender document fee shall also be deposited by the applicant/ contractor with at the time of application in the shape of Demand Draft or Cash (Non-Refundable) otherwise tender documents/ Forms shall not be issued. The offer of tender shall be kept upon for 60 days. The conditional tender or tender received by post will also be rejected. The undersigned reserves the right to reject any or all tenders without assigning any reason. All the approved eligible contractors should bring copy of their valid enlistment/renewal/exemption from earnest money with them. The tender documents will be issued only to those who fulfill the eligibility conditions. **The contractor should be registered as dealer under GST Act, Valid copy of Registration as required, Copy of PAN Card, EPF failing which no tender form will be issued to him.**

Work/Job No.	Name of Work	Estimated Cost	Earnest Money	Time Period	Eligible of Class
1	Restoration of Rain Damages on Una Barera road (SH: C/o E/wall in Km 5/800 to 5/821.40) Under RRD Head.	96850.00	2000.00	One Month	C&D
2	Restoration of Rain Damages on Mohala Batian in GIP Panoh (SH: C/o R/wall in Km 0/180 to 0/187) Under RRD Head.	96561.00	2000.00	One Month	C&D
3	Restoration of Rain Damages on link road to Village Mata ka Mandir upto Mohalla Jattan (SH: C/o B/wall in km 1/529.65 to 1/539.30) Under RRD Head.	96654.00	2000.00	One Month	C&D
4	Restoration of Rain Damages on Link road to Village Bhalola (SH: C/o V-shape Drain & C.C. Pavement in Km 2/030 to 2/060) Under RRD Head.	98511.00	2000.00	One Month	C&D
5	Restoration of Rain Damages on Link road Lower Chalola to Upper Chalola (SH: P/L Interlocking paver Block flooring in approaches of 3.00 meter span at Rd 0/220 to 0/234.80) Under RRD Head.	99191.00	2000.00	One Month	C&D
6	Restoration of Rain Damages on link road Ghandawal to Batuhi road (SH: C/o R/wall in Km 0/373 to 0/383.15) Under RRD Head.	99041.00	2000.00	One Month	C&D
7	Restoration of Rain Damages on link road Takka to Jorre Khoo Km 0/000 to 2/200 (SH: P/L Interlocking Paver Block flooring in Km 1/051 to 1/068) Under RRD Head.	98906.00	2000.00	One Month	C&D
8	Restoration of Rain Damages on Link road Lower Chalola to Upper Chalola (SH: P/L Interlocking paver Block flooring in approaches of 3.00 meter span at Rd 0/234.80 to 0/249.60) Under RRD Head.	99191.00	2000.00	One Month	C&D
9	Restoration of Rain Damages on link road Ghandawal to Batuhi road (SH: C/o R/wall in Km 0/383.15 to 0/393.30) Under RRD Head.	99041.00	2000.00	One Month	C&D
10	Restoration of Rain Damages on link road to Village Mata ka Mandir upto Mohalla Jattan (SH: C/o B/wall in km 1/520 to 1/529.65) Under RRD Head.	96654.00	2000.00	One Month	C&D
11	Restoration of Rain Damages on link road Takka to Jorre Khoo Km 0/000 to 2/200 (SH: P/L Interlocking Paver Block flooring in Km 1/000 to 1/017) Under RRD Head.	98906.00	2000.00	One Month	C&D
12	Restoration of Rain Damages on Link road to Village Bhalola (SH: C/o V-shape Drain & C.C. Pavement in Km 2/000 to 2/030) Under RRD Head.	98511.00	2000.00	One Month	C&D

HIM SUCHANA, WAM JAN SAMPARK.


 Executive Engineer
 Bangana Division
 HPPWD Bangana
 On behalf of Governor of Himachal Pradesh.

Percentage BOQ

Tender Inviting Authority:- Excecutive Engineer HPPWD Division Bangana	Estimated Cost Rs	96850.00
Name of work:- Restoration of Rain Damages on Una Barera road (SH: C/o E/wall in Km 5/800 to 5/821.40)	Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-	Time Limit:	One Month

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty milimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	10.27	Per cubic metre	280.00	2876.00	Rupees Two Thousand Eight Hundred & Seventy Six Only
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803, 1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	23.11	Per Cubic metre.	3850.00	88974.00	Rupees Eighty Eight Thousand Nine Hundred & Seventy Four Only
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	20.00	Each	250.00	5000.00	Rupees Five Thousand Only
Total in Figures					96850.00	Rupees Ninety Six Thousand Eight Hundred & Fifty Only
Quoted Rate in Figures					Excess (+)	
Less (-)						


Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Excecutive Engineer HPPWD Division Bangana

Name of work:- Restoration of Rain Damages on Mohala Batian in GP Panoh (SH: C/o R/wall in Km 0/180 to 0/187)

Estimated Cost Rs **96561.00**

Earnest Money Rs **2000.00**


Name of Bidder/ Bidding Firm/ Company :-

Time Limit: **One Month**

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty milimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	7.77	Per cubic metre	280.00	2176.00	Rupees Two Thousand One Hundred & Seventy Six Only
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802 803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	22.12	Per Cubic metre.	3850.00	85162.00	Rupees Eighty Five Thousand One Hundred & Sixty Two Only
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	12.00	Each	250.00	3000.00	Rupees Three Thousand Only
4.00	Back filling with granular material behind abutment, wing wall and return wall complete as per drawing, direction of Engineer in charge and MORD 2014 technical specification clause 1604 7.8 including carriage of materials/machinery required to execute the work with in all leads and lifts including other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	8.89	Per Cubic metre	700.00	6223.00	Rupees Six Thousand Two Hundred & Twenty Three Only
Total in Figures					96561.00	Rupees Ninety Six Thousand Five Hundred & Sixty One Only
Quoted Rate in Figures				Excess (+)		
				Less (-)		


Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- Restoration of Rain Damages on link road to Village Mata ka Mandir upto Mohalla Jattan (SH: C/o B/wall in km 1/529.65 to 1/539.30)

Estimated Cost
Rs **96654.00**

Earnest Money
Rs **2000.00**


Time Limit: **One Month**

Name of Bidder/ Bidding Firm/ Company :-

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	17.27	Per cubic metre	280.00	4836.00	Rupees Four Thousand Eight Hundred & Thirty Six Only
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	22.68	Per Cubic metre.	3850.00	87318.00	Rupees Eighty Seven Thousand Three Hundred & Eighteen Only
3.00	Providing weep holes in stone masonry, plain reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	18.00	Each	250.00	4500.00	Rupees Four Thousand Five Hundred Only
Total in Figures					96654.00	Rupees Ninety Six Thousand Six Hundred & Fifty Four Only
Quoted Rate in Figures					Excess (+)	
Less (-)						


Executive Engineer
Bangana Division
HP.PWD, Bangana

Percentage BOQ


Tender Inviting Authority:- Excecutive Engineer HPPWD Division Bangana	Estimated Cost Rs	98511.00
Name of work:- Restoration of Rain Damages on Link road to Village Bhalola (SH: C/o V-shape Drain & C.C. Pavement in Km 2/030 to 2/060)	Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-	Time Limit:	One Month

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty milimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	8.85	Per cubic metre	280.00	2478.00	Rupees Two Thousand Four Hundred & Seventy Eight Only
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	6.15	Per Cubic metre.	3850.00	23678.00	Rupees Twenty Three Thousand Six Hundred & Seventy Eight Only
3.00	Construction of pavement with 80mm (Eighty millimetre) thick concrete blocks make ISI conforming to clause 1504.2.1 of MORD specifications, paved and compacted over a thin bedding of sand layers (material meeting the requirement of Table 1500.6 of these specifications) of specified grading to be spread over a properly constructed and profiled base course and bounded by properly edge restraints conforming to clause 1504.2.2 and 1504.2.3 of these specifications and complete the work to the satisfaction of Junior Engineer and Assistant Engineer of the area. (Subject to further entire satisfaction of the Engineer-in-Charge), including carriage of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	35.00	Per Square metre	1100.00	38500.00	Rupees Thirty Eight Thousand Five Hundred Only
4.00	Providing and laying mechanically mixed and vibrated reinforced cement concrete of nominal mix 1 : 2 : 4 {one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimetres)} nominal size grade M-20 (M-twenty) in substructure as per drawings and M.O.R.D. technical specification for Rural Roads Clauses 802,804,805,806,807,1202 and 1204 including the cost of form work but excluding the cost of reinforcement for reinforced concrete work in bed block , dirt wall and curing complete including hauling of materials in all kinds of leads, lifts and other incidental, as per the entire satisfaction and directions of Engineer-in-Charge. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	0.60	Per cubic metre	5200.00	3120.00	Rupees Three Thousand One Hundred & Twenty Only

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
5.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete grade M-10 (M-Ten) in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	6.83	Per cubic metre	4500.00	30735.00	Rupees Thirty Thousand Seven Hundred & Thirty Five Only
Total in Figures					98511.00	Rupees Ninety Eight Thousand Five Hundred & Eleven Only
Qouted Rate in Figures		Excess (+)				
		Less (-)				


Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- Restoration of Rain Damages on Link road Lower Chalola to Upper Chalola (SH: P/L Interlocking paver Block flooring in approaches of 3.00 meter span at Rd 0/220 to 0/234.80)

Name of Bidder/ Bidding Firm/ Company :-

Estimated Cost
Rs 99191.00

Earnest Money
Rs 2000.00

Time Limit: One Month

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	9.10	Per cubic metre	280.00	2548.00	Rupees Two Thousand Five Hundred & Fourty Eight Only
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	9.10	Per Cubic metre.	3850.00	35035.00	Rupees Thirty Five Thousand & Thirty Five Only
3.00	Construction of pavement with 80mm (Eighty millimetre) thick concrete blocks make ISI conforming to clause 1504.2.1 of MORD specifications, paved and compacted over a thin bedding of sand layers (material meeting the requirement of Table 1500.6 of these specifications) of specified grading to be spread over a properly constructed and profiled base course and bounded by properly edge restraints conforming to clause 1504.2.2 and 1504.2.3 of these specifications and complete the work to the satisfaction of Junior Engineer and Assistant Engineer of the area. (Subject to further entire satisfaction of the Engineer-in-Charge), including carriage of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	51.80	Per Square metre	1100.00	56980.00	Rupees Fifty Six Thousand Nine Hundred & Eighty Only
4.00	Providing and laying mechanically mixed and vibrated reinforced cement concrete of nominal mix 1 : 2 : 4 (one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimetres); nominal size grade M-20 (M-twenty) in substructure as per drawings and M.O.R.D. technical specification for Rural Roads Clauses 802,804,805,806,807,1202 and 1204 including the cost of form work but excluding the cost of reinforcement for reinforced concrete work in bed block , dirt wall and curing complete including hauling of materials in all kinds of leads, lifts and other incidental, as per the entire satisfaction and directions of Engineer-in-Charge. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	0.89	Per cubic metre	5200.00	4628.00	Rupees Four Thousand Six Hundred & Twenty Eight Only
Total in Figures					99191.00	Rupees Ninety Nine Thousand One Hundred & Ninety One Only
Quoted Rate in Figures					Excess (+)	
					Less (-)	


Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- Restoration of Rain Damages on link road Ghandawal to Batuhi road (SH: C/o R/wall in Km 0/373 to 0/383.15)

Estimated Cost Rs **99041.00**

Earnest Money Rs **2000.00**

Time Limit: **One Month**

Name of Bidder/ Bidding Firm/ Company :-

PRICE SCHEDULE
(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	7.92	Per cubic metre	280.00	2218.00	Rupees Two Thousand Two Hundred & Eighteen Only
2.00	Providing and laying mechanically mixed and vibrated concrete for plain reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802,803 1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	23.85	Per Cubic metre.	3850.00	91823.00	Rupees Ninety One Thousand Eight Hundred & Twenty Three Only
3.00	Providing weep holes in stone masonry, plain reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	20.00	Each	250.00	5000.00	Rupees Five Thousand Only
Total in Figures					99041.00	Rupees Ninety Nine Thousand & Fourty One Only
Quoted Rate in Figures					Excess (+)	
					Less (-)	


Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Estimated Cost
Rs 98906.00

Name of work:-Restoration of Rain Damages on link road Takka to Jorre Khoo Km 0/000 to 2/200 (SH: P/L Interlocking Paver Block flooring in Km 1/051 to 1/068)

Earnest Money
Rs 2000.00

Name of Bidder/ Bidding Firm/ Company :-

Time Limit: One Month

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty milimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	10.20	Per cubic metre	280.00	2856.00	Rupees Two Thousand Eight Hundred & Fifty Six Only
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	6.80	Per Cubic metre.	3850.00	26180.00	Rupees Twenty Six Thousand One Hundred & Eighty Only
3.00	Construction of pavement with 80mm (Eighty millimetre) thick concrete blocks make ISI conforming to clause 1504.2.1 of MORD specifications, paved and compacted over a thin bedding of sand layers (material meeting the requirement of Table 1500.6 of these specifications) of specified grading to be spread over a properly constructed and profiled base course and bounded by properly edge restraints conforming to clause 1504.2.2 and 1504.2.3 of these specifications and complete the work to the satisfaction of Junior Engineer and Assistant Engineer of the area. (Subject to further entire satisfaction of the Engineer-in-Charge), including carriage of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	59.50	Per Square metre	1100.00	65450.00	Rupees Sixty Five Thousand Four Hundred & Fifty Only
4.00	Providing and laying mechanically mixed and vibrated reinforced cement concrete of nominal mix 1 : 2 : 4 {one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimetres)} nominal size grade M-20 (M-twenty) in substructure as per drawings and M.O.R.D. technical specification for Rural Roads Clauses 802,804,805,806,807,1202 and 1204 including the cost of form work but excluding the cost of reinforcement for reinforced concrete work in bed block , dirt wall and curing complete including hauling of materials in all kinds of leads, lifts and other incidental, as per the entire satisfaction and directions of Engineer-in-Charge. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	0.85	Per cubic metre	5200.00	4420.00	Rupees Four Thousand Four Hundred & Twenty Only
Total in Figures					98906.00	Rupees Ninety Eight Thousand Nine Hundred & Six Only
Quoted Rate in Figures					Excess (+)	
Less (-)						


Executive Engineer
Bangana Division
HP.PWD.Bangana


Percentage BOQ

Tender Inviting Authority:- Excecutive Engineer HPPWD Division Bangana	Estimated Cost Rs	99191.00
Name of work:-Restoration of Rain Damages on Link road Lower Chalola to Upper Chalola (SH: P/L Interlocking paver Block flooring in aproaches of 3.00 meter span at Rd 0/234.80 to 0/249.60)	Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-	Time Limit:	One Month

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty milimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	9.10	Per cubic metre	280.00	2548.00	Rupees Two Thousand Five Hundred & Forty Eight Only
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803,1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	9.10	Per Cubic metre	3850.00	35035.00	Rupees Thirty Five Thousand & Thirty Five Only
3.00	Construction of pavement with 80mm (Eighty millimetre) thick concrete blocks make ISI conforming to clause 1504.2.1 of MORD specifications, paved and compacted over a thin bedding of sand layers (material meeting the requirement of Table 1500.6 of these specifications) of specified grading to be spread over a properly constructed and profiled base course and bounded by properly edge restraints conforming to clause 1504.2.2 and 1504.2.3 of these specifications and complete the work to the satisfaction of Junior Engineer and Assistant Engineer of the area. (Subject to further entire satisfaction of the Engineer-in-Charge), including carriage of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	51.80	Per Square metre	1100.00	56980.00	Rupees Fifty Six Thousand Nine Hundred & Eighty Only
4.00	Providing and laying mechanically mixed and vibrated reinforced cement concrete of nominal mix 1 : 2 : 4 (one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimetres); nominal size grade M-20 (M-twenty) in substructure as per drawings and M.O.R.D. technical specification for Rural Roads Clauses 802,804,805,806,807,1202 and 1204 including the cost of form work but excluding the cost of reinforcement for reinforced concrete work in bed block , dirt wall and curing complete including hauling of materials in all kinds of leads, lifts and other incidental, as per the entire satisfaction and directions of Engineer-in-Charge. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	0.89	Per cubic metre	5200.00	4628.00	Rupees Four Thousand Six Hundred & Twenty Eight Only
Total in Figures					99191.00	Rupees Ninety Nine Thousand One Hundred & Ninety One Only
Quoted Rate in Figures					Excess (+)	
Less (-)						


Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority :- Executive Engineer HPPWD Division Bangana

Name of work:- Restoration of Rain Damages on link road Ghandawal to Batuhi road (SH: C/o R/wall in Km 0/383.15 to 0/393.30)

Estimated Cost Rs **99041.00**

Earnest Money Rs **2000.00**


Name of Bidder/ Bidding Firm/ Company :-

Time Limit: **One Month**

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks (where blasting is prohibited) as per drawings and M O R D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	7.92	Per cubic metre	280.00	2218.00	Rupees Two Thousand Two Hundred & Eighteen Only
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand eight graded crushed /broken stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	23.85	Per Cubic metre.	3850.00	91823.00	Rupees Ninety One Thousand Eight Hundred & Twenty Three Only
3.00	Providing sweep holes in stone masonry, plain reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical 20 (twenty horizontal) toward drawing face complete as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	20.00	Each	250.00	5000.00	Rupees Five Thousand Only
Total in Figures					99041.00	Rupees Ninety Nine Thousand & Forty One Only
Quoted Rate in Figures					Excess (+)	
					Less (-)	


Executive Engineer
Bangana Division
HP. PWD. Bangana


Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana	Estimated Cost	96654.00
Name of work:- Restoration of Rain Damages on link road to Village Mata ka Mandir upto Mohalla Jattan (SH: C/o B/wall in km 1/520 to 1/529.65)	Earnest Money	2000.00
Name of Bidder/ Bidding Firm/ Company :-	Time Limit:	One Month

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	17.27	Per cubic metre	280.00	4836.00	Rupees Four Thousand Eight Hundred & Thirty Six Only
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	22.68	Per Cubic metre.	3850.00	87318.00	Rupees Eighty Seven Thousand Three Hundred & Eighteen Only
3.00	Providing weep holes in stone masonry, plain reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	18.00	Each	250.00	4500.00	Rupees Four Thousand Five Hundred Only
Total in Figures					96654.00	Rupees Ninety Six Thousand Six Hundred & Fifty Four Only
Quoted Rate in Figures					Excess (+)	
Less (-)						


Executive Engineer
Bangana Division
HP.PWD, Bangana

Percentage BOQ

Tender Inviting Authority:- Excecutive Engineer HPPWD Division Bangana	<i>Estimated Cost</i>	98906.00
Name of work:-Restoration of Rain Damages on link road Takka to Jorre Khoo Km 0/000 to 2/200 (SH: P/L Interlocking Paver Block flooring in Km 1/000 to 1/017)	<i>Earnest Money</i>	2000.00
Name of Bidder/ Bidding Firm/ Company :-	<i>Time Limit:</i>	One Month

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	10.20	Per cubic metre	280.00	2856.00	Rupees Two Thousand Eight Hundred & Fifty Six Only
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	6.80	Per Cubic metre.	3850.00	26180.00	Rupees Twenty Six Thousand One Hundred & Eighty Only
3.00	Construction of pavement with 80mm (Eighty millimetre) thick concrete blocks make ISI conforming to clause 1504.2.1 of MORD specifications, paved and compacted over a thin bedding of sand layers (material meeting the requirement of Table 1500.6 of these specifications) of specified grading to be spread over a properly constructed and profiled base course and bounded by properly edge restraints conforming to clause 1504.2.2 and 1504.2.3 of these specifications and complete the work to the satisfaction of Junior Engineer and Assistant Engineer of the area. (Subject to further entire satisfaction of the Engineer-in-Charge), including carriage of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	59.50	Per Square metre	1100.00	65450.00	Rupees Sixty Five Thousand Four Hundred & Fifty Only
4.00	Providing and laying mechanically mixed and vibrated reinforced cement concrete of nominal mix 1 : 2 : 4 {one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimetres)}; nominal size grade M-20 (M-twenty) in substructure as per drawings and M.O.R.D. technical specification for Rural Roads Clauses 802,804,805,806,807,1202 and 1204 including the cost of form work but excluding the cost of reinforcement for reinforced concrete work in bed block , dirt wall and curing complete including hauling of materials in all kinds of leads, lifts and other incidental, as per the entire satisfaction and directions of Engineer-in-Charge. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	0.85	Per cubic metre	5200.00	4420.00	Rupees Four Thousand Four Hundred & Twenty Only
Total in Figures					98906.00	Rupees Ninety Eight Thousand Nine Hundred & Six Only
Quoted Rate in Figures					Excess (+)	
Less (-)						


Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- Restoration of Rain Damages on Link road to Village Bhalola (SH: C/o V-shape Drain & C.C. Pavement in Km 2/000 to 2/030)

Estimated Cost Rs 98511.00

Earnest Money Rs 2000.00

Name of Bidder/ Bidding Firm/ Company :-


Time Limit: One Month

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty milimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	8.85	Per cubic metre	280.00	2478.00	Rupees Two Thousand Four Hundred & Seventy Eight Only
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	6.15	Per Cubic metre.	3850.00	23678.00	Rupees Twenty Three Thousand Six Hundred & Seventy Eight Only
3.00	Construction of pavement with 80mm (Eighty millimetre) thick concrete blocks make ISI conforming to clause 1504.2.1 of MORD specifications, paved and compacted over a thin bedding of sand layers (material meeting the requirement of Table 1500.6 of these specifications) of specified grading to be spread over a properly constructed and profiled base course and bounded by properly edge restraints conforming to clause 1504.2.2 and 1504.2.3 of these specifications and complete the work to the satisfaction of Junior Engineer and Assistant Engineer of the area. (Subject to further entire satisfaction of the Engineer-in-Charge), including carriage of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	35.00	Per Square metre	1100.00	38500.00	Rupees Thirty Eight Thousand Five Hundred Only
4.00	Providing and laying mechanically mixed and vibrated reinforced cement concrete of nominal mix 1 : 2 : 4 {one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimetres)} nominal size grade M-20 (M-twenty) in substructure as per drawings and M.O.R.D. technical specification for Rural Roads Clauses 802,804,805,806,807,1202 and 1204 including the cost of form work but excluding the cost of reinforcement for reinforced concrete work in bed block , dirt wall and curing complete including hauling of materials in all kinds of leads, lifts and other incidental, as per the entire satisfaction and directions of Engineer-in-Charge. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	0.60	Per cubic metre	5200.00	3120.00	Rupees Three Thousand One Hundred & Twenty Only

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
5.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete grade M-10 (M-Ten) in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	6.83	Per cubic metre	4500.00	30735.00	Rupees Thirty Thousand Seven Hundred & Thirty Five Only
Total in Figures					98511.00	Rupees Ninety Eight Thousand Five Hundred & Eleven Only
Qouted Rate in Figures		Excess (+)				
Less (-)						


Executive Engineer
Bangana Division
HP.PWD.Bangana