



Office of the
Executive Engineer
Una Division, HP PWD Una
Tel: +911975226036,
E-mail: ee-una-hp@nic.in

No. PW U/CB/TA/Tender/2025-26/-:- 10699-10709

Dated :- 20.03.2026

To
The Executive Engineer (IT) Cell,
Nirman Bhawan, Nigam Vihar,
Shimla-171002.

Subject: - Regarding publication of Tenders Notice.

Sir,

“JAI HIND”

Enclosed please find herewith Tenders Notice along with Schedule of Quantities for uploading the same on Departmental website as per Notification Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW (B) A(3)/2024 dated Shimla-2 the 03/01/2025 as the work mentioned in the Tender Notice are urgent in nature and in Public interest. This is for your kind information and necessary action at your end please.

DA:-As above.

Executive Engineer,
Bharwain , Division,
HPPWD, Bharwain

Copy along with its enclosures is forwarded to the following for favour of information please:-

1. The Superintending Engineer, 15th Circle, HPPWD, Una.
2. All the Assistant Engineer working under this Division.
3. All the Head of Branches in this office.
4. Notice Board.

Executive Engineer,
Bharwain , Division,
HPPWD, Bharwain

Certificate

Certified that the tenders called vide this office letter
No. PWU/CB/TA/Tender Notice 2025-26 :- **10699-10709** dated **20.03.2026**
emergent nature and in Public interest.



Executive Engineer,
Bharwain, Division,
HPPWD, Bharwain

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
"NOTICE INVITING TENDERS"

Scaled Percentage rate tender on PWD Form No. 6 & 8 are hereby invited by the Executive Engineer, Bharwain Division HPPWD Bharwain H.P. on behalf of Governor of H.P. for the following works from the approved and eligible contractors/ firms enlisted in PWD Department so as to reach in this office and opened as per time schedule given below. The offer of the tender will be kept open for 75 days from the date of opening of the tenders.

Date and time of receipt of applications for the tender form:- 25.03.2026(upto 01.30 P.M.)

Date of time issue/sale of tender forms against cash payment:- 25.03.2026(3.00 to 5.00 PM)

Date and time of receipt of tenders:- 27.03.2026 (upto 11.00 AM)

Date and time of opening of tenders:- 27.03.2026 at 11.30 AM


The earnest money in the shape of F.D.Rs if any of the Nationalized Bank in H.P. duly pledged in the favour of the Executive Engineer, Bharwain Division HPPWD Bharwain , will be received alongwith the applications for obtaining tender forms. The applications received without earnest money shall summarily be rejected. The Executive Engineer reserves the right to reject any tender without assigning any reason. The conditional / telegraphic tenders shall also be rejected. The scope of the work can be increased/ decreased without any Notice.

Sr. No	Name of work	Estimate Amount	Earnest Money	Time	Cost of tender	Eligible class of contractor
1	Improvement of Black Spots on various roads under HPPWD Sub Division, Jole (SH: (SH:- Supply and stacking Dual Directional Delinicator for road side with plastic head unbreakable at Neck)	99,600/-	2000	One Month	350/-	Class-C & D
2	R&M of Residential Building under HPPWD Division Bharwain (SH: Providing and laying 40mm thick CC interlocking paver block in front and back of Type-III qtr. at PWD Colony Bharwain).	99,878/-	2000	One month	350/-	Class-C & D
3	Improvement of Black Spots on various roads under HPPWD Sub Division Amb, Section Amb (SH: (SH:- Providing & fixing of dual directional reflective PVC speed breaker/rumble strip)	99,600	2000	One month	350/-	Class-C & D
4	Restoration to rain damages on Jole to Kaint Road via Amroh, bhood, Dhrum, khuroo and Sanjot km 0/0 to 14/255 (SH:- Removal of slips, Restoration of rain cuts and construction of unlined drain between km 5/500 to 7/860)	99,760/-	2000	One month	350/-	Class-C & D
5	Improvement of black spots on Dada Siba to Daulatpur road Km.0/0 to 14/0 (SH: Providing and fixing W metal beam crash barrier at RD 4/720 to 4/744)	99,149/-	2000	One month	350/-	Class-C & D
6	Improvement of Black Spots on various roads under HPPWD Sub Division, Jole (SH: (SH:- Supply and stacking cautionary Sign board)	99,000/-	2000	One month	350/-	Class-C & D
7	Improvement of black spots on Dada Siba to Daulatpur road Km.0/0 to 14/0 (SH: Providing and fixing W metal beam crash barrier at RD 4/751 to 4/775) under Road Satfy.	99,149/-	2000	One month	350/-	Class-C & D

8	Improvement of Black Spots on various roads under HPPWD Sub Division Amb, Section Panjoa (SH: (SH:- Providing & fixing of dual directional reflective PVC speed breaker/trumble strip)	99,600/-	2000	One month	₹50/-	Class-C & D
9	R&M of Residential Building under HPPWD Division Bharwain (SH: Providing and laying 40mm thick CC interlocking paver block in front of AE residence Bharwain).	99,407	2000	One month	₹50/-	Class-C & D

TERM & CONDITIONS:-

- The contractor/ firms should be registered as or/ dealer under HP Sales Tax Act, 1968 and also produce Sale Tax clearance certificate from the Excise and Taxation Department, GST No. and Permanent account No. (PAN No.).
 - The intending contractors/ firms shall have to produce the copy of latest enlistment and renewal enlisted in HP: PWD.
 - The contractor/firms are required to quote their rates clearly both in words as well as in figures, failing which the Executive Engineer reserve the right to accept/ reject any or all tenders.
 - The conditional / ambiguous/ telegraphic tenders or tender by fax shall not entertain/ considered in any case
 - No payment will be made to the contractor/ firms for damage caused by flood, rain, local disturbance, war, epidemic or either natural calamities during execution of work and no such claim on this account will be entertained.
 - Security shall be released after 1 year from the date of completion of work provided no defect certificate is issued by the Engineer-in-charge.
 - The Executive Engineer has right to accept or reject any or all the tender without assigning any reason.
 - Any material left at site one month after completion of work shall become the property of the department and no payment shall be made to the contractor for the material.
 - A sign Board " Men at work / work in progress " shall be placed " by Contr. At least 200-150 meters ahead or places / roads where road are under repair / construction.
 - The tender shall be issued to those contractors/ firms who have not more than two works in hand.
 - Work should be completed by the contractor within stipulated period.
- DA Notice inviting tender / Schedule of Quantity and A Certificate.


Executive Engineer
Bharwain Division,
HP: PWD, Bharwain..

Executive Engineer
Bharwain Division,
HP: PWD, Bharwain

Copy is forwarded for information and necessary action to:-

- The Engineer-in-Chief, HP: PWD, Shimla-1.
- The Chief Engineer, Hamirpur Zone, HP: PWD, Hamirpur.
- The Superintending Engineer, 15th Circle, HPPWD, Una.
- All the Assistant Engineers under this Division.
- All the Head of the Branches in this office.
- The Notice Board.

JOB-1

BILL OF QUANTITY


Estimate Cost :- Rs. 99600/-

Earnest Money :-Rs. 2000/-

Time Limit :-One Month

Name of work:- Improvement of Black Spots on various roads under HPPWD Sub Division, Jole (SH: (SH:- Supply and stacking Dual Directional Delineator for road side with plastic head unbreakable at Neck)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Supply and Stacking dual direction delinators made of dia 18 (eighteen) gauge M.S. rectangular pipe of size 25x63mm (twenty five into sixty three millimeters) and of length 600mm (six hundred millimeters) pipe stove enameled and baket to 120(one hundred twenty) power coated head made of ABC plastic Rectangular moulded with high intensity prismatic reflectors of colour white /yellow/red od size 100x125mm (one hundred into one hundred twenty five millimeters) with additional to redlective strips of 20mm wide make greens/green lite asper ihe direction of the Engineer -in charge including Carriage of materials with in all leads and lifts and other incidentals. The rate includes of Octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government..	120.00 Number	830.00	Rupees Eight Hundred Thirty Only	Each	99,600.00
TOTAL						99,600.00
Quoted Rate in Figure		% above/below				
Quoted Rate in Words						


Executive Engineer,
Bharwain Division,
HPPWD Bharwain

BILL OF QUANTITY


Estimate Cost :- Rs. 99,878/-

Earnest Money :-Rs. 2000/-

Time Limit :-One Month.

Name of work:- R&M of Residential Building under HPPWD Division Bharwain (SH: Providing and laying 40mm thick CC interlocking paver block in front and back of Type-III qtr. at PWD Coloney Bharwain).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade M-10 (M-Ten) with minimum nominal mix 1:3:6 (One cement isto three sand isto six graded crushed stone aggregate 20mm (Twenty millimeter) nominal size), in or under water in open foundation for all type of structure and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water) including removal of slush which may arise at time of laying under water for all heights/ depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900 and 1200 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	8.70 Cubic metre	4200.00	Rupees Four Thousand Two Hundred Only	Per Cubic metre	36,540.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade-M20 (M-Twenty) Nominal mix 1:2:4 (one cement isto two sand isto four graded crushed stone aggregate (40mm) forty millimeter nominal size) in or under water in open foundation for all types of structure including cost of form work and curing complete as per drawing and MORD technical specification section 800, 900 & 1200 and as per the direction and the entire satisfaction of Engineer-in-Charge, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water for all heights/depths and any quantum of water complete including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	3.50 Cubic metre	5150.00	Rupees Five Thousand Thirty Three Only	Per Cubic metre	18,025.00
3	Providing and laying of inter locking concrete paver blocks make of NTC/NITCO/HPPWD approved having thickness 40mm (Forty millimeter) as per Technical Specification Clause 1504 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	72.50 Square metre	625.00	Rupees Nine Hundred Eighty Four And Paise Eighty Only	Per Square metre	45,313.00
TOTAL						99,878.00
		Quoted Rate in Figure	% above/below			
		Quoted Rate in Words				


**Executive Engineer,
 Bharwain Division,
 HPPWD Bharwain**

BILL OF QUANTITY


Estimate Cost :- Rs. 99600/-

Earnest Money :-Rs. 2000/-

Time Limit :-One Month

Name of work:- Improvement of Black Spots on various roads under HPPWD Sub Division Amb, Section Amb (SH: (SH:- Providing & fixing of dual directional reflective PVC

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing and fixing double directional reflective speed breaker/rumble strip high impact resistant plastic body of size 275x150x32mm (Two hundred seventy five into one hundred fifty into thirty two millimetre) having 6 (six) glass large 12mm (twelve millimetre) dia reflector leases to one side 12 Nos. (Twelve numbers) on both side provided with two plastic bolted stems 32x50mm (thirty two into fifty millimetre) for fixing round by epoxy make greenlite as per the direction of the Engineering-in-Charge, including carriage of materials within all leads and lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sales tax or any other taxes imposed by the Government.	80.00 Number	1245.00	Rupees One Thousand Two Hundred Forty Five Only	Each	99,600.00
TOTAL						99,600.00
Quoted Rate in Figure		% above/below				
Quoted Rate in Words						



**Executive Engineer,
Bharwain Division,
HPPWD Bharwain**

BILL OF QUANTITY


Estimate Cost :- Rs. 99,760/-

Earnest Money :-Rs. 2000/-

Time Limit :-One Month.

Name of work:- Restoration to rain damages on Jole to Kaint Road via Amroh, bhoo, Dhru, khuroo and Sanjot km 0/0 to 14/255 (SH:- Removal of slips, Restoration of rain cuts and construction of unlined drain between km 5/500 to 7/860)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts complete as per technical specification 302.3.5 and 1611. including carriage of the machinery required within all leads and lifts complete and as per directions and entire satisfaction of the Engineer in Charge.	727.10 Cubic metre	100.00	Rupees One Hundred Only	Per Cubic metre	72,710.00
2	Restoration of rain cuts with soil, moorum gravel or a mixture of these, clearing the loose soil, benching for 300 mm (three hundred millimetres) width laying fresh material in layers not exceeding 250 mm (two hundred fifty millimetres) and compaction with plate compactor or power rammer to restore the original alignment, level and slopes as per drawings and technical specification clause 1902 including carriage of material within all leads and lifts and other incidentals.	110.00 Cubic metre	195.00	Rupees Five Thousand Thirty Three Only	Per Cubic metre	21,450.00
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307. including carriage of the machinery required within all leads and lifts complete and as per directions and entire satisfaction of the Engineer in Charge and including all other incidentals.	140.00 Running metre	40.00	Rupees Nine Hundred Eighty Four And Paise Eighty Only	Per Running metre	5,600.00
TOTAL						99,760.00
		Quoted Rate in Figure	% above/below			
		Quoted Rate in Words				


**Executive Engineer,
 Bharwain Division,
 HPPWD Bharwain**

BILL OF QUANTITY**JOB-5**


Estimate Cost :- Rs. 99,149/-

Earnest Money :-Rs. 2000/-

Time Limit :-One Month.

Name of work:- Improvement of black spots on Dada Siba to Daulatpur road Km.0/0 to 14/0 (SH: Providing and fixing W- metal beam crash barrier at RD 4/720 to 4/744)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	2.07 Cubic metre	220.00	Rupees Two Hundred Twenty Only	Per Cubic metre	455.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade M-10 (M-Ten) with minimum nominal mix 1:3:6 (One cement isto three sand isto six graded crushed stone aggregate 20mm (Twentymillimeter) nominal size), in or under water in open foundation for all type of structure and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying under water for all heights/ depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900 and 1200 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	2.07 Cubic metre	4200.00	Rupees Four Thousand Two Hundred Only	Per Cubic metre	8,694.00
3	Providing and erecting "W" metal beam crash barrier comprising of 3mm (three millimetre) thick corrugated sheet metal beam rail to be kept 70cm (seventy centimetre) above road/ground level, fixed on channel vertical post 150x75x5mm (one hundred fifty into seventy five into five millimetre) spaced 2 m. (two metre) centre to centre, 1.80m. (one decimal eighty metre) high with 15 cm (fifteen centimetre) retro-reflective tape on post and 1.10m. (one decimal ten metre) below ground/road level, all steel parts and fitment to be galvanised by hot dip process, all fittings to confirm to IS:1367 & IS: 1364, metal beam rail to be fixed on the vertical post with a space of channel saction 150x75x5mm (one hundred fifty into seventy five into five millimetre) and 330mm (three hundred thirty millimetre) long complete as per clause 810 conforming to MORT&H Ministry of Road Transport & Highways) specifications (Latest revision) including all fittings required for erection at road site as per drawing and technical specifications complete in all respect as directed by the Engineer-in-Charge including carriage of material within all leads ,lifts and other incidentals. The rate including Octroi, toll tax, sale tax or any other taxes imposed by the Government.	24.00 Running Metre	3750.00	Rupees Three Thousand Seven Hundred Fifty Only	Per running metre	90,000.00
TOTAL						99,149.00
		Quoted Rate in Figure	% above/below			
		Quoted Rate in Words				



**Executive Engineer,
Bharwain Division,
HPPWD Bharwain**

BILL OF QUANTITY


Estimate Cost :- Rs. 99000/-

Earnest Money :-Rs. 2000/-

Time Limit :-One Month

Name of work:- Improvement of Black Spots on various roads under HPPWD Sub Division, Jole (SH: (SH:- Supply and stacking cautionary Sign board)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Manufacturing and Supplying of sign boards of size 1200mm x 900mm x 1.6mm thick Twelve hundred millimeter into nine hundred millimeter into one point six millimeter) of mild steel sheet welded on 2 Nos. MS tubes 47mm x 47mm of 12 SWG sheet 2400mm long in vertically and 4700mm x 4700mm 12 SWG sheet 1200mm long in horizontally frame board duly welded with MS flat iron 25mm x 5mm size on back of edges as per direction of Engineer-In charge all MS will be stored enameled on both sides lettering and printing arrows border etc. will be printed with ready mixed synthetic enamel paint of superior quality in required shade and colour all section of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing clause 1701 and as per direction of Engineer-In Charge i/c carriage of material within all leads and lifts.and other incidentials. The rate including octroi, Royalty Malkhana GST toll tax or other taxes imposed by the Govt.	15.00 Number	6600.00	Rupees Six Thousand Six Hundred Only	Each	99,000.00
TOTAL						99,000.00
		Quoted Rate in Figure	% above/below			
		Quoted Rate in Words				



**Executive Engineer,
Bharwain Division,
HPPWD Bharwain**

BILL OF QUANTITY**JOB-7**


Estimate Cost :- Rs. 99,149/-

Earnest Money :-Rs. 2000/-

Time Limit :-One Month.

Name of work:- Improvement of black spots on Dada Siba to Daulatpur road Km.0/0 to 14/0 (SH: Providing and fixing W metal beam crash barrier at RD 4/751 to 4/775)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	2.07 Cubic metre	220.00	Rupees Two Hundred Twenty Only	Per Cubic metre	455.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade M-10 (M-Ten) with minimum nominal mix 1:3:6 (One cement isto three sand isto six graded crushed stone aggregate 20mm (Twentymillimeter) nominal size), in or under water in open foundation for all type of structure and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying under water for all heights/ depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900 and 1200 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	2.07 Cubic metre	4200.00	Rupees Four Thousand Two Hundred Only	Per Cubic metre	8,694.00
3	Providing and erecting "W" metal beam crash barrier comprising of 3mm (three millimetre) thick corrugated sheet metal beam rail to be kept 70cm (seventy centimetre) above road/ground level, fixed on channel vertical post 150x75x5mm (one hundred fifty into seventy five into five millimetre) spaced 2 m. (two metre) centre to centre, 1.80m. (one decimal eighty metre) high with 15 cm (fifteen centimetre) retro-reflective tape on post and 1.10m. (one decimal ten metre) below ground/road level, all steel parts and fitment to be galvanised by hot dip process, all fittings to confirm to IS:1367 & IS: 1364, metal beam rail to be fixed on the vertical post with a space of channel saction 150x75x5mm (one hundred fifty into seventy five into five millimetre) and 330mm (three hundred thirty millimetre) long complete as per clause 810 conforming to MORT&H Ministry of Road Transport & Highways) specifications (Latest revision) including all fittings required for errection at road site as per drawing and technical specifications complete in all respect as directed by the Engineer-in-Charge including carriage of material within all leads ,lifts and other incidentals. The rate including Octroi, toll tax, sale tax or any other taxes imposed by the Government.	24.00 Running Metre	3750.00	Rupees Three Thousand Seven Hundred Fifty Only	Per running metre	90,000.00
TOTAL						99,149.00
		Quoted Rate in Figure	% above/below			
		Quoted Rate in Words				



**Executive Engineer,
Bharwain Division,
HPPWD Bharwain**

BILL OF QUANTITY


Estimate Cost :- Rs. 99600/-

Earnest Money :-Rs. 2000/-

Time Limit :-One Month

Name of work:- Improvement of Black Spots on various roads under HPPWD Sub Division Amb, Section Panjoa (SH: (SH:- Providing & fixing of dual directional reflective PVC speed breaker/rumble strip)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing and fixing double directional reflective speed breaker/rumble strip high impact resistant plastic body of size 275x150x32mm (Two hundred seventy five into one hundred fifty into thirty two millimetre) having 6 (six) glass large 12mm (twelve millimetre) dia reflector leases to one side 12 Nos. (Twelve numbers) on both side provided with two plastic bolted stems 32x50mm (thirty two into fifty millimetre) for fixing round by epoxy make greenlite as per the direction of the Engineering-in-Charge, including carriage of materials within all leads and lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sales tax or any other taxes imposed by the Government.	80.00 Number	1245.00	Rupees One Thousand Two Hundred Forty Five Only	Each	99,600.00
TOTAL						99,600.00
Quoted Rate in Figure		% above/below				
Quoted Rate in Words						


**Executive Engineer,
 Bharwain Division,
 HPPWD Bharwain**

BILL OF QUANTITY


Estimate Cost :- Rs. 99,407/-

Earnest Money :-Rs. 2000/-

Time Limit :-One Month.

Name of work:- R&M of Residential Building under HPPWD Division Bharwain (SH: Providing and laying 40mm thick CC interlocking paver block in front of AE residence Bharwain).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade M-10 (M-Ten) with minimum nominal mix 1:3:6 (One cement isto three sand isto six graded crushed stone aggregate 20mm (Twenty millimeter) nominal size), in or under water in open foundation for all type of structure and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water) including removal of slush which may arise at time of laying under water for all heights/ depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900 and 1200 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	8.60 Cubic metre	4200.00	Rupees Four Thousand Two Hundred Only	Per Cubic metre	36,120.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade-M20 (M-Twenty) Nominal mix 1:2:4 (one cement isto two sand isto four graded crushed stone aggregate (40mm) forty millimeter nominal size) in or under water in open foundation for all types of structure including cost of form work and curing complete as per drawing and MORD technical specification section 800, 900 & 1200 and as per the direction and the entire satisfaction of Engineer-in-Charge, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water for all heights/depths and any quantum of water complete including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	3.49 Cubic metre	5150.00	Rupees Five Thousand Thirty Three Only	Per Cubic metre	17,974.00
3	Providing and laying of inter locking concrete paver blocks make of NTC/NITCO/HPPWD approved having thickness 40mm (Forty millimeter) as per Technical Specification Clause 1504 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	72.50 Square metre	625.00	Rupees Nine Hundred Eighty Four And Paise Eighty Only	Per Square metre	45,313.00
TOTAL						99,407.00
		Quoted Rate in Figure	% above/below			
		Quoted Rate in Words				


**Executive Engineer,
 Bharwain Division,
 HPPWD Bharwain**