



Himachal Pradesh
Public Works Department
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

"NOTICE INVITING TENDERS"

Sealed percentage rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Bhawarna Division HP.PWD, Bhawarna on behalf of the Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **06-04-2026** up to 11.00 AM, and the same shall be opened on the same day at **11.30 A.M.** in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable) on 04-04-2026 up to **4.00 P.M** and the application for issue of tender form shall be received on 04-04-2026 up to **1.00 PM**.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

Sr. No.	Name of Work	Estimated Cost	Earnest Money	Time Limit	Cost of Tender form
1	Restoration of Retaining wall Patti Ram house of Gurbachan Land Saloh (SH:- C/O R/Wall & V-shape drain) (DC Deposit) SDF/2024/529	62,789/-	1300/-	Two Month	350/-
2	C/O Retaining wall Main road Mansimbal near Paras Public School (SH:- C/O R/Wall & Parapets) DC Deposit (VKV/2025/1230	1,99,349/-	4000/-	Three Month	350/-
3	C/O Ambulance road to Katwal Basti Lower Boda GP Boda km. 0/0 to 1/0 (SH:- C/O R/Wall (length 9.00mtr) DC Deposit (SDP/2020/491)	2,48,753/-	4900/-	Two Month	350/-
4	Restoration of rain damages on Sai to Sai Bharanta road km. 0/0 to 2/0 (SH:- C/O Wire crate for protection at RD. 0/090)	63,530/-	1300/-	Three Month	350/-
5	Construction of Link road from existing Garh Boun Samba Haldra Kon Sanhoon road to the house of Sh. Santosh Kumar Dhiman and other in GP Roda (SH:- P/L CC Work in km. 0/030 to 0/057) DC Deposit (VKV/2024/1307)	80,278/-	1600/-	Two Month	350/-

Terms & Conditions:-

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor/firm has to produce the copy of latest enlistment and renewal enlisted in HP.PWD.
3. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tender without assigning any reason.

Executive Engineer
Bhawarna Division
HPPWD Bhawarna

On behalf of Governor of Himachal Pradesh
Dated:- **25-03-2026.**

No. PWD/BWD/TA/NIT/2025-26/

16753-65

Copy is forwarded to the following for information and necessary action:-

1. The Chief Engineer (KZ), HPPWD, Dharamshala.
2. The Superintending Engineer, 5th Circle, HPPWD., Palampur.
3. All the Assistant Engineers under this Division.
4. The Computer Cell office of the Engineer-in-Chief, HPPWD. Shimla for uploading the NIT on the departmental website.
5. The Drawing /Accounts Branch in this office.
6. Notice Board.


Executive Engineer,
Bhawarna Division
HPPWD. Bhawarna.



Himachal Pradesh
Public Works Department
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

CERTIFICATE

Certified that tender of works are being called of an emergent nature and for larger public interest so there is exigencies/ emergency in calling these tenders without press vide this office letter No. PWD/BWD/TA/NIT/2025-26- 16753-65 dated 25-03 -2026.


Executive Engineer,
Bhawarna Division,
HPPWD. Bhawarna.

Schedule of Quantity

Name of Work:- Restoration of Retaining wall Patti Ram House to Gurbachan Land Saloh. (SH:- C/O R/wall & V-Shape drain) (DC Deposit)


SDF/2024/529

Estimated Cost :- Rs.62,789/-

Earnest Money :- Rs.1300/-

Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M O R D technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arrise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana toll tax, sale tax, GST or other taxes imposed by the Government.	1.30	250.00	Rupees Two Hundred Fifty Only	Per Cubic metre	325.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement : four sand : eight graded crushed/ broken stone aggregate 40mm (forty millimetre) nominal size on ground or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M O R D technical specification section 800, 900 and 1200 and as per the entire satisfaction and direction of the Engineer -in-Charge including carriage of materials within all lead, and lifts and other incidental . The rate is including octroi, royalty, Malkana toll tax, sale tax, GST or other taxes imposed by the Government.	8.10	4300.00	Rupees Four Thousand Three Hundred Only	Per Cubic metre	34830.00
3	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete nominal mix 1:3:6 (one cement :Three sand :Six graded crushed /broken stone aggregate 20 mm (Twenty Millimeters) nominal size on ground or under water including curing complete, pumping or bailing out water ,dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/depths including the cost of form work in drain as per drawings and MORD technical specifications section 800, 900 and 1200 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana toll tax, sale tax, GST or other taxes imposed by the Government.	5.33	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per Cubic metre	26384.00
4	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M O R D technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	5.00	250.00	Rupees Two Hundred Fifty Only	Each	1250.00
Total :-						62789.00
Quoted rates percentage in figures						
Quoted rates percentage in words						


 Executive Engineer
 Bhawana Division
 H.P. P. Dhawan

Name of Work :- C/o Retaining wall main road Mansimbal near Paras Public School (SH:- C/o R/wall & Parapets) (DC Deposit)

Schedule of Quantity

Estimated Cost :-Rs. 1,99,349/-


Earnest Money :-Rs. 4000/-

Time Limit :- Three Months

VKV/2025/1230

S.No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In – Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arrise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	36.64	250.00	Rupees Two Hundred Fifty Only	Per Cubic metre	9160.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement : four sand : eight graded crushed/ broken stone aggregate 40mm (forty millimetre) nominal size on ground or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification section 800, 900 and 1200 and as per the entire satisfaction and direction of the Engineer –in-Charge including carriage of materials within all lead, and lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, GST or other taxes imposed by the Government.	39.68	4300.00	Rupees Four Thousand Three Hundred Only	Per Cubic metre	170624.00
3	Providing and laying mechanically mixed and vibrated concrete for plain concrete in open foundation for all type of structure complete of plain cement concrete grade M-15 (M- fifteen) designed mix with cement contents not less than 275 Kg. (Two hundred seventy five kilogram) per cubic metre with crushed stone aggregate 40mm (Forty millimetre) nominal size on ground or under water and curing complete for 14 (fourteen) days including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in all type of structure as per drawings and MORTH technical specification section 1500, 1700 and 2100 and as directed by the Engineer-in-charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	2.83	5500.00	Rupees Five Thousand Five Hundred Only	Per Cubic metre	15565.00

4	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	16	250.00	Rupees Two Hundred Fifty Only	Each	4000.00	
	Quoted rates percentage in figures			Total :-			199349.00
	Quoted rates percentage in words						



 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work:- C/O Ambulance road to Katwal Basti Lower Boda G.P Boda Km 0/00 to 1/00(SH:- C/O R/wall (length 9.00 mtr)) (DC
 Deposit) **SDP/2024/491**

Estimated Cost :- Rs.2,48,753/-
 Earnest Money :- Rs.4900/-
 Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M O R D technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana toll tax, sale tax, GST or other taxes imposed by the Government	16.83	250.00	Rupees Two Hundred Fifty Only	Per Cubic metre	4208.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement : four sand : eight graded crushed/ broken stone aggregate 40mm (forty millimetre) nominal size on ground or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification section 800, 900 and 1200 and as per the entire satisfaction and direction of the Engineer -in-Charge including carriage of materials within all lead, and lifts and other incidental The rate is including octroi, royalty, Malkana toll tax, sale tax, GST or other taxes imposed by the Government	53.01	4300.00	Rupees Four Thousand Three Hundred Only	Per Cubic metre	227943.00
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V) 20 (H) (one vertical twenty horizontal) towards draining face complete as per drawing and M O R D technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	15.00	250.00	Rupees Two Hundred Fifty Only	Each	3750.00
4	Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental The rate is including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government	18.36	700.00	Rupees Seven Hundred Only	Per Cubic metre	12852.00
Total :-						248753.00
Quoted rates percentage in figures						
Quoted rates percentage in words						


 Executive Engineer
 Bhawarna Division
 H.P. BWL Bhawarna

Schedule of Quantity


Name of Work :- Restoration of rain damages on Sai to Sai Bharanta road Km 0/0 to 2/0. (SH:- C/o Wire crate for protection at RD 0/090)

Estimated Cost :-Rs. 63,530/-

Earnest Money :-Rs. 1300/-

Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In – Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arrise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	12.20	250.00	Rupees Two Hundred Fifty Only	Per Cubic metre	3050.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100mm x100mm (Hundred millimetre into hundred millimetre) mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone bounders weighing not less than 25 Kg (Twenty five kilogram) each as per drawing and technical specification clause 1301 as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	21.60	2800.00	Rupees Two Thousand Eight Hundred Only	Per Cubic metre	60480.00
Total :-						63530.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					



 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of work:- Construction of link road from existing Garh Boun Samba Haldra Kona Sanhoon road to the House of Sh. Santosh Kumar Dhiman and other in G.P Roda. (SH:- P/L CC Work in Km 0/030 to 0/057)(DC Deposit). *VKY/224/1307*

Estimated Cost :- Rs. 80,278/-
 Earnest Money :- Rs. 1600/-
 Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		Rs.
1	Providing, laying, Soling 90 to 45mm (Ninety to forty five-millimetre) nominal size Grading-1, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 Kn. Static roller in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 1 as per technical specification Clasue 405 as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is including octrai, royalty, Malkana toll tax, sale tax, GST or other taxes imposed by the Government	8.24	2000.00	Rupees Two Thousand Only	Per Cubic metre	16480.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) in sub structure nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 40mm (forty millimetre) nominal size using cement contents not less than 330 Kg (Three hundred thirty kilogram) per cubic metre on ground or under water and curing complete including pumping or boiling out water, dewatering, removal of slush which may arise at the time of laying concrete complete for all height/ depths including cost of form work in open foundation as per drawing and MORD technical specification section 800, 900, 1200 including carriage of material with in all leads, lifts and other incidentals as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	10.29	6200.00	Rupees Six Thousand Two Hundred Only	Per Cubic metre	63798.00
Total :-						80278.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna