

- 1 -

OFFICE OF

EXECUTIVE ENGINEER, CHAMBA DIVISION HPPWD CHAMBA  
HIMACHAL PRADESH, PUBLIC WORKS DEPARTMENT CHAMBA  
Phone No. 01899-222229 Email ee-cha-hp@nic.in

NOTING INVITING TENDER

Sealed item rate tender on form 6&8 are hereby invited by the undersigned for the works on behalf of the Governor of Himachal Pradesh from the approved and eligible contractor senlsted in HPPWD . So as to reach in his office on or before **10-04-2026 to 11:00 AM** and will be opened on the same day at **11:30 AM**, in the presence of the intending Contractor or their authorized representatives if any. The tender application will be received in this office on **08-04-2006 upto 10.00 AM to 12.30 PM** and tender form can be had from this office on **09-04-2026 from 3.00 PM to 5.00 PM**. The earnest money in the form of FDR from nationalized bank in HP duly pledged in favour of the Executive Engineer, Chamba Division HPPWD Chamba must be accompanied with each tender . The tender form will be issued to contractor who giving proof of enlistment ,GST ,Conditional tenders and the tenders received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer, reserves the right to reject the tender without assigning any reason. Special care should be taken to write the rates both in figure and in words.

Sr. No.	Name of work	Estimate Cost (Rs.)	Earnest Money (Rs.)	Cost of tender form (Rs.)	Class	Completion period
1	2	3	4	5	6	7
1	Construction of Link road to Village Bhuin Km. 0/0 to 1/750 (SH:- Formation cutting work in Km. 0/0 to 0/065) under VKVNY .	4,32,578/-	8700/-	350/-	D & C	One Month
2	Construction of Jeepable Link road Jared via Sanoti Km. 0/0 to 2/750 (SH:- Formation cutting work in Km. 0/0 to 2/750) under VKVNY .	4,39,978/-	8800/-	350/-	D & C	One Month
3	Construction of Jeepable Link road Nagela to Padhruin Km. 0/0 to 2/450 (SH:- Formation cutting work in Km. 0/0 to 0/360) under VKVNY .	4,39,978/-	8800/-	350/-	D & C	One Month

-2-

4	Construction of Rain Damages on Link road to Village Mangla Km. 0/0 to 2/400 (SH:- Construction of Retaining wall at RD 0/250 to 0/260 )	3,18,698/-	6,400/-	350/-	D & C	One Month
5	Restoration of Rain Damages on Various road under Chamba Sub Division No.II, HPPWD., Chamba (SH:- Hiring of Crawler Excavator for removal of slips at various Rds.)	4,97,700/-	10,000/-	350/-	D & C	One Month
6	Restoration of Rain Damages on Various road under Chamba Sub Division No.II, HPPWD., Chamba (SH:- Hiring of Tipper for disposal of muck of slip )	4,99,280/-	10,000/-	350/-	D & C	One Month
7	Restoration of Rain Damages on Various road under Chamba Sub Division No.II, HPPWD., Chamba (SH:- Hiring of Crawler Excavator for removal of slips at various Rds.)	4,97,700/-	10,000/-	350/-	D & C	One Month
8	Providing Protection work on Link road to village Daroga Km. 0/0 to 4/500 (SH:- Construction of retaining wall at RD 3/460 to 3/470) Under VKVNY	4,99,640/-	10,000/-	350/-	D & C	One Month
9	Providing Protection work on Link road to village Daroga Km. 0/0 to 4/500 (SH:- Construction of retaining wall at RD 1/940 to 1/955) Under VKVNY	4,99,640/-	10,000/-	350/-	D & C	One Month

TERMS AND CONDITIONS:-

1. The contractor should produce a copy of enlistment /renewal at time of application .
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor /firm have his registration and GST No. ,the copy of same be attached with the application
4. The earnest Money shall be deposited duly pledged in favour of executive Engineer, Chamba Division HPPWD Chamba and cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected .
5. The contractor /firms are requested to insert the rate of each item in works as well as in figures failing which XEN reserves the right to accept/reject any tender without assigning any reasons at any stage.

Executive Engineer,  
Chamba Division  
HPPWD Chamba

No. PWC-WA-II/Contract/2025-26- 61552-601 Dated:- 30/03/2026

Copy forwarded to:-

1. The F.C-cum-Principal Secretary (PW) to the govt. of Himachal Pradesh Shimla-2 for favour of information, please.
2. The Engineer-in-Chief, HPPWD., Shimla
3. The Chief Engineer (KZ) HPPWD Dharamshala
- 4 The Superintending Engineer, 7<sup>th</sup> Circle HPPWD Dalhousie .
5. The Executive Engineer (IT Cell) office of Engineer-in-Chief HPPWD Shimla for uploading the NIT on the Departmental website.
- 6 All the Assistant Engineers under Chamba Division
7. All the Contractor working under this division
- 8 H.D.M./Supdt./Acctt. of this office.
9. Notice Board..

Executive Engineer,  
Chamba Division  
HPPWD Chamba

-4-



OFFICE OF

EXECUTIVE ENGINEER, CHAMBA DIVISION HPPWD CHAMBA  
HIMACHAL PRADESH, PUBLIC WORKS DEPARTMENT CHAMBA

Phone No. 01899-222229 Email ee-cha-hp@nic.in

CERTIFICATE

Certified that tender of works, as called vide this office  
letter No. PWC-WA-II/ Contract/2025-26- 61552-601 Dated:- 30/03/26  
are emergent nature in exigency of public interest

  
Executive Engineer,  
Chamba Division  
HPPWD Chamba  


**DRAFT SCHEDULE OF QUANTITIES**  
**Name of work:- Construction of link road to village Upper Bhuin Km. 0/0 to 1/750 (SH:- Formation cutting work in Km. 0/0 to 0/065 ) under VKVMN**

Estimated cost : 432578/-  
 Rs.

Earnest Money : 8,700/-  
 Rs.

Time limit one month

Sl.N	Description of Work / Item(s)	Quantity	Units	Rate		Amount
				In Fig	In words	
01	Excavation in hilly area in all heights and depths and in all kind of soil by manual /mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock chiselling, wedging out of rock(where blasting is prohibited) and their intermediate classification of soil complete including setting out true to the required lines grades ,width, cutting and trimming of side slopes and level as shown in the drawing and as directed by Engineer-in-Charge at site according to the MORD technical specification clause 302,1603.1 and 1603.2 and sorting out useful materials and stacking the same within all leads and lifts in acquired width of road and transportation of un-useful material for filling in road ways camber, embankments for grade improvements and disposal of all surplus material to approved dumping sites through all modes of transportation including head load or animal transport or mechanical means alongwith its leveling fine dressing and carriage of machineries ,materials, tools, equipments and safety measures and other incidentals necessary to complete the work by mechanical means/ labour if required. The useful materials such as stones, shingle aggregate and slates etcetera shall be sorted out and stacked in prooper stack. <b>Any loss to the public/private property</b> during the course of execution shall be the absolute responsibility of the contractor which shall have to be compensated by him in all cases. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	2012.06	Per Cubic Metre	214.99	Rupees Two Hundred & Fourteen - Paise Ninety Nine Only	432573.00
	<b>DNIT</b>					
		<b>Total</b>				<b>432573.00</b>

*DNIT approved for Rs 432573/- only*

  
 Executive Engineer,  
 Chamba Division,  
 HPPWD Chamba

DRAFT SCHEDULE OF QUANTITIES

Name of work:- Construction of jeepable link road Jajred via Sanoti km 0/0 to 2/750 . (SH:- Formation cutting work in Km. 0/0 to 0/180 ) *Under VK VVVV*

SI.N	Description of Work / Item(s)	Quantity	Units	Estimated cost : Rs.	
				Earnest Money : Rs.	439978.00
				Time limit	one month
				Rate	Amount
01	Excavation in hilly area in all heights and depths and in all kind of soil by manual /mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock chiselling, wedging out of rock(where blasting is prohibited) and their intermediate classification of soil complete including setting out true to the required lines grades, width, cutting and trimming of side slopes and level as shown in the drawing and as directed by Engineer-in-Charge at site according to the MORD technical specification clause 302.1603.1 and 1603.2 and sorting out useful materials and stacking the same within all leads and lifts in acquired width of road and transportation of un-useful material for filling in road ways camber, embankments for grade improvements and disposal of all surplus material to approved dumping sites through all modes of transportation including head load or animal transport or mechanical means alongwith its leveling fine dressing and carriage of machineries ,materials, tools, equipments and safety measures and other incidentals necessary to complete the work by mechanical means/ labour if required. The useful materials such as stones , shingle aggregate and slates etcetera shall be sorted out and stacked in prooper stack. <b>Any loss to the public/private property</b> during the course of execution shall be the absolute responsibility of the contractor which shall have to be compensated by him in all cases. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	2048.22	Per Cubic Metre	In Fig 214.81 Rupees Two Hundred & Fourteen - Paise Eighty One Only	439978.00
Total					439978.00

*DMIT approved for Rs 439978/- only*

*[Signature]*  
Executive Engineer,  
Chamba Division,  
HPPWD Chamba

5

DRAFT SCHEDULE OF QUANTITIES

Name of work:- Construction of jeepable link road Nagela to Padhrain km 0/0 to 2/450 . (SH:- Formation cutting work in Km. 0/0 to 0/360 ) *Can div Vik Vinay*

Estimated cost : Rs. 428296/-  
 Earnest Money : Rs. 8600/-  
 Time limit one month

SI.N	Description of Work / Item(s)	Quantity	Units	Rate		Amount
				In Fig	In words	
01	Excavation in hilly area in all heights and depths and in all kind of soil by manual /mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock chiselling, wedging out of rock(where blasting is prohibited) and their intermediate classification of soil complete including setting out true to the required lines grades ,width, cutting and trimming of side slopes and level as shown in the drawing and as directed by Engineer-in-Charge at site according to the MORR technical specification clause 302,1603.1 and 1603.2 and sorting out useful materials and stacking the same within all leads and lifts in acquired width of road and transportation of un-useful material for filling in road ways camber, embankments for grade improvements and disposal of all surplus material to approved dumping sites through all modes of transportation including head load or animal transport or mechanical means alongwith its leveling fine dressing and carriage of machineries ,materials, tools, equipments and safety measures and other incidentals necessary to complete the work by mechanical means/ labour if required. The useful materials such as stones , shingle aggregate and slates etcetera shall be sorted out and stacked in prooper stack. <b>Any loss to the public/private property</b> during the course of execution shall be the absolute responsibility of the contractor which shall have to be compensated by him in all cases. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	1993.56	Per Cubic Metre	214.84	Rupees Two Hundred & Fourteen - Paise Eighty Four Only	428296.00
			<i>DMT</i>		<i>approved for Rs 428296/- all</i>	<i>428296.00</i>
					Total	428296.00

*[Signature]*  
 Executive Engineer,  
 Chamba Division,  
 HPPWD Chamba

Draft Schedule of quantity

Estimated Cost: Rs. 3,18,698/-  
 Earnest Money :- Rs. 6,400/-  
 Time Limit :- One Month

Name of Work:- Restoration of rain Damages on link road to village Mangla km 0/0 to 2/400 (SH- construction of retaining wall at Rd 0/250 to 0/260 )

Sr.No	Description of Work / Item (S)	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiselling / wedging out rocks ( where blasting is prohibited) as per drawings and MORO technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated Suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimetre). Compacted thickness including shoring and strutting and pumping and bailing out water ( surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government.	24.05	350.00	Rupees Three Hundred & Fifty Only	Per Cubic Metre	8418.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete 1:5:10 ( One cement is to five sand is to eight graded crushed stone aggregate 40mm (forty millimetre) nominal size or ground or under water including pumping or bailing out water/ surface and sub soil water), dewatering for all heights / depths and any quantum of water including removal of slush which may arise at the time of laying concrete for all heights/ depths, including the cost of form work and curing for 14 ( fourteen) days complete in Retaining walls and Breast walls etcetera as per drawings and MORO technical specification section 800, 900 and 1200 and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	59.10	4900.00	Rupees Four Thousand Nine Hundred Only	Per Cubic Metre	289590.00
3	Back filling with granular material behind abutments, return walls, wing walls and retaining walls etc. complete as per drawings and MORO technical specification clause 1204.3.8 or as directed by the Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sales tax or any other taxes imposed by the Government.	16.50	950.00	Rupees Nine Hundred & Fifty Only	Per Cubic Metre	15675.00
4	Providing 100mmr. (Hundred millimetre) diameter PVC pipe Weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing walls, return walls and retaining, breast walls etc., extending through the full width of the structure with slope of 1 (V) : 20 (H); one vertical is to twenty horizontal ) towards drawing face complete as per drawings and MORO technical specifications clause 614, 709, 1204.3.7 or as directed by the Engineer in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty ,Malkana, toll tax, sales tax or any other taxes imposed by the Government.	17	295.00	Rupees Two Hundred & Ninety Five Only	each	5015.00
<b>Total</b>						<b>318698.00</b>

*D.H.I.T approved for Rs 318698 finally*

*[Signature]*  
 Engineer  
 Chamba Division  
 H.P.P.W.D., Chamba

6

Draft Schedule of Quantity

Name of work :- Restoration of rain damages on Various road under Chamba Sub Division No\_II HPPWD  
(SH : Hiring of Crawler excavator for removal of slips at various RDs).

Estimated cost : Rs.497700  
Earnest money : Rs. 10000/-  
Time : One month

S.No.	Descriptions of Item.	Qty.	Rate		Unit	Amount
			In fig	In words		
1	Hiring of Crawler Excavator cum Pokelane or JS 210 or equivalent for removal of slips, debris, and boulders clear from the road surface upto all heights and depths in all kinds of soil including rocky portion and saturated soil and then disposing of all unserviceable material upto all leads as per directions and entire satisfaction of Engineer-in-Charge. The Excavator should work minimum 8.00 hours from 9.00 AM to 5.00 PM daily and excavate at least 200 cum quantity of snow/slips per hour. Any loss to the public / private property or any accident etc. happened during the course of hiring period/ execution shall be the absolute responsibility of owner of the machinery which shall have to be compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner at his own cost and repair & spare, watch and ward of the machine will also be borne by the contractor/ owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate is including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	158.00	3150.00	Rupees three thousand one hundred fifty & paise zero only	Per hour	497700.00
<b>Total</b>						<b>497700.00</b>

Assistant Engineer  
Chamba Sub Division No-2  
HPPWD Chamba

*DWT approve for Rs 497700/only*

Engineer  
Chamba Division  
H.P.P.W.D., Chamba

6

DNT

Name of work :- Restoration of rain damages on Various road under Chamba Sub Division No\_II HPPWD Chamba (SH : Hiring of Tipper for disposal of muck of slip).

Estimated cost : Rs.4,99,280/-  
Earnest money : Rs. 10000/-

Time : One month

S.No.	Descriptions of Item.	Qty.	Rate		Unit	Amount
			In fig	In words		
1	Hiring of Tipper 10 cum/ 18 tonne capacity for disposing and transporting of surplus excavated material and shifting of any type of construction material in all leads as per directions and entire satisfaction of Engineer-in-Charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period/ execution shall be the absolute responsibility of owner of the machinery which shall have to be compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner at his own cost and repair & spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate is including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government	632.00	790.00	Rupees seven hundred ninety paise zero only	Per hour	499280.00
<b>Total :</b>						<b>499280.00</b>

Assistant Engineer  
Chamba Sub Division No-2  
HPPWD Chamba

*DNT approved for Rs 4,99,280/-*

Assistant Engineer  
Chamba Division  
H.P.P.W.D., Chamba

7

Draft Schedule of Quantity

Name of work :- Restoration of rain damages on Various road under Chamba Sub Division No\_II HPPWD  
(SH : Hiring of Crawler excavator for removal of slips at various RDs).

Estimated cost : Rs.497700  
Earnest money : Rs. 10000/-  
Time : One month

S.No.	Descriptions of Item.	Qty.	Rate		Unit	Amount
			In fig	In words		
1	Hiring of Crawler Excavator cum Povelane or JS 210 or equivalent for removal of slips, debris, and boulders clear from the road surface upto all heights and depths in all kinds of soil including rocky portion and saturated soil and then disposing of all unserviceable material upto all leads as per directions and entire satisfaction of Engineer-in-Charge. The Excavator should work minimum 8.00 hours from 9.00 AM to 5.00 PM daily and excavate at least 200 cum quantity of snow/slips per hour. Any loss to the public / private property or any accident etc. happened during the course of hiring period/ execution shall be the absolute responsibility of owner of the machinery which shall have to be compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner at his own cost and repair & spare, watch and ward of the machine will also be borne by the contractor/ owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate is including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	158.00	3150.00	Rupees three thousand one hundred fifty & paise zero only	Per hour	497700.00
<b>Total</b>						<b>497700.00</b>

Assistant Engineer  
Chamba Slips Division No-2  
H.P.P.W.D Chamba

*DN 17 approved for Rs 497700/-*

Assistant Engineer  
Chamba Division  
H.P.P.W.D., Chamba

Draft Schedule of quantity

Name of Work:-Providing Protection work on link road to village Daroga km 0/0 to 4/500 (SH- construction of retaining wall at Rd 3/460 to 3/470) under VKVNY

Estimated Cost: Rs. 499640/-  
Earnest Money :- Rs. 10,000/-  
Time Limit :- One Month

Sr.No Description of Work / Item (S)

1	Qty.	Rate		Unit	Amount
		In fig.	In words		
1	41.15	350.00	Rupees Three Hundred & Fifty Only	Per Cubic Metre	14403.00
2	87.90	5160.00	Rupees Five Thousand One Hundred & Sixty Only	Per Cubic Metre	453564.00
3	13.45	950.00	Rupees Nine Hundred & Fifty Only	Per Cubic Metre	12778.00
4	22	295.00	Rupees Two Hundred & Ninety Five Only	each	6490.00
<b>Total</b>					<b>487235.00</b>

DNIT approved for Rs 487235/-

Engineer  
Chamba Division  
H.P.P.W.D CHAMBA

Draft Schedule of quantity

Estimated Cost: Rs. 499640/-  
 Earnest Money :- Rs. 10,000/-  
 Time Limit :- One Month

Name of Work:- Providing Protection work on link road to village Daroga km 0/0 to 4/500 (SH:- construction of retaining wall at Rd 1/940 to 1/955) under VKVNY  
 Sr.No Description of Work / Item (S)

1	Qty.	Rate		Unit	Amount
		In fig.	In words		
1	44.55	350.00	Rupees Three Hundred & Fifty Only	Per Cubic Metre	15593.00
2	88.65	5160.00	Rupees Five Thousand One Hundred & Sixty Only	Per Cubic Metre	457434.00
3	20.25	950.00	Rupees Nine Hundred & Fifty Only	Per Cubic Metre	19238.00
4	25	295.00	Rupees Two Hundred & Ninety Five Only	each	7375.00
<b>Total</b>					<b>499640.00</b>

DMIT approved for Rs 499640/- only

  
 Executive Engineer  
 Chamba Division  
 H P P.W.D CHAMBA