



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Tel.01899-299219.

cepwd-chowari@hp.gov.in

No. PWD-CHW/Tender /2025-26- 14809-860

Dated:- 28/03/2026

To


The Executive Engineer (IT Cell)
Nigam Bihar Shimla-2

Subject: - Publishing of Tender Notice.

Dear Sir,


Enclosed please find herewith the tender Notice of work as give in the Notice inviting Tender for uploading on department web site as per notification Principal Secretary (PW) to the Govt. of Himachal Pradesh letter No. PBW-(B) A9 (3)1/2020 dated Shimla-2 the 16th July 2021 as the work mentioned in the tender notice are urgent in nature and public interest.

DA/ As above.


Executive Engineer,
Chowari Division,
HPPWD, Chowari.


Copy forwarded to the Superintending Engineer, 7th Circle, HPPWD, Dalhousie for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer, (IT Cell) Nigam Bihar Shimla-2 for information and further necessary action.


Executive Engineer,
Chowari Division,
HPPWD, Chowari.

Certificate

Certified that the tenders called vide this office letter No. PWD-CHW/Tender /2025-26.....dated..... is emergent nature and in public interest.


Executive Engineer,
Chowari Division,
HPPWD, Chowari.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

"NOTICE INVITING TENDERS"

Sealed percentage/item rate tender(s) on PWD from No 6 & 7/8 are hereby invited by the Executive Engineer, Chowari Division, HPPWD, Chowari on behalf of the Governor of HP for the following works from the approved and eligible contractor/firm of appropriate Class enlisted in HPPWD as per the latest instructions so as to reach in this office as per time schedule given below. The offer of the tender will be kept open for 90 days from the date of opening of the tender. The undersigned reserves the right to reject any or all the tender without assigning any reasons: -

- 3 **Date of issued/sale of tender form against** 04.04.2026
4 **Cash payment (nonrefundable).** 06.04.2026

The tender shall be received upto **11.00 AM on 06.04.2026** and will be opened on the day of **06.04.2026 at 12.00 PM** in the presence of intending Contractor or their authorized representative who may like to be present. The tender can be had from this office against cash payment as shown below (Nonrefundable) during the working hours on **04.04.2026**. The Earnest Money in the shape of National Saving Certificate/Deposit at call/Time deposit/Account/in any Post Office/Nationalized Bank in HP duly pledged in favour of Executive Engineer, Chowari Division, HPPWD, Chowari must accompany with each application. Conditional tender and the tender received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 90 days. The XEN reserve the right to accept or reject the tender without assigning any reasons: -

S. No.	Name of work	Estimated cost	Earnest Money	Cost of tender	Time Limit	Class
1	Restoration of rain damage on link road to village Ganiyar Km 0/0 to 1/425 (SH: - C/o R/wall at RD 1/415 to 1/425).	309205.00	6200.00	Rs. 350/-	One Month	Class-D & C
2	Extension of Kahri Kothi to Kut road (portion Kahri Kothi to Gunha Nallah) Km 0/0 to 1/500 (SH: - C/o R/wall in wire crate at Rd 0/435 to 0/440).	98409.00	2000.00	Rs. 350/-	One Month	Class-D & C
3	Restoration of Rain Damage on Shahpur Sihunta Chowari Road Km. 40/00 to 53/00 (SH-C/O R/Wall at Rd. 48/230 to 48/247.50)	495124.00	10000.00	Rs. 350/-	One Month	Class-D & C
4	Restoration of Rain Damage on NSLT Road Km. 25/00 to 40/810 (SH: C/O R/wall in PCC at Km. 26/250 to 26/260)	214467.00	4300.00	Rs. 350/-	One Month	Class-D & C
5	Restoration of rain damage on Chowari to Jot Road Km. 0/00 to 23/00 (SH-removal of slips in in Km. 1/00 to 8/00).	483001.00	10000.00	Rs. 350/-	One Month	Class-D & C
6	A/R & MO NR Building Under Chowari Sub Division (SH C/O Boundary Wall & P/L. Painting work, P/F Sanitary Work)	96996.00	2000.00	Rs. 350/-	One Month	Class-D & C
7	Restoration of rain damage on Shahpur Sihunta Chowari Road Km. 24/00 to 47/00 (SH- Removal of slips in in Km. 32/500 to 37/00)	479859.00	10000.00	Rs. 350/-	One Month	Class-D & C
8	Protection Work of HPPWD Rest House Kakira Under Tehsil Bhattiyat Distt. Chamba (SH C/O R/wall in Wire Crate along With PCC Pushta)	245682.00	5000.00	Rs. 350/-	One Month	Class-D & C
9	C/O Bulkti Nallah To Tathi Road Km. 0/00 to 2/00 (SH: C/O R/wall in Wire Crate at Km. 0/085 to 0/100)	327737.00	6600.00	Rs. 350/-	One Month	Class-D & C


10	Restoration of Rain Damage on Dramnala Dhulara Rajain road Km. 0/00 to 9/00 (SH- Construction of Breast wall at RD. 6/575 to 6/585 and 6/591 to 6/599)	276110.00	5600.00	Rs. 350/-	One Month	Class-D & C
11	Restoration of rain damage on Various Road Under Mail Section (SH: Hiring of excavator cum loader for removal of slips Various Road Under Mail Section)	442800.00	9000.00	Rs. 350/-	One Month	Class-D & C
12	Restoration of Rain Damage on Dukhar to Morthu road Km. 0/00 to 8/00 (SH- Construction of Breast wall at RD. 0/840 to 0/885)	240009.00	4800.00	Rs. 350/-	One Month	Class-D & C
13	Construction of link road to Naag Bintru Road Km. 0/00 to 2/580 (SH Construction of Retaining wall with PCC Pushta at RD. 0/870 to 0/879)	479640.00	9600.00	Rs. 350/-	One Month	Class-D & C
14	Restoration of rain damage on Chowari to Jot Road Km. 0/00 to 23/00 (SH: C/O R/wall at Rd. 17060 to 1/065)	96008.00	2000.00	Rs. 350/-	One Month	Class-D & C
15	C/O Stage at Govt. Post Graduate College at Chowari Distt. Chamba HP (SH-C/O R/wall & P/F MS BP Sheet)	317412.00	6400.00	Rs. 350/-	One Month	Class-D & C
16	Restoration of Rain damage on link road to village Fakrodu Km. 0/00 to 2/810 (SHC/O R/Wall at Rd. 0/345 to 0/351)	270492.00	5500.00	Rs. 350/-	One Month	Class-D & C
17	Restoration of Rain damage on Kamladi Bakloh Ghatasani road Km. 0/00 to 5/00 (SH: - Construction of wire crate alongwith PCC Pushta at RD 3/830 to 3/840).	362542.00	7300.00	Rs. 350/-	One Month	Class-D & C
18	Construction of link road to Naag Bintru road Km. 0/00 to 2/580 (SH Construction of Retaining wall in wire crate with PCC Pushta at RD 0/690 to 0/709).	485013.00	9700.00	Rs. 350/-	One Month	Class-D & C
19	Restoration of rain damage on Hunera to Kahri Kothi road Km. 0/00 to 2/420 (SH - Removal of slips on various at RD. 0/0 to 2/300)	161280.00	5300.00	Rs. 350/-	One Month	Class-D & C
20	Restoration of rain damage on Langhi to Daroni road Km. 0/00 to 3/225 (SH Removal of slips on various at RD. 0/0 to 3/200)	479776.00	9600.00	Rs. 350/-	One Month	Class-D & C
21	Restoration of rain damage on Patka Dalhousie road Km. 0/00 to 32/00 (SH Construction of PCC Retaining wall at RD 30/548 to 30/554).	291456.00	5900.00	Rs. 350/-	One Month	Class-D & C
22	Restoration of rain damage on Parshiyara to Kathiyadi road Km 0/00 to 5/00 (SH Removal of slips on various at RD. 0/0 to 4/860)	493574.00	10000.00	Rs. 350/-	One Month	Class-D & C
23	A/R & M/O Various Road under HP PWD Sub Division Kakira (SH. Painting and Lettering Writing of Sign boards, Kilometers Stone culvert Etc.) (Under Telecom Deposit).	187571.00	4000.00	Rs. 350/-	One Month	Class-D & C

Estimate
Earnest
ime Limit :
all At Rd
ate

ious SH-
3 of
nder
vari
/00
of
to
ink
issa
1 of
)
a to
/00
to
tru
SH
ith
rad
00
D.
var
SH
/0
ra
-:
).
ad
I:
'0
ii

24	Restoration of rain damage on various road under Chowari sub division (SH-Hiring of Tipper and for Shifting of Muck Debris various roads under Raipur section)	455100.00	10000.0	Rs. 350/-	One Month	Class-D & C
25	Restoration of Rain damage on Chowari Mandhiar Baloh Fagot Road Km. 0/00 to 13/330 (SH: Construction of Retaining wall at RD. 7/840 to 7/849.50)	462046.00	10000.00	Rs. 350/-	One Month	Class-D & C
26	Restoration of Rain damage on Link Road from Luhani to Bharana da Bassa Km. 0/00 to 1/405 (SH Construction of Retaining wall at RD. 0/210 to 0/217)	4659771.00	9200.00	Rs. 350/-	One Month	Class-D & C
27	Restoration of Rain damage on Patka to Dalhousie Road Km. 32/00 to 45/00 (SH: -C/O R/Wall at Rd. 35/980 to 35/989)	211424.00	4300.00	Rs. 350/-	One Month	Class-D & C
28	Construction of link road to Naag Bintru road Km. 0/00 to 2/580 (SH Construction of Retaining wall with PCC Pushta at RD. 0/855 to 0/862)	478901.00	9600.00	Rs. 350/-	One Month	Class-D & C
29	Restoration of rain damage on Link road to village Nahana Km. 0/00 to 4/100 (SH Removal of slips on various at RD. 0/0 to 4/100)	482052.00	9700.00	Rs. 350/-	One Month	Class-D & C
30	Restoration of rain damage on Dukhar to Morthu road Km. 0/00 to 8/00 (SH Removal of slips on various at RD. 4/0 to 6/640)	497088.00	10000.00	Rs. 350/-	One Month	Class-D & C
31	Restoration of Rain damage on Balana to Balli road Km. 0/00 to 5/490 (SH: Construction of Retaining wall at RD. 5/021 to 5/026).	432087.00	8700.00	Rs. 350/-	One Month	Class-D & C
32.	Restoration of rain damage on Dugred to Naloh road Km. 0/00 to 5/630 (SH: Removal of slips on various at RD. 2/0 to 5/00)	492443.00	10000.00	Rs. 350/-	One Month	Class-D & C
33	Restoration of Rain Damage on Gagoi to Jambal road Km. 0/00 to 3/00 (SH - Removal of slips on various at RD 0/400 to 2/500)	97715.00	2000.00	Rs. 350/-	One Month	Class-D & C

- 1 The tender forms will not be issued to those Contractors whose performance is not found satisfactory.
- 2 The Contractor should have executed two similar types of works 1/3 of each amount put to tender or single work of amount equal to the amount put to tender within list five year.
- 3 GST No/Earnest Money Tender Form cost, copy of enlistment should be accompanied with application.



 Executive Engineer,
 Chowari Division,
 HPPWD, Ch...

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damage on link Road to village Ganjyar km. 0/0 to 1/425(SH-C/O R/wall At Rd 1/415 TO 1/425

Estimate Cost - Rs.	309205.00
Earnest Money - Rs.	6200.00
Time Limit :-	One Month

Sr. No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	16.50	400.10	Rupees Four Hundred And Paise Ten Only	Per Cubic Metre	6602.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1:5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (Forty millimetre) nominal size in or under water and curingcomplete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights / depth including the cost of form work complete in all respect as per the drawing and technical specifications clause 802. 803. 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	58.80	4642.50	Rupees Four Thousand Six Hundred Forty Two And Paise Fifty Only	Per Cubic Metre	272979.00
3	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	17.00	1210.30	Rupees One Thousand Two Hundred Ten And Paise Thirty Only	Per Cubic Metre	20575.00
4	Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia meters. PVC pipe extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	22	411.30	Rupees Four Hundred Eleven And Paise Thirty Only	Each	9049.00
Total:-						309205.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						


 Executive Engineer
 Chowari Division
 HP PWD Chowari

SCHEDULE OF QUANTITY

Name of work:- Extension of Kahri Kothi to Kut Road (Portion Kahri Kothi to Gunha Nallah) Km. 0/00 to 1/500 (SH :- C/O R/wall in Wire Crate at Rd. 0/435 to 0/440)

Estimated Cost: - Rs. 98409.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In Fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	4.70	559.10	Rupees Five Hundred Fifty Nine And Paise Ten Only	Per Cubic Metre	2628.00
2	Providing and laying of boulder apron laid in wire crates with 4 mm (four millimetre) dia G.I wire conforming to IS: 280 and IS: 4826 in 100 mm x 100 mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulders weighing not less than 25 Kg (twenty five kilogramme) each as per drawing technical specifications Clause 1301 and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	31.25	3065.00	Rupees Three Thousand Sixty Five Only	Per Cubic Metre	95781.00
Total: -						98409.00

Rate quoted in (%) Above / Below
 Rate quoted in (%) in Words


 Executive Engineer
 Chowari Division
 HP RWD Chowari


(2)

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damage on Shapur Sihunta Chowari Road Km. 40/00 to 53/00 (SH :- C/O R/Wall at Rd. 48/230 to 48/247.50)

Estimated Cost: - Rs.	495124.00
Earnest Money :- Rs.	10000.00
Time Limit :-	One Month.

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORO technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	28.88	559.10	Rupees Five Hundred Fifty Nine And Paise Ten Only	Per Cum	16147.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1.5:1:0 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (Forty millimetre) nominal size in or under water and curingcomplete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all hights / depth including the cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	102.90	4654.78	Rupees Four Thousand Six Hundred Fifty Four And Paise Seventy Eight Only	Per Cum	478977.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						
Total: -						495124.00


 Executive Engineer
 Chowari Division
 HP PWD, CHOWARI

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 214467.00
 Earnest Money :- Rs. 4300.00
 Time Limit :- One Month.

Name of work:- Restoration of Rain Damage on NSLT Road Km. 25/00 to 40/810 (SH :- C/O R/wall in PCC at Km. 26/250 to 26/260)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Providing and Laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1.5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (Forty millimetre) nominal size in or under water and curingcomplete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights / depth including the cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	44.40	4646.50	Rupees Four Thousand Six Hundred Forty Six And Paise Fifty Only	Per cum	206305.00
2	Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia meters, PVC pipe extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	20.00	408.10	Rupees Four Hundred Eight And Paise Ten Only	each	8162.00
Total: -						214467.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						


 Executive Engineer
 Chowari Division
 HP PWD Chowari

(4)


(S)

SCHEDULE OF QUANTITY

Estimated Cost: - Rs.	483001.00
Earnest Money :- Rs.	10000.00
Time Limit :-	One Month.

Name of work:- Restoration of rain damage on Chowari to Jot Road Km. 0/00 to 23/00 (SH :- Hiring of excavator cum loader for removal of slips in in Km. 1/00 to 8/00)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611 and as per the direction of the Engineer-in-charge. Including carriage of materials within all leads lifts and other incidental. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3070.57	157.30	Rupees One Hundred Fifty Seven And Paise Thirty Only	Per Cum	483001.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						
Total: -						483001.00


Executive Engineer
Chowari Division
HP PWD Chowari

SCHEDULE OF QUANTITY

Estimate Cost - Rs. 96996.00
Earnest Money - Rs. 2000.00
Time Limit: - One Month

Name of Work:- A/R & M/O NR Building under Chowari Sub Division (SH:- C/o Boundary wall & P/A Painting work, P/F Sanitary item).

Sr. No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In word		
1	Excavation in foundation and trenches in all heights and depths and in all kinds of soil including saturated soils comprising of pick work, jumper work, pick jumper work, blasting work both in soft and hard rock chiseling/wedging out of rock (where blasting is prohibited) and their intermediate classification of soil setting out true to the required lines, grade, width, cutting and trimming of side slopes as shown in the drawing and if water is met within the excavation due to springs, seepage, rain and other causes it shall be removed by the suitable diversion pumping or bailing out and excavation shall be kept dry where ever so required by the contractor at his own cost as directed by the Engineer -in - Charge and disposal of all surplus excavated soil in acquired width or at an approved dumping site including its stacking leveling dressing in all leads and lifts by head load, mechanical transportation or by any other mode of transportation with all cost of labours, machineries and other incidentals to complete the work as per HPPWD specifications. Any loss to the public and private property during the course of execution and disposal of unserviceable materials shall be absolute responsibility of the contractor which shall have to be compensated by him in all cases.	1.01	400.10	Rupees Four Hundred And Paise Ten Only	Per Cubic Metre	404.00
2	Providing and laying mechanically mixed plain cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed / broken stone aggregate 40 mm (Forty millimetre) nominal size) and curing complete excluding the cost of form work in foundation and plinth as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax, GST or other taxes imposed by the Government.	3.11	5286.20	Rupees Five Thousand Two Hundred Eighty Six And Paise Twenty Only	Per Cubic Metre	16440.00
3	Second class brick work using common burnt clay building bricks in super structure above plinth level upto floor to all level in cement mortar 1:6 (one cement isto six sand) within all leads and lifts and as per direction of the Engineer-In-Charge and other incidentals. The rate including of octroi, royalty, Malkana, Tol Tax, sales tax or any other taxes imposed by the Government.	0.59	8910.30	Rupees Eight Thousand Nine Hundred Ten And Paise Thirty Only	Per Cubic Metre	5257.00
4	Half brick masonry in common clay second class bricks building bricks in super structure in cement mortar 1:4 (one cement isto four sand) within all leads and lifts and as per direction of the Engineer-In-Charge and other incidentals. The rate including of octroi, royalty, Malkana, Tol Tax, sales tax or any other taxes imposed by the Government.	15.17	1041.20	Rupees One Thousand Forty One And Paise Twenty Only	Per Square Metre	15795.00
5	15 mm (fifteen millimetre) Cement plaster in single coat on rough side of brick / stone masonry for interior plastering upto floor two level including arrises, internal rounded angles, chamfers and / or rounded angles not exceeding 80 mm (eighty millimetre) in girth and finished even and smooth Cement Mortar 1:6 (one cement isto six sand) and as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government.	22.36	259.60	Rupees Two Hundred Fifty Nine And Paise Sixty Only	Per Square Metre	5805.00


6	15 mm (fifteen millimetre) Cement plaster in single coat on fair side of brick / stone masonry for interior plastering upto floor two level including arrises, internal rounded angles, chamfers and / or rounded angles not exceeding 80 mm (eighty millimetre) in girth and finished even and smooth Cement Mortar 1:6 (one cement isto six sand) and as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax, GST or other taxes imposed by the Government.	21.41	269.90	Rupees Two Hundred Sixty Nine And Paise Ninety Only	Per Square Metre	5779.00
7	Finishing wall with water proofing cement paint of approved brand and manufacture and of required shade on undecorated wall surfaces (two coats) to give an even shade after thoroughly brushing the surface to remove all dirt and remains of loose powdered materials within all leads and lifts and as per direction of the Engineer-In-Charge and other incidentals. The rate including of octroi, royalty, Malkana, Tol Tax, sales tax, GST or any other taxes imposed by the Government.	24.53	128.10	Rupees One Hundred Twenty Eight And Paise Ten Only	Per Square Metre	3142.00
8	Providing and fixing 10 mm (ten millimetre) thick anti skid water proof stain and impact resistant heavy duty verified tiles Nitco or equivalent 600 x 600 mm x 10 mm (six hundred into six hundred millimetre into ten millimetre) manufactured of approved shade and colour in flooring, treads of steps and landings laid over 12 mm (twelve millimetre) thick cement mortar 1:3 (one cement isto three sand) jointed with cement slurry mixed with pigment to match the shade of tiles as required complete and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Octroi, Toll Tax Sales tax, GST or any other taxes imposed by the Government.	3.23	2197.00	Rupees Two Thousand One Hundred Ninety Seven Only	Per Square Metre	7096.00
9	Providing and fixing vitreous China wash basin with single hole for pillar tap with C.I. or M.S. brackets painted white including cutting holes and making good the same but excluding fittings Flat back 550 mm x 400 mm (five hundred fifty millimetre) into four hundred millimetre) and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Octroi, Toll Tax Sales tax, GST or any other taxes imposed by the Government.	2.00	7667.90	Rupees Seven Thousand Six Hundred Sixty Seven And Paise Ninety Only	Each	15336.00
10	Providing and fixing C.P.15mm (Fifteen millimetre) dia long nose brass bib tap superior type of heavy duty and as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax, GST or other taxes imposed by the Government.	1.00	1538.90	Rupees One Thousand Five Hundred Thirty Eight And Paise Ninety Only	Each	1539.00
11	Wall painting (two coats) with premium emulsion paint of Asian / Dulux / Berger paint / Nerolac paint (above Dado Skirting) of approved brand and manufacture for interior grade on undecorated concrete / stone / plastered wall surfaces to give an even shade including thoroughly brushing the surface free from mortar dropping and other foreign matter and sand papered smooth including applying of putty a required for metting the surface and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	38.29	186.60	Rupees One Hundred Eighty Six And Paise Sixty Only	Per Square Metre	7145.00
12	Painting two or more coats (excluding priming coat) on new wood and wood based surfaces with enamel paint brushing to give an even shade including cleaning the surface of dirt, dust and other foreign matter, sand papering and stoping with enamel paint white or other than white and as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax, GST or other taxes imposed by the Government.	59.31	131.30	Rupees One Hundred Thirty One And Paise Thirty Only	Per Square Metre	7787.00

SCHEDULE OF QUANTITY

Estimated Cost :- Rs. 479859.00
 Earnest Money :- Rs. 10000.00
 Time Limit :- One Month.

Name of work:- Restoration of rain damage on Shahpur Sihunta Chowari Road Km. 24/00 to 47/00 (SH :- Hiring of excavator cum loader for removal of slips in in Km. 32/500 to 37/00)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of stops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611 and as per the direction of the Engineer-in-charge. Including carriage of materials within all leads lifts and other incidental. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3050.60	157.30	Rupees One Hundred Fifty Seven And Paise Thirty Only	Per cum	479859.00
Total: -						479859.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						


 Executive Engineer
 Chowari Division
 HP Road Chowari

SCHEDULE OF QUANTITY

Name of work:- Protection Work of HPPWD Rest House Kakira Under Tehsil Bhattiyat Dist. Chamba (SH :- C/O R/wall in Wire Crate along With PCC Pushla)


Estimated Cost: - Rs.	245682.00
Earnest Money :- Rs.	5000.00
Time Limit :-	One Month.

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	26.50	559.10	Rupess Five Hundred Fifty Nine And Paise Ten Only	Per cum	14816.00
2	Providing and Laying plain cement concrete 1:4:8 (one cement is to four sand isto eight graded crushed stone aggregate with nominal mix in open foundations complete as per drawing and technical specifications clauses 802, 803, 1202 & 1203 and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	24.00	5280.70	Rupess Five Thousand Two Hundred Eighty And Paise Seventy Only	Per cum	126737.00
3	Providing and laying of boulder apron laid in wire crates with 4 mm (four millimetre) dia G.I wire conforming to IS: 280 and IS: 4826 in 100 mm x 100 mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulders weighing not less than 25 Kg (twenty five kilogram) each as per drawing technical specifications Clause 1301 and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	31.24	3052.20	Rupess Three Thousand Fifty Two And Paise Twenty Only	Per cum	95351.00
4	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	4.62	1370.02	Rupess One Thousand Three Hundred Seventy And Paise Two Only	Per cum	6329.00

(8)

(9)

5	6	408.10	Rupees Four Hundred Eight And Paise Ten Only	Per Each	2449.00
Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia meters. PVC pipe extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.				Total: -	245682.00



Executive Engineer
Chowari Division
HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 327737.00
Earnest Money :- Rs. 6600.00
Time Limit :- One Month.

Name of work:- C/O Burki Nallah to Tathi Road Km. 0/00 to 2/00 (SH :- C/O R/wall in Wire Crate at Km. 0/085 to 0/100)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In Fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	29.04	400.10	Rupees Four Hundred And Paise Ten Only	Per cum	11619.00
2	Providing and laying of boulder apron laid in wire crates with 4 mm (four millimetre) dia G.I wire conforming to IS: 280 and IS: 4826 in 100 mm x 100 mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulders weighting not less than 25 Kg (twenty five kilogram) each as per drawing technical specifications Clause 1301 and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octori, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	103.68	2910.30	Rupees Two Thousand Nine Hundred Ten And Paise Thirty Only	Per cum	301740.00
3	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	11.88	1210.30	Rupees One Thousand Two Hundred Ten And Paise Thirty Only	Per cum	14378.00
Total: -						327737.00
		Rate quoted in (%) Above / Below				
		Rate quoted in (%) in Words				



 Executive Engineer
 Chowari Division
 HP PWD Chowari

SCHEDULE OF QUANTITY

Name of Work:- Restoration of Rain Damage on Drammala Dhulara Rajain road Km. 0/00 to 9/00 (SH :- Construction of Breast wall at RD. 6/575 to 6/585 and 6/591 to 6/599).

Estimate Cost - Rs. 276110.00
Earnest Money - Rs. 5600.00
Time Limit:- One Month

Sr. No.	Description	Quantity	Rate		Unit	Amount	
			In Fig.	In word			
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	21.08	400.10	Rupess Four Hundred And Paise Ten Only	Per Cubic Metre	8434.00	
2	Providing and Laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1:5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (Forty millimetre) nominal size in or under water and curingcomplete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all hights / depth including the cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	54.00	4682.30	Rupess Four Thousand Six Hundred Eighty Two And Paise Thirty Only	Per Cubic Metre	252844.00	
3	Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia meters, PVC pipe extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	36	412.00	Rupess Four Hundred Twelve Only	Each	14832.00	
Rate quoted in (%) Above / Below						Total: -	276110.00
Rate quoted in (%) in Words							


 Executive Engineer
 Chowari Division
 HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 442800.00
 Earnest Money :- Rs. 90000.00
 Time Limit :- One Month.

Name of work:- Restoration of rain damage on various Road Under Kaktra Sub Division (SH :- Removal of slips on various Road under Mail Section)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611 and as per the direction of the Engineer-in-charge. Including carriage of materials within all leads lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2815.00	157.30	Rupees One Hundred Fifty Seven And Paise Thirty Only	Per cum	442800.00
Total: -						442800.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						


 Executive Engineer
 Chowari Division
 HP PWD Chowari


(11)

SCHEDULE OF QUANTITY

Name of Work:- Restoration of Rain Damage on Dukhar to Morthu road Km. 0/00 to 8/00 (SH :- Construction of Breast wall at RD. 0/840 to 0/885).

Estimate Cost - Rs. 240009.00
Earnest Money - Rs. 4800.00
Time Limit: - One Month

Sr. No.	Description	Quantity	Rate		Unit	Amount	
			In Fig.	In word			
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deteriorous materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	28.35	400.10	Rupees Four Hundred And Paise Ten Only	Per Cubic Metre	11343.00	
2	Providing and Laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1:5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (Forty millimetre) nominal size in or under water and curingcomplete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all hights / depth including the cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	45.45	4642.30	Rupees Four Thousand Six Hundred Forty Two And Paise Thirty Only	Per Cubic Metre	210993.00	
3	Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia meters, PVC pipe extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	43	411.00	Rupees Four Hundred Eleven Only	Each	17673.00	
Rate quoted in (%) Above / Below							
Rate quoted in (%) in Words						Total: -	240009.00


 Executive Engineer
 Chowari Division
 HP PWD, Chowari

(62)


SCHEDULE OF QUANTITY

Name of Work:- Construction of link road to Naag Bhitru road Km. 0/00 to 2/580 (SH :- Construction of Retaining wall with PCC Pushra at RD. 0/870 to 0/879).

Estimate Cost - Rs. 479640.00
 Earnest Money - Rs. 9600.00
 Time Limit: - One Month

Sr. No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	37.80	400.10	Rupees Four Hundred And Paise Ten Only	Per Cubic Metre	15124.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1:5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (Forty millimetre) nominal size in or under water and curingcomplete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all hights / depth including the cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	92.75	4740.30	Rupees Four Thousand Seven Hundred Forty And Paise Thirty Only	Per Cubic Metre	439663.00
3	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	12.85	1230.40	Rupees One Thousand Two Hundred Thirty And Paise Forty Only	Per Cubic Metre	15811.00
4	Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia meters, PVC pipe exetnding through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	22	411.00	Rupees Four Hundred Eleven Only	Each	9042.00
Total:-						479640.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						

(13)


 Executive Engineer
 Chowari Division
 HP PWD Chowari

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damage on Chowari to Jot Road Km. 0/00 to 23/00 (SH :- C/O R/wall at Rd. 1/060 to 1/065)

Estimate Cost - Rs. 96008.00
 Earnest Money - Rs. 2000.00
 Time Limit:- One Month

Sr. No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORO technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	6.45	400.10	Rupess Four Hundred And Paise Ten Only	Per Cubic Metre	2581.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1:5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (Forty millimetre) nominal size in or under water and currimcomplete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights / depth including the cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	17.85	4716.75	Rupess Four Thousand Seven Hundred Sixteen And Paise Seventy Five Only	Per Cubic Metre	84194.00
3	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORO technical specification clause 1204.3.8 or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	4.50	1230.10	Rupess One Thousand Two Hundred Thirty And Paise Ten Only	Per Cubic Metre	5535.00
4	Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia meters, PVC pipe extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	9	410.90	Rupess Four Hundred Ten And Paise Ninety Only	Each	3698.00
Total:-						96008.00
Rate quoted in (%) Above / Below Rate quoted in (%) in Words						

(14)


 Executive Engineer
 Chowari Division
 HP PWD Chowari

SCHEDULE OF QUANTITY

Estimate Cost - Rs. 317412.00
Earnest Money - Rs. 6400.00
Time Limit: - One Month

Name of Work:- Construction of stage at Govt. Post Graduate College at Chowari in Dist. Chamba (SH:- C/o R/wall & P/F M.S BP sheet).

Sr. No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	18.62	400.10	Rupees Four Hundred And Paise Ten Only	Per Cubic Metre	7450.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1:5:10 (one cement iso five sand iso ten graded) crushed stone aggregate 40 mm (Forty millimetre) nominal size in or under water and curingcomplete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights / depth including the cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	49.20	4610.30	Rupees Four Thousand Six Hundred Ten And Paise Thirty Only	Per Cubic Metre	226827.00
3	Government Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	4.95	1210.30	Rupees One Thousand Two Hundred Ten And Paise Thirty Only	Per Cubic Metre	5995.00
4	Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia meters. PVC pipe extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 and as per direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	15	411.00	Rupees Four Hundred Eleven Only	Each	6165.00

5	Providing and fixing M.S. BP Sheet 1.66 mm to 2 mm (one point sixty six to two millimetre) thick in eaves board / fascia / soffits / ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete as per the instruction of Engineer-in-charge (Base members of steel work shall be measured & paid separately) and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	35.53	1866.10	Rupees One Thousand Eight Hundred Sixty Six And Paise Ten Only	Per Square Metre	66303.00
6	Painting two coats (excluding priming cost) on new steel and other metal surfaces with enamel paint brushin to give an even shade including cleaning the surface of all dirt, dust and other foreign matters Enamel paint other than white and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	35.53	131.50	Rupees One Hundred Thirty One And Paise Fifty Only	Per Square Metre	4672.00
Total						317412.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						


 Executive Engineer
 Chowari Division
 HPWD, Chowari


SCHEDULE OF QUANTITY

Name of Work:- Restoration of Rain Damage on Link Road To Village Fakrodu Km. 0/00 to 2/810 (SH :- C/O R/Wall at Rd. 0/345 to 0/351)

Estimate Cost - Rs. 270492.00
 Earnest Money - Rs. 5500.00
 Time Limit: - One Month

(16)

Sr. No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORDD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	23.94	400.10	Rupees Four Hundred And Paise Ten Only	Per Cubic Metre	9578.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1:5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (Forty millimetre) nominal size in or under water and curingcomplete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all hights / depth including the cost of form work complete in all respect as per the drawing and technical specifications clause 802. 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	52.44	4646.30	Rupees Four Thousand Six Hundred Forty Six And Paise Thirty Only	Per Cubic Metre	243652.00
3	Malkana, toll tax, sale tax, GST or other taxes imposed by the Government. Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORDD technical specification clause 1204.3.8 or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	8.28	1240.90	Rupees One Thousand Two Hundred Forty And Paise Ninety Only	Per Cubic Metre	10275.00
4	Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia meters, PVC pipe extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	17	411.00	Rupees Four Hundred Eleven Only	Each	6987.00
Total: -						270492.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						


 Executive Engineer
 Chowari Division
 HP PWD Chowari

SCHEDULE OF QUANTITY

Estimate Cost - Rs. 362542.00
Earnest Money - Rs. 7300.00
Time Limit:- One Month

(17)

Name of Work:- Restoration of Rain damage on Kamaladi Bakloh Chatasani road Km. 0/00 to 5/00 (SH:- Construction of wire crate Alongwith PCC Pushtha at RD. 3/830 to 3/840).

Sr. No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	82.50	400.30	Rupees Four Hundred And Paise Thirty Only	Per Cubic Metre	33025.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1.5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (Forty millimetre) nominal size in or under water and curingcomplete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights / depth including the cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	26.40	4632.30	Rupees Four Thousand Six Hundred Thirty Two And Paise Thirty Only	Per Cubic Metre	122293.00
3	Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia meters, PVC pipe extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	9	355.10	Rupees Three Hundred Fifty Five And Paise Ten Only	Each	3196.00
4	Providing and laying of boulder apron laid in wire crates with 4 mm (four millimetre) dia G.I wire conforming to IS: 280 and IS: 4826 in 100 mm x 100 mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulders weighting not less than 25 Kg (twenty five kilogramme) each as per drawing technical specifications Clause 1301 and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	62.52	3001.40	Rupees Three Thousand One And Paise Forty Only	Per Cubic Metre	187648.00

5	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	13.20	1240.90	Rupces One Thousand Two Hundred Forty And Paise Ninety Only	Per Cubic Metre	16380.00
	Rate quoted in (%) Above / Below					
	Rate quoted in (%) in Words					
					Total: -	362542.00


 Executive Engineer
 Chowari Division
 HP PWD, Ghawari

SCHEDULE OF QUANTITY

Name of Work:- Construction of link road to Naag Bintaru road Km. 0/00 to 2/580 (SH :- Construction of Retaining wall in wire crate with PCC Pushata at RD. 0/690 to 0/709).

Estimate Cost - Rs. 485013.00
 Earnest Money - Rs. 9700.00
 Time Limit: - One Month

Sr. No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	24.75	400.10	Rupees Four Hundred And Paise Ten Only	Per Cubic Metre	9902.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1.5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (Forty millimetre) nominal size in or under water and curingcomplete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights / depth including the cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	34.56	4740.30	Rupees Four Thousand Seven Hundred Forty And Paise Thirty Only	Per Cubic Metre	163825.00
3	Malkana, toll tax, sale tax, GST or other taxes imposed by the Government. Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	28.80	1230.40	Rupees One Thousand Two Hundred Thirty And Paise Forty Only	Per Cubic Metre	35436.00
4	Providing and laying of boulder apron laid in wire crates with 4 mm (four millimetre) dia G.I wire conforming to IS: 280 and IS: 4826 in 100 mm x 100 mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulders weighing not less than 25 Kg (twenty five kilogram) each as per drawing technical specifications Clause 1301 and as per direction of Engineer In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	90.00	3065.00	Rupees Three Thousand Sixty Five Only	Per Cubic Metre	275850.00
Total: -						485013.00

Rate quoted in (%) Above / Below
 Rate quoted in (%) in Words

(Signature)
 Executive Engineer
 Chowari Division
 HP PWD Chowari

(19)

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 161280.00
Earnest Money :- Rs. 5300.00
Time Limit :- One Month.


Name of work:- Restoration of rain damage on Hunera to Kahri Kothi road Km. 0/00 to 2/420 (SH :- Removal of slips on various at RD. 0/0 to 2/300)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611 and as per the direction of the Engineer-in-charge. Including carriage of materials within all leads lifts and other incidental. The rate including the octori, royalty, Malkana. toll tax. sale tax. GST or other taxes imposed by the Government.	1025.30	157.30	Rupees One Hundred Fifty Seven And Paise Thirty Only	Per cum	161280.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						
Total: -						161280.00


Executive Engineer
Chowari Division
HP Road Chowari

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damage on Langhi to Daroni road Km. 0/00 to 3/225 (SH :- Removal of slips on various at RD. 0/0 to 3/200)						Estimated Cost: - Rs.	479776.00
						Earnest Money :- Rs.	9600.00
						Time Limit :-	One Month.
Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount	
			In fig.	In words			
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611 and as per the direction of the Engineer-in-charge. Including carriage of materials within all leads lifts and other incidental. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3050.07	157.30	Rupees One Hundred Fifty Seven And Paise Thirty Only	Per cum	479776.00	
Rate quoted in (%) Above / Below							
Rate quoted in (%) in Words						Total: -	479776.00



 Executive Engineer
 Chowari Division
 HP Chowari

SCHEDULE OF QUANTITY

Name of Work:- Restoration of Rain Damage on Patka Dallahouse road km. 0/00 to 32/00 (SH :- C/O R/Wall at Rd. 30/548 to 30/554)

Estimate Cost - Rs. 291456.00
 Earnest Money - Rs. 5900.00
 Time Limit: - One Month

Sr. No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	26.16	559.10	Rupess Five Hundred Fifty Nine And Paise Ten Only	Per Cubic Metre	14626.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1.5:10 (one cement iso five sand iso ten graded) crushed stone aggregate 40 mm (Forty millimetre) nominal size in or under water and curing complete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights / depth including the cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	54.54	4750.30	Rupess Four Thousand Seven Hundred Fifty And Paise Thirty Only	Per Cubic Metre	259081.00
3	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	7.74	1390.40	Rupess One Thousand Three Hundred Ninety And Paise Forty Only	Per Cubic Metre	10762.00
4	Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia meters, PVC pipe extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	17	411.00	Rupess Four Hundred Eleven Only	Each	6987.00
Total:-						291456.00
Rate quoted in (%) Above / Below Rate quoted in (%) in Words						


 Executive Engineer
 Chowari Division
 PPRWD Chowari

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damage on Parshiyara to Kathiyadi road Km. 0/00 to 5/00 (SH :- Removal of slips on various at RD. 0/0 to 4/860)

Estimated Cost: - Rs.	493574.00
Earnest Money :- Rs.	10000.00
Time Limit :-	One Month.

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611 and as per the direction of the Engineer-in-charge. Including carriage of materials within all leads lifts and other incidental. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3137.79	157.30	Rupees One Hundred Fifty Seven And Paise Thirty Only	Per cum	493574.00
Total:-						493574.00

Rate quoted in (%) Above / Below
Rate quoted in (%) in Words


 Executive Engineer
 Chowari Division
 HP Road Chowari

SCHEDULE OF QUANTITY

Name of work: - A/R & M/O Various road under HP PWD Sub Division Sihunta (SH: - Painting and Lettering / Writing of Sign boards, Kilometers Stone
Stone culvert Etc.).

Estimated Cost: - Rs. 187571.00
Earnest Money :- Rs. 4000.00
Time Limit :- One Month

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount	
			In fig.	In words			
1	Removing old paint from steel and other metal surfaces even with paint remover of approved brand and manufacture complete or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	285.00	81.50	Rupees Eighty One And Paise Fifty Only	Per Square Metre	23228.00	
2	Painting one coat (excluding priming coat on previously painted concrete / masonry / plastered surface with enamel paint of approved brand and manufacture for use to give an even shade thoroughly cleaning the surface to remove all dirt, dust and other foreign matter etc including sand paper smooth complete or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	285.00	92.40	Rupees Ninety Two And Paise Forty Only	Per Square Metre	26334.00	
3	Painting one coat (excluding priming coat on previously painted steel and other metal surface to remove all dirt, dust and other foreign matter etc including sand paper smooth complete or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	285.00	98.10	Rupees Ninety Eight And Paise Ten Only	Per Square Metre	27959.00	
4	Writing letters of figures on any surface with synthetic enamel paint (other than white) stop . commas, hyphens and the like not to be measured and paid separately) block letters, indian letters / figures complete or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	35500	3.10	Rupees Three And Paise Ten Only	Per Square Metre	110050.00	
Rate quoted in (%) Above / Below						Total: -	187571.00
Rate quoted in (%) in Words							



 Executive Engineer
 Chowari Division
 H.P.P.V.D. Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 455100.00
 Earnest Money :- Rs. 9200.00
 Time Limit :- One Month.

Name of work:- Restoration of rain damage on various road under Chowari sub division (SH :- Hiring of Tipper and for Shifting of Muck Debris various roads under Raipur section)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of tipper having capacity 10.50 (ten decimal five Zero) cubic metre for carriage of all type maerial up to any leads and lifts as per direction and entire satisfaction of Engineer in charge. Any loss to public/private poperty or any accident etc happened during the course of said period shall be absolute responsibility of the trucker owner which shall be fully compensated by the contractor in all cases. The fuel and operational staff for truck will be provided by the owner. The repair and spare ,watch &ward of machine also borne by the contractor /Owner. The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge. The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	410.00	1110.00	Ruppes One Thousand One Hundred Ten Only	Per Hour	455100.00
Total:-						455100.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						


 Executive Engineer
 Chowari Division
 HPWD Chowari

(22)

(22)

SCHEDULE OF QUANTITY

Name of Work:- Restoration of Rain damage on Chowari Mandhiar Baloh Fagot road Km. 0/00 to 13/330 (SH :- Construction of Retaining wall at RD. 7/840 to 7/849.50).

Estimate Cost - Rs. 462046.00
Earnest Money - Rs. 9300.00
Time Limit:- One Month

Sr. No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORR technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	30.21	400.10	Rupees Four Hundred And Paise Ten Only	Per Cubic Metre	12087.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1:5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (Forty millimetre) nominal size in or under water and curingcomplete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights / depth including the cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	91.77	4610.90	Rupees Four Thousand Six Hundred Ten And Paise Niney Only	Per Cubic Metre	423142.00
3	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORR technical specification clause 1204.3.8 or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	13.11	1230.40	Rupees One Thousand Two Hundred Thirty And Paise Forty Only	Per Cubic Metre	16131.00
4	Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia meters, PVC pipe extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	26	4111.00	Rupees Four Hundred Eleven Only	Each	10686.00
Total:-						462046.00

Rate quoted in (%) Above / Below

Rate quoted in (%) in Words


 Executive Engineer
 Chowari Division
 P. P. Chowari

(25)
(26)

SCHEDULE OF QUANTITY


(26)

Estimate Cost - Rs. 459771.00
Earnest Money - Rs. 9200.00
Time Limit: - One Month

Name of Work:- Restoration of Rain damage on Link road from Luhni to Bharana da Bassa Km. 0/00 to 1/405 (SH :- Construction of Retaining wall at RD. 0/210 to 0/217).

Sr. No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	34.93	400.10	Rupess Four Hundred And Paise Ten Only	Per Cubic Metre	13975.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1:5:10 (one cement iso five sand iso ten graded) crushed stone aggregate 40 mm (Forty millimetre) nominal size in or under water and currimcomplete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all hights / depth including the cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	90.30	4605.10	Rupess Four Thousand Six Hundred Five And Paise Ten Only	Per Cubic Metre	415841.00
3	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	10.50	1230.40	Rupess One Thousand Two Hundred Thirty And Paise Forty Only	Per Cubic Metre	12919.00
4	Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia meters, PVC pipe extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	23	411.00	Rupess Four Hundred Eleven Only	Each	9453.00

5	Providing and fixing Dowle Bar of 25mm dia including drilling holes and plugging the bars with cement grout as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	20.00	379.15	Rupees Three Hundred Seventy Nine And Paise Fifteen Only	Per Running Metre	7583.00
	Rate quoted in (%) Above / Below				Total: -	459771.00
	Rate quoted in (%) in Words					


 Executive Engineer
 Chowari Division
 HP PWD, Chowari

(27)

SCHEDULE OF QUANTITY

Name of Work:- Restoration of Rain Damage on Patka Dalthousie road km. 0/00 to 32/00 (SH :- C/O R/Wall at Rd. 35/980 to 35/989)

Estimate Cost - Rs. 211424.00
 Earnest Money - Rs. 4300.00
 Time Limit: - One Month

Sr. No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	26.16	400.10	Rupees Four Hundred And Paise Ten Only	Per Cubic Metre	10467.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1:5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (Forty millimetre) nominal size in or under water and curingcomplete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights / depth including the cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	39.80	4663.40	Rupees Four Thousand Six Hundred Sixty Three And Paise Forty Only	Per Cubic Metre	185603.00
3	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	7.74	1240.30	Rupees One Thousand Two Hundred Forty And Paise Thirty Only	Per Cubic Metre	9600.00
4	Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia meters, PVC pipe extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	14	411.00	Rupees Four Hundred Eleven Only	Each	5754.00
Total:-						211424.00

Rate quoted in (%) Above / Below
 Rate quoted in (%) in Words

(Signature)
 Executive Engineer
 Chowari Division
 HP PWD Chowari

HP PWD Chowari

SCHEDULE OF QUANTITY


Name of Work:- Construction of link road to Naag Birturu road Km. 0/00 to 2/580 (SH :- Construction of Retaining wall with PCC Pushita at RD. 0/855 to 0/862).

Estimate Cost - Rs. 478901.00
 Earnest Money - Rs. 9600.00
 Time Limit: - One Month

Sr. No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	37.80	400.10	Ruppes Four Hundred And Paise Ten Only	Per Cubic Metre	15124.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1.5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (Forty millimetre) nominal size in or under water and curingcomplete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights / depth including the cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	92.75	4740.30	Ruppes Four Thousand Seven Hundred Forty And Paise Thirty Only	Per Cubic Metre	439663.00
3	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	12.25	1230.40	Ruppes One Thousand Two Hundred Thirty And Paise Forty Only	Per Cubic Metre	15072.00
4	Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia meters, PVC pipe extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	22	411.00	Ruppes Four Hundred Eleven Only	Each	9042.00
Total:-						478901.00

Rate quoted in (%) Above / Below

Rate quoted in (%) in Words


 Executive Engineer
 Chowari Division
 HP PWD Chowari

22

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damage on Link road to village Nahana Km. 0/00 to 4/100 (SH :- Removal of slips on various at RD. 0/0 to 4/100)

Estimated Cost :- Rs. 482052.00
 Earnest Money :- Rs. 9700.00
 Time Limit :- One Month.

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611 and as per the direction of the Engineer-in-charge. Including carriage of materials within all leads lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3064.54	157.30	Rupees One Hundred Fifty Seven And Paise Thirty Only	Per cum	482052.00
Total: -						482052.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						


 Executive Engineer
 Chowari Division
 HP BWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 497088.00
 Earnest Money :- Rs. 10000.00

Time Limit :- One Month.

Name of work:- Restoration of rain damage on Dukhar to Morthu road Km. 0/00 to 8/00 (SH :- Removal of slips on various at RD. 4/0 to 6/640)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611 and as per the direction of the Engineer-in-charge. Including carriage of materials within all leads lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3160.13	157.30	Rupees One Hundred Fifty Seven And Paise Thirty Only	Per cum	497088.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						
Total: -						497088.00



 Executive Engineer
 Chowari Division
 HP PWD Chowari

SCHEDULE OF QUANTITY

Name of Work:- Restoration of Rain damage on Balana to Balli road Km. 0/00 to 5/490 (SH :- Construction of Retaining wall at RD. 5/021 to 5/026).

Estimate Cost - Rs. 432087.00
Earnest Money - Rs. 8700.00
Time Limit: - One Month

Sr. No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	32.67	400.10	Rupees Four Hundred And Paise Ten Only	Per Cubic Metre	13071.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1.5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (Forty millimetre) nominal size in or under water and curingcomplete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all hights / depth including the cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	87.18	4592.10	Rupees Four Thousand Five Hundred Ninety Two And Paise Ten Only	Per Cubic Metre	400339.00
3	Back filling with granular material behind abutments; return walls, wing walls and retaining walls complete as per drawings and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	6.44	1240.90	Rupees One Thousand Two Hundred Forty And Paise Ninety Only	Per Cubic Metre	7991.00
4	Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia meters. PVC pipe extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	26	411.00	Rupees Four Hundred Eleven Only	Each	10686.00
Total:-						432087.00
		Rate quoted in (%) Above / Below				
		Rate quoted in (%) in Words				



 Executive Engineer
 Chowari Division
 Howari

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damage on Dugred to Naloh road Km. 0/00 to 5/630 (SH :- Removal of slips on various at RD. 2/0 to 5/00)

Estimated Cost: - Rs.	492443.00
Earnest Money :- Rs.	100000.00
Time Limit :-	One Month.

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611 and as per the direction of the Engineer-in-charge. Including carriage of materials within all leads lifts and other incidental. The rate including the octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	3130.60	157.30	Rupees One Hundred Fifty Seven And Paise Thirty Only	Per cum	492443.00
Total: -						492443.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						



 Executive Engineer
 Chowari Division
 HP PWD, Chowari

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damage on Gagoi to Jambal road Km. 0/00 to 3/00 (SH :- Removal of slips on various at RD. 0/400 to 2/500)

Estimated Cost: - Rs.	97715.00
Earnest Money :- Rs.	10000.00
Time Limit :-	One Month.

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611 and as per the direction of the Engineer-in-charge. Including carriage of materials within all leads lifts and other incidental. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	621.20	157.30	Rupees One Hundred Fifty Seven And Paise Thirty Only	Per cum	97715.00
Total:-						97715.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						


 Executive Engineer
 Chowari Division
 H.P.W.D. Chowari