

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

No. PW-DPD-CB-Tender/2025-26- 21412
To

Dated:- 25.3.2026

The Executive Engineer(IT) Cell,
HP.PWD,Nirman Bhawan, Nigam Vihar,
HP.PWD,Shimla-2.


Subject: Regarding publication of Tender notice on department website.

Sir,

With reference to the notification issued by the Secretary (PW) to the Government of Himachal Pradesh No. PBW(B) A(3)I/2024 dated 03/01/2024 , further corrigendum on dated 08/01/2025 and Under Secretary (PW) to the Government of Himachal Pradesh No. PWD-B-A0(3)/1/2024-241828 dated 02-02-2026 . Enclosed please find herewith the copy of tender notice for the publishing on departmental website.

Certified that the work mentioned in the Tender Notice are urgenet in nature.

DA:- As above


Executive Engineer,
Dharampur Division,
HP.PWD. Dharampur.

H.P P W D NOTICE INVITING TENDER

The **percentage** rate off line tender notice on the form 6 & 8 are invited by the Executive Engineer, Dharampur Division, HPPWD Dharampur on behalf of Governor of HP for the following works from the approved and eligible contractor enlisted in HPPWD.

TENDER SCHEDULE:

- | | | |
|-----------|--|--------------------------------------|
| 1 | Date and time of receipt of application for the tender form : | 01-04-2026 -2026 upto 4.00 PM |
| 2 | Date and time of issue of tender form : | 02-04-2026 upto 4.00 PM |
| 3 | Date and time of receipt of tenders: | 04-04 -2026 upto 11.00 AM |
| 4. | Date and time of opening of tenders: | 04-04 -2026 upto 11.30 AM |


The tender form will be issued against cash payment (non refundable), the **earnest money in the shape of NSC/FDR/Deposit** at call of any Post Office/Bank in H.P duly pledged in the name of the Executive Engineer, Dharampur Division, HPPWD Dharampur must accompany with each tender. Conditional tender and tender received without earnest money will summarily be rejected.

Sr. No	Name of Works	Estimated Cost (in Rs)	EMD (in Rs.)	Time Limit	Cost of Tender Form	Eligible class of Contractor
01.	Restoration of Rain damages on various roads under Baroti section HPPWD Sub-Division Mandap(SH:- Deployment/Hiring of Tipper for removal of land slide/slips)	1,10,250	2,300/-	Two months	350/-	"D"
02	Restoration of Rain damages on various roads under Mandap section HPPWD Sub-division Mandap(SH:- Hiring of excavator cum loader and Hiring of Tipper for removal of land lside/slips)	1,41,750/-	2,900/-	Two Months	350/-	"D"
03	Restoration of rain damages on JNSG road and Baroti Rakhera KandapattanRoad HPPWD Sub-Division Dharampur (SH:- Deployment/Hiring of excavator cum loader and hiring of tipper for removal of alnd slide/slips)	3,49,250/-	7,000/-	Two Months	350/-	"D"
04	Restoration of Rain damages on Dharampur to Satrehar via Mathi Banwar road Km. 0/0 to 5/500(SH:- Hiring of Excavator cum loader for removal of alnd slide/slips)	1,53,000/-	3,100/-	Two Months	350/-	"D"
05	R/R Dmages on Sajao to Chatryana Road Km. 0/00 to 2/15(SH:- C/O R/wall and steel truss element for the Rain Shelter, C/O PCC R/wall for the protection of Rain Shelter) PDNA	2,66,936/-	6,000/-	One months	350/-	"D"
06	R/R Damges on Sarkaghat Tihra Sandhole Road Km. 59/400 to 98/420(SH:- C/O Wire crate at RD 89/660 to 89/637.50)PDNA	4,80,735/-	10,000/-	Two months	350/-	"D"
07	R/R Damges on Bharouri to Kot Road Km. 0/0 to 2/500(SH:- Repair of Pot holes at RD 0/0 to 2/500) PDNA	96,986/-	2,000/-	Two Months	350/-	"D"
08	C/O Link Road Harizen Basti Saklana Km. 0/00 to 0/500(SH:- P/L C.C. Pavement at RD 0/00 to 0/087) BASP	1,99,071/-	4,000/-	Two Months	350/-	"D"
09	R/R Damages on Upper Balh Km. 0/00 to 0/870 (SH:- C/O R/wall in wire crate at RD 0/421 to 0/436).	4,91,400/-	10,000/-	Two Months	350/-	"D"
10	C/O Shahid Capt. Deepak Guleria Govt. Sr.Sec. School Cholthra Tehsil Sarkaghat Distt. Mandi (HP) (SH:- Repair & Maintenance of Basket Ball court) DC Deposit	1,98,550/-	4,000/-	Two Months	350/-	"D"
11	Annual Repair and Maintenance on	50,055/-	1,200/--	Two	350/-	"D"

	onHukkal Chatter Road (SH:- Painiting on Railing and wheel guard)					
12	Annual Repair and Maintenance on 75.00 mtrs span bridge over Sun Khad (SH:- Painiting on Railing and Wheel Guard)	52,875/-	1,200/-	Two Months	350/-	"D"

Terms and Conditions:-

- 1 The contractors/firms should posses the following documents at the time of application (Photocopy to be attached):- i) Latest renewal of enlistment. (ii) PAN (Permanent Account No.), (iii) Copy of GST registration. (iv) Copy of EPF Number, (v) Owned/Hired documentary proof of the machinery required for the work. (Vi) Cost of tender, (vii) Earnest Money.
2. The Contractors/firms are required to quote their rates both in figures and words, failing which under-signed reserve the right to accept/reject any or all tenders without assigning any reasons.
3. 1% cess charges on the amount of work awarded will be recovered from the contractor and the contractor has to get registered with Labour Officer-cum-Registering Officer-cum- Cess Collector within one month from the issue of the award letter.
4. The contractor will give affidavit that he has not two or more works in hand for execution, failing which the application shall be rejected.
5. The offer of the tender shall remain valid upto 60 days after the opening.
6. The Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason(s).



Executive Engineer,
Dharampur Division,
HP.PWD, Dharampur,
Distt: Mandi (H.P).

No.PW-DPD-CB-Tender/2025-26/

Dated:-

Copy forwarded to the following for information and necessary action to:-

1. The Chief Engineer , Hamirpur Zone HP.PWD ,Hamirpur H.P.
2. The Superintending Engineer Dharampur Circle HP.PWD Dharampur .
3. The Executive Engineer (IT) O/o Engineer-In Chief HPPWD Shimla through email-eeict-pwd-shi@hp.gov.in & ee-pwd-hp@nic.in for uploading the same on HPPWD web portal.
4. Notice Board.
5. A/B, D/B. Of this office.


Executive Engineer,
Dharampur Division,
HP.PWD, Dharampur,
Distt: Mandi (H.P).

136

1

DRAFT SCHEDULE OF QUANTITY

Work :- Restoration of rain damages on various roads under Baroti section HPPWD Sub Division Mandap
Employment /Hiring of Tipper for removal of land slide /slips)

Estimated cost :-		110250
Earnest Money :-		2300
Time Limit Two Months		
In Figure	Rates	
	In words	Unit
4	5	6
3150.00	Rupees Three Thousand One Hundred Fifty Only	Per Day
3	35.00	7
Total		110250

Description of item/Sub Head	Quantity	Rates		Unit	Amount
		In Figure	In words		
2	35.00	3150.00	Rupees Three Thousand One Hundred Fifty Only	Per Day	110250
<p>Hiring of tipper for disposal of excavated material from cutting having capacity of 5.50 cum (Five point five cubic metre) Per trip and minimum 70 Km (Seventy kilometre) of trip per day. The contractor / Owner of tipper shall bear the expensive of P.O.L charges, repair of machineries. Any accident and other damages to private and Govt. property occur during the working hours is the whole responsibility of the contractor and debris disposal with in all leads lifts and technical specifications as per the direction by the Engineer-in-Charge and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.</p>					

Draft schedule of quantity approved
RS-110250/- Videsy No.136/2025-26

Executive Engineer,
Dharampur Division
H.P.P.W.D., Dharampur

[Signature]

135
54

2

DRAFT SCHEDULE OF QUANTITY

Work :- Restoration of rain damages on various roads under Mandap Section HPPWD Sub Division
p (Sh:-Deployment/Hiring of Tipper for removal of land slide /slips)

Estimated cost :- 141750
Earnest Money:- 2900

Description of item/Sub Head	Quantity	Rates		Unit	Amount
		In Figure	In words		
		Time Limit Two Months			
2 Hiring of tipper for disposal of excavated material from cutting having capacity of 5.50 cum (Five point five cubic metre) Per trip and minimum 70 Km (Seventy kilometre) of trip per day. The contractor / Owner of tipper shall bear the expensive of P.O.L charges, repair of machineries. Any accident and other damages to private and Govt. property occur during the working hours is the whole responsibility of the contractor and debris disposal with in all leads lifts and technical specifications as per the direction by the Engineer-in-Charge and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3 45.00	4 3150.00	5 Rupees Three Thousand One Hundred Fifty Only	6 Per Day	7 141750
				Total	141750

*Draft schedule of quantity approved
RS-141750/- Videsa No: 135/202526*

[Signature]
Executive Engineer,
Dharampur Division
H.P.P.W.D., Dharampur

164
74

18

3

DRAFT SCHEDULE OF QUANTITY

Name of Work :- Restoration of rain damages on JNSG Road and Baroti Rakhera Kandapattan Road HPPWD Division Dharampur (SH :- Deployment/Hiring of Excavator cum loader and Hiring of Tipper for removal of slide/slips)

Description of item/Sub Head	Quantity	Estimated cost :-		Unit	Two Months Amount
		Earnest Money:-			
		In Figure	In words		
2	3	4	5	6	7
Deployment/Hiring of Excavator-cum-loader 0.90cum bucket capacity @ 20.00 cubic metre per hour for removal of slips, Road side berms, katcha drain and boulder in all kinds of soils including rocky portion and saturated soil and disposing of all excavated earth of unserviceable material from the road surface including cost of fuel oil lubricant and wages of operating staff. Any repair /breakage during operation will be carried out by the contractor / owner at his own risk. Shifting of machinery from one place to another place will be absolute responsibility of the contractor and no payment will be made for the same only actual working hours will be accounted for the payment. The rate should be inclusive of POL and all other charges. The payment will be made for the exact hour for which the machine will work at site. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Govt.	250.00	1275.00	Rupees One Thousand Two Hundred SeventyFive Only	Per Hours	318750
Deployment/Hiring of tipper for disposal of excavated material from cutting having capacity of 150 cubic ft Per trip and minimum 70 Km of trip per day. The contractor / Owner of tipper shall bear the expensive of P.O.L charges, repair of machineries. Any accident and other damages to private and Govt. property occur during the working hours is the whole responsibility of the contractor and debris disposal with in all leads and lifts as per direction of Engineer - in- Charge with in all leads and lifts. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Govt	10.00	3050.00	Rupees Three Thousand Fifty Only	Perdays	30500
Total:-					349250

Draft schedule of quantity approved

RS-349250-Vide SN/164.

2025-26

Executive Engineer,
Dharampur Division
H.P.W.D., Dharampur

DRAFT SCHEDULE OF QUANTITY

Work :- Restoration of rain damages on Dharampur to Satrehar via Mathi Banwar road km 0/0 to
 SH:- Hiring of Excavator Cum loader for removal of land slides /slips)

Description of item/Sub Head	Quantity	Rates:		Unit	Amount
		In Figure	In words		
		Time Limit Two Months			
2 Deployment / Hiring of Excavator cum loader 0.90 cum(Zero point nine zero cubic metre) bucket capacity @ 20.00(Twenty) cubic metre per hour for removal of slips, Road side berms, katch drain and boulder in all kinds of soils including rocky portion and saturated soil and disposing of all excavated earth of unserviceable materials from the road surfaceIncluding cost of fuel oil lubricant and wages of staff , any repair /breakage during operation will be carried out by the contractor /owner at his own risk .shifting of machinery from one place to another place will be absolute responsibility of the contractor and no payment will be made for same only actual working hours will be accounted for the payment. The rate should be inclusive of POL and all other charges. The payment will be made for the exact hour for which the machine will work at site.The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3	4 1275.00	5 Rupees One Thousand Two Hundred SeventyFive Only	6 Per Hour	7 153000
Total					153000

Draft schedule of quantity approved
RS.153000 / Under No.167
2022

Executive Engineer,
 Dharampur Division
 H.P.P.W.D., Dharampur.

4

10

167/77

236/83

09

DRAFT SCHEDULE OF QUANTITY

Name of Work :- R/R Damages on Link Road Upper Bath Km 0/00 to 0/870(SH :- C/O Wire crate wall at RD

o 0/436)

Description of item/Sub Head	Quantity	Estimated cost :-		Unit	Two Months Amount
		Earnest Money:-			
		In Figure	In words		
	3	4	5	6	7
2 Earthwork in excavation in all kinds classification of soil in foundation of structures upto all depth/ height as per drawing and technical specification Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead and lifts dressing of sides and bottom and back filling with approved material and disposal of all surplus excavated earth in specified site and as per direction of Engineer-in-charge complete. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	30.24	250.00	Rupees Two Hundred Fifty Only	Per Cubic Metre	7560
Providing and laying boulder apron laid in wire crates with 4 mm diameter G.I. wire confirming to IS:280 and IS:4826 in 100mm x 100mm mesh (woven diagonally) including 10% extra for laps and joints laid with stones boulders weighting not less than 25 kg. (twenty five kilogramme) each as per drawing and technical specifications clause 1301 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	151.20	3200.00	Rupees Three Thousand Two Hundred Only	Per Cubic Metre	483840
Total:-					491400

Dmt amount approved for Rs 491400/- vide Sr no 236

Executive Engineer,
Dharampur Division
H.P.W.D., Dharampur.

providing and fixing M.S Tube tie made of hollow tubes (38x38x2.6) (Thirty into thirty into two point six millimetre)	70.40	115.00	Rupees One Hundred Fifteen Only	Per Kilogramme	8096
				Total	266936

Direct amount approved for Rs 266936 vide S.O 224

[Signature]

Executive Engineer,
Dharampur Division
H.P.P.W.D., Dharampur.

244
87

SCHEDULE OF QUANTITY

Work: R/R Damages on Sarkaghat Tihra Sandhole road Km 59/400 to 98/240 (SH :- C/O Wire Crate at RD 89/660 to

00) PDMA

Estimated cost :-
Earnest Money :-

480735
9700

Two Months

Description of item/Sub Head	Quantity	Rates		Unit	Amount
		In Figure	In words		
		4	5		
2 Earthwork in excavation in all kinds classification of soil in foundation of structures upto all depth/ height as per drawing and technical specification Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead and lifts dressing of sides and bottom and back filling with approved material and disposal of all surplus excavated earth in specified site and as per direction of Engineer-in-charge complete.	56.70	250.00	Rupees Two Hundred Fifty Only	Per Cubic Metre	14175
Providing and laying boulder apron laid in wire crates with 4 mm diametre G.I. wire conforming to IS:280 and IS:4826 in 100mm x 100mm mesh (woven diagonally) including 10 % extra for laps and joints laid with stones boulders weighting not less than 25 kg. each as per drawing and technical specifications clause 1301 including entire carriage of material with in all leads lifts and technical specifications as per the direction by the Engineer-in-charge and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	145.80	3200.00	Rupees Three Thousand Two Hundred Only	Per Cubic Metre	466560
Total:-					480735

*Duit amount approved for Rs 480735/-
vide Sr No 244*

[Signature]
Executive Engineer,
Dharanpur Division
H.P.P.W.D., Dharampur.

223
99

DRAFT SCHEDULE OF QUANTITY

of work:-Resoration of rain damages on Bharori to Kot road km 0/0 to 2/500(Sh:- Repair of pot hole at Rd 0/0 to

Estimated cost :- 96986
Earnest Money:- 2000

Description of item/Sub Head	Quantity	Rates		Unit	Amount
		In Figure	In words		
		4	5		
2 Repair of pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm (Twenty millimetre) thick premix carpet and seal oat TYPE-B specification clause 1904.2 The Bitumen will be issued to contractor free of cost including hauling of material in all leads and lifts as jper the entire satisfaction and direction of the Engineer-in-Charge.	249.00	365	Rupees Three Hundred SixtyFive Only	Per Square metre	90885
Construction of penetration macadam over prepared base by providing a layer of compacted crushed coarse aggregate using chips spreader with alternate applications of bitumenious binder and key aggregates applications of bituminous binder and key aggregates and rolling with a three wheel 80-100 kn static roller to achieve the desired degree of compaction as per Technical Specification Clause 506 50mm (Fifty millimetre) thick including carriage of materials within all leads and lifts and other incidentals and direction of Engineer in charge .	24.90	245	Rupees Two Hundred FourtyFive Only	Per Square metre	6101
Total					96986

Draft Schuelude of quantity approved
RS.96986/- vide No 223/2023

Executive Engineer,
Dharampur Division
H.P.P.W.D., Dharampur

227
80

DRAFT SCHEDULE OF QUANTITY

Work :- Construction of link road to Harizen Basti Saklana km 0/0 to 0/500 (SH:- P/L cement
ete pavement at RD 0/040 to 0/087)

Description of item/Sub Head	Quantity	Estimated cost :-		199091	
		Earnest Money :-		4000	
		Time Limit		Two Months	
		In Figure	In words	Unit	Amount
2	3	4	5	6	7
Stone soling properly hand packed filling interstices with kharanja stone and consolidating complete to the requested gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD. specification. 100mm (One hundred millimetre) spread thickness (finished work including materials and labour) including carriage of materials within all leads and lifts and other incidentals charges. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	22.95	1275.00	Rupees One Thousand Two Hundred SeventyFive Only	Per cubic Metre	29261
Construction of un-reinforced and construction joint only, plain cement concrete pavement in 1:1.5:3 (one cement : one and half sand : three graded stone aggregate 20 mm (Twenty millimetre) nominal size), thickness as per design, over a prepared sub base, with 43 (Forty three) grade cement or any other type as per Clause 1501.2.2 to be ensure minimum strength of 25N/mm ² and minimum cement not less than 400 kg/ cum(Four hundred kilogramme per cubic metre) (with plasticizer), coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm,(Twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (Zero point two cubic metre) capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, , wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including provision of contraction and expansion, construction joints, applying debonding strips, primer, sealant, dowel bars, near approaches to bridge/culvert and construction joints, admixtures as approved, curing of concrete slabs for 14-days, using curing compound (where specified) and water finishing to lines and grade as per drawing and Technical specification clause 1501 including hauling of material within all leads and lifts and other incidental charges and as per direction of Engineer-In-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	22.95	7400.00	Rupees Seven Thousand Four Hundred Only	Per cubic Metre	169830
				Total	199091

Draft schedule of quantity approved
RS.199091/- Vide S.O No. 227/2025-26

[Signature]
Executive Engineer,
Dharanpur Division
H.P.P.W.D., Dharampur

245
88

10

DRAFT SCHEDULE OF QUANTITY

Work :- Construction of Shahid Capt. Deepak Guleria at Govt. Senior Secondary School at Cholthra
Sarkaghat Distt. Mandi (HP) (SH :- Repair and maintenance of basket ball court)

Description of item/Sub Head	Quantity	Estimated cost :-		Unit	Amount
		Earnest Money:-			
		In Figure	In words		
2 Providing and laying 40(forty) millimetres thick red sand stone slab flooring on 20(twenty) millimetres average thick base of cement mortar 1:4 (one cement : 4 four sand) laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab i/c rubbing and granite polish finish complete including entire carriage of material with in all leads lifts and technical specifications as per the direction of Engineer-in-Charge including other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3 180.80	4 1100.00	5 Rupees One Thousand One Hundred Only	6 Per Square meter	7 198880
Total:-					198880

DNIT amount approx 1-00

For Rs 198880/- vide S.N. 245

Executive Engineer,
Dharampur Division
H.P.W.D., Dharampur

246
79

11

DRAFT SCHEDULE OF QUANTITY						
Name of Work :- Annual repair and maintenance on 71.00 mtrs span bridge over Sun Khad on Hukkal Chatter (SH:-Painting on railing and wheel guard).						
Description of item/Sub Head	Quantity	Estimated cost :-			50055	
		Earnest Money:-			1500	
		Time Limit			Two Months	
		Rates		Unit	Amount	
		In Figure	In words			
2	3	4	5	6	7	
Removing white wash or colour wash by steel wire brushing and/or scrapping sand papering and preparing the wall surface smooth including necessary repairs to scratches complete. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	340.80	12.00	Rupees Twelve Only	Per Square meter	4090	
Finishing wall with water proofing cement paint of approved brand and manufacture and of required shade on decorated wall surfaces (one coat) to give an even shade after thoroughly brushing the surface to remove all dirt, loose or softened paint. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	241.40	75.00	Rupees SeventyFive Only	Per Square meter	18105	
Extra over item No. 17176000 and 17177000 for every sub sequent coat of water proofing cement paint of approved brand and manufacture. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	241.40	52.00	Rupees FiftyTwo Only	Per Square meter	12553	
Painting one coat (excluding priming coat) on previously painted concrete/masonry/plastered surface with readymixed paint/brushing for use on floors to give an even shade including cleaning the surface of all dirt, dust and other foreign matter and sand papering as required with. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	99.40	82.00	Rupees EightyTwo Only	Per Square meter	8151	
Extra over items 16074000 and 16075000 for every subsequent coat of paint. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	99.40	72.00	Rupees SeventyTwo Only	Per Square meter	7157	
				Total:-	50055	

Draft Schedule of Quantity approved for Rs 50055/-
vide Sr No 246

Executive Engineer,
Dharampur Division
H.P.W.D., Dharampur.

247
80

12

DRAFT SCHEDULE OF QUANTITY

Description of item/Sub Head	Quantity	Estimated cost :-			Two Months	
		Earned Money :-				Amount
		In Figure	Rates			
			In words	Unit		
	3				52875	
					1500	
2						
Removing white wash or colour wash by steel wire brushing and/or scrapping sand papering and preparing the wall surface smooth including necessary repairs to scratches complete. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	360.00	12.00	Rupees Twelve Only	Per Square meter	4320	
Finishing wall with water proofing cement paint of approved brand and manufacture and of required shade on decorated wall surfaces (one coat) to give an even shade after thoroughly brushing the surface to remove all dirt, loose or softened paint. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	255.00	75.00	Rupees SeventyFive Only	Per Square meter	19125	
Extra over item No. 17176000 and 17177000 for every sub sequent coat of water proofing cement paint of approved brand and manufacture. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	255.00	52.00	Rupees FiftyTwo Only	Per Square meter	13260	
Painting one coat (excluding priming coat) on previously painted concrete/masonry/plastered surface with readymixed paint/brushing for use on floors to give an even shade including cleaning the surface of all dirt, dust and other foreign matter and sand papering as required with. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	105.00	82.00	Rupees EightyTwo Only	Per Square meter	8610	
Extra over items 16074000 and 16075000 for every subsequent coat of paint. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	105.00	72.00	Rupees SeventyTwo Only	Per Square meter	7560	
				Total:-	52875	

Draft Schedule of Quantity approved for Rs 52875/- vide SN 247

Executive Engineer,
Dharampur Division
H.P.W.D., Dharampur.