

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No.: PW/ESDD/CONT/2025-26/- 10881-90

Dated: 23-03-2026

To

The Executive Engineer (IT Cell),
Nigam Vihar, Shimla-2.

Subject: Publishing of Short Term Tender Notice.

Jai Hind

Enclosed please find herewith the Tender Notice of works as given in the Notice Inviting Tender along with Schedule of Quantities for uploading on departmental website as per Notification Pr. SEC(PW) to the Govt. of HP letter No. PBW(B)A9(3)1/2020 dated Shimla-26th July 2021.

It is certified that the works mentioned in the Notice Inviting Tenders are urgent in nature and in public Interest.

DA/NIT,SQs

Executive Engineer
Electrical Division
HP PWD Palampur

Copy forwarded to the following for information and necessary action please:

1. The Superintending Engineer, 2nd Electrical Circle, HP PWD Dharamshala.
2. All the Assistant Engineers Working under this Division.
3. Drawing Branch of this office.
4. The Notice board in this office.

Executive Engineer
Electrical Division
HP PWD Palampur

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
"Notice Inviting Tenders"**

Sealed percentage rate tenders on form 7&8 are hereby invited by the Executive Engineer, Electrical Division, HP PWD Palampur on behalf of the Governor of H.P. for the following work from the approved and eligible contractors enlisted in HP.PWD. (Elect.) whose registration stood renewed as per revised rules and also registered under the H.P. General Sales Tax Act. 1968 so as to reach in his office on or before **27-03-2026** up to 11.00 AM, and the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable) on **27-03-2026** up to 4.00 P.M. and the application for issue of tender form shall be received on **27-03-2026** up to 12.00 noon.

| Sr. No | Name of Work | Estimated Cost | Earnest Money | Time Limit | Cost of Form |
|--------|---|----------------|---------------|------------|--------------|
| 1 | Replacement of Burnt out Sub Main Power, Circuit wiring and accessories of Ground Floor Rooms LHS area 104 to 109, Service/staff room, Kitchen area of PG Boys Hostel at Dr. RPGMC Kangra at Tanda. | 99561/- | 2000/- | One month | 350/- |
| 2 | Replacement of Burnt out Sub Main Power, Circuit wiring and accessories of Ground Floor Rooms RHS area of PG Boys Hostel at Dr. RPGMC Kangra at Tanda. | 99315/- | 2000/- | One month | 350/- |

HIM SUCHNA AVAM JAN SAMPARK VIBHAG

This is certified that the above works are required to be carried out immediately being emergent nature of work in Public Interest. The Tender documents shall be issued only to those contractor/firm who fulfill the following criteria/documents with the application.

Conditions:

1. The contractor should have the EPF registration certificate should be attached with application.
2. The GST registration certificate.
3. The contractor should produce a copy of latest enlistment/renewal.
4. The latest ITR filed should be attached with application.
5. The bidders enlisted in a particular class shall be eligible to tender for his own class or one step below.
6. The bidder should attach authorization and work done certificate with application for Specialized Jobs.
7. In case of Holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.
8. Ambiguous/telephonic/conditional tenders or tenders fax/email/whatsapp shall not be considered and will be summarily be rejected.
9. The FDR duly pledged should be attached separately with each tender.
10. Only two number tender forms will be issued to the eligible contractor.
11. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected.
12. The Executive Engineer, Electrical Division, HP PWD Palampur reserves the right to reject any tender without assigning any reasons.

Executive Engineer
Electrical Division
HP PWD Palampur
On behalf of Governor of Himachal Pradesh

DRAFT SCHEDULE OF QUANTITY

| NAME OF WORK :- Replacement of Burnt out Sub Main , Power , Circuit wiring and accessories of Ground Floor Rooms RHS area of PG Boys Hostel at Dr. RPGMC Kangra | | D | | ESTIMATED COST:99,316/-only. EARNEST MONEY: Rs.2000/-only TIME ALLOWED:-One Months | | |
|---|---|--------|---------|--|-----------|---------|
| SR. NO. | DESCRIPTION | job No | | WORDS | UNIT | AMOUNT |
| | | | RATES | | | |
| 1 | Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed heavy class PVC conduit having wall thickness 2.0mm as required | | | | | |
| 1.1 | 2 X 1.5 sq. mm + 1 X 1.5 sq. mm earth wire | 40 ✓ | 198.00 | Rs one hundred ninety eight only | Per Meter | 7920 ✓ |
| 1.2 | 2 X 4 sq. mm + 1 X 4 sq. mm earth wire | 57 ✓ | 311.00 | Rs. Three hundred eleven only | Per Meter | 17727 ✓ |
| 1.3 | 4 X 4 sq. mm + 2 X 4 sq. mm earth wire | 40 ✓ | 524.00 | Rs. Five hundred twenty four only | Per Meter | 20960 ✓ |
| 1.5 | 4 X 10 sq. mm + 2 X 6 sq. mm earth wire | 11 ✓ | 1782.00 | Rs. One thousand seven hundred eighty two only | Per Meter | 19602 ✓ |
| Make:- finolex/Anchor/Plaza | | | | | | |
| 2 | Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVCconduit as required. | ✓ | | | | |
| 2.1 | S/D 3x1.5 sq. mm | 50 ✓ | 100.00 | Rs. One hundred only | Per Meter | 5000 ✓ |

| | | | | | | |
|-------------------------------|---|----|--------|------------------------------------|-----------|------|
| 2.2 | S/D 3x4 sq. mm | 14 | 456.00 | Rs. Four hundred fifty six | Per Meter | 6384 |
| 2.3 | S/D 6x4 sq. mm | 20 | 428.00 | Rs. Four hundred twenty eight only | Per Meter | 8560 |
| Make:- Finolex/AnchorPlaza | | | | | | |
| 3 | Supplying and fixing of following sizes of heavy class FRLS PVC conduit having wall thickness 2.0mm along with accessories insurface/recess including painting in case of surface conduit, or cutting the walland making good the same in case of recessed conduit as required. | | | | | |
| 3.1 | 25 mm | 20 | 87.00 | Rs. Eighty seven only | Per Meter | 1740 |
| Make:- BEC/Diplast | | | | | | |
| 5 | Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required. | | | | | |
| 5.1 | 5/6 Amps Switch | 5 | 93.00 | Rs. Ninety three only | Each | 465 |
| 5.2 | 5/6 Amps Socket | 5 | 136.00 | Rs. One hundred thirty six only | Each | 680 |
| 5.3 | 15/16 Amps Switch | 5 | 164.00 | Rs. One hundred sixty four only | Each | 820 |
| 5.4 | 15/16 Amps Socket | 5 | 231.00 | Rs. Two hundred thirty one only | Each | 1155 |
| Makes:- Anchor/L&T/Schneider. | | | | | | |

| | | | | | | | | |
|-----|--|---|----|--------|-----------------------------------|------|---|------|
| 6 | Supplying and erection of 6 amps. to 32 amps. rating, 10 KA breaking capacity, 240 volts, 'C' curves, miniature circuit breaker of following poles in the existing MCB DB complete with connections etc. as required:- | | | | | | | |
| 6.1 | Single pole. Cat-A. | ✓ | 11 | 239.00 | Rs. Two hundred thirty nine only | Each | ✓ | 2629 |
| | Makes:- L&T/Legrand/Schneider. | | | | | | | |
| 7 | Supplying and fixing following rating, double pole, 240 volts, isolator in the existing MCB DB complete with connections, testing and commissioning etc. as required. | | | | | | | |
| 7.1 | 63 Amps | ✓ | 2 | 530.00 | Rs. Five hundred thirty only | Each | ✓ | 1060 |
| | Makes:- L&T/Legrand/Schneider. | | | | | | | |
| 8 | Supplying and fixing following rating, four pole, 415 volts, isolator in the existing MCB DB complete with connections, testing and commissioning etc. as required. | | | | | | | |
| 8.1 | 63 Amps | ✓ | 2 | 976.00 | Rs. Nine hundred seventy six only | Each | ✓ | 1952 |
| | Makes:- L&T/Legrand/Schneider. | | | | | | | |
| 9 | Supplying and fixing two module stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required. | | | | | | | |
| 9.1 | Fan Regulator | ✓ | 2 | 422.00 | Rs. Four hundred twenty two only | Each | ✓ | 844 |

| | | | | | | | | |
|---|---|---|--------|--------------------------|------|-------|--|--|
| 10 | Makes: Anchor/Bajaj/Havells Providing and fixing of LED batten having minimum efficacy of 100 lm/W, P.F.>0.95 with THD<10%, CCT 6500 K, CRI 80, Surge Protection range 2 kV. The LED with useful life of 50000 Hrs. at L70 with five years warranty. The Input voltage shall be 150V to 270V, 50/60 HZ along with all accessories, including connections, testing etc. as required complete in all respects. | | | | | | | |
| 10.1 | LED Batten 20 Watt | 3 | 606.00 | Rs. Six hundred six only | Each | 1818 | | |
| | Makes:-Havells/ Bajaj/Wipro | | | | | | | |
| Dismantel Credit of Useful Material (-)1500 | | | | | | | | |
| | Total:- | | | | | 99316 | | |

Orath Schedule of Quantity *Checked*
& Approved for fig. 99316/000

SH
 Executive Engineer
 Electrical Division
 HPPWD Palampur



DRAFT SCHEDULE OF QUANTITY

NAME OF WORK :- Replacement of Burnt out Sub Main , Power , Circuit wiring and accessories of Ground Floor Rooms LHS area 104 to 109, Service / staff room, Kitchen area of PG boys Hostel at Dr. RPGMC Kangra at Tanda.

2

ESTIMATED COST: 99,561/-/-only.
EARNEST MONEY: Rs.2000/-/only
TIME ALLOWED:- One Months

| SR. NO. | DESCRIPTION | job No | | WORDS | UNIT | AMOUNT |
|-----------------------------|---|--------|---------|--|-----------|---------|
| | | | RATES | | | |
| 1 | Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed heavy class PVC conduit having wall thickness 2.0mm as required | | | | | |
| 1.1 | 2 X 1.5 sq. mm + 1 X 1.5 sq. mm earth wire | 40 ✓ | 198.00 | Rs. One hundred ninety eight only | Per Meter | 7920 ✓ |
| 1.2 | 2 X 4 sq. mm + 1 X 4 sq. mm earth wire | 35 ✓ | 311.00 | Rs. Three hundred eleven only | Per Meter | 10885 ✓ |
| 1.3 | 4 X 4 sq. mm + 2 X 4 sq. mm earth wire | 40 ✓ | 524.00 | Rs. Five hundred twenty four only | Per Meter | 20960 ✓ |
| 1.5 | 4 X 10 sq. mm + 2 X 6 sq. mm earth wire | 11 ✓ | 1782.00 | Rs. One thousand seven hundred eighty two only | Per Meter | 19602 ✓ |
| 1.6 | 2 X 6 sq. mm + 1 X 6 sq. mm earth wire | 16 ✓ | 432.00 | Rs. Four hundred thirty two only | Per Meter | 6912 ✓ |
| Make:- finolex/Anchor/Plaza | | | | | | |
| 2 | Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVCconduit as required. | | | | | |

| | | | | | | |
|-----|--|----|---------|---|-----------|------|
| 2.1 | S/D 3x1.5 sq. mm | 30 | 100.00 | Rs. One hundred only | Per Meter | 3000 |
| 2.2 | S/D 3x4 sq. mm | 13 | 456.00 | Rs. Four hundred fifty six only | Per Meter | 5928 |
| | Make:- finolex/Anchor/Plaza | | | | | |
| | Supplying and fixing of following sizes of heavy class FRLS PVC conduit having wall thickness 2.0mm along with accessories insurface/recess including painting in case of surface conduit, or cutting the walland making good the same in case of recessed conduit as required. | | | | | |
| 3.1 | 25 mm | 20 | 87.00 | Rs. Eighty seven only | Per Meter | 1740 |
| | Make:- BEC/Diplast | | | | | |
| | Supplying and fixing suitable size GI box with modular plate and cover in FRLS on surface or in recess, including providing and fixing 6 pin 5/6 & 15/16 amps modular socket outlet and 15/16 amps modular switch, connection etc. as required. | 3 | 621.00 | Rs. Six hundred twenty one only | Each | 1863 |
| | Make:- Anchor/L&T/Schneider. | | | | | |
| | Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 volts, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator) | | | | | |
| 5 | | | | | | |
| 5.1 | 16 way, Double door | 1 | 2607.00 | Rs. Two thousand six hundred seven only | Each | 2607 |
| | L&T/HavellsSchneider. | | | | | |

| | | | | | | | | |
|-----|--|----|--------|----------------------------------|------|------|--|--|
| 6 | Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required. | | | | | | | |
| 6.1 | 5/6 Amps Switch | 3 | 93.00 | Rs. Ninety three only | Each | 279 | | |
| 6.2 | 5/6 Amps Socket | 3 | 136.00 | Rs. One hundred thirty six only | Each | 408 | | |
| 6.3 | 15/16 Amps Switch | 3 | 164.00 | Rs. One hundred sixty four only | Each | 492 | | |
| 6.4 | 15/16 Amps Socket | 3 | 231.00 | Rs. Two hundred thirty one only | Each | 693 | | |
| | Makes:- Anchor/L&T/Schneider. | | | | | | | |
| 7 | Supplying and erection of 6 amps. to 32 amps. rating, 10 KA breaking capacity, 240 volts, 'C' curves, miniature circuit breaker of following poles in the existing MCB DB complete with connections etc. as required:- | | | | | | | |
| 7.1 | Single pole. Cat-A. | 11 | 239.00 | Rs. Two hundred thirty nine only | Each | 2629 | | |
| | Makes:- L&T/Legrand/Schneider. | | | | | | | |
| 8 | Supplying and fixing following rating, double pole, 240 volts, isolator in the existing MCB DB complete with connections, testing and commissioning etc. as required. | | | | | | | |
| 8.1 | 63 Amps | 1 | 530.00 | Rs. Five hundred thirty only | Each | 530 | | |
| | Makes:- L&T/Legrand/Schneider. | | | | | | | |

| | | | | | | |
|------|--|---|--------|-----------------------------------|------|------|
| 9 | Supplying and fixing following rating, four pole, 415 volts, isolator in the existing MCB DB complete with connections, testing and commissioning etc. as required. | | | | | |
| 9.1 | 63 Amps | 2 | 976.00 | Rs. Nine hundred seventy six only | Each | 1952 |
| | Makes:- L&T/Legrand/Schneider. | | | | | |
| 10 | Supplying and fixing two module stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required. | | | | | |
| 10.1 | Fan Regulator | 2 | 422.00 | Rs. Four hundred twenty two only | Each | 844 |
| | Makes: Anchor/Bajaj/Havells | | | | | |
| 11 | Providing and Fixing of IP20 LED fixture of 18 watt +/- 1 W LED Surface Mounted Downlighter Round Shape with minimum system lumen efficacy of 100 lm/W with Polycarbonate housing, pressure die cast heat sink and P.F.>0.95 with THD<10% ,CRI 80. The LED shall be tested with LM80-08 standard with Useful life of 50000 Hrs at L70 . The LEDs used in the luminaire shall have CCT of ANSI Bin 5700 K with CRI of minimum 80. The Input voltage range shall be 150V to 270V, 50/60 HZ complete with all accessories, including connections, testing and commissioning etc.as required complete in all respects. | | | | | |

| | | | | | | |
|---|--|---|---------|--|------|-------|
| 11.1 | LED Surface mounting round downlighter 18 watt | 5 | 1821.00 | Rs. One thousand eight hundred twenty one only | Each | 9105 |
| | Makes:-Panasonic/ Bajaj/Wipro | | | | | |
| | Providing and fixing of LED batten having minimum efficacy of 100 lm/W, P.F.>0.95 with THD<10%, CCT 6500 K, CRI 80, Surge Protection range 2 KV. The LED with useful life of 50000 Hrs. at L70 with five years warranty. The Input voltage shall be 150V to 270V, 50/60 HZ along with all accessories, including connections, testing etc. as required complete in all respects. | | | | | |
| 12 | LED Batten 20 Watt | 2 | 606.00 | Rs. Six hundred & six only | Each | 1212 |
| | Makes:-Havells/ Bajaj/Wipro | | | | | |
| Dismantel Credit of Useful Material (-)1500 | | | | | | |
| | Total: | | | | | 99561 |

Grat Schedule of Quantity checked & Approved
 For No. 99561-Only.

HY
 Executive Engineer
 Electrical Division
 HPPWD Palampur
SM