

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No.PW.-ESD. (MC)/Tender/ 2025 -26

1238-40

Dated:-

16/3/26


To

✓ The Executive Engineer(IT),
Nirman Bhawan, HPPWD,
Shimla-2.

Subject: - Publication of Tender Notice.

Jai Hind

Please find enclosed herewith the tender notice of works as given in the notice inviting tender for uploading on department website as per Notification vide Pr. Secy.(PW) to the govt. of Himachal Pradesh letter No. PBW(B)1/2020 dated 27th May,2021 and PBW(B)A(3)1/2020 dated 16th July, 2021 and even file dated 12.01.2023 as the works mentioned in the tender notice is (are) urgent in nature and in public interest.


Assistant Engineer,
M.C. Elect. Sub-Division,
HPPWD, Snowdon Shimla.

Copy forwarded for information and further necessary action to:-

1. The Executive Engineer, Electrical Division No-II, HPPWD, Shimla-1.
2. Computer Cell O/O the Executive Engineer (IT Cell), Nirman Bhawan, Nigam Vihar, Shimla-2.

Assistant Engineer,
M.C. Elect. Sub-Division,
HPPWD, Snowdon Shimla.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**


'NOTICE INVITING TENDER'

Sealed Percentage rate tender on the prescribed form, terms and conditions mentioned in form- 6 & 7 ,8 are hereby invited for the following works by the undersigned from the approved firms/contractors, so as to reach in the office of the undersigned (i)Tender documents consisting of plans classes of work to be done and set of terms and conditions of contract to be complied with by the contractor/firms whose tender may be accepted and other necessary documents can be seen in the office of the Assistant Engineer between hours of 11.00 AM to 4.00 PM except on Sundays and public holidays. (2) The contractor who are not registered under HP general sale tax Act, 1968 and have not cleared all the dues on account of sale tax shall not be issued the tender documents. (3) The contractor who has no registration certificate with Excise and taxation department of HP will not be issued the tender documents (4) Tenders placed in sealed envelope with name of work and due date written on the envelope will be received by the undersigned and will be opened by him or his authorized representative in his office in the presence of contractors, present if any. (5)The earnest money in the shape of NSC/Time deposit account /saving account in any of the post offices of HP duly pledged in favour of undersigned must accompany with the tender in the separate envelope. The tenders without earnest money will summarily be rejected. (6) In case of holiday, the tenders shall be received and opened on the next working day.(7)Tenders of contractors who quote two or more than two rates for any item of work shall be rejected. (8) The competent authority on behalf of Governor of H.P reserves the right to reject any or all the tenders received without assigning any reason.

- (i) Last date of issue of tender documents: - 24.3.2025, Up to 5.00 P.M
(ii) Last date of receipt of bids: 25.03.2025 Up to 10.30 A.M
(iii) Date of bid opening: 25.3.2025 AT 11.30 A.M

S. N.	Name of work	Estimated cost	Earnest money	Time	Eligible class of registration
1.	Providing MCB, DB for Fan coil units in 2 nd , 3 rd & 4 th Floor of cancer hospital building IGMC Shimla.	Rs.99,217/-only	Rs.2000/-only	2 weeks	C & D
2.	Providing control wiring for FCU in 2 nd , 3 rd & 4 th Floor of cancer hospital building IGMC Shimla.	Rs.99,830/-only	Rs.2000/-only	2 weeks	C & D
3.	Replacement of damaged Auto Phase Corrector Device in Lift M/C No. J2007 (Block-E) at IGMC Shimla.	Rs.66,740/-only	Rs.1400/-only	One Month	C & D
4.	Providing Canopy for transformer 2 BBT at AIMSS Chamiana Shimla (HP) (SH:- Providing Canopy for building area)	Rs.96,184/-only	Rs.2000/-only	One Month	Specialized Job
5.	Providing Canopy for transformer 2 BBT at AIMSS Chamiana Shimla (HP) (SH:- Providing Canopy for transformer area)	Rs.96,184/-only	Rs.2000/-only	One Month	Specialized Job

6.	R/M of Central Heating Plant at Block-C building under IGMC Shimla (SH:- Replacement of damaged step controller, motor starter therein)	Rs.99,705/-only	Rs.2000/-only	2 Weeks	Specialized Job
7	Replacement of damaged butterfly valve for hydrant riser at Ground floor and fire alarm accessories at AIMSS Chamiana Shimla-12	Rs. 95796/- only	Rs.2000/-only	1 Month	Specialized Job
8	R/M of Central Heating Plant at Cancer Hospital Building under IGMC Shimla (SH:- Replacement of boiler element, replacement of step controller unit, PVC water tank, FCU motors, motor bearing etc therein)	Rs.76,248/-only	Rs.1600/-only	3 Months	Specialized Job
9	R/M of Central Heating Plant at Block-C, Block-D Building under IGMC Shimla (SH:- Rewinding of 12.5 hp motor starter, 400 Amps TP&N etc therein)	Rs.57,890/-only	Rs.1200/-only	15 Days	Specialized Job
10	Providing & Laying of copper cable for earthing of medical equipment at Cancer hospital building at IGMC Shimla	Rs.83,600/-only	Rs.1700/-only	One Week	C & D



Assistant Engineer,
Electrical Sub-Division.
HPPWD, Snowdon

No.PW.-ESD. (MC)/Tender/ 2025 -26- 1225-37

Dated:- 16/3/26


Copy forwarded for information to the following:-

1. The Executive Engineer, Elect. Division No.II, HPPWD Shimla-1.
2. All the JE's under this Sub. Divn.
3. The Income tax Officer, Shimla
4. All the approved contractors/firms/President Contrs./Association.
5. Notice Board.


Assistant Engineer,
Electrical Sub-Division.
HPPWD, Snowdon

CERTIFICATE: -

**IT IS CERTIFIED THAT THE TENDER FOR ABOVE WORK IS URGENTLY
REQUIRED IN PUBLIC INTEREST.**



Assistant Engineer
Electrical Sub Division
H.P.P.W.D., Snowdon,
Shimla-171001 (H.P.)

SCHEDULE OF QUANTITY

Estimated Cost:-Rs99,217/- Only ✓
 Earnest Money:-Rs2000/-Only ✓
 Time:- Two weeks ✓

Name of work : - Providing MCB, DB for fan coil units in 2nd, 3rd & 4th Floor of Cancer hospital building IGMC Shimla.

S.No.	Description of Items	Qty.	Unit	Rate		Amount
				In Figures	In Words	
1	Supplying and fixing of following way, single pole and neutral sheet steel MCB distribution board, 240 volts, on surface / recess, complete with tinned copper bus-bar, wire-set, neutral link, earth bar, din-bar, detachable gland plate, blanking plate, cable, identification labels interconnections, phosphatized and powder painted, including earthing etc. as required:-					0
1.01	Two way Single Door	47	each	976	Rs. Nine Hundred Seventy Six only ✓	45872 ✓
2	Supplying and fixing following rating, followings poles 10ka 240/415v 'C' curves miniature circuit breaker MCB DP suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.					
2.01	6A to 32 A MCB Double Pole	47	each ✓	1135	Rs. One Thousand One Hundred Thirty Five only ✓	53345 ✓
Total						99217 ✓

Swati
 Assistant Engineer
 M.C. Elect. Sub Division
 HPPVMD, Snowdon, Shri

*Draft schedule of quantity approved for Rs 99217/-
 (As Ninety Nine Thousand Two Hundred Seventy Seven only)*

helo
 Executive Engineer,
 Electrical Division No.-II,
 HP PWD (U.S. Club) Smtla-1

SCHEDULE OF QUANTITY

Name of work : - Providing control wiring for FCU in 2nd, 3rd & 4th Floor of Cancer hospital building IGMC Shimla.

Estimated Cost:-Rs 99,830/-Only
 Earnest Money:-Rs2000/-Only
 Time:- Two weeks

S.No.	Description of Items	Qty.	Unit	Rate		Amount
				In Figures	In Words	
1	Supply and fixing of following size PVC insulated copper conductor control cable including making connections complete as required					
1.01	3 Core 1.5 sqmm	335	Meter	298	Rs. Two Hundred Ninety Eight only	99830
	Total					99830

*Draft schedule of quantity approved for Rs 99830/-only
 (Rs Ninety Nine Thousand Eight Hundred Ninety only)*

[Signature]
Assistant Engineer
 M.C. Elect. Sub Division
 HPPV&D, Snowdon, Shir

[Signature]
Executive Engineer,
 Electrical Division No.-II,
 HP PWD (U.S. Club) Shimla-1

DRAFT SCHEDULE OF QUANTITY

Estimated Cost:-Rs 66740/-Only

Earnest Money:-Rs1400/-Only

Time:-One Month

Name of work :- Replacement of damaged Auto Phase Corrector Device in Lift M/C No. J2007 (Block-E) at IGM, Shimla.

EE

S.No.	Description of Items	Qty.	Unit	Rate		Amount
				In Figures	In Words	
1	Supply, installation, testing and commissioning of 63 Amps Three Phase Auto Phase corrector device fabricated in cubical type panel with approximate Size Size (H) 600MM X (W)500mm x (D) 350MM, single door, Wall mounted, fixed type, free standing single front, dust proof & compartmentalized Phase Corrector Panel made out of M.S. CRC Sheet 16G, duly painted with Siemens Grey Powder Coated Paint, as per specification. including Control Wiring with Copper Flexible Wire (size of control wire shall be 2.5 sq. mm copper flexible for C.T. Circuit & 1.0 sq. mm for Control Wiring) with thimbles printed sleeves, tie & belt etc and accessories like Gasket, Doorlocks, Rubber Gasket, legend plates etc. Also including assembly of Aluminium solid/ Copper Flexible wire interconnection On .Load .Motorised .Change .Over .Switch. to field side for Cable termination duly covered/ insulated with Heat Shrinkable sleeves of coloured coded Red, Yellow, Blue & Black. All Interconnections of fields side are supported by conical, L & Finger type insulators of adequate size to support & sustain the weight of cables complete in all respects as per the satisfaction of Engineer-in-Charge.					
1.01	Technical Specifications and Material detail of Phase Corrector Panel are as follows:-					

INCOMER						
1.02	Motorsised Changeover Switch 63A	GORLAN/LK	1			
	RY Indication Lamp LED	LK	2			
	B Indication Lamp LED	LK	1			
	Phase corrector Relay	LK	1			
	Auxiliary Relay 8 Pin with Base	LK	2			
	On Delay Timer	LK	1			
	MCB 6A SP 10KA for Control Neutral Link	REP/UTED	3 1			
2.00	Supplying and fixing of Residual Current Breaker with Overcurrent Protection Conforming to IEC 61009-1, IS 12640-2, EN 61009-1 with precise sensitivity and suitable for isolation with all connections required and complete in all respects as per satisfaction of Engineer-in-charge					
2.01	RCBO 4 Pole 63 Amp 300mA					
	Total		1	Job	61676	Rs. Sixty One Thousand Six Hundred Seventy Six only
			1	each	5064.00	Rs. Five Thousand Sixty Four only
						5064
						66740

*Draft schedule of quantity approved for Rs. 66,740/-
(Rs. Sixty six Thousand Seven hundred & forty only)*

M. C.
Assistant Engineer
M.C. Elect. Sub Division
H.P.P.W.D. Snowdon, Shir


Executive Engineer,
Electrical Division No.-11,
H.P.P.W.D. (U.S. Club) Shimla-1

DRAFT SCHEDULE OF QUANTITY

Estimated Cost:- Rs.96184/- only
 Earnest Money:- Rs. 2000 /- only
 Time:- 1 month

Name of work:- Providing Canopy for transformer 2 BBT at AIMSS Chamaina Shimla (H.P) (Sh: providing Canopy for transformer area)

S.No.	Description of Items	Qty.	Unit	In Figures	Rate	Amount
					In words	
1.00	Supply of canopy for 415V/690V/1000V Sandwich construction Busbar trunking system with Multilayer Class-F insulation and: Conductors : Aluminium Rating : 4000A Configuration : 3P4W IP Rating : IP54 Enclosure : GI 1.6mm thickness Impulse Withstand Voltage : 8kV Paint Shade : RAL7015 Epoxy Powder Coating to make bus bar IP-66/67 compliant this includes all accessories required and making arrangement air tight and moisture proof make Lnk	5.5	meter	17488.00	Rs. Seventeen Thousand Four Hundred Eighty Eight only	96184
Total:-						96184


Assistant Engineer
Electrical Sub Division
 H.P.P.W.D., Snowdon,
 Shimla-171001 (H.P.)

Draft Schedule of quantity approved for Rs. 96184/-
 CR.8. Ninety six Thousand, one hundred and eighty four only.


EXECUTIVE ENGINEER
 Electrical Sub Division No. 41,
 H.P. P.W.D. (S.S.) Shimla-1

DRAFT SCHEDULE OF QUANTITY

Estimated Cost:- Rs.96184 /- only
 Earnest Money:- Rs. 2000 /- only
 Time:-1 month

Name of work:- Providing Canopy for transformer 2 BBT at AIMSS Chamaina Shimla (H.P) (Sh: providing Canopy for building area)

S.No.	Description of Items	Qty.	Unit	Rate		Amount
				In Figures	In words	
1.00	Supply of canopy for 415V/690V/1000V Sandwich construction Busbar trunking system with Multilayer Class-F insulation and: Conductors : Aluminium Rating : 4000A Configuration : 3P4W; IP Rating : IP54 Enclosure : GI 1.6mm thickness Impulse Withstand Voltage : 8KV Paint Shade : RAL7015 Epoxy Powder Coating to make bus bar IP-65/67 compliant this includes all accessories required and making, interengagement air tight and moisture proof make Link	5.5	meter	17488.00	Rs: Seventeen Thousand Four Hundred Eighty Eight only	96184
Totals:-						96184


 Assistant Engineer
 Electrical Sub Division
 H.P.P.W.D., Snowdon,
 Shimla-171001 (H.P.)

Draft Schedule of quantity approved for Rs. 96,184/-
 (Rs. Ninety six Thousand, one hundred, eighty four only.)

EXECUTING ENGINEER,
 Electrical Division No. 11,
 H.P. PWD (U.S. Club) Shimla-1

1288

DRAFT SCHEDULE OF QUANTITY

Estimated Cost:-99705 /-
Earnest Money:-2000/-
Time :- Two Weeks

Name of Work:- R/M of Central Heating Plant at Block-C building under IGM C Shimla(SH):-Replacement of damaged step controller , motor starter therein)

S.No	Description of items	Qty.	Unit	Rates		Amount
				In figures	In words	
1	Replacement of damaged step controller for Hot water boiler 240 k.w rapidcool make i/c sensor wire and display, removing defective & refixing the new complete as required	2	each	35977	₹ Thirty Five Thousand Nine Hundred Seventy Seven only.	71954
2	Supply & fixing of Three Phase Hot water Pump Star Delta Controller/Starter (With Single Phase Preventer) Relay Range 28-42A 415V AC FASD(Fully Automatic Star Delta With Wideband Coil) i/c making	1	each	20091	₹ Twenty Thousand Ninety One only.	20091
3	Providing & Laying of one number aluminium conductor, PVC insulated and PVC sheathed armoured/ XLPE power cable, 1.1 KV grade of following sizes					
3.01	Armoured cable 16 sq. mm (four core)	20	mtr	383	₹ Three Hundred Twenty Three only.	7660
Total						99705

[Signature]
Assistant Engineer
Electrical Sub Division
HPPWD Snowdon, Shimla-1

Schedule of quantity approved
C Ninety Nine Mtr

for A. 99,705/- only
speed framed five papers only


[Signature]
Executive Engineer,
Electrical Division No-II,
HP PWD (U.S. Club) Shimla-1

DRAFT SCHEDULE OF QUANTITY


Estimated Cost:-95796/-
Earnest Money:-2000/-
Time :- 1 Month

Name of Work:- Replacement of damaged butterfly valve for hydrant riser at Ground floor and fire alarm accessories at AIMSS Chamiana Shimla-12 (H.P)

S.No	Description of items	Qty.	Unit	Rates		Amount
				In figures	In words	
1	Providing Cast iron/steel Butterfly Valve Confirming to type P.N 1.6 of I.S 13095-1991 Complete with Flanges bolt ,nuts ,gasket etc. As per table 'E' specification complete in all respect hydraulically test to 20 K./sqcm.Make. Zoloto, Sant, L.P, Kirloskar					
1.01	150 mm Dia	2	NO	9498.00	₹ Nine Thousand Four HUNDRED Ninety Eight only.	18996
2.00	Supplying, installation, testing & commissioning of dual action addressable manual call point semi flush mounted with built in bi colour LED designed for 24 V DC with alarm current 5ma temperature range from 0 to 49 c with braille text on handle complete as required.Honeywell model no NBG12LX	12	NO	6400	₹ Six Thousand Four Hundred only.	76800
	Total					95796


 Assistant Engineer
 Electrical Sub Division
 HPPWD Snowdon ,Shimla-1

Schedule of quantity approved from the Ministry five. Promoted. Senior Manager. Ninety six Papes (96,796) / - only.


 Executive Engineer,
 Electrical Division No.-II,
 HP PWD (U.S. Club) Shimla-1

122

22


DRAFT SCHEDULE OF QUANTITY

Estimated Cost:- 76248/-
Earnest Money:- 1600/-
Time :- 3 Months


Name of Work:- R/M of Central Heating Plant at Cancer hospital building under IGMC Shimla (SI:-Replacement of boiler element, replacement of step controller unit, PVC water tank , FCU motors , motor bearing etc therein)

S.No	Description of items	Qty.	Unit	Rates		Amount
				In figures	In words	
1	Replacement of damaged step controller for Hot water boiler 240 k.w rapidcool make i/c sensor wire and display, removing defective & refixing the new complete as required	1	each	35979	₹ Thirty Five Thousand Nine Hundred Seventy Seven only.	35977
2	Supply & fixing of 25 k.w element for 240 K.w hot water boiler complete as required	1	each	13029	₹ Thirteen Thousand Twenty Nine only.	13029
3	Providing motor bearing 6307,6308 complete in all respects as per the satisfaction of Engineer-in-charge.	4	each	1610	₹ One Thousand Six Hundred Ten Only.	6440
4	Supply and installation of Triple layer PVC tank 1000 liters. capacity i/c connection base frame tank nipple complete as required	1	each	8890	₹ Eight Thousand Eight Hundred Ninety only.	8890
5	Providing & fixing GI Tank Nipple 32mm ISI Marked of the complete with connections required at site as per the satisfaction of Engineer-in-charge.	1	each	200	₹ Two Hundred only.	200
6	Providing & fixing GI Socket 32mm ISI Marked of the complete with connections required at site as per the satisfaction of Engineer-in-charge.	1	each	170	₹ One Hundred Seventy only.	170

7	Providing & fixing GI Nipple 4" x 32mm ISI Marked of the complete with connections required at site as per the satisfaction of Engineer-in-charge.	1	each	240	₹ Two Hundred Forty Only.	240
8	SITC of 1-Ph three speed double shaft 65 W, 230V electric motor with 930 rpm & Cap 4.00/440 Volt complete with connections, testing and commissioning etc. as reqd. complete in all respects as per satisfaction of engineer-in-charge.	2	each	3706	₹ Three Thousand Seven Hundred Six only.	7412
9	Providing & fixing motor pump seal complete with connections required at site as per the satisfaction of Engineer-in-charge.	1	each	1690	₹ One Thousand Six Hundred Ninety only.	1690
10	Dismantling of existing hot water supply and return lines up to 6 metres in length, of sizes 32 mm diameter, comprising heavy class C mild steel pipe, bends, flanges and other accessories, using gas cutter and welding machine as required, including stacking the dismantled material at a suitable location, complete as required.	1	Job	2200	₹ Two Thousand Two Hundred only.	2200
Note:- Less Credit for dismantled material (Lump-sum) Rs 500						
Total						76248


Assistant Engineer
Electrical Sub Division
HPPWD Snowdon, Shimla-1

Quantity of quantity approved, for Rs 76,248/- only.
Six hundred two hundred forty (76,248) only.
(Seventy)


Executive Engineer,
Electrical Division No.-II,
HPPWD (U.S. Club) Shimla-1

121

62

DRAFT SCHEDULE OF QUANTITY

Estimated Cost:- 57890/-

Earnest Money:-1200/-

Time :- 15 days

Name of Work:- R/M of Central Heating Plant at Block-C, Block-D building under IGM Shimla(SH:-Rewinding of 12.5 hp motor.motor starter ,400 Amps TP&N etc therein)


S.No	Description of items	Qty.	Unit	Rates		Amount
				In figures	In words	
1	Rewinding of 12.5HP motor i/c replacement of bearings i/c opening & refixing the motor from site as required complete in all respects as per the satisfaction of Engineer-in-charge.	1	job	17950	₹ Seventeen Nine Hundred Fifty only.	17950
2	Supply & fixing of Three Phase Hot water Pump Star Delta Controller/Starter (With Single Phase Preventer) Relay Range 28-42A 415V AC FASD(Fully Automatic Star Delta With Wideband Coil) i/c making necessary connections, testing as required (Havells/L&T/ABB)	1	each	20091	₹ Twenty Thousand Ninety only.	20091
3	Providing & fixing cable thimble 400 Amps complete with connections required at site as per the satisfaction of Engineer-in-charge.	2	each	260	₹ Two Hundred Sixty Only.	520
4	Providing & fixing AHU fan belt complete with connections required at site as per the satisfaction of Engineer-in-charge.	1	each	890	₹ Eight Hundred Ninety only.	890
5	Providing & fixing 400 Amps FN 400 TPN Switch Disconnect Fuse Unit S-D-F Conforming to IEC 60947-3, IS/IEC 60947-3 including Terminal Shrouds on both sides and Phase Barriers complete with connections required at site as per the satisfaction of Engineer-in-charge.	1	each	18439.00	₹ Eighteen Thousand Four Hundred Thirty Nine only.	18439
Note:-Less Credit for dismantled material (Lump-sum) Rs 1000						

DRAFT SCHEDULE OF QUANTITY


Estimated Cost:- 83600/-
 Earnest Money:- 1700/-
 Time :- One Week

Name of Work:- Providing & Laying of copper cable for earthing of medical equipment at Cancer hospital building at IGMC Shimla.

S.No	Description of items	Qty.	Unit	Rates		Amount
				In figures	In words	
1	Supplying and drawing following sizes of F.R.L.S PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required					
1.1	1X 35 Sq.mm	100	each	836	₹ Eight Hundred Thirty Six only.	83600
Total						83600


 Assistant Engineer
 Electrical Sub Division
 HPPWD Snowdon, Shimla-1

*Schedule of quantity approved for lbs B3 line / only.
 C figure Three thousand six hundred rupees only.*


 Executive Engineer
 Electrical Division No.-II,
 HPPWD (U.S. Club) Shimla-1