

Himachal Pradesh
Public works Department
Notice inviting Tender

Sealed percentage rate tenders on form 6 & 8 are invited by the Executive Engineer, Gohar Division, H.P.PWD Gohar for the following works from the approved and eligible contractors enlisted in H.P.PWD so as to reach in his office on or before **27-03-2026 up to 11.00 A.M.** and will be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The D.N.I.T. tender documents can be had from this office against cash payment (Non-refundable) up to 5.00 P.M. on **25-03-2026**. The applications for issue of tender forms will be received **up to 2.00 P.M. on 24-03-2026**.

The earnest money in the shape of National Saving Certificate/ Time deposit accounts/Saving account/F.D. Rs. in any of the Post Office/Nationalized Banks in Himachal Pradesh duly pledged in favour of the Executive Engineer must accompany the request for issue of tender form for each work. Conditional tenders and the tenders received without earnest money will summarily be rejected. The Executive Engineer reserves the right to reject the tenders without assigning any reason. It is further added that the rates be quoted both in words and figures for proper checking to avoid any complications. If the date of opening will be holiday, the tenders will be opened on the next working day at the same time.

Sr. No.	Name of road/work	Estimated Cost	Earnest Money	Time limit
1	RRD on Dhanotu to Rohangaloo road km. 0/00 to 32/400 (SH:- C/o PCC R/wall at RD 13/110 to 13/115.50) Under PDNA	98945	2000	Two Months
2	RRD on Khandail Nandi road km. 0/00 to 1/2654 (SH:- ROFD at km. 0/685 to 0/715)	98769	2000	One Month
3	RRD on Maloh kateru road km. 0/00 to 14/250 (SH:- Maintenance of Earthen Shoulder and removal of slips at various RDs in km. 6/00 to 14/250)	99572	2000	Two Months

Certified that tender of above works are being called for emergent nature in exigency of public interest.

GENERAL CONDITIONS:-

1. The Contractors are required to submit the valid Enlistment/GST registration and latest ITR alongwith application form.
2. The Contractors should quote the percentage rates in the tenders both in figures and words.
3. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
4. An undertaking will have to be given by the contractor that he has not more than two works in hand at the time of opening of this tender.

5. Contractors will have to submit appropriate Earnest Money in the shape of F.D.R along with the application form for getting issued the tender forms. Applications with out EMD shall be summarily rejected.
6. As per Govt. Notification No.PBW(B)A(3)1/2020-I dated 07-10-2021 the tenders above 5% of estimated cost will be summarily rejected. The tender offered below 30 % will also be accepted as per the office letter No. Engineer-in- Chief office letter No. PW-CTR/32-20/Genl Inst. CPWD-2020-37996-38096 dated 13.03.2023 and further ex- post-facto approval has been granted by the Principal Secretary (PW) to the Govt. of H.P. letter No. PBW (B) A(3)1/2020-I dated 10.05.2023. Beside this the additional performance security will have to borne by the bidders as per the said notifications.
7. Conditional and incomplete tenders shall be rejected.
8. The Executive Engineer reserves the right to accept or reject the tender without any reason.

Executive Engineer,
Gohar Division (B&R),
HPPWD Gohar.

Dated 17-03-2026

No. PW-GHR-Tender/NIT/2025 11436-47


Copy along with Tender inviting Notice forwarded for information:-

- 1 The Deputy Commissioner, Mandi H.P.
- 2 The Engineer-in-Chief HP.PWD.Shimla.
- 3 The Superintending Engineer 1stCircle, HP.PWD Mandi.
- 4 ✓ The Executive Engineer (IT Cell) O/O Engineer-in-Chief, HPPWD Nirman Bhawan, Nigam Vihar, Shimla-2 for uploading the NIT on departmental website please.
- 5 The Sub- Divisional Officer (Civil) Chachiot at Gohar.
- 6 The Block Development Officer Gohar.
- 7 The Assistant Engineer HPPWD Sub- Division Gohar/Dhanotu.
- 8 Various contractors.
- 9 Notice Board/DB/AB.

Executive Engineer,
Gohar Division (B&R),
HPPWD., Gohar.

BILL OF QUANTITY

Name of work :- RRD on Dhanotu to Rohangaloo road km 0/000 to 32/400(SH:- Construction of PCC R/Wall at RD 13/110 to 13/115.50) Under PDNA					Estimated cost Rs. - 98,945/-	
					Earnest Money cost Rs.2,000/-	
					Time - Two Month	
SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	6.38	Per Cubic meter	230.00		
2	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge completer in all respect.	19.97	Per Cubic meter	4350.20		
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge completer in all respect.	7.92	Per Cubic meter	1050.60		
4	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	6.00	Each	380.70		
Total:-						
Percentage rate Quoted in figure						
Percentage rate Quoted in words						


 Executive Engineer
 Gohar Division
 H.P.P.W.D. Gohar

BILL OF QUANTITY

of work :- RRD on Khandail Nandi road km. 0/00 to 1/265 (SH:- ROFD at km. 0/685 to 0/715) .

Estimated cost **98769.00**

Earnest Money cost Rs. - 2000

Time - One Month

Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Cutting in earth work by mechanical means in all heights and depths in all kinds of soils comprising of pick work, jumper work and blasting work both in soft and hard rock with chiseling and wedging out of rock (where blasting work is prohibited) and their intermediate classification of soils including, dewatering wherever required, setting of the required lines, levels as shown on the drawing and directed by the Engineer-in-charge at site, and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site (to be arranged by the contractor) as per satisfaction of Engineer-in-charge through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools , equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required). All useful material such as stones, shingles aggregate and slates shall be properly stacked at site to the maximum possible extent in all leads and lifts through all modes of transportation as per the directions of the Engineer-in-charge. The recovery of stones, whether useful or not for 48.45 cum @ Rs. 300/- per cubic metre to Rs. 14535/- only shall be effected on pro rate basis in all circumstances. Any loss to the public and private property, human being, machinery during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.	420.22	Per Cubic metre	235.04		
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					


 Executive Engineer
 Gohar Division
 H.P.P.W.D. Gohar

BILL OF QUANTITY

Name of work :- RRD on Maloh Kateru road km. 0/00 to 14/250 (SH:- Maintenance of Earthen shoulder and removal of slips at various Rds. In km. 6/00 to 14/250).

Estimated cost Rs. - 99572.00

Earnest Money cost Rs. -2000.00

Time - One Month

Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Maintenance of Earthen shoulder (filling with fresh selected soil) Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil upto a lead of 1000 m as per technical specification Clause 1903 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	1632.00	Per Square Meter	30.20		
2	Removal of land slides in hilly area in ordinary rock not requireing blasting by mechanical means including cutting and trimming or slops and disposal of cut material with in all leads and lifts, stacking the serviceable material and disposal of unserviceable material as per technical specification, clause 302.3.5 and 1611 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	478.46	Per Cubic metre	105.10		
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					