

**Himachal Pradesh  
Public works Department  
Notice inviting Tender**

Sealed percentage rate tenders on form 6 & 8 are invited by the Executive Engineer, Gohar Division, H.P.PWD Gohar for the following works from the approved and eligible contractors enlisted in H.P.PWD so as to reach in his office on or before **30-03-2026 up to 11.00 A.M.** and will be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The D.N.I.T. tender documents can be had from this office against cash payment (Non-refundable) up to 5.00 P.M. on **28-03-2026**. The applications for issue of tender forms will be received **up to 2.00 P.M. on 27-03-2026**.

The earnest money in the shape of National Saving Certificate/ Time deposit accounts/Saving account/F.D. Rs. in any of the Post Office/Nationalized Banks in Himachal Pradesh duly pledged in favour of the Executive Engineer must accompany the request for issue of tender form for each work. Conditional tenders and the tenders received without earnest money will summarily be rejected. The Executive Engineer reserves the right to reject the tenders without assigning any reason. It is further added that the rates be quoted both in words and figures for proper checking to avoid any complications. If the date of opening will be holiday, the tenders will be opened on the next working day at the same time.

Sr. No.	Name of road/work	Estimated Cost	Earnest Money	Time limit
1	RRD on Dhanotu to Rohangaloo road km. 0/00 to 32/400 (SH:- C/o PCC R/wall on existing Toe wall RD 13/825 to 13/840) Under PDNA	498032	10000	Two Months
2	RRD on BBMB Colony to Sushan jawala road km. 0/00 to 3/00 (SH:- C/o Unlined surface drain, surface dressing, earth filling and Removal of slip in km. 0/00 to 3/00)	98162	2000	Two Months
3	RRD on Katal Dharamdwara road km. 0/00 to 13/00 (SH:- C/o unlined surface drain, surface dressing , earth filling and Removal of slip in km 0/00 to 13/00)	99271	2000	Two Months
4	RRD on Hateshwari Templel to shetal road km. 0/00 to 4/660(SH:- C/o unlined surface drain, surface dressing , earth filling and Removal of slip in km 0/00 to 4/660)	98775	2000	Two Months
5	RRD on Bhadetar Kandha Parua road km. 0/00 to 6/00 (AH:- Removal of slip, Maintenance of shoulder/berms in km. 0/00 to 6/00)	98955	2000	Two Months
6	RRD on Dhanotu Jaidevi rohangaloo road km. 13/00 to 32/400 (SH:- Removal of balance slips on various RDs between km. 17/00 to 21/630)	99875	2000	One Month
7	RRD on Khandail Nandi road km. 0/00 to 1/265 (SH:- Formation Cutting at km. 0/720 to 0/755)	94922	2000	Two Months

Certified that tender of above works are being called for emergent nature in exigency of public interest.

**GENERAL CONDITIONS:-**

1. The Contractors are required to submit the valid Enlistment/GST registration and latest ITR alongwith application form.
2. The Contractors should quote the percentage rates in the tenders both in figures and words.
3. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
4. An undertaking will have to be given by the contractor that he has not more than two works in hand at the time of opening of this tender.
5. Contractors will have to submit appropriate Earnest Money in the shape of F.D.R along with the application form for getting issued the tender forms. Applications with out EMD shall be summarily rejected.
6. As per Govt. Notification No.PBW(B)A(3)1/2020-I dated 07-10-2021 the tenders above 5% of estimated cost will be summarily rejected. The tender offered below 30 % will also be accepted as per the office letter No. Engineer-in- Chief office letter No. PW-CTR/32-20/Genl Inst. CPWD-2020-37996-38096 dated 13.03.2023 and further ex- post-facto approval has been granted by the Principal Secretary (PW) to the Govt. of H.P. letter No. PBW (B) A(3)1/2020-I dated 10.05.2023. Beside this the additional performance security will have to borne by the bidders as per the said notifications.
7. Conditional and incomplete tenders shall be rejected.
8. The Executive Engineer reserves the right to accept or reject the tender without any reason.

Executive Engineer,  
Gohar Division (B&R),  
HPPWD Gohar.

Dated 19-03-2026

No. PW-GHR-Tender/NIT/2025 11751-62

**Copy along with Tender inviting Notice forwarded for information:-**

1. The Deputy Commissioner, Mandi H.P.
2. The Engineer-in-Chief HP.PWD.Shimla.
1. The Superintending Engineer 1<sup>st</sup>Circle, HP.PWD Mandi.
2. **The Executive Engineer (IT Cell) O/O Engineer-in-Chief, HPPWD Nirman Bhawan, Nigam Vihar, Shimla-2 for uploading the NIT on departmental website please.**
3. The Sub- Divisional Officer (Civil) Chachiot at Gohar.
4. The Block Development Officer Gohar.
5. The Assistant Engineer HPPWD Sub- Division Gohar/Dhanotu.
6. Various contractors.
7. Notice Board/DB/AB.

Executive Engineer,  
Gohar Division (B&R),  
HPPWD., Gohar.

## BILL OF QUANTITY



of work :- RRD on Dhanotu to Rohangaloo road km 0/00 to 32/400 (SH:- Construction of PCC R/Wall on <sup>balanced work</sup> existing Toe wall at RD 13/825 to 13/840) Under PDNA

Estimated cost Rs. - 4,98,032/-

Earnest Money cost Rs.10,000/-

Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge completer in all respect.	99.00	Per Cubic meter	4350.20		
2	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge completer in all respect.	59.77	Per Cubic meter	1050.60		
3	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm ( one hundred millimetre ) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	12.00	Each	380.70		
	<b>Total:-</b>					
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					

  
 Executive Engineer  
 Gohar Division  
 H.P.P.W.D. Gohar  


## BILL OF QUANTITY



of work :- RRD on BBMB Colony to Sushan Jawala road km 0/00 to 3/00 (SH:- C/o Unlined surface  
in, surface dressing, earth filling and Removal of slip in KM 0/00 to 3/00)

Estimated cost Rs. - 98,162/-

Earnest Money cost Rs.2,000/-

Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Maintenance of earthen shoulder (Filling with fesh selected soil) Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903 within all leads , lifts and carriage of materials and other incidentals. as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	639.00	per square metre	30.20		
2	Maintenance of earthen shoulder (stripping of excess soil) Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 within all leads , lifts and carriage of materials and other incidentals.	1185.00	per square metre	15.10		
3	Construction of unlined surface drains of average cross-sectional area 0.20sqm ( zero point two zero square metre ) in ordinary rock to specified lines, grades, levels and dimensions. excavated material to be used in embankment with a lift upto any metre and lead of any metere as per Technical Specification Clause 307 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	1200.00	per Running metre	22.20		
4	Removal of landslide/slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in any lift and lead upto 1.5 m and land upto 1000 meter as per technical specification 302.3.5 and 1611 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	326.64	per Cubic metre	105.10		
<b>Total:-</b>						
<b>Percentage rate Quoted in figure</b>						
<b>Percentage rate Quoted in words</b>						



  
 Executive Engineer  
 Gohar Division  
 H.P.P.W.D. Gohar  


## BILL OF QUANTITY

of work :- RRD on Natal Katal Dharmdwara road km 0/00 to 13/00 (SH:- C/o Unlined surface drain, face dressing, earth filling and Removal of slip in KM 0/00 to 13/00)

Estimated cost Rs. - 99,271/-  
Earnest Money cost Rs.2,000/-  
Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Maintenance of earthen shoulder (Filling with fesh selected soil) Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer in charge with in all leads lifts and carriage of <u>materials and other incidentals.</u>	2700.00	per square metre	30.20		
2	Construction of unlined surface drains of average cross-sectional area 0.20sqm ( zero point two zero square metre ) in ordinary rock to specified lines, grades, levels and dimensions. excavated material to be used in embankment with a lift upto any metre and lead of any metere as per Technical Specification Clause 307 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	575.00	per Running metre	22.20		
3	Removal of landslide/slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in any lift and lead upto 1.5 m and land upto 1000 meter as per technical specification 302.3.5 and 1611 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	47.25	per Cubic metre	105.10		
<b>Total:-</b>						
Percentage rate Quoted in figure						
Percentage rate Quoted in words						

  
 Executive Engineer  
 Gohar Division  
 H.P.P.W.D. Gohar  


## BILL OF QUANTITY


of work :- RRD on Hateshwari Temple to Shetal road km 0/00 to 4/660 (SH:- C/o Unlined surface  
in, surface dressing, earth filling and Removal of slip in KM 0/00 to 4/660)

Estimated cost Rs. - 98,775/-

Earnest Money cost Rs.2,000/-

Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Maintenance of earthen shoulder (Filling with fesh selected soil) Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	624.00	per square metre	30.20		
2	Maintenance of earthen shoulder (stripping of excess soil) Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 within all leads , lifts and carriage of materials and other incidentals.	1200.00	per square metre	15.10		
3	Construction of unlined surface drains of average cross-sectional area 0.20sqm ( zero point two zero square metre ) in ordinary rock to specified lines, grades, levels and dimensions. excavated material to be used in embankment with a lift upto any metre and lead of any metere as per Technical Specification Clause 307 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	1200.00	per Running metre	22.20		
4	Removal of landslide/slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in any lift and lead upto 1.5 m and land upto 1000 meter as per technical specification 302.3.5 and 1611 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	334.63	per Cubic metre	105.10		
<b>Total:-</b>						
Percentage rate Quoted in figure						
Percentage rate Quoted in words						

  
 Executive Engineer  
 Gohar Division  
 H.P.P.W.D. Gohar

### BILL OF QUANTITY



Name of work :- RRD on Bhadetar Kandha Parua road km 0/00 to 6/00(SH:- Removal of slip, Maintenance of shoulder/berms in km 0/00 to 6/00)

Estimated cost Rs. 98,955/-

Earnest Money cost Rs. 2000/-

Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Maintenance of earthen shoulder (Filling with fesh selected soil) Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	1862.00	per square metre	30.20		
2	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in any lift and lead upto 1000 m as per technical specification 302.3.5 and 1611 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals in all leads and lifts and as per direction of Engineer in charge .	406.50	Per Cubic meter	105.10		
	<b>Total:-</b>					
	<b>Percentage rate Quoted in figure</b>					
	<b>Percentage rate Quoted in words</b>					

  
 Executive Engineer  
 Gohar Division  
 H.P.P.W.D. Gohar  


**BILL OF QUANTITY**


Name of work :- RRD on Dhanotu Jaidevi Rohangaloo road km. 13/00 to 32/400 (SH:- Removal of balance slips on various Rds between km. 17/00 to 21/630)

Estimated cost Rs. - 99875.00

Earnest Money cost Rs. -2000.00

Time - One Month

Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Removal of land slides in hilly area in ordinary rock not requireing blasting by mechanical means including cutting and trimming or slops and disposal of cut material with in all leads and lifts, stacking the serviceable material and disposal of unserviceable material as per technical specification, clause 302.3.5 and 1611 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	950.29	Per Cubic metre	105.10		
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					

  
 Executive Engineer  
 Gohar Division  
 H.P.P.W.D. Gohar

## BILL OF QUANTITY


Name of work :-RRD on Khandail Nandi road km 0/00 to 1/265( SH:- Formation Cutting at KM 0/720 to 0/755)

Estimated cost Rs. - 94,922/-

Earnest Money cost Rs. 2000/-

Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimate d Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Excavation in soil in hill area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper blasting work both in soft and hard rock with chiseling / wedging out side of rock ( where blasting is prohibited ) and their intermediate classification of soil including dewatering where required setting out to the required line grades , side slopes trimming bottom and level as shown on drawings as directed by the Engineer -in charge at site according to technical clause 1603.1 and 1603.2 sorting useful / un-useful materials and stacking the same in all leads and lifts and transportation of the un-useful materials for filling in roads ways , embankments for grades improvements and leveling to the require grade and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites through all modes of transportation including head load animal load or mechanical means along with its leveling fine dressing and all labour, machineries , materials , tools equipment's and sefety measures and incidentals necessary to complete the work by all means ( if any required ) recovery for <b>46.75 cubic metre @ Rs. 300.00</b> per cubic metre amount <b>Rs.14,025/-</b> shall be done on prorata basis for the quantity of cutting in earth work effected . Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor , which shall have to be duly compensated by him in all respect including all leada and lifts and materials and as per direction of Engineer in charge .	443.85	Per Cubic meter	213.86		
	<b>Total:-</b>					
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					

  
 Executive Engineer  
 Gohar Division  
 H.P.P.W.D. Gohar  
