

Himachal Pradesh
Public Works Department

No. PWH/HD/CB/T-I/2025-26
To

14237-39

Dated: - 25/03/2026


The Executive Engineer (IT Cell)
Nirman Bhawan, Nigam Vihar,
Shimla-2

Subject: - Publication of Notice inviting tender.

Sir,


Enclosed please find herewith copy of notice inviting tender for publishing on departmental website for favour of further necessary action please.

Encl: As above


Executive Engineer,
HPPWD Division Haroli,
Distt. Una HP).


Copy along with copy of notice inviting tender is forwarded for information and necessary action to:-

1. The Superintending Engineer, 15th Circle, HP: PWD, Una.
2. Copy to Notice board.


Executive Engineer,
HPPWD Division Haroli,
Distt. Una HP).

Certificate

Certified that the tenders for the works called vide this office letter No. PWH/HD
1/2025-26-14237-39 dated 25/3/2026 are required to be carried out immediately being emergent na
work in public interest.


Executive Engineer,
Haroli Division, HPPWD
Haroli Distt. Una (HP).

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
" NOTICE INVITING TENDERS "

Percentage rate tender on PWD Form No. 6 & 8 are hereby invited by the Executive Engineer, Haroli Division H.P. on behalf of Governor of H.P for the following works from the approved and eligible contractors/firms enlisted in the PWD Department as per latest instructions, so as to reach and open in his office as per time schedule given below. The office for opening the tender will be open for 45 days from the date of opening of tenders. The undersigned reserves the right to reject any of the tenders without assigning any reasons.

1. Date of receipt of application for the tender form a/w requisite documents: -
2. Date of issue/sale of tender forms against cash payment(non-refundable): -
3. Date of receipt of tenders: -
4. Date of opening of tenders: -

20/03/2024 up to 10.30 (AM).
31.03.2024 up to 3.00 PM
31-03-2024 up to 10.30 AM
31-03-2024 at 11.00 AM

Sr. No.	Name of work	Estimated cost	EMD	Time Limit	Cost of tender	Eligible class of contractor
1	2	3	4	5	6	7
1	C/O Driving Training Track and Traffic park at Rora, Haroli Distt. Una (SH:-P/F curve stone in campus area of traffic park-Phase-II(Deposit Work)	99110	2000/-	One Month	350/-	Class- C & D
2	Balance Work restoration & rain damages Old Saloh Bhadouri km. 0/00 to 9/600(SH:-C/O R/wall RD. 1/080 to 1/097.80 LHS)	98834	2000/-	One Month	350/-	Class- C & D
3	C/O Driving Training Track and Traffic park at Rora, Haroli Distt. Una (SH:-Providing & applying white cement based putty on Boundary wall length= 324.00 mtr. & Providing & applying Apex paint on Boundary wall length=38.00 mtr.)	99252	2000/-	One month	350/-	Class- C & D
4	C/O Driving Training Track and Traffic park at Rora, Haroli Distt. Una(SH:- P/F ACP sheet On Main Gate) (Deposit Work)Phase-VI (Balance Work)	99704	2000/-	One month	350/-	Class- C & D
5	Balance work Upgradation of link road Umrli Heeran Thara Pubowal to Polian via Kuthar Beet km. 7/00 to 9/900 (SH:-C/O Breast wall at RD. 8/417 to 8/434.50)	99806	2000/-	One month	350/-	Class- C & D
6	C/O Driving Training Track and Traffic park at Rora, Haroli Distt. Una (SH:-Painting on kerb in campus of Traffic Park length=960= mtr. & Approach road parapet=50.00 Nos. etc.)	98516	2000/-	One month	350/-	Class- C & D
7	C/O Driving Training Track and Traffic park at Rora, Haroli Distt. Una(SH:- P/F ACP sheet On Main Gate) (Deposit Work)Phase-VII (Balance Work)	99613	2000/-	One month	350/-	Class- C & D
8	Construction of collage Building at Govt. Degree Collage Haroli Distt. Una (SH:-Balance Painting works of Boundary wall-Phase-II) Deposit Work	99822	2000/-	One Month	350/-	Class- C & D
9	C/O Driving Training Track and Traffic Park at Rora, Haroli Distt. Una (SH:-Providing & applying Apex paint on Boundary wall length=71.00 mtr. & Painting of kerb stone in campus of Traffic park length=720 mtr.)	99133	2000/-	One Month	350/-	Class- C & D
10	C/O Driving Training Track and Traffic park at Rora, Haroli Distt. Una(SH:- P/F curve stone campus area of Traffic park) (Deposit Work)Phase-V (Balance Work)	98770	2000/-	One Month	350/-	Class- C & D

11	Upgradation of link road Umrali Heeran Thara Pubowal to Polian via Kuthar Beet km. 7/00 to 9/900 (SH:-C/O 900mm dia hume pipe culvert at RD. 8/720)	99874	2000/-	One Month	350/-	Class- C & D
12	C/O Driving Training Track and Traffic park at Rora, Haroli Distt. Una(SH:- P/F curve stone campus area of Traffic park) (Deposit Work)Phase-I (Balance Work)	99450	2000/-	One Month	350/-	Class- C & D
13	A/R & M/O on Panjwar bathri road km. 0/00 to 26/300(SH:-P/F cate eye & P/L hot applied thermoplastic on Haroli bridge approach at RD. 23/050)	99585	2000/-	One Month	350/-	Class- C & D
14	C/O Driving Training Track and Traffic park at Rora, Haroli Distt. Una(SH:-Providing & applying Apex paint on Boundary wall length=215-00 mtr.)	99330	2000/-	One Month	350/-	Class- C & D
15	Upgradation of link road Umrali Heeran Thara Pubowal to Polian via Kuthar Beet km. 7/00 to 9/900 (SH:-C/O 900mm dia hume pipe culvert at RD. 8/440)Phase-I	99658	2000/-	One Month	350/-	Class- C & D
16	C/O Driving Training Track and Traffic park at Rora, Haroli Distt. Una(SH:- P/F ACP sheet On Main Gate) (Deposit Work)Phase-VIII (Balance Work)	99521	2000/-	One Month	350/-	Class- C & D
17	A/R & M/O on Una Haroli Palkwah Polian Jaijon road km. 0/00 to 23/00(SH:-P/F Acrylics signages near Rampur bridge Phase-II)	89680	2000/-	One Month	350/-	Class- C & D
18	C/O Driving Training Track and Traffic park at Rora, Haroli Distt. Una(SH:- Painting on parapets of Approach road of traffic park & steel painting of main gate)	97512	2000/-	One Month	350/-	Class- C & D
19	C/O Driving Training Track and Traffic park at Rora, Haroli Distt. Una(SH:- P/F ACP sheet On Main Gate) (Deposit Work)Phase-X (Balance Work)	99796	2000/-	One Month	350/-	Class- C & D
20	A/R & M/O on Una Haroli Palkwah Polian Jaijon road km. 0/00 to 23/00(SH:-P/F Acrylics signages near Rampur bridge Phase-I)	89680	1760/-	15 days	350/-	Class- C & D
21	C/O Driving Training Track and Traffic park at Rora, Haroli Distt. Una(SH:- P/F curve stone campus area of Traffic park) (Deposit Work)Phase-VI (Balance Work)	99280	2000/-	One Month	350/-	Class- C & D
22	Construction of Collage Building at Govt. Degree Collage Haroli Distt. Una (SH:-Balance Painting works of Boundary wall-Phase-III) Deposit Work	99678	2000/-	One Month	350/-	Class- C & D
23	C/O Driving Training Track and Traffic park at Rora, Haroli Distt. Una(SH:- P/F curve stone campus area of Traffic park) (Deposit Work)Phase-IV (Balance Work)	98600	2000/-	One Month	350/-	Class- C & D
24	Construction of Collage Building at Govt. Degree Collage Haroli Distt. Una (SH:-Balance Painting works of Boundary wall-Phase-I) Deposit Work	99966	2000/-	One Month	350/-	Class- C & D
25	Construction of Collage Building at Govt. Degree Collage Haroli Distt. Una (SH:-Balance Painting works of Boundary wall-Phase-III) Deposit Work	98940	2000/-	One Month	350/-	Class- C & D
26	C/O Driving Training Track and Traffic Park at Rora Haroli distt. Una (SH:-P/F cat eye & P/L hot applied thermoplastic on approach road) Deposit Work (Balance work)	98740	2000/-	One Month	350/-	Class- C & D
27	C/O Driving Training Track and Traffic Park at Rora Haroli distt. Una (SH:-P/F ACP Sheet On Main Gate)Deposit Work Phase-X	99796	2000/-	One Month	350/-	Class- C & D

28	C/O Driving Training Track and Traffic Park at Rora Haroli distt. Una (SH:-P/F ACP Sheet On Main Gate)Deposit Work Phase-IX	99704	2000/-	One Month	350/-	Class- C & D
29	C/O heliport at Rora tehsil Haroli Distt. Una (SH:-Preparation of working estimate of Heliport) Deposit Work	99900	2000/-	One Month	350/-	Class- C & D
30	Restoration of rain damages on Panjwar bathri to mata ka Mandir Lower badhera via Rajesh House Saloh Nalka to Kumaran abadi km. 0/00 to 2/700(SH:-Repair of rain cut at various RDs.)	99840	2000/-	One Month	350/-	Class- C & D

The earnest money in the shape of National Saving certificate/ time deposit/ saving account of any post office or FDR, Nationalized bank duly pledged in the name of undersigned must be accompanied with each tender. The conditional tender and tender not accompanying the earnest money in the proper mode of deposit will summarily be rejected. The tender documents to be sent should have invariably be waxed in sealed cover and in failure of that those will not be entertained. The copy of valid enlistment, GST registration No., Income Tax, Pan No. and epf no. must be attached with application.

SPECIAL CONDITION: -

1. The contractor/firm shall have his resignation and GST No. and copy of same be attached with the application.
2. The earnest money for the above work should be submitted duly pledged in favour of Executive Engineer, Haroli Division HPPWD with the application for the purchase of tender forms. The application received without earnest money shall summarily be rejected.
3. The contractor/firms are required to insert the rate in words as well as figures, failing which Executive Engineer reserves the right to accept/rejects any or all tenders. If any of the date mentioned above happens to be local/gazetted holidays, the same shall be process on next date.
4. The tender form will be issued to those contractors who have relevant machinery and equipment, the list of which may be attached with their application a/w proof of ownership of machinery/legal tie up arrangement).
5. The Executive Engineer reserves the right to reject or cancel any or all tenders without assigning any reasons.
6. The conditional/ambiguous/telegraphic tenders by fax shall not entertained/considered in any case.

HIM SUCHANA AVAM JAN SAMPARK.

Executive Engineer
HPPWD Division Haroli
Distt.Una(HP).Pin Code-177220
Email: ee-haroli-hp@hp.gov.in
On behalf of Governor of Himachal Pradesh

19

Schedule of quantity

Name of work :- Balance Work Retoration & rain damages Old Saloh Bhadouri km. 0/00 to 9/600		Estimated Cost: Rs		Time:-		One month
(SH: C/O R/wall Rd. 1/080 to 1/097.80 Lhs)						2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	5.14	Cum.	160.00	Rupees One Hundred Sixty Only	822
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	27.50	Cum.	3300.00	Rupees Three Thousand Three Hundred Only	90753
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	16.00	Cum.	160.00	Rupees One Hundred Sixty Only	2560
4	Back filling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.54	Cum.	550.00	Rupees Five Hundred Fifty Only	4699
					Total	98834
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018					
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					

3

Schedule of quantity

Name of work :- C/O Driving Training Track and Traffic Park at Rora, Haroli Distt. Una.						Estimated Cost: Rs	₹ 99,252
						Time:-	One month
(SH: Providing & applying white cement based putty on Boundary wall length = 324.00 mtr. & Providing & applying Apex paint on Boundary wall length = 38.00 mtr)						Earnest Money:-	2000
S.No.	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount	
1	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1276.51	Sqm	64.00	Rupees SixtyFour Only	81696	
2	Providing and applying Apex paint (two or more coats) on any surface with Asian paint, Nerolac, Burger at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat preparation of surface, etc. complete as per direction of Engineer in charge including carriage of material within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkhana, GST toll tax sale tax other taxes imposed by the Govt.	133.00	Sqm	132.00	Rupees One Hundred ThirtyTwo Only	17556	
						Total	99252
Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018							
2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021							
Percentage quoted rate in figures							
Percentage quoted rate in words							
Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected							

Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H.P.)

SCHEDULE OF QUANTITY

Estimated cost 99806
 Earnest money 2000
 Time limit One month

Name of work: Balance work of Upgradation of link road Umralli Heeran Thara Pubowal to Polian via Kuthar Beet Km 7/00 to 9/900 (SH: C/O breast wall at RD 8/417 to 8/434.50)

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	9.63	Per cubic metre	160.00	Rupees one hundred sixty only	1541
2	Providing and laying cement concrete 1:4:8 (one cement: four sand: eight graded crushed stone aggregate 40mm(forty millimeter nominal size) mechanically mixed and curing complete including cost of form work in foundation and plinth in all heights / depths including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	29.05	Per cubic metre	3300.00	Rupees Three thousand two hundred fifty only.	95865
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)/dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax, octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	15.00	Each	160.00	Rupees One hundred sixty only	2400
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)(17)2/0212 dated 7.8.2018					
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy, PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
					Total	99806

Percentage quoted rate in Figures	
Percentage quoted rate in words	
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.	


 Executive Engineer,
 H.P.W.D. Division Haroli
 Distt. Una (H.P.)

Schedule of quantity

Name of work :- C/O Driving Training Track and Traffic Park at Rora, Haroli Distt. Una.		Estimated Cost: Rs		₹ 98,516		
		Time:-		One month		
(SH: Painting of kerb stone in campus of Traffic park length = 960.00 mtr & Approach road parapet =50.00 nos etc.)		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Providing and applying Apex paint (two or more coats) on any surface with Asian paint, Nerolac, Burger at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat preparation of surface, etc. complete as per direction of Engineer in charge including carriage of material within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkhana, GST toll tax sale tax other taxes imposed by the Govt.	746.34	Sqm	132.00	Rupees One Hundred ThirtyTwo Only	98516
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				Total	98516
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					


 Executive Engineer,
 H.P.P.W.D. Division Haroli
 Distt. Una (H.P.)

SCHEDULE OF QUANTITY

		Estimated Cost	99822			
		Earnest Money	2000			
		Time limit	One month			
Name of work:- Construction of college Building at Govt Degree College Haroli Distt Una (SH:- Balance Painting works of Boundary wall - Phase-II)-D/work						
S No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Painting steel work with Deluxe Multi surface paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture including entire carriage of material within all leads and lifts and other incidentals as per the direction of Engineer-in-charge. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	102.00	Per Square meter	85	Rupees eighty five only	8670
2	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	633.00	Per Square meter	12.00	Rupees twelve only	7596
3	Providing and applying apex paint (two or more coats) on any surface with Asian paint, Nerolac, Burger at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat preparation of surface, etc. complete as per direction of Engineer in charge including carriage of material within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkhana, GST toll tax sale tax other taxes imposed by the Govt.	633.00	Per Square meter	132.00	Rupees one hundred thirty two only	83556
				Total		99822
NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17)2/0212 dated 7.8.2018						
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandatory by the contractoe						

(a)

Schedule of quantity

Name of work :- C/O Driving Training Track and Traffic Park at Rora, Haroli Distt. Una.					Estimated Cost: Rs	₹ 99,133
					Time:-	One month
(SH: Providing & applying Apex paint ^{PH} boundary wall length =71.00 mtr & painting of kerb stone in campus of Traffic park length =720.00 mtr.)					Earnest Money:-	2000
S.NO	DESCRIPTION	Qty	Unit	T. Rate	Rate in words	Amount
1	Providing and applying Apex paint (two or more coats) on any surface with Asian paint, Nerolac, Burger at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat preparation of surface, etc. complete as per direction of Engineer in charge including carriage of material within all leads and lifts and other incidentials. The rate including octroi, royalty, Malkhana, GST toll tax sale tax other taxes imposed by the Govt.	751.01	Sqm	132.00	Rupees One Hundred ThirtyTwo Only	99133
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				Total	99133
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					


 Executive Engineer,
 H.P.P.W.D. Division Haroli
 Distt. Una (H.P.)

FUB

Schedule of quantity

Name of work :- C/O Driving Training Track and Traffic Park at Rora, Haroli Distt. Una. (SH: Providing & fixing curve stone in campus area of traffic park - Phase-v (Deposit work) (Balance work)		Estimated Cost: Rs		₹ 98,770		
		Time:-		One month		
		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Providing and fixing curve stone 80mm(Eighty millimeter) thick size 0.30m x 0.30m complete as per direction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government ..	581.00	Each	170.00	Rupess one hundred Seventy only	98770
					Total:	98770
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018					
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

SCHEDULE OF QUANTITY

Estimated cost 99874
 Earnest money 2000
 Time limit One month

Name of work: Upgradation of link road Umralli Heeran Thara Pubowal to Polian via Kuthar Beet Km-7/00 to 9/900 (SH: C/O 900mm dia hume pipe culvert at RD 8/720)

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	6.72	Per cubic metre	160.00	Rupees one hundred sixty only	1075
2	Providing and laying cement concrete 1:4:8 (one cement: four sand: eight graded crushed stone aggregate 40mm(forty millimeter nominal size) mechanically mixed and curing complete including cost of form work in foundation and plinth in all heights / depths including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	3.16	Per cubic metre	3300.00	Rupees Three thousand two hundred fifty only.	10428
3	Providing and laying (M-10 Grade)(M-Ten) vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification MORD 2014 Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	12.96	Per cubic metre	3850.00	Rupees Three thousand eight hundred fifty only	49896
4	Providing and laying non-pressure NP-3 class (light duty) RCC pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (One cement : two fine sand) including testing of joints etc. complete 900mm dia RCC pipe including carriage of materials within all leads and lifts. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	7.50	Per running metre	4850.00	Rupees four thousand eight hundred fifty only.	36375
5	Construction of embankment with approved material obtained from borrow pits lift upto any height and compacted to meet requirement of Table 300.1 and 300.2 within any lead as per Technical Specification Clause 301.5 including carriage of material with in all leads and lifts and other incidentals as per MORD specification 2014. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	8.40	Per cubic metre	250.00	Rupees two hundred fifty only.	2100
				Total		99874

Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.

Executive Engineer,
 H.P.P.W.D. Division Harohi
 Distt. Una (H.P.)

12

Schedule of quantity

Name of work :- C/O Driving Training Track and Traffic Park at Rora, Haroli Distt. Una. (SH:Providing & fixing curve stone in campus area of traffic park - Phase-1 (Deposit work) (Balance work)		Estimated Cost: Rs		₹ 99,450		
		Time:-		One month		
		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Providing and fixing curve stone 80mm(Eighty millimeter) thick size 0.30m x 0.30m complete as per direction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government ..	585.00	Each	170.00	Rupess one hundred Seventy only	99450
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17)2/0212 dated 7.8.2018				Total:	99450
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					

Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H.P.)

TS

Schedule of Quantity

13

Estimated Cost: Rs. 99585
Earnest Money: Rs. 2000-
Time Limit: One Month

Name of work: A/R & M/O on Panjawaar Bathri road Km 0/00 to 26/300 (SH: P/F cat eye & P/L hot applied thermoplastic on Haroli bridge approach at RD 23/050)

Sr. No.	Sub-Head and Items of work	Quantity	Unit	Rates in		Amount
				Figures	Words	
1	Providing and laying of hot applied thermoplastic compound 2.5 mm (two point five millimetre)thick including reflectorising glass beads @ 250 gms (at the rate of two hundred fifty gram per square metre)per sqm area, thickness of 2.5 mm(two point five millimetre) is exclusive of surface applied glass beads as per IRC:35 .The finished surface to be level, uniform and free from streaks and holes as per entire direction of Engineer-in - Charge including carriage of material within all leads and lifts .The rates are inclusive of octroi, royalty, Malkana, toll tax, GST , sale tax or other taxes imposed by the Government.	114.00	Per Square metre	580.00	Rupees six hundred fifty only	66120
2	Providing and fixing cat eye make(3M) of size 100x20mm made of heavy duty body shall be molded dual shank ASA /Acyclic styrene acrylonitrile) or HP/High impact polystyrene) ort ABS having electronically welded micro prismatic lens with abrasion resistant coating as approved by Engineer-in-charge. The road stud shall support a load of 13635 by tested in accordance with ASTM D4280.The slope of retro reflective surface shall be 35+/-5 degrees to base. The reflective panels on both side with at least 12cm. of each area side. The luminance intensity should be as per the specification ASTM as recommended in BS-8873 part 4 1973 as per approved sample and manufacture by the Engineer-in-charge .including carriage of material within all leads and lifts .The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	78.00	Each	280.00	Rupees two hundred eighty only	21840
3	Construction of sub grade and earthen shoulder with approved material obtained from borrow pits and laid in layers of suitable thickness not exceeding 200mm (two hundred millimetres) and compacted with 80-100 KN (Eighty to one hundred Kilonewton). static/ vibratory road roller to meet the requirements of table 300.1 and 300.2 of MORD 2014 specifications clause 303. The rate shall include carriage of machineries, equipment, tolls and materials and safety measures, payment of all taxes and other incidentals necessary to complete the work in all respects as per direction of Engineer-in-charge including entire carriage of materials within all leads lifts and other incidentals and per direction of Engineer-in-Charge. The rate excludes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	46.50	Per cubic metre	250.00	Rupees two hundred fifty only.	11625
	Total					99585
Note:-						
1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)(17)2/0212 dated 7.8.2018						
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(31)/2020 dated 22.07.20						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandatory by the contractor , otherwise the tender will be rejected.						

Executive Engineer,
H. P. W. D. Division Haroli
Distt. Una (H.P.)

14

Schedule of quantity

Name of work :- C/O Driving Training Track and Traffic Park at Rora, Haroli Distt. Una.		Estimated Cost: Rs		₹ 99,330		
		Time:-		One month		
		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Providing and applying Apex paint (two or more coats) on any surface with Asian paint, Nerolac, Burger at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat preparation of surface, etc. complete as per direction of Engineer in charge including carriage of material within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkhana, GST toll tax sale tax other taxes imposed by the Govt.	752.50	Sqm	132.00	Rupees One Hundred Thirty Two Only	99330
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018				Total	99330
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					

Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H.P.)

SCHEDULE OF QUANTITY

Estimated cost 99658
 Earnest money 2000
 Time limit One month

15

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	6.72	Per cubic metre	160.00	Rupees one hundred sixty only	1075
2	Providing and laying cement concrete 1:4:8 (one cement: four sand: eight graded crushed stone aggregate 40mm(forty millimeter nominal size) mechanically mixed and curing complete including cost of form work in foundation and plinth in all heights / depths including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	3.16	Per cubic metre	3300.00	Rupees Three thousand two hundred fifty only.	10428
3	Providing and laying (M-10 Grade)(M-Ten) vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification MORD 2014 Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government..	13.37	Per cubic metre	3850.00	Rupees Three thousand eight hundred fifty only.	51475
4	Providing and laying non-pressure NP-3 class (light duty) RCC pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (One cement : two fine sand) including testing of joints etc. complete 900mm dia RCC pipe including carriage of materials within all leads and lifts. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	5.00	Per running metre	4850.00	Rupees four thousand eight hundred fifty only.	24250
5	Providing and laying non-pressure NP-3 class (light duty) RCC pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (One cement : two fine sand) including testing of joints etc. complete 750mm dia RCC pipe including carriage of materials within all leads and lifts. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	2.50	Per running metre	4000.00	Rupees four thousand only.	10000

Name of work: Upgradation of link road Umralli Heeran Thara Pubowal to Pollian via Kuthar-Beet Km 7/00 to 9/900 (SH: C/O 900mm dia hume pipe culvert at RD 8/440- phase-I)

6	Construction of embankment with approved material obtained from borrow pits lift upto any height and compacted to meet requirement of Table 300.1 and 300.2 within any lead as per Technical Specification Clause 301.5 including carriage of material with in all leads and lifts and other incidentals as per MORD specification 2014. The rate includes sale tax octroi, royalty, maikhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	9.72	Per cubic metre	250.00	Rupees two hundred fifty only.	2430
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17/20212 dated 7.8.2018				Total	99658
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor , otherwise the tender will be rejected.					


 Executive Engineer,
 H.P.P.W.D. Division Haroli
 Distt. Una (H.P.)

Schedule of quantity

Name of work :- C/O Driving Training Track and Traffic Park at Rora, Haroli Distt. Una.

(SH: P/F ACP Sheet On Main Gate) (Deposit work) Phase- VIII *(Balance work)*

		Estimated Cost: Rs	₹ 99,521			
		Time:-	One month			
		Earnest Money:-	2000			
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Providing, fabricating and supplying and fixing panels of aluminium composite panel cladding in pan shape in metallic colour of approved shades made out of 4mm thick aluminium composite panel material consisting of 3mm thick FR grade mineral core sandwiched between two Aluminium sheets (each 0.5mm thick). The aluminium composite panel cladding sheet shall be coil coated, with Kynar 500 based PVDF / Lumiflon based fluoropolymer resin coating of approved colour and shade on face # 1 and polymer (Service) coating on face # 2 as specified using stainless steel screws, nuts, bolts, washers, cleats, weather silicone sealant, backer rods etc. including carriage of materials within all leads and lifts and other incidentals The rate is including of octroi, royalty, Malkana, toll tax, GST sale tax or other taxes imposed by the Government	21.72	Per Square metre	4582.00	Rupess four thousand five hundred eighty two only	99521
Total:						99521
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.						


 Executive Engineer,
 H.P.P.W.D. Division Haroli
 Distt. Una (H.P.)

Schedule of quantity

Name of work :- C/O Driving Training Track and Traffic Park at Rora, Haroli Distt. Una.		Estimated Cost: Rs	₹ 97,512			
		Time:-	One month			
(SH: Painting of parapet Approach road of traffic park, main road & steel painting of main gate)		Earnest Money:-	2000			
S.NO	DESCRIPTION	Qty	Unit	T. Rate	Rate in words	Amount
1	Providing and applying Apex paint (two or more coats) on any surface with Asian paint, Nerolac, Burger at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat preparation of surface, etc. complete as per direction of Engineer in charge including carriage of material within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkhana, GST toll tax sale tax other taxes imposed by the Govt.	635.07	Sqm	132.00	Rupees One Hundred ThirtyTwo Only	83829
2	Applying priming coat With ready mixed pink or Grey primer of approved brand and manufacture on steel work, complete as per direction of Engineer in charge including carriage of material within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkhana, GST toll tax sale tax other taxes imposed by the Govt.	101.35	Sqm	50.00	Rupees Fifty Only	5068
3	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkhana, toll tax , sale tax or other taxes imposed by the Government.	101.35	Sqm	85.00	Rupees EightyFive Only	8615
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018				Total	97512
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

90

SCHEDULE OF QUANTITY

Estimated Cost 89680
Earnest Money 2000
Time limit One month

Name of work:- A/R & M/O on Una Haroli Palkwah Poian Jaijon road Km 0/00 to 23/00 (SH: P/F Acrylic signages near Rampur bridge - phase-I)

S No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Providing and fixing ACRYLIC SIGNAGES in rectangular shape LED ACRYLIC SIGNAGES BOARD with power supply units and sensor system complete in all respect as per direction of Engineer in charge including carriage of material within all leads and lifts and other incidentials. The rate including octroi, royalty, Malkhana, GST toll tax sale tax other taxes imposed by the Govt. <small>NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW(B)@17/2/0212 dated 7.8.2018</small>	608.00	Per centimetre height	147.50	Rupees one hundred forty seven and paise fifty only	89680
					Total	89680
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					

Executive Engineer
Haroli Division
HPPWD Haroli

Schedule of quantity

Name of work :- C/O Driving Training Track and Traffic Park at Rora, Haroli Distt. Una.		Estimated Cost: Rs	₹ 99,280		
1) providing & fixing curve stone in campus area of traffic park - Phase-VI (Deposit work) (Balance work)		Time:-	One month		
		Earnest Money:-	2000		
DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
Providing and fixing curve stone 80mm(Eighty millimeter) thick size 0.30m x 0.30m complete as per direction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	584.00	Each	170.00	Rupess one hundred Seventy only	99280
NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@1712/0212 dated 7.8.2018				Total:	99280
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20					
Percentage quoted rate in Figures					
Percentage quoted rate in words					
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					


 Executive Engineer,
 H.P.P.W.D. Division Haroli
 Distt. Una (H.P.)

SCHEDULE OF QUANTITY							Estimated Cost	99678
							Earnest Money	2000
Name of work:- Construction of college Building at Govt Degree College Haroli Distt Una (SH:- Balance Painting works of Boundary wall - Phase-III)-D/work							Time limit	One month
S No.	Description of work	Quantity	Unit	RATE In		AMOUNT		
				Figures	Words			
1	Painting steel work with Deluxe Multi surface paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture including entire carriage of material within all leads and lifts and other incidentals as per the direction of Engineer-in-charge. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	102.00	Per Square meter	85	Rupees eighty five only	8670		
2	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	632.00	Per Square meter	12.00	Rupees twelve only	7584		
3	Providing and applying apex paint (two or more coats) on any surface with Asian paint, Nerolac, Burger at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat preparation of surface, etc. complete as per direction of Engineer in charge including carriage of material within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkhana, GST toll tax sale tax other taxes imposed by the Govt.	632.00	Per Square meter	132.00	Rupees one hundred thirty two only	83424		
						Total	99678	
NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@172/0212 dated 7.8.2018								
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20								
Percentage quoted rate in Figures								
Percentage quoted rate in words								
Note:- Rate quoted in figures & words are mandatory by the contractoe								


 Executive Engineer,
 H.P.W.D. Division Haroli
 Distt. Una (H.P.)

Schedule of quantity

Name of work :- C/O Driving Training Track and Traffic Park at Rora, Haroli Distt. Una.
 (SH:Providing & fixing curve stone in campus area of traffic park - Phase-IV (Deposit work)

Name of work :- C/O Driving Training Track and Traffic Park at Rora, Haroli Distt. Una. (SH:Providing & fixing curve stone in campus area of traffic park - Phase-IV (Deposit work)		Estimated Cost: Rs		₹ 98,600		
		Time:-	One month			
		Earnest Money:-	2000			
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Providing and fixing curve stone 80mm(Eighty millimeter) thick size 0.30m x 0.30m complete as per direction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana , toll tax,GST,labour cess or other taxes imposed by the Government..	580.00	Each	170.00	Rupess one hundred Seventy only	98600
					Total:	98600
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@1712/0212 dated 7.8.2018					
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					

Executive Engineer,
 H.P.P.W.D. Division Haroli
 Distt. Una (H.P.)



Schedule of quantity

Name of work :- C/O Driving Training Track and Traffic Park at Rora, Haroli Distt. Una.

(SH: Providing & fixing curve stone in campus area of traffic park - Phase-III (Deposit work) (Balance work)

Name of work :- C/O Driving Training Track and Traffic Park at Rora, Haroli Distt. Una.		Estimated Cost: Rs	₹ 98,940			
		Time:-	One month			
		Earnest Money:-	2000			
S.NO	DESCRIPTION	Qty	Unit	T. Rate	Rate in words	Amount
1	Providing and fixing curve stone 80mm(Eighty millimeter) thick size 0.30m x 0.30m complete as per direction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malakhana ,toll tax,GST,labour cess or other taxes imposed by the Government ..	582.00	Each	170.00	Rupess one hundred Seventy only	98940
					Total:	98940
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)(17)2/0212 dated 7.8.2018					
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					

Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H.P.)

96

Schedule of Quantity

Estimated Cost: Rs. 98740
Earnest Money: Rs. 2000-
Time Limit: One Month

Name of work: C/O Driving Training Track and Traffic Park at Rora Haroli Distt. Una (SH: P/F cat eye & P/L hot applied thermoplastic on approach road)- Deposit work (Balance work)

Sr. No.	Sub-Head and Items of work	Quantity	Unit	Rates in		Amount
				Figures	Words	
1	Providing and laying of hot applied thermoplastic compound 2.5 mm (two point five millimetre)thick including reflectorising glass beads @ 250 gms (at the rate of two hundred fifty gram per square metre)per sqm area, thickness of 2.5 mm(two point five millimetre) is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes as per entire direction of Engineer-in - Charge including carriage of material within all leads and lifts .The rates are inclusive of octroi, royalty, Malkana, toll tax, GST , sale tax or other taxes imposed by the Government.	44.00	Per square metre	620.00	Rupees six hundred twenty only	27280
2	Providing and fixing cat eye make(3M) of size 100x20mm made of heavy duty body shall be molded dual shank ASA /Acyclic styrene acyloretreite) or HP/High impact polystyrene) ort ABS having electronically welded micro prismatic lens with abrasion resistant coating as approved by Engineer-in-charge. The road stud shall support a load of 13635 by tested in accordance with ASTM D4280.The slope of retro reflective surface shall be 35+/-5 degrees to base. The reflective panels on both side with at least 12cm. of each area side. The luminance intensity should be as per the specification ASTM as recommended in BS-8873 part 4 1973 as per approved sample and manufacture by the Engineer-in-charge .including carriage of material within all leads and lifts .The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	108.00	Each	320.00	Rupees three hundred twenty only	34560
3	Providing and fixing cat eye make(3M) Solar Powered of size 100x20mm (one hundred into twenty millimetre) made of heavy duty body shall be molded dual shank ASA /Acyclic styrene acyloretreite) or HP/High impact polystyrene) ort ABS having electronically welded micro prismatic lens with abrasion resistant coating as approved by Engineer-in-charge. The road stud shall support a load of 13635 by tested in accordance with ASTM D 4280.The slope of retro reflective surface shall be 35+/-5 degrees to base. The reflective panels on both side with at least 12cm (Twelve centimetre) of each area side. The luminance intensity should be as per the specification ASTM as recommended in BS-8873 part 4 1973 as per approved sample and manufacture by the Engineer-in-charge including carriage of material within all leads and lifts	30.00	Each	1230.00	Rupees one thousand two hundred thirty only.	36900
Total						98740
Note:- 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)(17)2/0212 dated 7.8.2018						
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)/A(3)1/2020 dated 22.07.20						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandatory by the contractor , otherwise the tender will be rejected.						

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.R.)

Schedule of quantity

Name of work :- C/O Driving Training Track and Traffic Park at Rora, Haroli Distt. Una.
(SH: P/F ACP Sheet On Main Gate) (Deposit work) Phase- X

		Estimated Cost: Rs	₹ 99,796			
		Time:-	One month			
		Earnest Money:-	2000			
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Providing, fabricating and supplying and fixing panels of aluminium composite panel cladding in pan shape in metallic colour of approved shades made out of 4mm thick aluminium composite panel material consisting of 3mm thick FR grade mineral core sandwiched between two Aluminium sheets (each 0.5mm thick). The aluminium composite panel cladding sheet shall be coil coated, with Kynar 500 based PVDF / Lumiflon based fluoropolymer resin coating of approved colour and shade on face # 1 and polymer (Service) coating on face # 2 as specified using stainless steel screws, nuts, bolts, washers, cleats, weather silicone sealant, backer rods etc. including carriage of materials within all leads and lifts and other incidentals The rate is including of octroi, royalty, Malkana, toll tax, GST sale tax or other taxes imposed by the Government	21.78	Per Square metre	4582.00	Rupess four thousand five hundred eighty two only	99796
Total:						99796
NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)(17)2/0212 dated 7.8.2018						
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.						

**Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)**

Schedule of quantity

Name of work :- C/O Driving Training Track and Traffic Park at Rora, Haroli Distt. Una.
(SH: P/F ACP Sheet On Main Gate) (Deposit work) Phase- IX

Name of work :- C/O Driving Training Track and Traffic Park at Rora, Haroli Distt. Una. (SH: P/F ACP Sheet On Main Gate) (Deposit work) Phase- IX		Estimated Cost: Rs	₹ 99,704			
		Time:-	One month			
		Earnest Money:-	2000			
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Providing, fabricating and supplying and fixing panels of aluminium composite panel cladding in pan shape in metallic colour of approved shades made out of 4mm thick aluminium composite panel material consisting of 3mm thick FR grade mineral core sandwiched between two Aluminium sheets (each 0.5mm thick). The aluminium composite panel cladding sheet shall be coil coated, with Kynar 500 based PVDF / Lumiflon based fluoropolymer resin coating of approved colour and shade on face # 1 and polymer (Service) coating on face # 2 as specified using stainless steel screws, nuts, bolts, washers, cleats, weather silicone sealant, backer rods etc. including carriage of materials within all leads and lifts and other incidentals The rate is including of octroi, royalty, Malkana, toll tax ,GST sale tax or other taxes imposed by the Government	21.76	Per Square metre	4582.00	Rupess four thousand five hundred eighty two only	99704
					Total:	99704
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.						


Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

29

SCHEDULE OF QUANTITY

NAME OF WORK:- C/O Heliport at Rora Tehsil Haroli Distt. Una (SH: Preparation of working estimate of Heliport)- Deposit work		Estimated cost	99,900.0			
		Earnest money	2000.00			
		Time Limit	one month			
Sr. NO.	Description of item	Quantity	unit	Rate in numbers	Rate in words	Amount
1	2	3	4	5	6	7
1	Preparation and approval of working estimate and DNIT for the Construction of Heliport at Rora in all respect in fairout form and submission of 5 sets of estimate for approval and soft copy of estimate. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	1	Job	99,900.00	Rupees ninety nine thousand nine hundred only	99,900
			Total			99,900
Note:-	1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018					
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor , otherwise the tender will be rejected.					

Executive Engineer
Haroli Division
HPPWD Haroli

30

SCHEDULE OF QUANTITY

Name of work : Restoration of rain damage on Panjavar Bathri to Mata Ka Mandir Lower Badehra via Rajesh House Saloh Nalka to Kumaran abadi Km 0/00 to 2/700 (SH:- Repair of rain cut at various RDs)

Estimated Cost 99840
Earnest Money 2000/-
Time limit One month

Sl. No.	Description of work	Quantity	Unit	RATE IN		AMOUNT
				Figures	Words	
1	Banking excavated earth in layers not exceeding 20 cm depth, breaking clods without rolling and watering, dressing up, in embankment for roads , flood banks, marginal banks and guide banks etc. upto any lead and lift as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,maikhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	416.00	Per cubic metre	240.00	Rupees hundred forty only	99840
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17)2/0212 dated 7.8.2018				Total:	99840
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor , otherwise the tender will be rejected.					

Executive Engineer
Haroli Division
HPPWD