



OFFICE OF
Executive Engineer Jaisinghpur Division HPPWD Jaisinghpur Himachal Pradesh
Works Department Jaisinghpur 176095 Phone No. 01894-228030

"CERTIFICATE"

Certified that the tenders are being called in exigency of works of public interest vide this office letter No. PWD/JSD/TA/NIT/ 2025-26- 12435-44 dated

28/03/2026

Executive Engineer
Jaisinghpur Division
HP.PWD., Jaisinghpur.

OFFICE OF
Executive Engineer Jaisinghpur Division HPPWD Jaisinghpur Himachal Pradesh Works Department
Jaisinghpur 176095, Telephone No. 01894-228030,
Email ee-jaipwd-hp@gov.in

"NOTICE INVITING TENDERS"


Sealed percentage rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, HP.PWD., Division Jaisinghpur on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rules so as to reach in his office on or before on **06.04.2026 up to 11:00 A.M.** and the same shall be opened on the same day at **11:30 A.M.** in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on **04.04.2026 up to 4:00 PM** and the application for issue of tender form shall be received on **04.04.2026 up to 11:00 AM.** The applications for issue of tender forms should accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates / Saving Account of the Post Office / Time Deposit account / FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP.PWD., Division Jaisinghpur.

The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for **75 days**:-

Sr. No.	Name of Work	Estimated Cost (Rs.)	EMD	Time limit	Cost of tender form
1	R/O repair and tile work of road from main road towards Kuldevi Mata Mandir Uprali Gavn KM 0/00 to 0/180 (SH:- P/L 60mm thick interlocking paverblock at RD 0/00 to 0/055) BSP/2024/48	99776/-	2000/-	Two month	350/-
2	Completion of Shamshan Ghat at Malodan Ward No. 7 Alampur (SH:- C/O Edge wall for protection of Shed) VKV / 2024/ 1981	49895/-	1000/-	Two month	350/-
3	R/O concrete work of path from main road to Bawadi village Kalian KM 0/00 to 0/300 (SH:- Imp. & widening of road at RD 0/100 to 0/300 and CC pavement at RD 0/100 to 0/116) SDP/ 2024/ 967	199570/-	4000/-	Two month	350/-

Terms & Conditions:-

1. The contractors will have to produce a copy of enlistment / renewal of valid class at time of application / tender form.
2. The contractors will have to produce a copy of GST, EPF and PAN.
3. The contractors are directed to insert the rate / percentage both in figures and words.
4. The tenders forms will not be issued to those contractors who have not completed their previous works / commitments or whose performance is not found satisfactory.
5. The Executive Engineer reserves the right to reject / cancel any or all the tenders without assigning any reason.


Executive Engineer
Jaisinghpur Division
HP.PWD., Jaisinghpur.

On behalf of Governor of Himachal Pradesh)


Dated: **28/03/2026**

No.PWD/JSPR/CB/Tenders/2025-26-

12435-44

Copy to the following for information and necessary action:-


1. The Chief Engineer (K.Z.) HP.PWD., Dharamshala.
2. The Superintending Engineer, 5th Circle. HPPWD, Palampur.
3. The Executive Engineer (IT) O/O E-in-C, HP.PWD., Shimla.
- 4-6. All the Assistant Engineers under this Division.
- 7-8. The Drawings / Accounts Branch in this office.
9. N.I.T. Register.
10. Notice Board.


Executive Engineer
Jaisinghpur Division
HP.PWD., Jaisinghpur.

1

SCHEDULE OF QUANTITY


Name of work :-R/O repair and Tile work of road from Main road towards Kuldevi Mata Mandir Uparli Gavn Km 0/00 to 0/180 (SH:- P/L 60 mm thick Interlocking paverblock at RD 0/00 to 0/055) BSP/2024/48		Estimated cost Rs.	99776.00			
		Earnest Money Rs.	2000.00			
		Time Limits	Two Month			
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing and laying 60 mm thick Interlocking M-40 grade Concrete paver block pavement confirming to ISI 15658:2006 having thickness 60mm (sixty millimetre) as per drawings and Technical Specification Clause 1504 (The execution of interlocking paver block shall be allowed after duly testing from the authorized labs) and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	82.50	1150.00	Rupees one thousand one hundred fifty only	Per square metre	94875.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arrise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall ectera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	0.99	4950.00	Rupees four thousand nine hundred fifty only	Per cubic metre	4901.00
Total						99776.00
Quoted Rate (in Figures) Percentage		Excess (+)			%	
		Less (-)			%	
G.Total in Figures						
G.Total in Words						


Executive Engineer
Jaisinghpur Division
HPPWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :- Completion of Shamshan Ghat at Malodan ward No. 7 Alampur (SH:- C/O Edge wall for protection of shed) VKV/2024/1981		Estimated cost Rs.	49895.00			
		Earnest Money Rs.	1000.00			
		Time Limits	Two Month			
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	8.40	225.00	Rupees two hundred twenty five only	Per Cubic Metre	1890.00
2	Providing and laying cement concrete 1:4:8 (One cement: four sand: eight graded crushed/broken stone aggregate 40mm (forty millimetre) nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	10.35	4300.00	Rupees four thousand three hundred only	Per Cubic Metre	44505.00


3	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700, 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	14.00	250.00	Rupees two hundred fifty only	Per Running Metre	3500.00	
Total						49895.00	
Quoted Rate (in Figures) Percentage						Excess (+)	%
G.Total in Figures						Less (-)	%
G.Total in Words							


 Executive Engineer,
 Jaisinghpur Division,
 HP-PWD Jaisinghpur

(B)

SCHEDULE OF QUANTITY						
Name of work :-R/O Concrete work of path from main road to Bawadi Village Kailan Km 0/00 to 0/300 (SH:- Imp.& widening of road at RD 0/100 to 0/300 and CC pavement at RD 0/100 to 0/116) SDP/2024/967			Estimated cost Rs.		199570.00	
			Earnest Money Rs.		4000.00	
			Time Limits		Two Month	
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Excavation in hilly area in all heights and depths and in all kind of soil by all manual /mechanical means including saturated soil comprising of ordinary soil, ordinary rock, soft rocks, hard rocks, chiseling/ wedging out rock (where blasting is prohibited) and their intermediate classification of soil, complete including setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of un useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus / unuseful material to the approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for useful stone of 20.25 (twenty cubic decimal two five) cubic metre at the rate of Rs. 300/- (Rupees Three Hundred) per cubic metre shall be effected from the contractors running bill on pro-rata basis as per actual quantity executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	720.00	208.00	Rupees two hundred eight only	Per cubic metre	149760.00
2	Providing laying spreading and compacting by manual means 75 mm (seventy five millimetre) compacted thickness broken /crushed of stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to hundred) K.N. static roller in stages to proper grade and camber including applying and brooming, stone screening type-B of size 11.2mm (eleven decimal two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per drawing and M.O.R.D. technical specifications section 405 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate includes octroi,royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	3.40	2150.00	Rupees two thousand one hundred fifty only	Per cubic metre	7310.00

3	Providing and laying in position cement concrete of specified grade of reinforcement concrete excluding the cost of centering and shuttering finishig and reinforcement- All work up to plinth level : 1:2:4 (one cement : two coarse sand : four graded stone aggregate) 20 mm (twenty milimetre) nominal size including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	6.80	6250.00	Rupees six thousand two hundred fifty only	Per Cubic Metre	42500.00
Total						199570.00
Quoted Rate (in Figures) Percentage		Excess (+)		%		
		Less (-)		%		
G.Total in Figures						
G.Total in Words						


 Executive Engineer,
 Jaisinghpur Division,
 HP PWD Jaisinghpur