



Office of
Executive Engineer B&R Division HP.PWD. Joginder Nagar
Himachal Pradesh Public Works Department, Mandi-175015
Phone & Fax No. 01908-222033 E-Mail:- ee-jog-hp@nic.in

"NOTICE INVITING TENDER"

Sealed Item rate tender for the following works are hereby invited by the Executive Engineer, B&R Division HP.PWD., Joginder Nagar District Mandi (H.P) from the eligible contractors of the appropriate class registered in HP.PWD. as per revised enlistment rules so as to reach in the office of under signed on 04-04-2026 up to 11:30 A.M. and will be opened on the same day at (12:00 noon) in the presence of intending contractors. The tender application will be received in this office on 02-04-2026 up to 10.00 A.M. to 12:30 P.M. and tender form can be had from this office on the same day from 3.00 P.M. to 5.00 Pm. The earnest money as shown against each in the shape of F.D.R of any bank in Himachal Pradesh duly pledged in the name of the under signed must accompany with each tender. The tender form will be issued to contractor giving proof of enlistment, GST. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors in the office of the under signed on any working day during the office hours.

Sr. No.	Name of work	Amount put to tender/ Estimated cost	Earnest Money	Cost of tender form	Eligible Class of Contractor	Time
1	Restoration of Rain Damages on Machhiyal Bihun Nauhali Road km. 0/0 to 12/0 (SH: - Construction of Breast/Protection wall at RD. 8/890 to 8/901 & 9/521 to 9/541 50 under PDNA 2023	Rs. 4,92,342/-	Rs. 9,800/-	Rs. 350/-	Class "D"	Three Months
2.	Restoration of rain Damages on link Road to Labankhad to Bagla Project Road km. 0/00 to 2/250 (SH - Construction of Retaining wall 1.5:10 at 0/00 to 0/005)	Rs. 2,20,924/-	Rs. 4,400/-	Rs. 350/-	Class "D"	Two Months
3.	Restoration of rain damages on Dhelu Chowki Chauntra road km 0/00 to 10/0 (SH - Protection for Sukad Khad Bridge abutment at km. 2/445 (Sukad side 2 nd Part)	Rs. 4,65,033/-	Rs. 9,300/-	Rs. 350/-	Class "D"	Three Months

1. Certified that tender of above works are being called of emergent nature in exigency of public interest

Terms and conditions:-

1. The contractor should produce a copy of enlistment / renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor/Firm shall have his registration and GST No. the copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer B&R Division HPPWD., Joginder Nagar & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
5. No tender form will be issued to the contractor without producing the work done certificate from the Executive Engineer concerned.
6. The contractor/firms are requested to insert the rate of each item in words as well as in figures failing which XEN reserves the right to accept/reject any tender without assigning any reason at any stage.
7. The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar,
District Mandi (HP) for on behalf of
Governor of Himachal Pradesh
Ph. 01908-222033
Dated:- 18-03-2026

No. PW-JND-B&R-EA-I/NIT/Press/2026-27-

35499-548

1. Copy to the F C Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
2. The Engineer-in-Chief, HPPWD, Shimla.
3. The Chief Engineer (MZ), HPPWD, Mandi.
4. The Superintending Engineer, Joginder Nagar Circle HPPWD, Joginder Nagar.
5. All the Assistant Engineer working under this Division.
6. All the Contractor working under this Division.
7. Drawing Branch in this office.
8. Notice Board.
9. The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
B&R Division HP PWD.,
Joginder

END. 298

702

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : Restoration of rain damages on Machhhal Bhararu Bihun Nauhli road km.0/0 to 12/0 (SH: Construction of brast/ protection wall 8/890 to 8/901 & 9/521 to 9/541.50 (under under PDNA 2023		Estimate Cost:		Earnest Money:		Time Limit :
		4,92,342.00		9,800.00		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in lilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseled/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, culber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time including GST.	56.91	Per cubic metre	198.40	Rupees One Hundred Ninety Eight And Paise Forty Only	11,291.00
2	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, culber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost . The rate is inclusive all taxes levy by the government time to time including GST.	16.58	Per cubic metre	609.90	Rupees Six Hundred Nine And Paise Ninety Only	10,112.00

702

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls , in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time including GST.	76.38	Per cubic metre	6,036.80	Rupees Six Thousand Thirty Six And Paise Eighty Only	4,61,091.00
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time including GST.	30.00	Each	328.25	Rupees Three Hundred Twenty Eight And Paise Twenty Five Only	9,848.00
Total						4,92,342.00

*Draft schedule of quantity approved for 492,342/-
(Four Lacs ninety two thousand three hundred forty two) only*

[Signature]
Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

(702)

ENo. 523

724

DNIT/DRAFT SCHEDULE OF QUANTITY

Sr. No.		Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
					Figures	Words	
<p>Name of Work:- Restoration of rain Damages on link Road to Labankhad to Bagla Project Road km 0/00 to 2/250 (SH: Construction of Retaining wall 1:5:10 at 0/00 to 0/005</p>							
				<p>Estimate Cost: 220924.00 Earnest Money: 4,400.00 Time Limit : Two Months</p>			
1		<p>Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time including GST.</p>	8.75	Per metre	648.00	5,670.00	Rupees Five Thousand Hundred Seventy Only
2		<p>Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diametre G.I. hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 complete within all leads, lifts, carriage of material and other incidentials. The rate is inclusive all taxes levy by the government time to time including GST.</p>	32.85	Per metre	6,049.15	1,98,715.00	Rupees One Lakh(s) Eighty Seven Hundred Fifteen Only

724

724

23

Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
			Figures	Words	
Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentials. The rate is inclusive all taxes levy by the government time to time including GST.	10.95	Per cubic metre	1,149.10	12,583.00	Rupees Thousand Hundred Eighty Three Only
Providing, laying, spreading and compacting stone aggregates by manual means of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN (eighty-hundred kilo newton) static roller in stages to proper grade and camber applying and brooming, stone screening/ binding materials to fillup the interstics of course aggregate watering and compacting to the required density Grading-2 (two) as per technical specification clause 405 complete within all leads, lifts, carriage of material and other incidentials charges. The rate is inclusive all taxes levy by the government time to time including GST.	12	Per Cubic metre	329.65	3,956.00	Rupees Thousand Nine Hundred Fifty Six Only
Total				220924.00	

*Draft schedule of quantity approved for
220924/- (Rs Two lacs twenty thousand
nine hundred twenty four) only.*

Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

365

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : restoration of rain damages on Dhelu Chowki Chauntra road km 0/00 to 10/0 (SH: Protection for Sukad Khad Bridge abutment at km. 2/445(Sukad side 2nd part)

Estimate Cost: 4,65,033.00
 Earnest Money: 9,300.00
 Time Limit : Three Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	30.00	Per cubic metre	517.65	Rupees Five Hundred Seventeen And Paise Sixty Five Only	15,530.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203. Plain cement concrete Grade M-10 complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	76.80	Per cubic metre	5,852.90	Rupees Five Thousand Eight Hundred Fifty Two And Paise Ninety Only	4,49,503.00
Total						4,65,033.00

Draft schedule of quantity approved for ₹ 4,65,033/- (Four Lacs Sixty five thousand thirty three) only

Executive Engineer
 B & R Division HP.PWD,
 Joginder Nagar