



Office of
Executive Engineer B&R Division HP.PWD. Joginder Nagar
Himachal Pradesh Public Works Department, Mandi-175015
Phone & Fax No. 01908-222033 E-Mail:- ee-jog-hp@nic.in

"NOTICE INVITING TENDER"

Sealed item rate tender for the following works are hereby invited by the Executive Engineer, B&R Division HP.PWD., Joginder Nagar District Mandi (H.P) from the eligible contractors of the appropriate class registered in HP.PWD. as per revised enlistment rules so as to reach in the office of under signed on 30-03-2026 up to 11:30 A.M. and will be opened on the same day at (12:00 noon) in the presence of intending contractors. The tender application will be received in this office on 27-03-2026 up to 10.00 A.M. to 12:30 P.M. and tender form can be had from this office on 28-03-2026 from 2.00 P.M. to 5.00 Pm. The earnest money as shown against each in the shape of F.D.R of any bank in Himachal Pradesh duly pledged in the name of the under signed must accompany with each tender. The tender form will be issued to contractor giving proof of enlistment, GST. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors in the office of the under signed on any working day during the office hours.

Sr. No.	Name of work	Amount put to tender/ Estimated cost	Earnest Money	Cost of tender form	Eligible Class of Contractor	Time
1	Construction link road to Kass to Gaduhi km. 0/0 to 2/0 (GP Kass) (SH:- Providing Laying Wearing GII & CC pavement at RD 1/045 to 1/077) BASP deposit SID: BSP/2024/334	Rs. 99,361/-	Rs.6,600/-	Rs. 350/-	Class "D"	Two Months
2	Construction Road Banah Banehardy Sapara km. 0/0 to 2/500 (GP Vatari Biun) (SH:- Providing Laying Wearing G-II & CC Pavement at RD. 0/00 to 0/016) BASP deposit SID: BSP/2024/462.	Rs. 49,721/-	Rs.1,000/-	Rs. 350/-	Class "D"	One month
3	Construction link road Ambulance road Harijan Basti Banog to Upper Banog km. 0/0 to 4/0 (GP Nauhali) (SH:- Providing Laying Wearing G-II & CC pavement at RD. 0/0 to 0/063) BASP deposit SID.BSP/2024/61	Rs.1,99,360/-	Rs.4,000/-	Rs. 350/-	Class "D"	Three Months
4.	Construction link road Nichla Andaralu to Shamshanghat Bahali km. 0/0 to 2/0 (SH:- Providing Laying Wearing G-II & CC pavement at RD. 0/0 to 0/073) BASP deposit SID.BSP/ 2020/303.	Rs.2,96,987/-	Rs.5,900/-	Rs. 350/-	Class "D"	Three Months
5.	Restoration of Rain damages on link rod Lower Ladwan to Mata Chaturbhujia Mandir km. 0/0 to 2/00 (SH:- Construction of Unlined surface Drain in km. 0/0 to 2/0 and Maintenance of earthen shoulder in km. 0/00 to 0/645) under SDF deposit SID:SDF/2025/1349.	Rs. 1,49,429/-	RS. 3,000/-	Rs. 350/-	Class "D"	Three Months
6.	R/o Restoration of rain damages on link road to Village Chanehar Trind Kalehru Bharon in GP Uperli Dhar Ras Kalehru (GP Uperidhar) (SH:- Providing and laying soling & Cement concrete pavement from km., 0/470 to 0/497) under SDF deposit SID: SDF/2022/400.	Rs. 98,280/-	RS. 2,000/-	Rs. 350/-	Class "D"	Three Months
7.	R/O (Repair of) Restoration of rain damages on Baijnath Lad Bharol Kandapattan road km. 0/0 to 46/0 (GP Pihar Bydu) (SH:- Providing and laying U-shape drain at RD. 17/660 to 17/780) SDF deposit SID:SDF/2025/1409.	Rs. 3,99,218/-	RS. 8,000/-	Rs. 350/-	Class "D"	Three Months
8.	R/O restoration of rain damages on link road to village Gahru km. 0/0 to 2/0 (SH:- Construction of Retaining wall at km. 0/730 to 0/739.50 (under Deposit SID: SDF/2024/861.	Rs. 1,46,502/-	Rs. 2,900/-	Rs. 350/-	Class "D"	Three Months

1. Certified that tender of above works are being called of emergent nature in exigency of public interest

Terms and conditions:-

1. The contractor should produce a copy of enlistment / renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor/Firm shall have his registration and GST No, the copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer B&R Division HPPWD., Joginder Nagar & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
5. No tender form will be issued to the contractor without producing the work done certificate from the Executive Engineer concerned.
6. The contractor/firms are requested to insert the rate of each item in words as well as in figures failing which XEN reserves the right to accept/reject any tender without assigning any reason at any stage.
7. The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar.
District Mandi (HP) for on behalf of
Governor of Himachal Pradesh
Ph. 01908-222033

No. PW-JND-B&R-EA-I/NIT/Press/2026-27-

34479-528

Dated:- 09/03/26

1. Copy to the F.C. Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
2. The Engineer-in-Chief, HPPWD, Shimla.
3. The Chief Engineer (MZ), HPPWD, Mandi.
4. The Superintending Engineer, Joginder Nagar Circle HPPWD, Joginder Nagar.
5. All the Assistant Engineer working under this Division.
6. All the Contractor working under this Division.
7. Drawing Branch in this office.
8. Notice Board.
9. The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
B&R Division HP PWD.

①

692

E.No - 481

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : Construction link road to Kass to Gaduhi Km .0/0 to 2/0 (GP kass) (SH:-~~Construction~~ & Providing Laying Wearing G-II & CC Pavement at RD 1/045 to 1/077) BASP deposit SID: BSP/2024/334

Sr. No.	Description of work	No. or Qty.	Unit	Rate		Estimate Cost: Earnest Money: Time Limit :	AMOUNT
				Figures	Words		
1	Providing, laying, spreading and compacting stone aggregates by manual means of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN (eighty-hundred kilo newton) static roller in stages to proper grade and camber applying and brooming, stone screening/ binding materials to fillup the interstics of course aggregate watering and compacting to the required density Grading-2 (two) as per technical specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges. The rate is inclusive all taxes levy by the government time to time including GST.	6.80	Per cubic metre	3,596.25	Rupees Three Thousand Five Hundred Ninety Six And Paise Twenty Five Only	24,455.00	99,361.00 2,000.00
2	Construction of un-reinforced cement concrete pavement as per design and drawing with expansion and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five milimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time including GST.	9.07	Per cubic metre	8,258.60	Rupees Eight Thousand Two Hundred Fifty Eight And Paise Sixty Only	74,906.00	99,361.00
Total							99,361.00

Draft Schedule of Quantity approved for ₹ 99,361/- (Three Ninety nine thousand Three Hundred Sixty one) only /-

Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

692

E.No - 480

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : Construction Road Banah Banah Banah Sapara km. 0/0 to 2/500 (GP Vatari Biun) (SH:-
Construction & Providing Laying Wearing G-II & CC Pavement at RD 0/0 to 0/016) BASP deposit SID:
BSP/2024/462.

Sr. No.	Description of work	No. or Qty.	Unit	Rate		Estimate Cost: Earnest Money: Time Limit :	AMOUNT Rs. P
				Figures	Words		
1	Providing, laying, spreading and compacting stone aggregates by manual means of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN (eighty-hundred kilo newton) static roller in stages to proper grade and camber applying and brooming, stone screening/ binding materials to fillup the interstices of course aggregate watering and compacting to the required density Grading-2 (two) as per technical specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges. The rate is inclusive all taxes levy by the government time to time including GST.	3.40	Per cubic metre	3,596.25	Rupees Three Thousand Five Hundred Ninety Six And Paise Twenty Five Only	12,227.00	
2	Construction of un-reinforced cement concrete pavement as per design and drawing with expansion and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five milimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time including GST.	4.54	Per Cubic metre	8,258.60	Rupees Eight Thousand Two Hundred Fifty Eight And Paise Sixty Only	37,494.00	
Total						49,721.00	

Draft Schedule of Quantity approved for Rs. 49,721/-
(forty nine thousand seven hundred twenty one) only

Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

693

693

2

E.No - 479

694

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : Construction link Road Ambulance road Harijan Basti Banog to Upper km. 0/0 to 4/0 (GP Nohali) (SH:- Construction & Providing Laying Wearing G-II & CC Pavement at RD 0/0 to 0/063) BASP deposit		Estimate Cost: 1,99,360.00		Earnest Money: 4,000.00		Time Limit : Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Providing, laying, spreading and compacting stone aggregates by manual means of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN (eighty-hundred kilo newton) static roller in stages to proper grade and camber applying and brooming, stone screening/ binding materials to fillup the interstics of course aggregate watering and compacting to the required density Grading-2 (two) as per technical specification clause 405 complete within all leads, lifts, carriage of material and other incidentials charges. The rate is inclusive all taxes levy by the government time to time including GST.	13.64	Per cubic metre	3,596.25	Rupees Three Thousand Five Hundred Ninety Six And Paise Twenty Five Only	49,053.00	
2	Construction of un-reinforced cement concrete pavement as per design and drawing with expansion and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time including GST.	18.20	Per cubic metre	8,258.60	Rupees Eight Thousand Two Hundred Fifty Eight And Paise Sixty Only	1,50,307.00	
Total						1,99,360.00	

Draft Schedule of Quantity approved for 2,199,360. Come less Ninety nine thousand Three hundred sixty only

Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

694

E.No - 499

4

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : Construction link road Nichla Andaralu to Shamshanghat Bahali km.0/0 to 2/0) (SH:- Construction & Providing Laying Wearing G-II & CC Pavement at RD 0/0 to 0/073.40) BASP deposit SID: BSP/2020/303		Estimate Cost:		AMOUNT		
		Earnest Money:			Rs. P	
		Time Limit :		Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		
				Figures	Words	
1	Providing, laying, spreading and compacting stone aggregates by manual means of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN (eighty-hundred kilo newton) static roller in stages to proper grade and camber applying and brooming, stone screening/ binding materials to fillup the interstics of course aggregate watering and compacting to the required density Grading-2 (two) as per technical specification clause 405 complete within all leads, lifts, carriage of material and other incidentials charges. The rate is inclusive all taxes levy by the government time to time including GST.	16.52	Per cubic metre	3,596.25	Rupees Three Thousand Five Hundred Ninety Six And Paise Twenty Five Only	59,410.00
2	Construction of un-reinforced cement concrete pavement as per design and drawing with expansion and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five milimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time including GST.	28.91	Per cubic metre	8,217.80	Rupees Eight Thousand Two Hundred Seventeen And Paise Eighty Only	2,37,577.00
Total						2,96,987.00

*Draft schedule of quantity approval for ₹296987/-
(₹ Two Lacs Ninety Six thousand nine hundred eighty seven) only*

698

Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

E.No - 802

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work: Restoration of Rain damages on link road Lower Ladwan to Mata Chaturbhujia Mandir km 0/00 to 2/00 (SH: Construction of Unlined surface Drain in Km.0/0 to 2/0 and Maintenance of earthen shoulder in km 0/00 to 0/645) Under SF deposit S.D.S.F/2025/1349		Estimate Cost:				
		1,49,429.00	3,000.00			
Sr. No.	Description of work	No. or Qty.	Unit	Earnest Money:		
				Time Limit :	Three Months	
		Rate		AMOUNT		
		Figures	Words	Rs.	P	
1	Construction of unlined drain of average cross section area 40sqm (fourty square meter) in soil to specified lines grade levels and dimensions .Excavated materials to be used in embankment with a lift upto 3mm (three millimeter) and lead of 50m (fifty meter) (average lead 25m (twenty five meter)) as per technical specifications clause 307(Mechanical means) within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time including GST.	2000.00	Per running metre	29.00	Rupees Twenty Nine Only	58,000.00
2	Maintenance of earthen shoulder making uploss of materials /irregularities on shoulder to achieve the approved level and compacting with plate compactor at OMC to the desin level by adding fresh approved selected soil as per technical specification clause 1903 within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time including GST.	1935.00	Per square metre	47.25	Rupees Forty Seven And Paise Twenty Five Only	91,429.00
Total						1,49,429.00

695

Draft Schedule of Quantity approved for 1,49,429/-
(one lac & forty nine thousand four hundred twenty nine only)

[Signature]
Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

6

672

E.No - 478

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : R/o Restoration of rain damages on link road to village Chanehar Trind Kalehru Bharon in GP Uperli Dhar Ras Kalehru (GP Uperidhar) (Sub Head:-Providing & laying soling & cement concrete pavement from km.0/470 to 0/497) under SDF deposit SID:SDF/2022/400				Estimate Cost: 98,280.00		
				Earnest Money: 2,000.00		
				Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		
				Figures	Words	AMOUNT Rs. P
1	Stone soling properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm (one hundred millimeter) spread thickness (finished work including materials and labour) and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	12.97	Per Cubic metre	2,149.40	One thousand five hundred forty eight only	27,878.00
2	Construction of un-reinforced cement concrete pavement as per design and drawing with expension and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five milimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge.The rate is inclusive all taxes levy by the government time to time including GST.	8.65	Per Cubic metre	8,139.00	One thousand five hundred forty eight only	70,402.00
Total						98,280.00

Draft schedule of quantity approved for E 98,280/- (Ninty eight thousand two hundred eighty only)

672 478

Executive Engineer
 B & R Division HP.PWD,
 Joginder Nagar

7

Eno-501

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : R/O (Repair of) Restoration of rain damages on Baijnath Lad Bharol Kandapattan road km 0/0 to 46/0 (GP Pihar Bydu) (Sub Head:-Providing & laying U-shape drain at RD 17/660 to 17/780) SDF deposit SID SDF/2025/1409		Estimate Cost: Earnest Money: Time Limit :		AMOUNT	
		Figures	Words	Rs.	P
Sr. No.	Description of work	No. or Qty.	Unit	Rate	AMOUNT
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time including GST.	75.60	Per cubic metre	648.00 Rupees Six Hundred Forty Eight Only	48,989.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203. Plain cement concrete Grade M-10 complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time including GST.	47.25	Per cubic metre	7,412.25 Rupees Seven Thousand Four Hundred Twelve And Paise Twenty Five Only	3,50,229.00
Total					3,99,218.00

*Draft schedule of quantity approved for ₹ 399218 only
(i.e. three lacs ninety nine thousand two hundred and eighteen) only.*

696

Executive Engineer
RR Division Alwar,
Jagindras Nagar

ENo. 477

658

8

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : R/O restoration of rain damages on link road to village Gahru km.0/0 to 2/0 (S# : Construction of retaining wall at km. 0/730 to 0/739.50 (under Deposit SID:SDF/2024/861.)		Estimate Cost: 1,46,502.00		Earnest Money: 2,900.00			
		Time Limit :		Three Months			
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, haulage and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time including GST.	7.89	Per cubic metre	648.00	Rupees Six Hundred Forty Eight Only	5,113.00	
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls , in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time including GST.	22.33	Per cubic metre	5,940.10	Rupees Five Thousand Nine Hundred Forty And Paise Ten Only	1,32,642.00	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time including GST.	5.03	Per cubic metre	1,149.10	Rupees One Thousand One Hundred Forty Nine And Paise Ten Only	5,780.00	