

NOTICE INVITING TENDER


Sealed percentage rate tenders on form 6 & 8 are invited by the Executive Engineer, Division, HP: PWD, Kangra on behalf of the Governor of Himachal Pradesh for the following work from the approved and eligible contractors/firms enlisted in HPPWD in the appropriate class for the work mentioned below on **30.03.2026 up to 11-00 A.M.** and will be opened on the same day at **11-30 A.M.** in the presence of intending contractors or their authorized representatives who may wish to be present. The tender forms can be obtained from this office on cash payment (non refundable) on **28.03.2026 up to 4.30 P.M.** The tender applications for issue of tender forms will be received in this office on **28.03.2026 up to 11.30 A.M.** The earnest money in shape FDR National Saving certificate/Saving Account/Time Deposit Account in any of the Post Office/National Bank in H.P. duly pledged in favour of Executive Engineer, HPPWD., Division, Kangra. The conditional tenders and the tenders received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 75 days.

Sr. No.	Name of work	Estimated cost	Earnest Money	Cost of tender form	Time Limit
1.	Repair and Maintenance work of Hostel Block Wing "D" NIFT Campus(Chheb) at Kangra)(SH-Repair and Maintenance work of one No(Two Bedded Room)Hostel Block Wing-D Demolishing Cement Concrete, Doors Windows Roofs, Brick Work & Aluminum Work etc)(Deposit work)	75445/-	1500/-	350/-	One Month
2.	Repair and Maintenance work of Hostel Block Wing "D" NIFT Campus(Chheb) at Kangra)(SH-Repair and Maintenance work of one No(Two Bedded Room)Hostel Block Wing-D Demolishing Cement Concrete, Doors Windows Aluminum Work, Prelaminated Board, Cup Board, Mild Steel Bed Box and Study Table etc)(Deposit work)	82155/-	1650/-	350/-	One Month
3.	Repair and Maintenance of link road Village Tharu km. 0/000 to 0/665)(SH- Improvement of road at RD 0/000 to 0/128)	99933/-	2000/-	350/-	One Month
4.	Repair and Maintenance of link road Village Tharu km. 0/000 to 0/665)(SH- Improvement of road at RD 0/128 to 0/225)	98803/-	2000/-	350/-	One Month
5.	C/O Balance work of Ayurvedic Health Centre at Salol Tehsil and Distt. Kangra HP)(SH- Providing and fixing interlocking tiles and cupboard)(Deposit work)	99817/-	2000/-	350/-	One Month

Certified that tender of above works are being called of urgent nature in public interest.

TERMS & CONDITIONS-

1. The contractors/firms should be produce the attested copy of latest enlistment and renewal enlisted in HPPWD, GST No. and EPF No. with the application failing which their application will not be entertained.
2. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
3. The Earnest Money for the above works should be required at the time of sale of tender forms.
4. The contractor/firms should be quoted percentage rate in the tender both in figures and in words failing which tender is likely to be rejected.
5. The Executive Engineer, reserves the right to accept/reject any tender/application or all tenders without assigning any reason


Executive Engineer,
HPPWD, Division, Kangra,
Distt. Kangra (H.P.)


(On behalf of Governor of Himachal Pradesh)

Date: 19/3/26

Endst:- No.PW/KD/CB/Tenders/2025-26- 8817-40

Copy is forwarded to: -

1. The Computer Cell Office of the Engineer-in-Chief, HPPWD., Shimla for uploading the NIT on the Department website.
2. The Chief Engineer (KZ) HPPWD., Dharamshala for information please.
3. The Superintending Engineer, 5th Circle, HPPWD., Palampur for information please.
4. All the Assistant Engineer's working under Kangra Division.
5. NIT Register.
6. All Head of Branches.
7. Notice Board.


Executive Engineer,
HPPWD, Division, Kangra,
Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

NAME OF WORK:- REPAIR AND MAINTENANCE WORK OF HOSTEL BLOCK WING "D" NIFT CAMPUS (CHIEB) AT KANGRA (SUB HEAD:- REPAIR AND MAINTENANCE WORK OF ONE NO(TWO BEDDED ROOM) HOSTEL BLOCK WING-D DEMOLISHING CEMENT CONCRETE, DOORS WINDOWS ROOFS, BRICKWORK & ALUMINIUM WORK, ETC) (DEPOSIT WORK)

Sr. No.	Description of work	Qty	Unit	Rates		AMOUNT
				In Figures	In Words	
						Estimated Earnest 75445.00 Time Limit:- 01/2 Month 1500/-
1	Demolishing cement concrete manually/by mechanical means including disposal of material within 50 metres lead as Nominal concrete 1:3:6 or richer mix(1/c equivalent design mix) as per specifications, approved drawing, design complete, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana and toll tax, sale tax, GST or any other taxes imposed by the Government.	0.08	Per. Cubic metre	1004.50	Rupees One Thousand & Four - Paise Fifty Only	80.00
2	Dismantling doors, windows and clearstory window, ventilators shutters etc. (steel or wood) including chokhats, architraves, hold fast and other attachments etc. complete and stacking them 20 metres lead, of area 3 square metres and below as per specifications, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, GST or any other taxes imposed by the Government.	2.00	Each	156.25	Rupees One Hundred & Fifty Six - Paise Twenty Five Only	313.00
3	Dismantling wooden boardings in lining of walls and partitions, excluding supporting member but including stacking with in 50 metres lead. Thickness above 10mm up to 25mm as per specifications, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, GST or any other taxes imposed by the Government.	3.39	Per Square metre	26.10	Rupees Twenty Six - Paise Ten Only	88.00
4	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles 10mm to 25 mm(Tenmillimetre to Twenty five millimetre) as per specifications, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, GST or any other taxes imposed by the Government.	8.98	Per Square metre	33.30	Rupees Thirty Three - Paise Thirty Only	299.00
5	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50metres lead, as per specifications, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, GST or any other taxes imposed by the Government.	12.27	Per Square metre	22.25	Rupees Twenty Two - Paise Twenty Five Only	273.00

6	Demolishing brick work manually/by mechanical means including stacking of serviceable materials and disposal of unserviceable materials and disposal of unserviceable material within 50 metres lead in cement mortar as per specifications, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, GST or any other taxes imposed by the Government.	1.24	Per. Cubic metre	847.95	Rupees Eight Hundred & Forty Seven - Paise Ninety Five Only	1051.00
7	Brick work with common burnt clay F.P.S.(non modular) brick class of designation 7.5(seven point five) in super structure above plinth level up to floor V level in all shapes and sizes in cement mortar 1:6(One Cement is to Six Sand), as per specifications, approved drawing, design, as per entire satisfactions and direction of the Engineer-in-Charge including drawing, of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	0.47	Per. Cubic metre	8789.05	Rupees Eight Thousand Seven Hundred & Eighty Nine - Paise Five Only	4131.00
8	12 mm (Twelve milimetre) thick cement plaster in single coat on rough side of brick/concretes/ stone walls for interior plastering up to all floor level including arises, internal angles, chamfers and /or rounded angles not exceeding 80mm (Eighty milimetre) in girth and finished even and smooth with cement mortar 1:6 (One cement isto Six sand), as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana and toll tax, GST or any other taxes imposed by the Government.	18.57	Per Square metre	279.80	Rupees Two Hundred & Seventy Nine - Paise Eighty Only	5196.00
9	Repairs to plaster of thickness 12mm to 20mm in patches of area 2.5 square meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground,all complete with cement mortar 1:4(1cement:4 coarse sand)as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana and toll tax, GST or any other taxes imposed by the Government.	1.49	Per Square metre	276.15	Rupees Two Hundred & Seventy Six - Paise Fifteen Only	411.00
10	Applying Birla J.K. white wall care putty (two or more coats) over plaster surface after thoroughly brushing the surface free from mortar drops, dirt, dust, loose materials and other all floor levels, as per specifications, approved drawing, design, as per entire satisfaction upto direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana and toll tax, sale tax, GST or any other taxes imposed by the Government.	20.06	Per Square metre	108.00	Rupees One Hundred & Eight Only	2166.00

11	<p>Wall painting (two coats) with acrylic emulsion paint of approved brand and manufacture for interior grade on undecorated concrete/stone/plastered wall surfaces to give an even shade including thoroughly brushing the surface free from mortar droppings and as per specifications, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkhana and toll tax, sale tax, GST or any other taxes imposed by the Government.</p>	38.85	Per Square metre	90.57	Rupees Ninety - Paise Fifty Seven Only	3519.00
12	<p>Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% (Zero point zero eight percent) and conforming to IS: 15622, of oriental/ well/ spenza/ somany and other equivalent approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (One cement isto Four coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm (Three point three kilogram/square metre) including grouting the joints with white cement and matching pigments etc., complete size of tile 600x600mm (Six hundred into Six hundred milimetre) (in flooring) and as per the direction of the Engineer-in-Charge and carriage of material within all leads, lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.</p>	8.99	Per Square metre	1407.85	Rupees One Thousand Four Hundred & Seven - Paise Eighty Five Only	12642.00
13	<p>Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% (Zero point zero eight percent) and conforming to IS: 15622, of oriental/ well/ spenza/ somany and other equivalent approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (One cement isto Four coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm (Three point three kilogram/square metre) including grouting the joints with white cement and matching pigments etc., complete size of tile 600x600mm (Six hundred into Six hundred milimetre) (in skirting, riser of steps) and as per the direction of the Engineer-in-Charge and carriage of material within all leads, lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.</p>	1.11	Per Square metre	1506.10	Rupees One Thousand Five Hundred & Six - Paise Ten Only	1672.00

14	<p>Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling. C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in charge. (Glazing, paneling and dash fasteners to be paid for separately) polyester powder coated aluminium (minimum thickness of polyester powder coating 50 micron) for fixed portion Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC15) as per specifications, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.</p>	34.38	Per Kilogram	388.10	Rupees Three Hundred & Eighty Eight - Paise Ten Only	13343.00
15	<p>Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling. C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in charge. (Glazing, paneling and dash fasteners to be paid for separately) polyester powder coated aluminium (minimum thickness of polyester powder coating 50 micron) For shutter of doors, windows & ventilators including providing and fixing hinges/pivots and making provision for fixing wherever required including the cost of EPDM rubber/neoprene gasket required (Fitting shall be paid for separately) Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC15) as per specifications, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the</p>	49.53	Per Kilogram	449.45	Rupees Four Hundred & Forty Nine - Paise Forty Five Only	22261.00

16	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge. (Cost of aluminium snap beading shall be paid in basic item); With float glass panes of 5mm(Five millimetre) thickness glass panes(weight not less than 12.50 kg/ sqm) as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, GST or any other taxes imposed by the Government.	2.96	Per-Square metre	1129.70	Rupees One Thousand One Hundred & Twenty Nine - Paise Seventy Only	3344.00
17	Providing and fixing anodised aluminium grill(anodised transparent or dyed to required shade according to IS:1868 with minimum anodic coating of grade AC 15)of approved design/pattern with approved design/pattern,with approved standard section and fixed to the existing window frame with C.P brass/stainless screws @200mm centre to centre, including cutting the grill to proper opening size for fixing and operation of handles and fixing approval anodised aluminium standard section around the opening ,all complete as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, GST or any other taxes imposed by the Government.	9.65	Per Kilogram	482.50	Rupees Four Hundred & Eighty Two - Paise Fifty Only	4656.00
Total:						7544.00

EXCESS = _____ %

LESS = _____ %


Executive Engineer,
HPPWD Kangra
Division Kangra.

SCHEDULE OF QUANTITY

NAME OF WORK:- REPAIR AND MAINTENANCE WORK OF HOSTEL BLOCK WING "D" NIPT CAMPUS (CHHEB) AT KANGRA (SUB HEAD)- REPAIR AND MAINTENANCE WORK OF ONE NO TWO BEDDED ROOM) HOSTEL BLOCK WING-D ALUMINIUM WORK. ,PRELAMINATED BOARD, CUP BOARD ,MILD STEEL BED BOX AND STUDY TABLE ETC.) (approx work)

Sr. No.	Description of work	Qty	Unit	In Figures	Rates		Estimated Cost: Earnest Money:-
					In Words	AMOUNT	
1	Providing and fixing 12mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type I, in panelling fixed in aluminium doors, windows shutters and partition frames with C.P. brass/stainless steel screws etc. complete as per architectural drawings pre-laminated particle board with decorative lamination on one side and balancing lamination on other side. as per specifications, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, GST or any other taxes imposed by the Government.	2.00	Per Square metre	900.00	Rupees Nine Hundred Only	1800.00	
2	Providing and fixing 200mmx10mm (Two hundred millimetre into Ten millimetre) aluminium tower bolts (Barrel type) make of PILOT/SHEEL or equivalent anodized transparent or dyed to required shade and colour with screws etc. complete. The rate is inclusive for carriage of materials within all leads, lifts and other incidentals. The rate including of octroi, royalty, Malkhana, toll tax, GST or other taxes imposed by the Government.	2.00	Each	85.60	Rupees Eighty Five - Paise Sixty Only	171.00	
3	Providing and fixing 150mmx10mm (one hundred millimetre into Ten millimetre) aluminium tower bolts (Barrel type) make of PILOT/SHEEL or equivalent anodized transparent or dyed to required shade and colour with screws etc. complete. The rate is inclusive for carriage of materials within all leads, lifts and other incidentals. The rate including of octroi, royalty, Malkhana, toll tax, GST or other taxes imposed by the Government.	8.00	Each	72.20	Rupees Seventy Two - Paise Twenty Only	578.00	
4	Providing and fixing 125mm (One hundred twenty five millimetres) size aluminium anodized make of PILOT/ Sheel handles anodized transparent or dyed to required colour and shade with necessary screws extra complete, as per specifications, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, GST or any other taxes imposed by the Government.	2.00	Each	57.55	Rupees Fifty Seven - Paise Fifty Five Only	115.00	

82155.00

1650/-

One Month

5	Providing and fixing 100mm (One hundred millimetres) size aluminium anodized make of PILOT/ Steel handles anodized transparent or dyed to required colour and shade with necessary screws etcetra complete, as per specifications, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkhana, toll tax, GST or any other taxes imposed by the Government.	4.00	Each	50.75	Rupees Fifty - Paise Seventy Five Only	203.00
6	Providing and fixing 250x16mm(Two hundred fifty into Sixteen millimetres) size anodized aluminium sliding door bolts anodized colour and shade with necessary bolts, nuts and screws etc. completed within all leads, lifts of materials and other incidentals. The rate including of octroi, royalty, Malkhana, toll tax, GST or other taxes imposed by the Government.	1.00	Each	214.20	Rupees Two Hundred & Fourteen - Paise Twenty Only	214.00
7	Providing and fixing aluminium hanging floor door stopper, ISI marked,(Twin rubber stoper) anodised (anodic coating not less than grade AC 10 as per IS:1868) transparent or Dyed to Required colour and shade, with necessary screw etc complete as per specifications, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkhana, toll tax, GST or any other taxes imposed by the Government	1.00	Each	61.00	Rupees Sixty One Only	61.00
8	Providing and fixing 250mm(Two hundred millimetre)bright finished hrad drawn hooks and eyes with screws complete,as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkhana and toll tax, GST or any other taxes imposed by the Government.	4.00	Each	47.60	Rupees Fourty Seven - Paise Sixty Only	190.00
9	Providing, supplying,transporting, and fixing a complete cup board of of overall size 600mm(W)x500 mm(D)x1950 mm(H),fabricated from 18 gauge mild steel(MS) sheet, comprising 4(four)fixed shelves,with locking arrangements,all welded and finished including surface preparation,anti-rust treatment,and powder coated finish, complete in all respects as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkhana and toll tax, GST or any other taxes imposed by the Government.	2.00	Each	15600.00	Rupees Fifteen Thousand Six Hundred Only	31200.00

10	<p>Providing, supplying, transporting and fixing single mild steel bed box with integrated storage of overall size 1950mmx450mm(LxWxH), fabricated with mild steel frame of approved section, incorporating 18 gauge MS sheet base/platform and 12mm thick commercial board of unioly/greenply/Centryply/Kit ply/Dura Ply at top, properly cut and fixed over the frame, complete with welding, grinding, smooth finishing, anti-rust primer treatment and powder coated finish, including all necessary fittings, fasteners, loading, unloading, shifting to respective rooms and installation at site complete in all respects per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana and toll tax, GST or any other taxes imposed by the Government.</p>	2.00	Each	15750.00	Rupees Fifteen Thousand Seven Hundred & Fifty Only	31500.00
11	<p>Providing, supplying, transporting and fixing Study Table of overall size 750mmx600mmx750(LxWxH), fabricated with 18 gauge mild steel square pipe of 25mmx25mm frame section, including 18mm thick commercial board of unioly/greenply/Centryply/Kit ply/Dura Ply at top, properly cut edge finished and fixed over the frame, complete with welding, grinding, smooth finishing, anti-rust primer treatment and powder coated finish, including all necessary fittings, fasteners, loading, unloading, shifting to respective rooms and installation at site complete in all respect as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana and toll tax, GST or any other taxes imposed by the Government.</p>	2.00	Each	5850.00	Rupees Five Thousand Eight Hundred & Fifty Only	11700.00
12	<p>Providing and fixing UV stabilised fiberglass reinforced plastic sheet roofing up to any pitch, including fixing with polymer coated 'J' or L hooks, bolts & nuts 8mm dia. G.I. plain/bitumen washers complete but excluding the cost of purlins, rafters, trusses, etc. The sheet shall be manufactured out of 2400 TEX panel roving incorporating minimum 0.3% ultra violet stabiliser in resin system under approximately 2400 psi and hot cured. They shall be of uniform pigmentation and thickness without air pockets and shall conform to IS 10192 and IS 12866. The sheets shall be opaque or translucent, clear or pigmented, textured or smooth as specified 2mm thick corrugated 2.5" or 4.2" or 6" or step-down (2" or 3" or 6") as specified, as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana and toll tax, GST or any other taxes imposed by the Government.</p>	1.61	Per Square metre	1031.85	Rupees One Thousand & Thirty One Paise Eighty Five Only	1661.00

13	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete, as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana and toll tax, GST or any other taxes imposed by the Government.	31.88	Per Kilogram	86.65	Rupees Eighty Six - Paise Sixty Five Only	2762.00
EXCESS = %		Total:				82155.00
LESS = %						


 Executive Engineer,
 HPPWD Kangra
 Division Kangra.

SCHEDULE OF QUANTITY

NAME OF WORK :- REPAIR AND MAINTENANCE OF LINK ROAD VILLAGE THARU KM. 0/000 TO 0/665 (SUB HEAD:- IMPROVEMENT OF ROAD AT RD 0/000 to 0/128)

S.NO	Description of work	Qty	Unit	Rates		AMOUNT
				In Figures	In Words	
1	Excavation in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with a lift up to 1.5 mtr and lead up to 20 metre as per clause 1603.2 as per specification, approved drawing design as per the entire satisfaction and direction of the Engineer-in-Charge including carriage of material within leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, GST or any other taxes imposed by the Government.	191.59	Per Cubic metre	305.80	Rupees Three Hundred & Five Paise Eighty Only	58588.00
2	Excavation in hilly area in Soil by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift up to 1.5 metre and a lead up to 20 metre as per technical specification clause 1603.1 per specification, approved drawing design as per the entire satisfaction and direction of the Engineer-in-Charge including carriage of material within leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, GST or any other taxes imposed by the Government.	191.59	Per Cubic metre	215.80	Rupees Two Hundred & Fifteen - Paise Eighty Only	41345.00
Total:						99933.00

EXCESS = _____ %

LESS = _____ %


 Executive Engineer,
 HPPWD Kangra
 Division Kangra

SCHEDULE OF QUANTITY

NAME OF WORK :-REPAIR AND MAINTENANCE OF LINK ROAD VILLAGE THARU KM. 0/000 TO 0/665(SUB HEAD:- IMPROVEMENT OF ROAD AT RD 0/128 to 0/225)						
					Estimated Cost:-	98803.00
					Earnest Money:-	2000/-
					Time Limit:-	ONE MONTH
S.NO	Description of work	Qty	Unit	Rates		AMOUNT
				In Figures	In Words	
1	Excavation in tully area in ordinary rock, not requiring blasting by mechanical means including cutting and firming of slopes and disposal of cut material with a lift up to 1.5 mtr and lead up to 20 metre as per clause 1603.2as per specification, approved drawing design as per the entire satisfaction and direction of the Engineer-in-Charge including carriage of material within leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malakhana, toll tax, GST or any other taxes imposed by the Government.	206.44	Per Cubic metre	305.80	Rupees Three Hundred & Five Paise Eighty Only	63129.00
2	Excavation in tully area in Soil by mechanical means including cutting and firming of side slopes and disposing of excavated earth with a lift up to 1.5 metre and a lead up to 20metre as per technical specification clause 1603.1 per specification, approved drawing design as per the entire satisfaction and direction of the Engineer-in-Charge including carriage of material within leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, GST or any other taxes imposed by the Government.	165.31	Per Cubic metre	215.80	Rupees Two Hundred & Fifteen - Paise Eighty Only	35674.00
Total:						98803.00

EXCESS = _____ %

LESS = _____ %


 Executive Engineer,
 HPPWD Kangra
 Division Kangra

SCHEDULE OF QUANTITY

**NAME OF WORK:- CONSTRUCTION OF BALANCE WORK OF AYURVEDIC HEALTH CENTRE AT SALOL
TEHSIL AND DIST. KANGRA HP. (SH:- PROVIDING AND FIXING INTERLOCKING TILES AND CUP BOARD)**

(Deposit work)

Sr. No.	Description of work	Qty	Unit	Rates		Estimated Cost:- Earnest Money:- Time Limit:-	ONE MONTHS AMOUNT
				In Figures	In Words		
				Per Square metre	Rupees One Thousand Five Hundred & Ninety Only		
1	Providing and fixing cup board shutters 19 mm thick, Commercial board water proof shutter for cup board including fixing nickel plated piano hinges with screw etc complete in all respect as per direction of Engineer-in-charge including carriage of materials with in all leads and lifts and other incidentals. The rate including of octroi, malkhana, tolltax, sale Tax or other taxes imposed by the government.	30.39	Per Square metre	1590.00	Rupees One Thousand Five Hundred & Ninety Only	99817.00 2000/-	48320.00
2	Providing and laying 40mm.-(Forty millimetre) thick factory made cement concrete interlocking paver blocks of M30 grade made by blocks making machine with strong vibratory compaction of approved size, design and shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand filling the joints with fine sand etc. complete in all respect as directed by the Engineer-in-charge, within all leads, lifts of materials and other incidentals. The rate including of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	66.00	Per Square metre	650.00	Rupees Six Hundred & Fifty Only		42900.00
3	Providing and laying mechanically mixed and vibrated, concrete for plain cement concrete in open foundation of all type of structure complete, grade- M-20 (M twenty) nominal mix 1:2:4 (One cement isto Two sand isto four graded crushed stone aggregate 20mm: (Twenty millimetre) nominal size with cement contents not less than of 330 (Three hundred thirty) Kilogramme Per Cubic metre with 20mm (Twenty millimetre) nominal size graded crushed stone aggregate and curing complete, for all heights/-depths including the cost of form work as per drawings and MORD technical section 800, 900 and 1200 and as per the direction of Engineer-in-Charge. The rate is inclusive for carriage of materials within all leads, lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	1.36	Per Cubic metres	6321.20	Rupees Six Thousand Three Hundred & Twenty One - Paise Twenty Only		8597.00
Total:							99817.00

EXCESS = _____ %

LESS = _____ %


EXECUTIVE ENGINEER
KANGRA DIVISION
HP, PWD, KANGRA