

O/o the Executive Engineer, Karchham Division, HP.PWD., Bhabanagar.

Web: [www.hppwd.gov.in](http://www.hppwd.gov.in), Email: [ee-karc-hp@nic.in](mailto:ee-karc-hp@nic.in)

Phone No.-01786-292897

No. PW/BHNR-B&R-EA-I-Tender/2025-26- *13138*  
To


Dated:- *19-3-2026*

The Executive Engineer, (IT)  
Nigam Vihar Shimla-2.

Subject: - Publication of tender notice

Tender Notice alongwith Schedule of Quantities for the works tenders invited vide this office NIT No. PW/BHNR-B&R-EA-I-Tender/25-26- dated 19.03.2026 as per Notification No. PWD-B-A0(3)/1/2024-241828 dated 18.09.2025 issued by the Additional Chief Secretary (PW) to the Govt. of HP & circulated by the Engineer-in-Chief, HP.PWD., office letter No.PW/CTR/32-20/Genl Inst/ GCC/2025-10063-10163 dated 27.09.2025 is enclosed herewith for uploading the same on departmental website for wide publicity.

DA:- Copy of NIT & Schedule of Quantity

  
Executive Engineer,  
Karchham Division,  
HP.PWD., Bhabanagar

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT  
NOTICE INVITING TENDER**

Sealed percentage tender(s) on PWD form No.6 & 8 are hereby invited by the Executive Engineer, Karchham Division, HP.PWD, Bhabanagar Distt. Kinnaur (H.P) on behalf of the Governor of H.P for the following works from the registered contractors in HP.PWD in appropriate class to reach in this office on **28.03.2026** up to 10.30 A.M. and will be opened on the same day at 11.00A.M. in the presence of Contractors or their authorized representative who wish to be present at that time. The application for obtaining the tender form will be received on **27.03.2026** i.e. 11.00 AM to 1.00 PM and the tender form can be had from this office against this cash payment (Non- refundable) on the same day from 2.00P.M. to 5.00 P.M. No application shall be entertained through e-mail or FAX.


Earnest money shall be in shape of NSC/FDR duly pledged in favour of Executive Engineer, Karchham Division, HP.PWD, Bhabanagar Distt. Kinnaur H.P. Ambiguous /Telegraphically/conditional tenders or tender through FAX shall not be entertained/ considered in any case.

Sr. No.	Name of Work	Estimated Cost	Earnest Money	Time	Cost of form
1	A/R & M/O road from Urni Bus Stand to Village Urni Km 0/00 to 0/725.(SH:-C/O Interlocking Concrete Block Pavement from RD 0/199 to 0/264.)	490073	9900	Two months	350/
2	C/O jeepable road from Baltrang to Kanai via Yengskone road km 0/00 to 5/300(SH:-C/O R /Wall in wire crate at RD 0/00 to 0/045)	486929	9800	Two months	350/
3	R/R damages on jeepable road from Katgaon to Katgoan Kanda Km 0/00 to 5/500(SH:-C/o B/wall at RD 1/932 to 1/950)	191183	3900	Two months	350/
4	A/R & M/O Residential Building at Det Sungra (SH :- P/L Cement Concrete in slab Painting etc)	138543	2800	Two months	350/
5	R/R Damages on Kafnoo to Yangpa road km 0/00 to 5/00.(SH:-Protection both side abutment on Kafnoo to Yangpa road at RD 1/195 to 1/204).	488262	9800	Two months	350/
6	R/R damages on jeepable road from Katgaon to Katgaon Kanda Km 0/00 to 5/500(SH:-C/o B/wall at RD 3/270 to 3/286)	478108	9600	Two months	350/
7	R/R Damages from Nigulsari to Tranda Road km 0/00 to 5/555.(SH:-C/O of B/ wall in CC 1:4:8 at RD 3/260 to 3/272).	198049	4000	Two months	350/
8	RR Damages on Wangtoo Kafnoo road km 0/00 to 20/00 (SH:-C/o B/wall at RD 15/470 to 15/488).	411356	8300	Two months	350/
9	R/R Damages on Katgoan Kanda road km 0/00 to 5/00(SH:-C/o R/wall at RD 2/900 to 2/913.5)	492899	9900	Two months	350/
10	R/R damages on Link road to village Nanspo to Upper Tranda Road km 0/00 to 3/500.(SH:-C/O R/ wall in C.C 1:4:8 at RD 3/410 to 3/414 and Kharanja Soling and CC 1:2:4 AT rd 3/390 to3/450.)	267278	5400	Two months	350/
11	R/R Damages on link road to village Themgarang Km 0/00 to 1/00 (SH:-Improvement of curve and C/O of B/wall at RD 0/210 to 0/225).	489469	9800	Two months	350/
12	Preparation of DPR for the construction of link road to Brua Kanda Km 0/00 to 6/00.	210000	4200	One Months	350/
13	R/R Damages on link road to village Themgarang Km 0/00 to 1/00 (SH:- C/o B/wall at RD 0/230 to 0/240 and 0/260 to 0/268 ) in Gram Panchyat Themgarang )	390059	7900	Two months	350/
14	RR Damages On Palingi to Nichar road Km 0/00 to 16/00 (SH:- C/O R/wall at RD 5/935 to 5/950)	341174	6900	Two months	350/

15	R/R Damages on Jeepable road from Katgoan to Katgoan Kanda Km 0/00 to 5/500. (SH:-C/o R/wall at RD 0/364 to 0/374).	481314	9700	Two months	350/
16	R/R Damages on link road Karchham to Sapni Km 0/00 to 8/300.(SH:-C/O Random rubble masonry R/ wall at RD 7/775 to 7/786.50)	485571	9800	Two months	350/-
17	R/R Damages Kafnoo Yangpa road Km 0/00 to 5/00 (SH:-C/o R/wall at RD 3/540 to 3/560)	454714	9100	Two months	350/-
18	R/R Damages link road from NH-05 to Chaura to Forest Rest House Choura Km 0/00 to 3/500 SH:-C/O R/wall in CC 1:4:8 and R/R masonry 1:6 at Rd 0/070 to 0/075.70)	481836	9700	Two months	350/-

### SPECIAL CONDITIONS


1. The material shall be arranged by the contractor himself.
2. The detail of documents to be attached with the application is given below.
  - i Latest copy of renewal enlistment.
  - ii Copy of Pan Card.
  - iii Copy of GST No.
3. The offer of the tender shall be kept open for 90 days
4. Tender received after the specified time/date shall not be opened.
5. Executive Engineer, Karchham Division, HP.PWD, Bhabanagar Distt. Kinnaur H.P. reserves the right to reject any or all tender/s without assigning any reasons.
6. If due to any unforeseen reasons the office of the Executive Engineer, Karchham Division, HP.PWD, Bhabanagar Distt. Kinnaur remain closed on the notified date of sale and receipt of tender, tender will be sold and received/opened the next working day of same specified time.
7. Tenderers may contact the Executive Engineer for any further information they may require during the working day/ office hours.
8. The contractors are requested to insert the rate of each in words as well as in figures failing which Executive Engineer reserves the right to reject any or all tenders.
9. The labourcess shall allow/ deduction @ 2% TDS amount of GST (1% CGST and 1% SGST).
10. The labour cess @ 1% will be deducted from the gross amount of the bill
11. All the works are of urgent nature hence the contractor already having two works are not eligible to participate for the tendering.
12. A contractors enlisted in a particular class shall be eligible to tender for his own class and one step below as per Govt. notification.
13. The Contractor will have to submit the proof of registration under Employees Provident Funds & Miscellaneous Provision Act.1952 before award of work.
14. Cement should be purchased from H.P. State Civil Supply Corporation.
15. GST will be deducted from each bill as per latest instruction of the Government.
16. L-1 bidder shall be borne an additional performance security for unbalanced financial bid in accordance with the Govt. Notification PBW(B) A(3)1/2020-1 dated 07.10.2021.

  
Executive Engineer,  
Karchham Division,  
HP.PWD Bhabanagar.

Dated:- 19-3-2026


No.PW/BHNR/B&R/EA-I-Tender Notice/2025-26- 13127 -37  
Copy forwarded for information to the:-

1. Engineer-in-Chief, HP.PWD, Shimla
2. Chief Engineer (SZ) HP.PWD, Shimla-1
3. Superintending Engineer, 11<sup>th</sup> Circle, HP.PWD, Rampur
4. All the Assistant Engineer working under this division
5. A/B & D/B in this office.
6. Notice board of this office.

  
Executive Engineer,  
Karchham Division,  
HP.PWD Bhabanagar.

## Certificate

Certified that the tenders for the works invited vide this office NIT No. PW/BHNR- B&R -EA -I- Tender/ 25-26-~~13127-37~~ dated 19.03.2026 is of urgent nature in exigency of public interest.

  
Executive Engineer,  
Karchham Division,  
HP.PWD., Bhabanagar

247

Draft Schedule of Quantity

Job No-01

Estimated Cost:- 490073.00  
Earnest Money:- 9900.00  
Time:- Two Months

Name of work:- A/R & M/O road from Urmi Bus Stand to Village Urmi Km 0/00 to 0/725.  
Sub Head:- C/O Interlocking Concrete Block Pavement from RD 0/199 to 0/264.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	45.50	300.00	Rupees Three Hundred Only	Per cubic metre	13650.00
2	Providing & laying stone soling properly hard packed filling interstices with kharanja stone and consolidating with power road roller to the required gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HPPWD specification and direction of the Engineer-in-Charge.	23.40	1960.65	Rupees One Thousand Nine Hundred Sixty and Sixty Five Paisas	Per cubic metre	45879.00
3	Providing and laying cement concrete 1:6:12 (one cement : six sand: twelve graded stone aggregate 40mm (forty millimeter) nominal size for plain /reinforced concrete in open foundations complete as per drawings and technical specification clauses 802, 803, 1202 and 1203 and curing complete including the cost of form work and carriage of materials in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	15.60	4315.25	Rupees Four Thousand Three Hundred Fifteen and Twenty Five Paisas Only	Per cubic metre	67318.00
4	Providing and laying of interlocking Concrete Block Pavements having thickness 80mm as per Drawings and Technical Specifications Clause 1504 as per the direction of the Engineer-in-Charge.	156.00	1497.29	Rupees One Thousand Four Hundred Ninety Seven and Twenty Nine Paisas Only	Per cubic metre	233577.00
5	Providing and laying plain / Reinforced cement concrete 1:2:4 (One cement : two sand : four graded crushed stone aggregate 25 mm (forty millimeters ) nominal size curing complete including the cost of formwork for plain / Reinforced concrete in Retaining / Breast walls as per drawing and H.P.P.W.D. specification and carriage of materials all leads and lifts.	8.14	6179.70	Rupees Six Thousand One Hundred Seventy Nine and Seventy Paises Only	Per cubic metre	50278.00
6	Supplying, fitting and placing TMT bar reinforcement in superstructure complete as per drawings and technical specifications Clauses 1000 and 1202 and carriage of materials in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	758.807	104.60	Rupees One Hundred Four and Sixty Paisas Only	Kg	79371.00
					Total	490073.00

*Draft Schedule of Quantity approved for amounting to Rs 490073/only*

*[Signature]*

Executive Engineer,  
Karchham Division, HPPWD.,  
Karchham at Bhaba Nagar

248

Draft Schedule of Quantity

Job-02

Estimated Cost:- 486929.00

Earnest Money:- 9800.00

Time:- Two Months

Name of work:-C/O jeepable road from Baltrang to Kanai via Yengskone road km 0/00 to 5/300

Sub Head:- (C/O R /Wall in wire crate at RD 0/00 to 0/045).

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation in foundation structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidentals.	25.60	300.00	Rupees Three Hundred Only	Per cubic metre	7680.00
2	Providing and laying boulder apron laid in wire crates with 4 mm diameter G.I. wire confirming to IS:280 and IS:4826 in 100mmx 100mm (one hundred into one hundred millimetre) mesh (woven diagonally) including 10 % (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge.	133.20	3236.55	Rupees Three Thousand Two Hundred Thirty Six and Fifty Five Paisas Only	Per cubic metre	431108.00
3	Construction of embankment with approved material obtained from borrow pits within all leads and lifts, transporting to site, spreading, grading to required slope and compacting to meet requirement of table 300.1 and 300.2 as per technical specification clause 301.5 and as per the entire satisfaction and direction of Engineer-in-charge.	161.90	297.35	Rupees Two Hundred Ninety Seven and Thirty Five Paisas Only	Per cubic metre	48141.00
					Total	486929.00

*Draft Schedule of Quantity approved for amounting to Rs 486929/-only*

*[Signature]*

Executive Engineer,  
Karchham Division, HPPWD.,  
Karchham at Bhaba Naga

## Draft Schedule of Quantity

Job-03

191183.00

Estimated Cost:-

3900.00

Earnest Money:-

Two Months

Time:-

Name of work:-R/R damages on jeepable road from Katgaon to Katgaon Kanda Km 0/00 to 5/500

Sub Head:- (SH:-C/o B/wall at RD 1/932 to 1/950)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation in foundation structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidentals.	33.75	300.00	Rupees Three Hundred Only	Per cubic metre	10125.00
2	Providing and laying boulder apron laid in wire crates with 4 mm diameter G.I. wire conforming to IS:280 and IS:4826 in 100mmx 100mm (one hundred into one hundred millimetre) mesh (woven diagonally) including 10 % (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge.	56.25	3218.80	Rupees Three Thousand Two Hundred Eighteen and Eighty Paisas Only	Per cubic metre	181058.00
					Total	191183.00

*Draft Schedule of Quantity approved for amounting to Rs:- 191183/- only*

Executive Engineer,  
Karchham Division, HPPWD.,  
Karchham at Bhaba Nagark

**Draft Schedule of Quantity**

Job-04

138543.00

2800.00

Two Months

Estimated Cost:-

Earnest Money:-


Time:-

250

Name of work:-A/R & M/O Residential Building at Det Sungra.( P/L Cement Concrete in slab, painting etc.)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Distemping (one coat) i/c one No. subsequent coat with oil bound washable distemper of approved brand and manufacture and of required shade, on decorated wall surfaces to give an even shade, after thoroughly brushing the surface clean of all grease, dirt, loose pieces of scales and also including preparing the surface even and sand papered smooth including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	197.64	145.10	Rupees One Hundred Forty Five and Ten Paises Only	Per Square meter	28678.00
2	Distemping(one coat) i/c one No. subsequent coat with oil bound washable distemper of approved brand and manufacture and of required shade, on decorated wall surfaces to give an even shade, after thoroughly brushing the surface clean of all grease, dirt, loose pieces of scales and also including preparing the surface even and sand papered smooth including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax.	63.65	105.30	Rupees One Hundred Five and Thirty Paises Only	Per Square meter	6702.00
3	Providing and laying cement concrete 1:1.5:3 (1cement 15 sand 3 graded stone aggregate 20mm. nominal size) and curing complete excluding cost of form work and reinforcement for reinforced concrete work in Suspended floors roofs, landings and shelves and their supports, balconies, beams, girders, bressumers and cantilevers up to floor two level including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals The rates are inclusive of octroi, royalty, malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	7.10	12688.60	Rupees Twelve Thousand Six Hundred Eighty Eight and Sixty Paises Only	Per cubic metre	90089.00
4	Providing and fixing PTMT colored /white high density polyethylene/ poly propylene 10 ltr. Capacity (Full flush) European Standard control low level flushing cistern with fittings with a pair of brackets with fittings such as lead valve, syphon, 15 mm nominal size PVC ball valve with polythene float, with push button, couplings for connections with inlet, out let and overflow pipe, 40 mm dia C.P. flush bend including cutting holes in walls and making good the same and connecting the flush bend with cistern and closet (overflow) pipe to be measured and paid for separately including carmage of maternal with in all leads and other incidentals including carriage of material, labour, tool and plants through all modes of transpiration within all leads and as per direction of the Engineer-in-charge	1.00	2100.00	Rupees Two Thousand One Hundred Only	Nos	2100.00
5	Providing and fixing 1000 ltr PVC water storage tank of ISI 12701 marked, G.I. inlet and outlet connection, 15mm nominal bore ball valve and mosquito proof PVC cover with locking arrangement including hoisting up to all heights above ground level -	1.00	10973.85	Rupees Ten Thousand Nine Hundred Seventy Three and Eighty Five Paises Only	Nos	10974.00
					<b>Total</b>	<b>138543.00</b>

*Draft Schedule of Quantity approved amounting to Rs 138543/- only*

  
 Executive Engineer,  
 Karchham Division, HPPWD.,  
 Karchham at Bhaba Nagary

**Draft Schedule of Quantity**

**Job-05**

488262.00

9800.00

Two Months

Estimated Cost:-

Earnest Money:-

Time:-

Name of work:-/R Damages on Kafnoo to Yangpa road km 0/00 to 5/00.

Sub Head:- Protection of both side abutment on Kafnoo to Yangpa road at RD 1/195 to 1/204).

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation in foundation structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidentals.	49.14	300.00	Rupees Three Hundred Only	Per cubic metre	14742.00
2	Providing and laying boulder apron laid in wire crates with 4 mm diametre G.I. wire confirming to IS:280 and IS:4826 in 100mmx 100mm (one hundred into one hundred millimetre) mesh (woven diagonally) including 10 % (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge.	40.50	3218.80	Rupees Three Thousand Two Hundred Eighteen and Eighty Paises Only	Per cubic metre	130361.00
3	Providing and laying cement concrete 1:4:8 (One cement : four sand : eight graded stone aggregate 25mm (Twenty Five millimetre) nominal size) and curing complete including cost of form work in retaining walls/breast walls, as per drawing and technical specification clause 802, 803, 1202 & 1203 as per HPPWD specification within all leads and lifts and as per the direction of Engineer-in-charge.	61.56	5281.00	Rupees Five Thousand Two Hundred Eighty One Only	Per cubic metre	325098.00
4	Providing weep holes in brick masonry/stone masonry/plain/ reinforced concrete abutment wing wall, return wall with 100mm.(One hundred millimetre) dia PVC pipe extneiding through the full with of the structures with slope of 1 (v) : 20(H) towards drawing face complete as per drawing and technical specification clause 614,709,12.04.3.7 within all leads and lifts and as per direction of Engineer-in-charge.	10.00	260.10	Rupees Two Hundred Sixty and Ten Paises Only	Each	2601.00
5	Back filling behind abutment, wing wall and return wall/breast wall and retaining walls complete as per drawing and technical specification within all leads and lifts and as per the direction of Engineer-in-charge.	15.93	970.50	Rupees Nine Hundred Seventy and Fifty Paises Only	Per cubic metre	15460.00
					<b>Total</b>	<b>488262.00</b>

*Draft schedule of quantity approved for amounting to Rs. 488262/- only*

*Yank*  
Executive Engineer,  
Karchham Division, HPPWD.,  
Karchham at Bhaba Nagar.

**Draft Schedule of Quantity**

**Job-06**

478108.00

9600.00

Two Months

Estimated Cost:-

Earnest Money:-

Time:-

252

Name of work:-R/R Damages on jeeppable road from Katgaon to Katgaon Kanda Km 0/00 to 5/500  
Sub Head:-(C/o B/wall at RD 3/270 to 3/286)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation in foundation structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidentals.	54.40	300.00	Rupees Three Hundred Only	Per cubic metre	16320.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C. grade Nominal mix (1:4:8) (one Cement: four sand: eight coarse aggregate) and curing complete including carriage of materials in all leads lifts as per the entire satisfaction and direction of Engineer-in-Charge.	38.40	5281.00	Rupees Five Thousand Two Hundred Eighty One Only	Per cubic metre	202790.00
3	Providing and laying boulder apron laid in wire crates with 4 mm diameter G.I. wire confirming to IS:280 and IS:4826 in 100mmx 100mm (one hundred into one hundred millimetre) mesh (woven diagonally) including 10 % (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge.	74.88	3218.80	Rupees Three Thousand Two Hundred Eighteen and Eighty Paisas Only	Per cubic metre	241024.00
4	Providing weep holes in brick masonry/stone masonry/plain/ reinforced concrete abutment wing wall, return wall with 100mm.(One hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1 (v) : 20(H) towards drawing face complete as per drawing and technical specification clause 614,709,12.04.3.7 within all leads and lifts and as per direction of Engineer-in-charge.	10.00	260.10	Rupees Two Hundred Sixty and Ten Paisas Only	Each	2601.00
5	Back filling behind abutment, wing wall and return wall/breast wall and retaining walls complete as per drawing and technical specification within all leads and lifts and as per the direction of Engineer-in-charge.	15.84	970.50	Rupees Nine Hundred Seventy and Fifty Paisas Only	Per cubic metre	15373.00
					<b>Total</b>	<b>478108.00</b>

*Draft Schedule of Quantity approved for amounting to Rs. 478108/- only*

*[Signature]*

Executive Engineer,  
Karchham Division, HPPWD.,  
Karchham at Bhaba Nagar

253

Draft Schedule of Quantity

Job-07

Estimated Cost:- 198049.00

Earnest Money:- 4000.00

Time:- Two Months

Name of work:-R/R Damages from Nigulsari to Tranda Road km 0/00 to 5/555.  
Sub Head:-C/O of B/ wall in CC 1:4:8 at RD 3/260 to 3/272.)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation in foundation structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidentals.	45.48	300.00	Rupees Three Hundred Only	Per cubic metre	13644.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C. grade Nominal mix (1:4:8) (one Cement: four sand: eight coarse aggregate) and curing complete including carriage of materials in all leads lifts as per the entire satisfaction and direction of Engineer-in-Charge.	34.20	5270.25	Rupees Five Thousand Two Hundred Seventy and Twenty Five Paisas Only	Per cubic metre	180243.00
3	Providing weep holes in brick masonry/stone masonry/plain/ reinforced concrete abutment wing wall, return wall with 100mm.(One hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1 (v) : 20(H) towards drawing face complete as per drawing and technical specification clause 614,709,12.04.3.7 within all leads and lifts and as per direction of Engineer-in-charge.	16.00	260.10	Rupees Two Hundred Sixty and Ten Paisas Only	Each	4162.00
					Total	198049.00

*Draft Schedule of Quantity approved for amounting to Rs:- 198049/only*  
Executive Engineer,  
Karchham Division, HPPWD.,  
Karchham at Bhaba Nagars

254

### Draft Schedule of Quantity

Job-08

411356.00

Estimated Cost:-

8300.00

Earnest Money:-

Two Months

Time:-

Name of work:-RR Damages on Wangtoo Kafnoo road km 0/00 to 20/00  
Sub Head:-C/o B/wall at RD 15/470 to 15/488)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation in foundation structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidentals.	54.90	300.00	Rupees Three Hundred Only	Per cubic metre	16470.00
2	Providing and laying cement concrete 1:6:12 (one cement : six sand: twelve graded stone aggregate 40mm (forty millimeter) nominal size for plain /reinforced concrete in open foundations complete as per drawings and technical specification clauses 802, 803, 1202 and 1203 and curing complete including the cost of form work and carriage of materials in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	5.94	4298.55	Rupees Four Thousand Two Hundred Ninety Eight and Fifty Five Paises Only	Per cubic metre	25533.00
3	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for structure like retaining walls, breast walls wing walls, toe walls, abutment and similar works etc. in all heights complete as per drawing and technical specification clauses 702, 704, 1202 & 1204 and curing complete including carriage of materials in all leads lifts as per the entire satisfaction and direction of Engineer-in-Charge.	65.81	5489.90	Rupees Five Thousand Four Hundred Eighty Nine and Ninety Paises Only	Per cubic metre	361290.00
4	Providing weep holes in brick masonry/stone masonry/plain/ reinforced concrete abutment wing wall, return wall with 100mm.(One hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1 (v) : 20(H) towards drawing face complete as per drawing and technical specification clause 614,709,12.04.3.7 within all leads and lifts and as per direction of Engineer-in-charge.	31.00	260.10	Rupees Two Hundred Sixty and Ten Paises Only	Each	8063.00
					Total	411356.00

*Draft Schedule of Quantity approved for amounting to Rs 411356/-only*

Executive Engineer,  
Karchham Division, HPPWD.,  
Karchham at Bhaba Nagars

255

Draft Schedule of Quantity

Job-09

Estimated Cost:- 492899.00

Earnest Money:- 9900.00

Time:- Two Months

Name of work:-R/R Damages on Katgaon to Katgaon Kanda road km 0/00 to 5/00

Sub Head:-C/o R/wall at RD 2/900 to 2/913.5)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation in foundation structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidentals.	49.68	300.00	Rupees Three Hundred Only	Per cubic metre	14904.00
2	Providing and laying cement concrete 1:6:12 (one cement : six sand: twelve graded stone aggregate 40mm (forty millimeter) nominal size for plain /reinforced concrete in open foundations complete as per drawings and technical specification clauses 802, 803, 1202 and 1203 and curing complete including the cost of form work and carriage of materials in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge	6.21	4298.55	Rupees Four Thousand Two Hundred Ninety Eight and Fifty Five Paises Only	Per cubic metre	26694.00
3	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for structure like retaining walls, breast walls wing walls, toe walls, abutment and similar works etc. in all heights complete as per drawing and technical specification clauses 702, 704, 1202 & 1204 and curing complete including carriage of materials in all leads lifts as per the entire satisfaction and direction of Engineer-in-Charge.	81.00	5278.05	Rupees Five Thousand Two Hundred Seventy Eight and Five Paises Only	Per cubic metre	427522.00
4	Providing weep holes in brick masonry/stone masonry/plain/ reinforced concrete abutment wing wall, return wall with 100mm.(One hundred millimetre) dia PVC pipe extneiding through the full with of the structures with slope of 1 (v) : 20(H) towards drawing face complete as per drawing and technical specification clause 614,709,12.04.3.7 within all leads and lifts and as per direction of Engineer-in-charge.	34.00	260.10	Rupees Two Hundred Sixty and Ten Paises Only	Each	8843.00
5	Back filling behind Retaining wall with granular material complete as per drawing and M.O.R.D. technical specification clause 1204.3.8. Including carriage of material within all lead and lifts and other incidentals.	15.39	970.50	Rupees Nine Hundred Seventy and Fifty Paises Only	Per cubic metre	14936.00
					Total	492899.00

Draft Schedule of Quantity approved for amounting to Rs 492899/only

*[Signature]*

Executive Engineer,  
Karchham Division, HPPWD.,  
Karchham at Bhaba Nagar.

**Draft Schedule of Quantity**

**Job-10**

267278.00

5400.00

Two Months

Estimated Cost:-

Earnest Money:-

Time:-

Name of work:- R/R damages on Link road to village Nanspo to Upper Tranda Road km 0/00 to 3/500.

Sub Head:- C/O R/ wall in C.C.1:4:8 at RD 3/410 to 3/414 and Kharanja Soling and CC 1:2:4 AT rd 3/390 to 3/450.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation in foundation structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidentals.	35.60	300.00	Rupees Three Hundred Only	Per cubic metre	10680.00
2	Stone soling properly hand packed filling interstices with kharanja stone and consolidating with power road roller to the required gradient and camber including spreading watering and rolling of binding materials moorum or earth etcetra complete as per HP.PWD. specification. 100mm (one hundred millimetre) spread thickness (finished work including materials and labour) including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge.	33.20	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	74700.00
3	Providing and laying plain cement concrete Grade M -20(Twenty) nominal mix 1:2:4 (one cement: two sand: four graded crushed stone aggregate 20mm (twenty millimeter) nominal size concrete for plain/reinforced concrete in open foundations complete including form work as per drawings and Technical Specifications Clause 802, 803, 1202 & 1203 and as per the direction of the Engineer-in-Charge including carriage of material through all modes of transportation within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tal, sale tax, or other taxes imposed by government.	21.75	7020.90	Rupees Seven Thousand Twenty and Ninety Paises Only	Per cubic metre	152705.00
4	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C. grade Nominal mix (1:4:8) (one Cement: four sand: eight coarse aggregate) and curing complete including carriage of materials in all leads lifts as per the entire satisfaction and direction of Engineer-in-Charge.	5.40	5309.90	Rupees Five Thousand Three Hundred Nine and Ninety Paises Only	Per Cubic Meter	28673.00
5	Providing weep holes in brick masonry/stone masonry/plain/ reinforced concrete abutment wing wall, return wall with 100mm.(One hundred millimeter) dia PVC pipe extneiding through the full with of the structures with slope of l (v) : 20(H) towards drawing face complete as per drawing and technical specification clause 614,709,12.04.3.7 within all leads and lifts and as per direction of Engineer-in-charge.	2.00	260.10	Rupees Two Hundred Sixty and Ten Paises Only	Each	520.00
					<i>[Signature]</i>	
					<b>Total</b>	<b>267278.00</b>

*Draft Schedule of Quantity approved for amounting to Rs 267278/- only*

**Executive Engineer,  
Karchham Division, HPPWD.,  
Karchham at Bhaba Nagar**

257

**Draft Schedule of Quantity**

**Job-11**

Estimated Cost:- 489469.00  
 Earnest Money:- 9800.00  
 Time:- Two Months

Name of work:- R/R Damages on link road to village Themgarang Km 0/00 to 1/00  
 Sub Head:- Improvement of curve and C/o of B/wall at RD 0/210 to 0/225)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Cutting in earth work in all depths and heights in hard rock with chiseling and wedging out of rock (where blasting is prohibited), or setting out to the required lines grades, side slopes, trimming of bottom and levels as shown on the drawing and as directed by the Engineer-in-charge at site according to the HPPWD specification of 1990 volume-1 and sorting of useful and unuseful materials and stacking the useful material along road side which shall not be less than 97.65/- cubic meter failing which recovery @ Rs. 300/- per cubic meter shall be effected and transportation of the unuseful material for filling in roadway embankments for grade improvement and level to required grades and then disposing off all surplus excavated material in acquired width of the road or on approved dumping site through all modes of transportations including head load, animal loads or mechanical means along with its leveling and fine dressing and carriage of all labour machinery, materials, tools, equipments and safety measured and other incidentals necessary to complete the work by mechanical means and or labor (if any required complete as per the direction of Engineer-in-Charge). Any loss to the public and private property during the course of execution and transportation of useful and unuseful materials shall be absolute responsibility of the contractor which shall have to be dully compensated by him to full extent complete in all respects and in all cases.	496.50	343.79	Rupees Three Hundred Forty Three and Seventy Eight Paisas Only	Per cubic metre	170690.00
2	Earth work in excavation in foundation structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidentals.	6.75	300	Rupees Three Hundred Only	Per cubic metre	2025.00
3	Providing and laying cement concrete 1:6:12 (One cement : Six sand : Twelve graded/crushed stone aggregate 40mm (Forty millimetre) nominal size) mechanically mixed and curing complete excluding cost of form work in foundation and plinth including carriage of materials within all leads and lifts complete in all respect.	6.75	4332.7	Rupees Four Thousand Three Hundred Thirty Two and Seventy Paisas Only	Per cubic metre	29246.00
4	Random rubble masonry/polygonal rubble masonry (uncoursed/brought to courses) with hard stone of approved quality/quarry in foundation and plinth including leveling up with cement concrete 1:6:12 (one cement : six sand : twelve graded/crushed crushed stone aggregate 20mm (Twenty millimetre) nominal size) at plinth level in cement mortar 1:6 (one cement : six sand) including curing and carriage of materials within all leads and lifts complete in all respect as per direction of Engineer in Charge.	53.16	5310.5	Rupees Five Thousand Three Hundred Ten and Fifty Paisas Only	Per cubic metre	282306.00
5	Providing weep holes in brick masonry/stone masonry/plain/ reinforced concrete abutment wing wall, return wall with 100mm.(One hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1 (v) : 20(H) towards drawing face complete as per drawing and technical specification clause 614,709,12.04.3.7 within all leads and lifts and as per direction of Engineer-in-charge.	20.00	260.1	Rupees Two Hundred Sixty and Ten Paisas Only	Each	5202.00
					Total	489469.00

*Draft schedule of quantity approved for amounting to Rs. 489469/- only*

*[Signature]*

Executive Engineer,  
 Karchham Division, HPPWD,  
 Karchham at Bhaba Nagar.

**Draft Schedule of Quantity**

258

Estimated Cost:- 210000.00  
 Earnest Money:- 4200.00  
 Time:- One Month

Name of work:- Preparation of DPR. for the construction of link road to Brua Kanda Km 0/00 to 6/00

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	A) Topography survey by Digital total station with two second accuracy , showing all features on survey plan like trees, culvert, bridge, electric pole, telephone poles, hand pumps, school, habitant villages. B) Draw cross section at 15 m (fifteen meter) interval, L-section & calculate the quantity of earth work in standart format of autocad showing all layer of pavement components as applicable. C) Prepration of survey plan showing all provision and preparation of detailed project report as per MORD guidelines.	6.000	35000.00	Rupees thirty thousand and paise nill only	Per Km	210000.00
					<b>Total</b>	<b>210000.00</b>

**Terms and Conditions**

- 1) 50% of payment to be released on submission of DPR to HPPWD Division office.
- 2) 30% of payment to be released on submission of 4 faired out sets prepared in accordance with the manuscript copy and submitted to NABARD cell of HPPWD.
- 3) 20% of payment shall be released on approval from NABARD.

*Draft Schedule of Quantity approved for amounting to Rs 210000/- only*



Executive Engineer,  
 Karchham Division, HPPWD.,  
 Karchham at Bhaba Naga

259

Draft Schedule of Quantity

Job-13

Estimated Cost:- 390059.00  
Earnest Money:- 7900.00  
Time:- Two Months

Name of work:- R/R Damages on link road to village Themgarang Km 0/00 to 1/00  
Sub Head:- C/o B/wall at RD 0/230 to 0/240 and 0/260 to 0/268 ) in Gram Panchyat Themgarang )

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation in foundation structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidentals.	34.95	300.00	Rupees Three Hundred Only	Per cubic metre	10485.00
2	Providing and laying cement concrete 1:6:12 (One cement : Six sand : Twelve graded/crushed/crushed stone aggregate 40mm (Forty millimetre) nominal size) mechanically mixed and curing complete excluding cost of form work in foundation and plinth including carriage of materials within all leads and lifts complete in all respect.	8.10	4332.70	Rupees Four Thousand Three Hundred Thirty Two and Seventy Paises Only	Per cubic metre	35095.00
3	Random rubble masonry/polygonal rubble masonry (uncoursed/brought to courses) with hard stone of approved quality/quarry in foundation and plinth including leveling up with cement concrete 1:6:12 (one cement : six sand : twelve graded/crushed stone aggregate 20mm (Twenty millimetre) nominal size) at plinth level in cement mortar 1:6 (one cement : six sand) including curing and carriage of materials within all leads and lifts complete in all respect as per direction of Engineer in Charge.	63.79	5310.50	Rupees Five Thousand Three Hundred Ten and Fifty Paises Only	Per cubic metre	338757.00
4	Providing weep holes in brick masonry/stone masonry/plain/ reinforced concrete abutment wing wall, return wall with 100mm.(One hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1 (v) : 20(H) towards drawing face complete as per drawing and technical specification clause 614,709,12.04.3.7 within all leads and lifts and as per direction of Engineer-in-charge.	22.00	260.10	Rupees Two Hundred Sixty and Ten Paises Only	Each	5722.00
					Total	390059.00

*[Signature]*

Executive Engineer,  
Karchham Division, HPPWD.,  
Karchham at Bhaba Nagars

*Draft Schedule of Quantity approved for amounting to Rs 390059/- only*

260

### Draft Schedule of Quantity

Job-14

Estimated Cost:- 341174.00

Earnest Money:- 6900.00

Time:- Two Months

Name of work:-R/R Damages On Palingi to Nichar road Km 0/00 to 16/00 .  
Sub Head:-C/O R/wall at RD 5/935 to 5/950)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation in foundation structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidentals.	26.33	300.00	Rupees Three Hundred Only	Per cubic metre	7899.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C. grade Nominal mix (1:4:8) (one Cement: four sand: eight coarse aggregate) and curing complete including carriage of materials in all leads lifts as per the entire satisfaction and direction of Engineer-in-Charge.	62.25	5270.25	Rupees Five Thousand Two Hundred Seventy and Twenty Five Paisas Only	Per cubic metre	328073.00
3	Providing weep holes in brick masonry/stone masonry/plain/ reinforced concrete abutment wing wall, return wall with 100mm.(One hundred milimetre) dia PVC pipe extending through the full with of the structures with slope of (v) : 20(H) towards drawing face complete as per drawing and technical specification clause 614,709,12.04.3.7 within all leads and lifts and as per direction of Engineer-in-charge.	20.00	260.10	Rupees Two Hundred Sixty and Ten Paisas Only	Each	5202.00
					Total	341174.00

*Draft Schedule of Quantity approved for amounting to Rs 341174/- only*

*[Signature]*  
Executive Engineer,  
Karchham Division, HPPWD.,  
Karchham at Bhaba Nagar

**Draft Schedule of Quantity**

**Job-15**

481314.00

7900.00

Two Months

Estimated Cost:-

Earnest Money:-

Time:-

Name of work:- R/R Damages on Jeepable road from Katgoan to Katgoan Kanda Km 0/00 to 5/500 .  
Sub Head:- C/o R/wall at RD 0/364 to 0/374).

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation in foundation structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidentals.	56.32	300.00	Rupees Three Hundred Only	Per cubic metre	16896.00
2	Providing and laying cement concrete 1:6:12 (One cement : Six sand : Twelve graded/crushed/stone aggregate 40mm (Forty millimetre) nominal size) mechanically mixed and curing complete excluding cost of form work in foundation and plinth including carriage of materials within all leads and lifts complete in all respect.	3.84	4298.55	Rupees Four Thousand Two Hundred Ninety Eight and Fifty Five Paisas Only	Per cubic metre	16506.00
3	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for structure like retaining walls, breast walls wing walls, toe walls, abutment and similar works etc. in all heights complete as per drawing and technical specification clauses 702, 704, 1202 & 1204 and curing complete including carriage of materials in all leads lifts as per the entire satisfaction and direction of Engineer-in-Charge.	81.09	5278.05	Rupees Five Thousand Two Hundred Seventy Eight and Five Paisas Only	Per cubic metre	427997.00
4	Providing weep holes in brick masonry/stone masonry/plain/ reinforced concrete abutment wing wall, return wall with 100mm.(One hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1 (v) : 20(H) towards drawing face complete as per drawing and technical specification clause 614,709,12.04.3.7 within all leads and lifts and as per direction of Engineer-in-charge.	30.00	260.10	Rupees Two Hundred Sixty and Ten Paisas Only	Each	7803.00
5	Back filling behind abutment, wing wall and return wall/breast wall and retaining walls complete as per drawing and technical specification within all leads and lifts and as per the direction of Engineer-in-charge.	12.48	970.50	Rupees Nine Hundred Seventy and Fifty Paisas Only	Per cubic metre	12112.00
					<b>Total</b>	<b>481314.00</b>

*Draft Schedule of Quantity approved for amounting to Rs 481314.00*



Executive Engineer,  
Karchham Division, HPPWD.,  
Karchham at Bhaba Nagar.

262

Job-16  
485571.00  
9800.00  
Two Months

Estimated Cost:-  
Earnest Money:-  
Time:-

Draft Schedule of Quantity

Name of work:- R/R Damages on link road Karchham to sapni Km 0/00 to 8/300.  
Sub Head:- C/O Random rubble masonry R/ wall at RD 7/775 to 7/786.50

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation in foundation structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidentals.	41.40	300.00	Rupees Three Hundred Only	Per cubic metre	12420.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C. grade Nominal mix (1:4:8) (one Cement: four sand: eight coarse aggregate) and curing complete including carriage of materials in all leads lifts as per the entire satisfaction and direction of Engineer-in-Charge.	5.95	5294.80	Rupees Five Thousand Two Hundred Ninety Four and Eighty Paises Only	Per cubic metre	31504.00
3	Providing and laying cement concrete 1:6:12 (one cement : six sand: twelve graded stone aggregate 40mm (forty millimeter) nominal size for plain /reinforced concrete in open foundations complete as per drawings and technical specification clauses 802, 803, 1202 and 1203 and curing complete including the cost of form work and carriage of materials in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	78.23	5295.60	Rupees Five Thousand Two Hundred Ninety Five and Sixty Paises Only	Per cubic metre	414275.00
5	Providing weep holes in brick masonry/stone masonry/plain/ reinforced concrete abutment wing wall, return wall with 100mm.(One hundred millimeter) dia PVC pipe extending through the full width of the structures with slope of 1 (v) : 20(H) towards drawing face complete as per drawing and technical specification clause 614,709,12.04.3.7 within all leads and lifts and as per direction of Engineer-in-charge.	28.00	260.10	Rupees Two Hundred Sixty and Ten Paises Only	Each	7283.00
6	Back filling behind abutment, wing wall and return wall/breast wall and retaining walls complete as per drawing and technical specification within all leads and lifts and as per the direction of Engineer-in-charge.	20.70	970.50	Rupees Nine Hundred Seventy and Fifty Paises Only	Per cubic metre	20089.00
					Total	485571.00

*Draft Schedule of Quantity approved for amounting to Rs 485571/- only*

Executive Engineer,  
Karchham Division, HPPWD.,  
Karchham at Bhaba Nagar

263

Draft Schedule of Quantity

Job-17

Estimated Cost:- 454714.00

Earnest Money:- 9100.00

Time:- Two Months

Name of work:-R/R Damages Kafnoo Yangpa road Km 0/00 to 5/00  
Sub Head:-C/o R/wall at RD 3/540 to 3/560.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation in foundation structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidentals.	57.41	300.00	Rupees Three Hundred Only	Per cubic metre	17223.00
2	Providing and laying cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40mm (forty millimeter) nominal size for plain /reinforced concrete in open foundations complete as per drawings and technical specification clauses 802, 803, 1202 and 1203 and curing complete including the cost of form work and carriage of materials in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge	5.52	4298.55	Rupees Four Thousand Two Hundred Ninety Eight and Fifty Five Paisas Only	Per cubic metre	23728.00
3	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for structure like retaining walls, breast walls wing walls, toe walls, abutment and similar works etc. in all heights complete as per drawing and technical specification clauses 702, 704, 1202 & 1204 and curing complete including carriage of materials in all leads lifts as per the entire satisfaction and direction of Engineer-in-Charge.	74.94	5278.05	Rupees Five Thousand Two Hundred Seventy Eight and Five Paisas Only	Per cubic metre	395537.00
4	Providing weep holes in brick masonry/stone masonry/plain/ reinforced concrete abutment wing wall, return wall with 100mm.(One hundred millimetre) dia PVC pipe extneiding through the full with of the structures with slope of I (v) : 20(H) towards drawing face complete as per drawing and technical specification clause 614,709,12.04.3.7 within all leads and lifts and as per direction of Engineer-in-charge.	30.00	260.10	Rupees Two Hundred Sixty and Ten Paisas Only	Each	7803.00
5	Back filling behind Retaining wall with granular material complete as per drawing and M.O.R.D. technical specification clause 1204.3.8. Including carriage of material within all lead and lifts and other incidentals.	10.74	970.50	Rupees Nine Hundred Seventy and Fifty Paisas Only	Per cubic metre	10423.00
					Total	454714.00

*Draft Schedule of Quantity approved for amounting to Rs 454714/- only*

*[Signature]*

Executive Engineer,  
Karchham Division, HPPWD.,  
Karchham at Bhaba Nagar

184

Draft Schedule of Quantity

Job-18

Estimated Cost:- 481836.00  
 Earnest Money:- 9700.00  
 Time:- Two Months

Name of work:-R/R Damages link road from NH-05 to Chaura to Forest Rest House Choura Km 0/00 to 3/500  
 Sub Head:- C/O R/wall in CC 1:4:8 and R/R mausonary 1:6 at Rd 0/070 to 0/075.70

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation in foundation structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidentals.	14.99	300.00	Rupees Three Hundred Only	Per cubic metre	4497.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C. grade Nominal mix (1:4:8) (one Cement: four sand: eight coarse aggregate) and curing complete including carriage of materials in all leads lifts as per the entire satisfaction and direction of Engineer-in-Charge.	38.48	5270.25	Rupees Five Thousand Two Hundred Seventy and Twenty Five <small>Paisas Only</small>	Per cubic metre	202799.00
3	Random rubble masonry/polygonal rubble masonry (uncoursed/brought to courses) with hard stone of approved quality/quarry in foundation and plinth including leveling up with cement concrete 1:6:12 (one cement : six sand : twelve graded/crushed stone aggregate 20mm (Twenty millimetre) nominal size) at plinth level in cement mortar 1:6 (one cement : six sand) including curing and carriage of materials within all leads and lifts complete in all respect as per direction of Engineer in Charge.	50.05	5259.15	Rupees Five Thousand Two Hundred Fifty Nine and Fifteen Paisas Only	Per cubic metre	263220.00
4	Providing weep holes in brick masonry/stone masonry/plain/ reinforced concrete abutment wing wall, return wall with 100mm.(One hundred milimetre) dia PVC pipe extneiding through the full with of the structures with slope of l (v) : 20(H) towards drawing face complete as per drawing and technical specification clause 614,709,12.04. 3.7 within all leads and lifts and as per direction of Engineer-in-charge.	18.00	260.10	Rupees Two Hundred Sixty and Ten Paisas Only	Each	4682.00
5	Back filling behind abutment, wing wall and return wall/breast wall and retaining walls complete as per drawing and technical specification within all leads and lifts and as per the direction of Engineer-in-charge.	6.84	970.50	Rupees Nine Hundred Seventy and Fifty Paisas Only	Per cubic metre	6638.00
					Total	481836.00

*Draft Schedule of Quantity approved for amounting to Rs 481836/- only*

*[Signature]*

Executive Engineer,  
 Karchham Division, HPPWD.,  
 Karchham at Bhaba Nagar