

OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG

PH: 01907-222229 Fax: 222229 , e-mail : ee-kar-hp@nic.in

No.PW-KSG-E-Tenders/2024-

15300

Dated:- 19-3-2026

To

The Executive Engineer (IT) Cell,
HPPWD, Nirman Bhawan, Nigam Vihar,
Shimla-2.

Subject :-

Regarding publication of Tender on departmental site.

With reference to the notification issued by the Secretary(PW) to the Government of Himachal Pradesh No. P BW(B)A(3)1/2024 dated 03.01.2024 and PBW-B-F0(2)/3/2024-284016 dated 18.07.2025, enclosed please find herewith the copy of Notice Inviting Tender for the loading on departmental web-site as

Certified that the works mentioned in the Tender Notice are urgent in nature and in coordination with the Disaster Management Act, 2005 Section 24 (i).

Encl:- As above.

Executive Engineer,
B&R Division,
HP PWD Karsog

**OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG**
PH: 01907-222229 Fax: 222229 , E-mail : ee-kar-hp@nic.in
Notice inviting tender

Sealed item rates tender on form 6 & 8 are hereby invited by the Executive Engineer, B&R Division HPPWD Karsog on behalf of Governor of Himachal Pradesh from the approved/eligible contractors enlisted in HP,PWD for the following works so as to reach in this office on or before **27.03.2026 upto 11.00 AM** and shall be opened on the same day at **12.00 AM** in presence of the contractor or their authorized representatives who may like to be present. The tender form can be obtained from this office against cash payment (Non refundable) **upto 4.00 PM on 25.03.2026** for which the application should reach in this office **upto 1.00 PM 25.03.2026**.

The earnest money in shape of National saving certificate/time deposit account/saving account in any Nationalized Bank in H.P duly pledged in favour of the Executive Engineer Karsog Division HPPWD Karsog will be received alongwith application for obtaining tenders form. The conditional tenders will summarily be rejected. The offer of the tenders shall be kept open for 51 days from the date of opening of tender. The Executive Engineer, HP PWD, Karsog reserves the right to reject any or all tenders without assigning any reason. The contractors should append their enlistment/renewed certificates/sale Tax registration Numbers with the application for issue of tender form. If any of the date mentioned above happens to be holiday the same shall be processed on next working day.

Sr. No.	Name of work	Estimated cost	Earnest money	Time allowed	Cost of Form
1	R/R damages on Alsindi Tattapani via Dhundan road Km. 0/00 to 5/00 (SH:- Providing Retaining wall at RD 4/645 to 4/658) under PDNA 2023	4,99,646/-	10,000/-	One Month	350/-
2	R/R damages on Alsindi Tattapani via Dhundan road Km. 0/00 to 5/00 (SH:- Providing Retaining wall at RD 4/658 to 4/680) under PDNA 2023	4,99,496/-	10,000/-	One Month	350/-
3	R/R damages on Alsindi Tattapani via Dhundan road Km. 0/00 to 5/00 (SH:- Providing Retaining wall at RD 4/680 to 4/693) under PDNA 2023	4,99,511/-	10,000/-	One Month	350/-
4	R/R damages on Chamanpur to Sihni road Km. 0/00 to 2/00 (SH:- C/o B/wall at RD 0/680 to 0/700) Balance work Job No. 1 (Step-II)	98,376/-	2,000/-	One Month	350/-
5	R/R damages on Chamanpur to Sihni road Km. 0/00 to 2/00 (SH:- C/o B/wall at RD 0/680 to 0/700) Balance work Job No. 2 (Step-III)	98,749/-	2,000/-	One Month	350/-
6	R/R damages on Shilh to Tharmi via Pokhi road Km. 0/00 to 12/746 (SH:- Removal of slips & maintenance of berms in Km. 0/00 to 7/00) Job No. 1	98,718/-	2,000/-	One Month	350/-
7	R/R damages on Chouridhar Kotlu road Km. 0/00 to 8/00 (SH:- Hiring of JCb Rock Breaker for breaking/removal of rock/boulders in Km. 5/500 to 6/700)	97,200/-	2,000/-	One Month	350/-
8	R/R damages on Chouridhar Kotlu road Km. 0/00 to 8/00 (SH:- Removal of slips in various RDs in Km. 6/800 to 7/900) under PDNA Job No. 4	4,88,850/-	9,800/-	One Month	350/-
9	R/R damages on Shakelar to Tuman Km. 0/00 to 2/700 (SH:- Removal of slips in Km. 0/00 to 2/700) Job No. 1	99,318/-	2,000/-	One Month	350/-

	R/R damages on Shilh to Tharmi via Pokhi road Km. 0/00 to 12/746 (SH:- Removal of slips and maintenance of berms in K.m. 0/00 to 7/00) Job No. 3	98,445/-	2,000/-	One Month	350/-
11	R/R damages on Bakhrot Sanarli Kelodhar Luhri road Km. 0/00 to 41/800 (SH:- Removal of slips at RD 40/390 to 40/540)	93,679/-	1,900/-	One Month	350/-
12	R/R damages on Bakhrot Sanarli Kelodhar Luhri road Km. 0/00 to 41/800 (SH:- Removal of slips at RD 37/00 to 37/020, 37/380 to 37/400, 37/830 to 37/845, 37/845 to 37/860, 38/830 to 38/850, 38/940 to 38/960, 39/510 to 39/525, 39/525 to 39/540, 40/030 to 40/053)	96,191/-	2,000/-	One Month	350/-
13	R/R damages on Dharmour to Ashni Mandir road Km. 0/00 to 4/300 (SH:- Removal of slips at various RDs)	99,445/-	2,000/-	One Month	350/-
14	R/R damages on Seri Shout road KM. 0/00 to 19/00 (SH:- Removal of slips, maintenance of berms & C/o unlined drain in KM. 0/00 to 19/00) under PDNA	4,97,523/-	10,000/-	One Month	350/-
15	R/R damages on Seri Shout road Km. 0/00 to 19/00 (SH:- Removal of slips, maintenance of berms & C/o unlined drain in Km. 0/00 to 19/00) under PDNA	4,97,523/-	10,000/-	One Month	350/-
15	R/R damages on Shimla Mandi via Tattapani road Km. 52/250 to 90/00 (SH:- C/o R/wall at RD 55/715 to 55/726) under PDNA 2023	4,11,953/-	8,300/-	One Month	350/-
16	R/R damages on Nanj Bhamala road Km. 0/00 to 8/00 (SH:- Hiring of JCB/Excavator cum loader for removal of slips, dressing of road surface and construction of road side katcha drain in various RDs)	98,900/-	2,000/-	One Month	350/-

TERMS & CONDITIONS:-

1. No tender form will be issued to those contractors who are not registered under HPGST Act.
2. The Contractor/firm should be registered as or dealer GST NO.
3. If any of the date mentioned above happened to be Gazetted holidays the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/ application or all tenders without assigning any reason.
5. No tender form will be issued to those contractors who are not registered under EPF Act.
6. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
7. The earnest money for the above work should be attached with the application.
8. The intending contractors/firms shall have to produce the copy of latest enlistment and renewal enlisted in HP,PWD.
9. As per Govt. Notification PW/CTR/32-20Genl Inst-CPWD/2020-37996-3809+5 dated 13-03-2023 the tenders above 5% will be summarily rejected and tenders amounts below 30% of amount put to tender will also be accepted.

Executive Engineer
B&R Division
HPPWD Karsog

No. PW-E-Tender-NIT/2025-26-

15293-99 Dated:- 19-3-2026

1. All the Assistant Engineers, working under this Division.
2. Copy to Drawing & Account Branch.
3. Notice board of this office.


Executive Engineer,
B&R Division,
HP PWD Karsog

Percentage Schedule Of Quantity

Estimated Cost 499646.00
Earnest Money 10000.00
Time One Month

Name of Work:- R/R Damages on Aisindi Tattapani via Dhundan road Km. 0/00 to 5/00 (SH:-Providing Retaining Wall at RD 4/645 to 4/658) under PDNA-2023

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stems and other deleterious materials and disposal upto lead any meter dressing of side and bottom and back filling in trenches with excavated suitable material ordinary soil upto any depth or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	50.12	Per Cubic Meter	390.20	19557.00	Rupees Nineteen Thousand Five Hundred Fifty Seven and Paise Zero Only
2	Providing and laying concrete for plain/reinforced concrete 1:4:8 (one cement : four sand : eight graded stone aggregate) in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	82.46	Per Cubic Meter	5500.00	453530.00	Rupees Four Lakhs Fifty Three Thousand Five Hundred Thirty and Paise Zero Only
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	44.00	Each	373.15	16419.00	Rupees Sixteen Thousand Four Hundred Nineteen and Paise Zero Only
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	8.45	Per Cubic Meter	1200.00	10140.00	Rupees Ten Thousand One Hundred Forty and Paise Zero Only
Total in Figures					499646.00	
Quoted Rate in Figures						
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
CHPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost
Earnest Money
Time
One Month

499496.00
10000.00
One Month

Sub-Head and items of works.

Sr.No.	Name of Work:- R/R Damages on Aisindi Tattapani via Dhundan road Km. 0/00 to 5/00 (SH:-Providing Retaining Wall at RD 4/658 to 4/680) under PDNA-2023	No. Or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes including GST In	Total Amount with all taxes including GST In
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stems and other deleterious materials and disposal upto lead any meter dressing of side and bottom and back filling in trenches with excavated suitable material ordinary soil upto any depth or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	32.89	Per Cubic Meter	390.20	12834.00	Rupees Twelve Thousand Eight Hundred Thirty Four and Paise Zero Only
2	Providing and laying concrete for palm/reinforced concrete 1:4:8 (one cement : four sand : eight graded stone aggregate) in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	83.60	Per Cubic Meter	5500.00	459800.00	Rupees Four Lakhs Fifty Nine Thousand Eight Hundred and Paise Zero Only
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	26.00	Each	373.15	9702.00	Rupees Nine Thousand Seven Hundred Two and Paise Zero Only
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	14.30	Per Cubic Meter	1200.00	17160.00	Rupees Seventeen Thousand One Hundred Sixty and Paise Zero
Total in Figures					499496.00	
Quoted Rate in Figures						
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
CHPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 499511.00
Earnest Money 10000.00
Time One Month

Name of Work:- R/R Damages on Alsindi Tattapani via Dhundan road Km. 0/00 to 5/00 (SH:-Providing Retaining Wall at RD 4/680 to 4/693) under PDNA-2023


S.No.	Sub-Head and items of works.	No. Or Qty.	Unit	Estimated Rate (Rs.)	Total Amount with all taxes including GST In	Total Amount with all taxes including GST In
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stems and other deleterious materials and disposal upto lead any meter dressing of side and bottom and back filling in trenches with excavated suitable material ordinary soil upto any depth or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	50.12	Per Cubic Meter	390.20	19557.00	Rupees Nineteen Thousand Five Hundred Fifty Seven and Paise Zero Only
2	Providing and laying concrete for pain/reinforced concrete 1:4:8 (one cement : four sand : eight graded stone aggregate) in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	82.46	Per Cubic Meter	5500.00	453530.00	Rupees Four Lakhs Fifty Three Thousand Five Hundred Thirty and Paise Zero Only
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipe extending through the full width of structures with slope of 1(v):20 (H) towards drawing face complete as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	52.00	Each	373.15	19404.00	Rupees Nineteen Thousand Four Hundred Four and Paise Zero Only
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204,3,8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	5.85	Per Cubic Meter	1200.00	7020.00	Rupees Seven Thousand Twenty and Paise Zero Only
Total in Figures					499511.00	
Quoted Rate in Figures						
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
CHPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 98376.00
Earnest Money 2000
Time One Month

Name of Work:- R/R Damages on Chamanpur to Sihani road Km. 0/00 to 2/00 (SH:- C/O B/Wall at RD 0/680 to 0/700) (Balance work) (Job No.1) (Step-II).						
Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit	Estimated Rate (Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Excavation in soil in hilly area by mechanical mean including cutting and trimming of side slope and disposing of excavated earth with lift upto 1.50 mtr (one point fifty metre) and a lead upto 20 mtr (twenty metre) as per technical specification clause 1603.1 as per direction of engineer in charge with in all lead and lift As per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	14.18	Per Cubic Meter	198.35	2813.00	Rupees Two Thousand Eight Hundred Thirteen and Paise Zero Only
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stumps and other deleterious materials and disposal upto lead any meter dressing of side and bottom and back filling in trenches with excavated suitable material ordinary soil upto any depth or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	3.89	Per Cubic Meter	390.20	1518.00	Rupees One Thousand Five Hundred Eighteen and Paise Zero Only
3	Providing and laying concrete for paint/reinforced concrete 1:4:8 (one cement : four sand : eight graded stone aggregate) in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	15.81	Per Cubic Meter	5500.00	86955.00	Rupees Eighty Six Thousand Nine Hundred Fifty Five and Paise Zero Only
4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipe extending through the full width of structures with slope of 1(v):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	19.00	Each	373.15	7090.00	Rupees Seven Thousand Ninety and Paise Zero Only
Total in Figures					98376.00	
Quoted Rate in Figures						
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
CHPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost
Earnest Money

98749.00
2000
One Month

Name of Work:- R/R Damages on Chamanpur to Sihani road Km. 0/00 to 2/00 (SI:- C/O B/Wall at RD 0/680 to 0/700) (Balance work) (Job No.2) (Step- III).
Sub-Head and items of works.

Sr.No.		No. Or Qty.	Unit	Estimated Rate (Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Excavation in soil in hilly area by mechanical mean including cutting and trimming of side slope and disposing of excavated earth with lift upto 1.50 mtr (one point fifty metre) and a lead upto 20 mtr (twenty metre) as per technical specification clause 1603.1 as per direction of engineer in charge within in all lead and lift As per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	14.18	Per Cubic Meter	198.35	2813.00	Rupees Two Thousand Eight Hundred Thirteen and Paise Zero Only
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stumps and other deleterious materials and disposal upto lead any meter dressing of side and bottom and back filling in trenches with excavated suitable material ordinary soil upto any depth or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	3.89	Per Cubic Meter	390.20	1518.00	Rupees One Thousand Five Hundred Eighteen and Paise Zero Only
3	Providing and laying concrete for pain/reinforced concrete 1:4:8 (one cement : four sand : eight graded stone aggregate) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	15.81	Per Cubic Meter	5500.00	86955.00	Rupees Eighty Six Thousand Nine Hundred Fifty Five and Paise Zero Only
4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	20.00	Each	373.15	7463.00	Rupees Seven Thousand Four Hundred Sixty Three and Paise Zero Only
Total in Figures					98749.00	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
JHPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 98718.00
Earnest Money 2000
Time One Month

Name of Work:- R/R Damages on Shilah to Therni via Pokhi road Km. 0/00 to 127/46(SH):- Removal of slips & Maintenance of berms in 0/00 to 7/00) Job No.1						
Sub-Head and Items of works.						
Sr.No.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words	
1	739.35	Per Cubic Meter	120.00	88722.00	Rupees Eighty Eight Thousand Seven Hundred Twenty Two and Paise Zero Only	
2	420.00	Per Running Meter	23.80	9996.00	Rupees Nine Thousand Nine Hundred Ninety Six and Paise Zero Only	
Total in Figures				98718.00		
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
GHPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 97200
Earnest Money 2000
Time One month
Name of Work:- R/R Damages on Chaurdhar Kottu road Km. 0/00 to 8/00 (SH):- hiring of JCB Rock Breaker for breaking/removal of rock/boulders in Km. 5/500 to 6/700)

Sl.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes Including GST In Rs. P	Total Amount with all taxes Including GST In Words
1	Hiring of JCB Breaker for breaking/removal of rock/boulders including the cost of fuel oil, lubricants, wages of operational staff, any repair during operation will be carried out at his risk and cost including carriage of machinery from one place to another at required location actual working will be accounted for payment and proper disposal of muck/debris will be ensured by the contractor and including all leads and lifts and work will be executed as per the direction of Engineer-in-Charge.	54.00	Per Hours	1800.00	97200.00	Rupees Ninety Seven Thousand Two Hundred and Paise Zero Only
Total in Figures					97200.00	
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
CHPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost
Earnest Money
Time

488850
9800
One Month

Name of Work:- RRD on Chouridhar Kotlu road Km. 0/00 to 8/00 (SH:- Removal of slips in various RD's in Km. 6/800 to 7/900) Under PDNA Job No. 4.								
Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words		
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals.	4073.75	Per Cubic Meter	120.00	488850.00	Rupess Four Lakhs Eighty Eight Thousand Eight Hundred Fifty and Paise Zero Only		
Total in Figures					488850.00			
Quoted Rate in Figures								
Quoted Rate in Words								


Executive Engineer,
Karsog Division,
CHPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 99318
Earnest Money 2000
Time One Month

Name of Work:- R/R Damages on Shakelar to Tuman Km. 0/00 to 2/700 (SH:- Removal of slips in KM 0/00 to 2/700) Job No. 1

Sub-Head and items of works.		No. Or Qty.	Unit.	Estimated Rate * (in Rs.)	Total Amount with all taxes including GST	Total Amount with all taxes including GST in Words
1	Removal of land slide slip clearance Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lift upto 1.5 m (one point five metre) and lead upto 1000m (one thousand metre) as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals	827.65	Per Cubic Meter	120.00	99318.00	Rupees Niney Nine Thousand Three Hundred Eighteen and Paise Zero Only
Total in Figures					99318.00	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
CHPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 98445.00
Earnest Money 2000.00
Time One Month

Name of Work:- R/R Damages on Shilah to Thermi via Pokhi road Km. 0/00 to 12/746(SH):- Removal of slips & Maintenance of berms in 0/00 to 7/00) Job No.3

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Removal of land slide slip clearance:- Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	662.70	Per Cubic Meter	120.00	79524.00	Rupees Seventy Nine Thousand Five Hundred Twenty Four and Paise Zero Only
2	Construction of unlined surface drain of average cross-section area 0.20 sqm (zero point twenty square metre) in soil specified line grade, level and dimension. Excavated material to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per directin of Engineer- in - charge with in all lead and lifts and other incidentals.	795.00	Per Running Meter	23.80	18921.00	Rupees Eighteen Thousand Nine Hundred Twenty One and Paise Zero Only
Total in Figures					98445.00	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
ChappWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost
Earnest Money
Time

93679
1900
One Month

Name of Work:- R/R Damages on Bakhrot Sanarti Kelodhar Luhri road Km. 0/00 to 41/800 (SH:- Removal of slips at RD 40/390 to 40/540)

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST in Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	780.66	Per Cubic Meter	120.00	93679.00	Rupees Ninety Three Thousand Six Hundred Seventy Nine and Paise Zero Only
Total in Figures					93679.00	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost
Earnest Money
Time

96191
2000
One Month

Name of Work:- R/R Damages on Bakhtrot Sanaril Kelodhar Luhn road Km. 0/00 to 41/800 (SH:- Removal of slips at RD 37/00 to 37/020, 37/380 to 37/400, 37/830 to 37/845, 37/845 to 37/860, 38/830 to 38/850, 38/940 to 38/960, 39/510 to 39/525, 39/525 to 39/540, 40/030 to 40/053).

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	801.59	Per Cubic Meter	120.00	96191.00	Rupees Ninety Six Thousand One Hundred Ninety One and Paise Zero Only
Total in Figures					96191.00	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
JHPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 99445
Earnest Money 2000
Time One Month

Name of Work:- R/R Damages on Dharmour To Ashni Mandir Road Km. 0/00 to 4/300 (SH:- Removal of slips at various RD's).

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (in	Total Amount	Total Amount with all taxes including GST in
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	828.71	Per Cubic Metre	120.00	99445.00	Rupees Ninety Nine Thousand Four Hundred Forty Five and Paise Zero Only
Total in Figures					99445.00	
Quoted Rate in Figures						
Quoted Rate in Words						



Executive Engineer,
Karsog Division,
CHPPWD, Karsog.

Percentage Schedule of Quantity

Name of Work:- R/R Damages on Seri Shout road Km. 0/00 to 19/00(SH:- Removal of slips, Maintenance of berms & C/O Unlined Drain in Km 0/00 to 19/00) Under PDNA.

Estimated Cost 497523.00
Earnest Money 10000.00
Time One month

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes Including GST In Rs. P	Total Amount with all taxes Including GST In Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	2327.28	Per Cubic Meter	120.00	279274.00	Rupees Two Lakhs Seventy Nine Thousand Two Hundred Seventy Four and Paise Zero Only
2	Construction of unlined surface drain of average cross-section area 0.20 sqm(zero point twenty square metre) in soil specified line grade, level and dimension . Excavated material to be used to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per direction of Engineer- in -charge with in all lead and lifts and other incidentals.	3000.00	Per Running Meter	23.80	71400.00	Rupees Seventy One Thousand Four Hundred and Paise Zero Only
3	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	6675.00	Per Square Meter	22.00	146850.00	Rupees One Lakh Forty Six Thousand Eight Hundred Fifty and Paise Zero Only
Total in Figures					497523.00	
Quoted Rate in Figures						
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
CHPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 411953.00
Earnest Money 8300.00
Time One Month

Name of Work:- R/R Damages on Shimla Mandi via Tattapani road Km. 52/250 to 90/00 (SH:- C/O R/Mall at RD 55/715 to 55/726) under PDNA-2023

Sr.No.	Sub-Head and items of works.	No. Or		Unit	Estimated Rate (Rs.)	Total Amount with all		Total Amount with all	
		Qty.				taxes including GST In		taxes including GST In	
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stems and other deleterious materials and disposal upto lead any meter dressing of side and bottom and back filling in trenches with excavated suitable material ordinary soil upto any depth or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	42.41		Per Cubic Meter	390.20	16548.00		Rupees Sixteen Thousand Five Hundred Forty Eight and Paise Zero Only	
2	Providing and laying concrete for plain/reinforced concrete 1:4:8 (one cement : four sand : eight graded stone aggregate) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	68.50		Per Cubic Meter	5500.00	376750.00		Rupees Three Lakhs Seventy Six Thousand Seven Hundred Fifty and Paise Zero Only	
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	27.00		Each	373.15	10075.00		Rupees Ten Thousand Seventy Five and Paise Zero Only	
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	7.15		Per Cubic Meter	1200.00	8580.00		Rupees Eight Thousand Five Hundred Eighty and Paise Zero Only	
Total in Figures						411953.00			
Quoted Rate in Figures									
Quoted Rate in Words									

Executive Engineer,
Karsog Division,
CHPPWD, Karsog.

Percentage Schedule of Quantity


Estimated Cost
Earnest money
Time

98900
2000

Name of Work:- R/R Damages on Nanj Bhamala road Km. 0/00 to 8/00 (SH:- Hiring of JCB/Excavator cum loader for removal of slips, dressing of road surface and construction of road side katcha drain in various RD's).

One Month

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Hiring of JCB/excavator for dressing of road surface construction of road side Katcha drain and removal of slips and boulder in all kinds of soil including rock portion and saturated soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts as per direction of Engineer-In-Charge. Any loss to the public/private property or any accident etc. should be absolute responsibility of the JCB/excavator owner which shall have to be fully compensated by him in all cases. The fuel and operational staff for excavator will be provided by the owner, the repair and spare watch and ward of excavator also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by Engineer-In-Charge.	86.00	Per Hour	1150.00	98900.00	Rupees Ninety Eight Thousand Nine Hundred and Paise Zero Only
Total in Figures						
Quoted Rate in Figures					98900.00	
Quoted Rate in Words						


 Executive Engineer,
 Karsog Division,
 AHPWD, Karsog.