REEMENT NO.:- 181

H.P.P.W.D.

KASAUALI

Himachal Pradesh
Public Works Department

No-PW/Ksli/CB/Tender /2025-26- 20285-92 Dated:- 20/03/2026

To

The Executive Engineer, (I.T. cell)
HPPWD, nirman Bhwan, Nigam Vihar,
Shimla-2.

Subject:- Publication of Tender Notice on departmental site.

Sir,

Enclosed please find herewith the tender notice of works as given in the Notice inviting Tenders for uploading on departmental web site as per Notification of the Pr. Secretary (PW) to the Govt. of H.P. No. PBW-(B)A((3)1/2024 dated 03.01.2024 & PWD-B-A)(3)/8/2025-300858 dated 09.10.2025 as the work mentioned in the tender notice are urgent in nature and public interest.

DA:- As Above.

Executive Engineer,
Kasauli Division, HPPWD,
Kasauli.

Copy to Superintending Engineer, 3rd Circle, HPPWD, Solan for information please.

Copy to All the AE working under this Division for information .
Copy to AB/DB of this office for information.

Executive Engineer,
Kasauli Division, HPPWD,
Kasauli.

Scanned with OKEN Scanner

Himachal Pradesh
Public Works Department
NOTICE INVITING TENDER
(Exigency)

Sealed percentage rate tenders on **Form No. 6 , 7&8** are hereby invited by the **Executive Engineer Kasauli Division, HPPWD, Kasauli** for the following works on behalf of the Governor of Himachal Pradesh for the following works from registered contractors of appropriate class enlised in HPPWD, whose registrations stood renewed as per revised instructions and also registered dealers under the himachal Pradesh General Sakes Tax act, 1968 The Improvement dates of tender are as under -

Sr No	Tender Schedule	Date	Time
1	Receipt of application for tender forms	25 03 2026	Upto 3 00 PM
2	Issue of Tender Forms	27 03 2026	Upto 5 00 PM
3	Receipt of Tenders	28 03 2026	Upto 11 00 AM
4	Opening of Tenders	28 03 2026	At 11.30 AM

The tender Shall be received upto 11 00AM on 28 03 2026 and will be opened on the same day at 11.30AM in the presence of office against cash payment as shown below (Non-refundable)during the working hours The earnest money in the shape of National Saving Certificate, FDR/Account/Sving account in any of the post office/Nationalized Bank in H P duly intending Contractors or their authorized representatives who may like to be present The tender from can be had from this pledged in favour of Executive Engineer, (B&R) Division, HPPWD, Kasauli must accompany with each tender, conditional tenders and the tenders received without earnest money will simultaneously be rejected The offier of the tender hall be kept open for 120days The Executive Engineer reserves the right to reject the tender without assigning any reason

Job No	Name of Work	Tentative Cost	Earnest Money	Time allowed	Cost of Form
1	R/R of rain damages on Grownghat to Raupul Km 0/00 to 3/500 (SH - Hiring of JCB/loader Cum-excavator for removal of slips and hiring of Tipper for shifting of earth etc in Km 0/00 to 3/500)	99,500/-	1990/-	One Month	350/-
2	R/R of Rain damages on Subathu Bye Pass Km. 0/00 to 0/785 (SH - Hiring of JCB/loader Cum-Exacavator for removal of slips, C/O unlined drain, berm dressing and hiring of Tipper for shifting of earth etc in Km 0/00 to 0/785)	99,500/-	1990/-	One Month	350/-
3	R/O rain damages to Barotiwala to Gunai road in Km 0/00 to 19/120 (SH - Hiring of exacavator Cum loader & Tractor with trolley for removal of slips and clearance of road side drain in Km 4/00 to 7/00)	98,300/-	2000/-	Two Month	350/-
4	R/O rain damages to Barotiwala to Gunai road in Km 0/00 to 19/120 (SH - Hiring of exacavator Cum loader & Tractor with trolley for removal of slips and clearance of road side drain in Km 7/00 to 9/00)	99,400/-	2000/-	Two Month	350/-
5	R/R damages on SAKB road in Km 26/00 to 70/00 (SH - C/O unlined drain in Km 26/00 to 32/00)Under PDNA	98,490/-	2000/-	One Months	350/-
6	R/R damages on SAKB road in Km 26/00 to 70/00 (SH - C/O unlined drain in Km 32/00 to 37/00)Under PDNA	98,892/-	2000/-	One Months	350/-
7	Improvement of Curve on CNYK road Km 75/375 to 86/450 (SH - Hiring of Pocklaine, exacavtor-Cum-loader along with Tipper for improvement of curve at Rd 80/290 to 80/360, 80/430 to 80/470 and 80/910 to 80/980)	96,000/-	2000/-	One Months	350/-
8	R/O rain damages on Subathu to Delgi road Km 0/00 to 13/380 (SH -= Repair to railing of slab culvert on both side at Rd 9/220 qnd 8/840)Under PDNA	98,463/-	1970/-	One Months	350/-
9	Preparation of FRA Case for the work C/O link road from Kamlog to Tindu Khadimu Km 0/00 to 1/280 Under HPPWD Sub-Division Parwanoo	75,000/-	1500/-	Three Months	350/-
10	A/R & M/O to Gandhigram to Tarol via Green Hills Engineering Collage road in Km 0/00 to 8/00 (SH - P/L WBM G-III in Km 0/00 to 1/00)	99,950/-	2000/-	Two Months	350/-
11	A/R & M/O to Gandhigram to Tarol via Green Hills Engineering Collage road in Km 0/00 to 8/00 (SH - P/L WBM G-III in Km 1/00 to 2/00)	93,286/-	1900/-	Two Months	350/-
12	A/R & M/O to Gandhigram to Tarol via Green Hills Engineering Collage road in Km 0/00 to 8/00.(SH - P/L WBM G-III in Km 2/00 to 3/00)	99,950/-	2000/-	Two Months	350/-
13	R/R damages on pattaGoelaChachlu road in Km 0/00 to 20/00 (SH - C/O B/Wall at Rds 2/058 90 to 2/061 90)	99,888/-	2000/-	Two Months	350/-

Scanned with OKEN Scanner

14	R/O rain damages to SAKB road in Km 26/00 to 70/00 (SH - Hiring of Excavator Cum loader for removal of slips and clearance of road side drain and hiring of Tipper for shifting of earth and debris in Km 58/00 to 61/00)	98,400/-	2000/-	Two Months	350/-
15	R/O rain damages to SAKB road in Km 26/00 to 70/00 (SH - Hiring of Excavator Cum loader for removal of slips and clearance of road side drain and hiring of Tipper for shifting of earth and debris in Km 55/00 to 58/00)	99,500/-	2000/-	Two Months	350/-
16	A/R & M/O Circuit house Building at Parwanoo (SH - Providing Wood work etc)	99,682/-	2000/-	Two Months	350/-
17	A/R & M/O Circuit house Building at Parwanoo (SH - Ceiling paint and wood work etc)	99,850/-	2000/-	Two Months	350/-
18	A/R & M/O Circuit house Building at Parwanoo (SH - exterior Paint etc)	99,968/-	2000/-	Two Months	350/-
19	A/R & M/O Circuit house Building at Parwanoo (SH - P/L wood & steel work and Sanitary work etc)	99,942/-	2000/-	Two Months	350/-
20	A/R & M/O Circuit house Building at Parwanoo (SH - Providing Steel Work etc)	99,983/-	2000/-	Two Months	350/-
21	A/R & M/O Circuit House & Rest House Building at Parwanoo (SH - Repair of Plaster in Patches and Supply of Double bed Cover & Plaster Lawn Chair etc)	99,948/-	2000/-	Two Months	350/-
22	R/R damages to link road to Gharshi Brahmana in Km 0/00 to 1/300 (SH - C/O PCC R/Wall at Rd 0/670 to 0/674 30)	99,219/-	2000/-	Two Months	350/-
23	R/R damages to link road to Ghari Brahmana in Km 0/00 to 1/300 (SH - C/O PCC R/Wall at Rd 0/684 to 0/688 30)	99,783/-	2000/-	Two Months	350/-
24	C/O Shardighat to Deora Guard Chewam Kamthanu Via Parwat Raj Mandir road Km 0/00 to 2/500 (SH - P/L 80mm thick interlocking tile Pavement at Various Rds. between Kms 0/00 to 2/500 (18 mtr length) DC Deposit	99973/-	2000/-	Two Months	350/-
25	R/R damages on BarotiwalaMandhalaGunar road in Km 16/900 to 26/135 (SH - Hiring of excavator Cum loader for removal of slips. Clearance of drain and dressing of berms in Km 19/00 to 26 135)	99,000/-	2000/-	One Months	350/-
26	R/R damages on Joharji Mallah road in Km 0/00 to 27/465 (SH - Hiring of Excavator Cum loader for removal of slips. Clearance of drain and dressing of berms in Km 0/00 to 2/00)	96,800/-	2000/-	One Months	350/-
27	R/R damages on JandauriPrathaNabon road in Km 0/00 to 8/00 (SH - Hiring of Excavator Cum loader for removal of slips. Clearance of drain and dressing of berms in Km 5/00 to 8/00)	97,900/-	2000/-	One Months	350/-
28	R/R damages on Joharji Kaba Kalan road in Km 0/00 to 5/270 (SH - Hiring of Excavator Cum loader for removal of slips. Clearance of drain and dressing of berms in Km 0/00 to 5/270)	99,000/-	2000/-	One Months	350/-
29	R/O rain damages on various road under Chandi Sub-Division Chandi Section (SH - Hiring of JCB/loader Cum-Excavator for Removal of slips. berm dressing & clearance of drain)	99,000/-	2000/-	One Months	350/-
30	C/O additional accommodation of Senior secondary School building at Haripu in Tehsil &DisttSolan (HP) under PMJVK (SH - Preparation of detailed site Plan and Contour Plan)	40,000/-	800/-	One Month	350/-

Terms &Conditions:-

1. Tender form shall be issued to those contractors who have owned machinery like JCB/Tipper The application without ownership charges of JCB/Tipper will not be accepted
2. The tender from will not be issued to those contractor whose performance has been found unsatisfactory
3. The contractor should have submitted the proof of registration No EPF No & GST No at the Time of tender application failure should not be issued tender forms
4. Application without earnest money will not be entertained
5. Executive engineer reserves the right to reject or cancel any or all the tenders without assigning any reason

Executive Engineer,
Kasauli Division
HPPWD Kasauli

Scanned with OKEN Scanner

Draft SCHEDULE OF QUANTITY

Job No.

	AMOUNT
Estimated Cost: -	99500.00
Earnest Money: -	1990.00
Time Limit: -	One month.

Name of Work: R/R of rain damages on Grownghatti to Raupul KM 0/00 to 3/500 (SH :- Hiring of JCB / loader cum-excavator for Removal of slips and hiring of Tipper for shifting of earth etc in KM 0/00 to 3/500.)

Sl. No.	Description of work	Qty.	Unit	RATE In		AMOUNT Rs.
				Figures	Words	
	Hiring of JCB / loader cum-excavator.					
	Terms and Conditions :-					
1	Hire charges should include expenses on account of establishment POL Major and minor repairs /over hauling and replacement of tyres and batteries if reqd. Hire charges should also include insurance of machinery/vehicles and establishment and the department shall not be responsible for any fatal/non fatal accidents, The bucket and loader capacity of JCB cum-excavator should not be less than 0.24 cum and one, The machinery should be of latest modal not older than 1999 . quantity of excavated / removed material should not be less than 28 cum / per hour.	**65.00**	Per hour.	1100.00	Rupees One Thousand One Hundred Only	**71500.00**
2	Hiring of tipper which shall include all expenses on account of establishment POL repair and other overhead charges etc. The tipper has to perform not less than as prescribed in the norms of HPPWD and as per direction of Engineer in charge , including carriage of all labour equipment and material to various locations through all modes of transportion in all leads and lifts and all incidental charges.	**7.00**	Per day	4000.00	Rupees two thousands two hundred and sixteen only	**28000.00**
	Total :-					**99500.00**

Total in Words **Rupees Ninety Nine Thousand Five Hundred Only**

Draft Schedule of Quantity Recommended for approval for Rs. **99500.00** only.

Assistant Engineer,
B&R Sub Division, HP.PWD. Subathu

Sr. No.630 for the year 25-26

Draft Schedule of Quantity approved for Rs. 99500.00 only.

Executive Engineer
B&R Division, HP.PWD. Kasauli.

Scanned with OKEN Scanner

Draft SCHEDULE OF QUANTITY

Job No.

	AMOUNT
Estimated Cost: -	99500.00
Earnest Money: -	1990.00
Time Limit: -	One month.

Name of Work: R/R of rain damages on Subathu Bye Pass KM 0/00 to 0/785 (SH :- Hiring of JCB / loader cum-excavator for Removal of slips ,C/O of unlined drain, Berm dressing and hiring of Tipper for shifting of earth etc in KM 0/00 to 0/785.)

Sl. No.	Description of work	Qty.	Unit	RATE In		AMOUNT Rs.
				Figures	Words	
	Hiring of JCB / loader cum-excavator.					
	Terms and Conditions :-					
1	Hire charges should include expenses on account of establishment POL Major and minor repairs /over hauling and replacement of tyres and batteries if reqd. Hire charges should also include insurance of machinery/vehicles and establishment and the department shall not be responsible for any fatal/non fatal accidents, The bucket and loader capacity of JCB cum-excavator should not be less than 0.24 cum and one, The machinery should be of latest modal not older than 1999 . quantity of excavated / removed material should not be less than 28 cum / per hour.	**65.00**	Per hour.	1100.00	Rupees One Thousand One Hundred Only	**71500.00**
2	Hiring of tipper which shall include all expenses on account of establishment POL repair and other overhead charges etc. The tipper has to perform not less than as prescribed in the norms of HPPWD and as per direction of Engineer in charge , including carriage of all labour equipment and material to various locations through all modes of transportion in all leads and lifts and all incidental charges.	**7.00**	Per day	4000.00	Rupees two thousands two hundred and sixteen only	**28000.00**
	Total :-					**99500.00**

Total in Words **Rupees Ninety Nine Thousand Five Hundred Only**

Draft Schedule of Quantity Recommended for approval for Rs. **99500.00** only.

Assistant Engineer,
B&R Sub Division, HP.PWD. Subathu

Sr. No.631 for the year 25-26

Draft Schedule of Quantity approved for Rs. 99500.00 only.

Executive Engineer
B&R Division, HP.PWD. Kasauli.

Scanned with OKEN Scanner

DRAFT SCHEDULE OF QUANTITY

Job No. :-

Estimated Cost: -	99400.00
Earnest Money: -	2000.00
Time limit : -	Two Month

Name of Work :- Restoration of rain damages to Barotiwala to Gunai road in Km. 0/00 to 19/120. (SH:- Hiring of excavator cum loader & tractor with trolley for removal of slips and clearance of road side drain in Km 7/00 to ~~10/00~~ 9/00 .

Sr.No	Description of work	Qty.	Unit	Rate in		Amount
				Figures	Words	
1	Hiring of Excavator cum loader for excavation, removal of slips, removal of slips, removal of debris & dressing of berms with a mimimum capacity of 28.00 (Twenty Eight cubic meter) per hour minimum six hour per day including pay of operators, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibilities of the contractor. The work shall be executed as per the MORT&H specification and the direction of Engineer-In-Charge.	70.00 Hr	Per Hour	1100.00	Rupees One Thousand One Hundred Only	77000.00
2	Hiring of Tractor-Trolley with haudraulic jack, minimum 8 (Eight) working hours per day, which shall include all expenses on A/C of establishment, POL, repair & other overhead charges including insurance of machinery/vehicles. All useful material i.e. stones etc. shall belongs to department. maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibilities of the contractor. The work shall be executed as per the MORT&H specification and the direction of Engineer-In-Charge.	8.00 day	Per day	2800.00	Rupees Two Thousand Eight Hundred Only	22400.00
	Total :-					99400.0
			Rupees Ninety Nine Thousand Four Hundred Only			
l in Words						
	% above/below to the DNIT amount i.e. Rs.					

T/S No. for the year 2025-26
DNITNo. 634 for the year 2025-26

Draft Schedule of Quantity approved for Rs. 99400.0 only

Executive Engineer
B&R Division, HP.PWD.
Kasauli

Scanned with OKEN Scanner

DRAFT SCHEDULE OF QUANTITY

Job No.						Estimated Cost:-	98490.00
						Earnest Money:-	2000.00
						Time:-	one Months
	Name of work:- R/R Damages on SAKB road in km 26/00 to 70/00 (SH:- Construction of Unlined deain in km 26/00 to 32/00) Under PDNA						
Sr. No	Description of work	Qty	Unit	Rate in		Amount	
				Figures	Words		
1	Construction of unlined surface drains of average cross-sectional area 0.20 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 50 m) as per Technical Specification Clause 307. By Mechanical means as per the direction of Engineer-in-Charge including carriage of all labour equipments and materials to various location through all modes of transporation in all leads lifts and all incidental charges.	3675.00	Rmt	26.80	Rupees Twenty Six - Paise Eighty Only	98490.00	
						98490.00	
	Total:- Rupees Ninety Eight Thousand Four Hundred & Ninety Only						

T/S No. 588 for the year 2025-2026
Sr. No. 641 for the year 2025-2026

Executive Engineer
B&R Division, HP.PWD. Kasauli

Scanned with OKEN Scanner

DRAFT SCHEDULE OF QUANTITY

Job No.	Estimated Cost: -	98892.00
	Earnest Money: -	2000.00
	Time: -	one Months

Name of work:- R/R Damages on SAKB road in km 26/00 to 70/00 (SH:- Construction of Unlined deain in km 32/00 to 37/00) Under PDNA

Sr. No	Description of work	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Construction of unlined surface drains of average cross-sectional area 0.20 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 50 m) as per Technical Specification Clause 307. By Mechanical means as per the direction of Engineer-in-Charge Including carriage of all labour equipments and materials to various location through all modes of transporation in all leads lifts and all incidental charges.	3690.00	Rmt	26.80	Rupees Twenty Six - Paise Eighty Only	98892.00
	Total:-					98892.00
	Rupees Ninety Eight Thousand Eight Hundred & Ninety Two Only					

T/S No. 589 for the year 2025-2026
Sr. No. 642 for the year 2025-2026

Executive Engineer
B&R Division, HP.PWD, Kasauli

Scanned with OKEN Scanner

Draft Schedule of Quantity

Name of work :- Improvement of Curve on Chailla Neripul Yashwantnagar Kumarhatti road km 75/375 to 86/450 (SH: Hiring of Pocklaine, Exacavtor-cum-loader along with tipper for improvement of curve at RD 80/290 to 80/360, 80/430 to 80/470 and 80/910 to 80/980)

Estimated cost :- Rs. 96,000/- only
Earnest Money :- Rs. 2000 /- only
Time limit :- One month

S.No	Sub heads and items of work	Qty.	Unit	Rate in		Amount
				Figures	Words	
1	Hiring of Poclain (76 HP) for excavation/cutting or removal of debris & dressing of ground as per desired level, clearing the entire debris generated during the excavation work including all leads and lift with a maximum bucket capacity of 1 Cum and a capcity of 45 cum per hour minimum six hour per day including pay of operator, POL charges, maintenance of any minor or major accidental and other damages to private and Govt. property is the whole responsibility of the contractor. The work shall be executed as per the direction of Engineer in Charge, including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	48.00	Per hour	1500.00	Rupees One thousand five hundred only	72000.00
3	Hiring of tipper which shall include all expenses on a/c establishment , POL, repair, and other overhead charges etc. The tipper has to perform not less than as prescribed in the norms of HPPWD and as per directions of Engineer in charge including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges	6.00	per day	4000.00	Rupees four thousand only	24000.00
					Total=	**96000.00**

TS NO.
DNIT NO. 645 for the year 2025-26

Assistant Engineer
Kasauli Sub- Division (B&R)
HPPWD Kasauli

Executive Engineer
Kasauli Division (B&R)
HPPWD Kasauli

Scanned with OKEN Scanner

Draft SCHEDULE OF QUANTITY

Job No.

	AMOUNT
Estimated Cost: -	98462.69
Earnest Money: -	1969.25
Time Limit: -	One month.

NAME OF WORK :- Restoration of rain damages on Subathu to Delgi road KM0/00 to 13/380 (SH:- Repair to railing of slab culvert on both side at RD 9/220 anf 8/840 under PDNA.)

Sl. No.	Description of work	Qty.	Unit	RATE In		AMOUNT Rs.
				Figures	Words	
1	Providing and fixing in position pipe railing consisting of IS Rolled steel joist posts designation IS MB 100 (100x75) at 2.5 m interval and three rows of 50 mm dia steel pipes (light) including fixing in position on bridge deck complete as per drawing and technical specifications Clause 1208.2	36.00	RMT Sqm	2208.64	Rupees Two Thousand Two Hundred & Eight - Paise Sixty Four Only	79511
	Providing and fixing of retro-reflectorised cautionary, mandatory and informatory sign Chevron board 300 x 900 mm as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3, fixed over aluminium sheeting, 1.5 mm thick supported on GI pipe 50 mm dia firmly fixed to the ground by means of properly designed foundation with M-15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 1701	5.00	Each	3790.33	Rupees Three Thousand Seven Hundred & Ninety - Paise Thirty Three Only	18952
	Total :-					98463

Total in Words Rupees Ninety Eight Thousand Four Hundred & Sixty Two - Paise Sixty Nine Only

Draft Schedule of Quantity Recommended for approval for Rs. **98463** only.

Assistant Engineer,
B&R Sub Division, HP.PWD. Subathu

Sr. No. for the year 25-26

Draft Schedule of Quantity approved for Rs. 98463 only.

Executive Engineer
B&R Division, HP.PWD. Kasauli.

Scanned with OKEN Scanner

DRAFT SCHEDULE OF QUANTITY

Estimated Cost	75,000
Earnest Money Rs	1500
Time: -	3 Months

Name of Work : Preparation of FRA Case for the work C/o of Link Road from Kamlog to Tindu Khadimu Km 0/00 to 1/280 under HPPWD Sub-Division Parwanoo.

S.No.	Description of item	No.	Rate. (Exclusive of GST)	Unit	Amount(Inclusive of GST)
1	Preparation of FRA Case with all relevant check lists, Digital Map, Toposheet and Layout Plan as per the latest guidelines of MoEF&CC of Proposed Road with G.P.S. Coordinates @ 100 meter interval with collecting the data from site including preparation of KML files/SHP file as per the direction of Engineer- in-charge alongwith preparation of 03 No. of proposal folders alongwith Monitoring with concerned forest department for early processing of the proposed forest case including compliances of the observations raised in the forest case till In-Principle/Final Approval.	1	75000	Per Case	75,000
				Total	75,000

SCHEDULE OF PAYMENT

Sr. No.	Scope	Rates (In Percentage)
1	After Site Inspection of the Proposed Road including collection of data with G P.S. Coordinates @ 100 meter interval, including collection of revenue records from the site, collection of data from Gram Panchayat i.e. VLC proceedings, Van Adhikar Samiti & necessary NOCs.	35%
2	After Joint Inspection & preparation of FRA case with all relevant check lists, KML File, Digital Map, Toposheet and Layout Plan, 03 No. of Proposal Folders and signed by authorized User Agency	35%
3	After submission of Proposal Folder to DFO Office alongwith attending the observations raised including enumeration of trees in coordination with concerned Forest Department Officials (i.e. Forest Guard, Range Officer etc.)	20%
4	Final Approval	10%

Total in Words — Rupees Seventy Five Thousand only

Draft Schedule of Quantity Recommended for approval for Rs. 75,000

Assistant Engineer,
B&R Sub Division, HP.PWD. Parwanoo

Sr. No. 674 for the year 2025-26

Draft Schedule of Quantity approved for Rs. 75000.00 only.

Executive Engineer
B&R Division, HP.PWD. Kasauli

Scanned with OKEN Scanner

DRAFT SCHEDULE OF QUANTITY

Job No.	Estimated Cost:-	99950.00
	Earnest Money:-	2000.00
	Time:-	Two Months

Name of Work :- A/R & M/O Gandhigram to Tarol via Green Hills Engineering Collage road in km 0/00 to 8/00 (SH:- P/L WBM G-III in km 0/00 to 1/00)

Sr. No	Description of work	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Scarifying the existing bituminous road surface to a depth of 150 mm and disposal of scarified material with a lift upto 3 m and lead upto 1000 m as per Technical Specification Clause 301.4 or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidental charges.	480.00	Per Square Meter	14.80	Rupees Fourteen - Paise Eighty Only	7104.00
2	Providing, laying, spreading and compacting **75mm thick (seventy Five milimeter) WBM Gr-III** with stone aggregates of specific sizes **(53mm to 22.4mm)** to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density as per MORD Technical Specification Clause 405 by mechanical means as per the direction of Engineer-in-charge including carriage of materials,labour and equipments to various location of site of work through all modes of transportation in all leads,lifts and all incidental charges .	36.00	Per Cubic Meter	2579.05	Rupees Two Thousand Five Hundred & Seventy Nine - Paise Five Only	92846.00
	Total:-					99950.00
	Rupees Ninety Nine Thousand Nine Hundred & Fifty Only					

T/S No.617 for the year 2025-2026
Sr. No. 656 for the year 2025-2026

Executive Engineer
B&R Division, HP.PWD. Kasauli

Scanned with OKEN Scanner

DRAFT SCHEDULE OF QUANTITY

Job No.	Estimated Cost: -	93286.00
	Earnest Money: -	1900.00
	Time: -	Two Months

Name of Work :- A/R & M/O Gandhigram to Tarol via Green Hills Engineering Collage road in km 0/00 to 8/00 (SH:- P/L WBM G-III in km 1/00 to 2/00)

Sr. No	Description of work	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Scarifying the existing bituminous road surface to a depth of 150 mm and disposal of scarified material with a lift upto 3 m and lead upto 1000 m as per Technical Specification Clause 301.4 or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidental charges.	448.00	Per Square Meter	14.80	Rupees Fourteen - Paise Eighty Only	6630.00
2	Providing, laying, spreading and compacting **75mm thick (seventy Five milimeter) WBM Gr-III** with stone aggregates of specific sizes **(53mm to 22.4mm)** to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density as per MORD Technical Specification Clause 405 by mechanical means as per the direction of Engineer-in-charge including carriage of materials,labour and equipments to various location of site of work through all modes of transportation in all leads,lifts and all incidental charges .	33.60	Per Cubic Meter	2579.05	Rupees Two Thousand Five Hundred & Seventy Nine - Paise Five Only	86656.00
	Total:-					93286.00
	Rupees Ninety Three Thousand Two Hundred & Eighty Six Only					

T/S No. 618 for the year 2025-2026
Sr. No. 657 for the year 2025-2026

Executive Engineer
B&R Division, HP.PWD. Kasauli

Scanned with OKEN Scanner

DRAFT SCHEDULE OF QUANTITY

Job No.	Estimated Cost: -	99950.00
	Earnest Money: -	2000.00
	Time: -	Two Months

Name of Work :- A/R & M/O Gandhigram to Tarol via Green Hills Engineering Collage road in km 0/00 to 8/00 (SH:- P/L WBM G-III in km 2/00 to 3/00)

Sr. No	Description of work	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Scarifying the existing bituminous road surface to a depth of 150 mm and disposal of scarified material with a lift upto 3 m and lead upto 1000 m as per Technical Specification Clause 301.4 or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidental charges.	480.00	Per Square Meter	14.80	Rupees Fourteen - Paise Eighty Only	7104.00
2	Providing, laying, spreading and compacting **75mm thick (seventy Five milimeter) WBM Gr-III** with stone aggregates of specific sizes **(53mm to 22.4mm)** to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density as per MORD Technical Specification Clause 405 by mechanical means as per the direction of Engineer-in-charge including carriage of materials,labour and equipments to various location of site of work through all modes of transportation in all leads,lifts and all incidental charges .	36.00	Per Cubic Meter	2579.05	Rupees Two Thousand Five Hundred & Seventy Nine - Paise Five Only	92846.00
	Total:-					99950.00
	Rupees Ninety Nine Thousand Nine Hundred & Fifty Only					

T/S No.619 for the year 2025-2026
Sr. No.658 for the year 2025-2026

Executive Engineer
B&R Division, HP.PWD. Kasauli

Scanned with OKEN Scanner

DRAFT SCHEDULE OF QUANTITY

Job No.	Estimated Cost: -	99888.00
	Earnest Money: -	2000.00
	Time: -	Two Months

Name of Work :- R/R Damages on Patta Goela Chachhi road in km 0/00 to 20/00 (SH:- C/O B/Wall at RDs 2/058.90 to 2/061.90)

Sr. No	Description of work	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibeted) as per drawing and technical specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) including trimming, dressing of sides and bottom, filling of unevenness blindages, backfilling in trenches with excavated suitable material and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	16.38	Per Cubic Meter	277.50	Rupees Two Hundred & Seventy Seven Paise Fifty Only	4545.00
2	Providing and laying Plain Cement Concrete nominal mix 1:6:12 (one cement isto six sand isto twelve graded stone aggregate 40mm (fourty milimeters) nominal size) Mechanically mixed, vibrated and curing complete in open foundations and plinths for all type of structure including the cost of form work as per drawing and MORD Technical Specifications Clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidental charges.	0.95	Per Cubic Meter	4039.45	Rupees Four Thousand &Thirty Nine - Paise Fourty Five Only	3837.00
3	Stone masonry with cement mortar in foundation complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203 Random rubble masonry.or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidental charges.	18.29	Per Cubic Meter	4886.45	Rupees Four Thousand Eight Hundred & Eighty Six - Paise Fourty Five Only	89373.00

Scanned with OKEN Scanner

4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia meter PVC pipe extending through the full width of the structure with slope of 1 (v) : 20 (h) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. Including carriage of all labour equipment and materials to various location through all modes of transporsation in all leads lifts and all incidental charges.	7.00	No	304.74	Rupees Three Hundred & Four Paise Seventy Four Only	2133.00
	Total:-					99888.00

Rupees Ninety Nine Thousand Eight Hundred & Eighty Eight Only

T/S No.607 for the year 2025-2026
Sr. No. 655 for the year 2025-2026

Executive Engineer
B&R Division, HP,PWD. Kasauli

Scanned with OKEN Scanner

DRAFT SCHEDULE OF QUANTITY

Job No. :-

Estimated Cost: -	98400.00
Earnest Money: -	2000.00
Time limit : -	Two Month

Name of Work :- Restoration of rain damages to SAKB road in Km. 26/00 to 70/00. (SH:- Hiring of excavator cum loader for removal of slips and clearance of road side drain and hiring of tipper for shifting of earth and debris in Km 58/00 to 61/00).

(PDNA)

Sr.No	Description of work	Qty.	Unit	Rate in		Amount
				Figures	Words	
1	Hiring of Excavator cum loader for excavation, removal of slips, removal of slips, removal of debris & dressing of berms with a mimimum capacity of 28.00 (Twenty Eight cubic meter) per hour minimum six hour per day including pay of operators, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibilities of the contractor. The work shall be executed as per the MORT&H specification and the direction of Engineer-In-Charge.	64.00 Hr	Per Hour	1100.00	Rupees One Thousand One Hundred Only	70400.00
2	Hiring of Tipper which shall include all expenses on A/C of establishment, POL, repair & other overhead charges etc. The tipper has to perform not less than as prescribed in the norms of HP. PWD. and as per direction of Engineer in Charge, including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	7.00 day	Per day	4000.00	Rupees Four Thousand Only	28000.00
	Total :-					98400.0
In Words			Rupees Ninety Eight Thousand Four Hundred Only			
	% above/below to the DNIT amount i.e. Rs.					

T/S No. for the year 2025-26
DNITNo.67/ for the year 2025-26

Draft Schedule of Quantity approved for Rs. 98400.0 only

Executive Engineer
B&R Division, HP.PWD.
Kasauli.

Scanned with OKEN Scanner

DRAFT SCHEDULE OF QUANTITY

Job No. :-

Estimated Cost:-	99500.00
Earnest Money:-	2000.00
Time limit :-	Two Month

Name of Work :- Restoration of rain damages to SAKB road in Km. 26/00 to 70/00. (SH:- Hiring of excavator cum loader for removal of slips and clearance of road side drain and hiring of tipper for shifting of earth and debris in Km 55/00 to 58/00). PDMA

Sr.No	Description of work	Qty.	Unit	Rate in		Amount
				Figures	Words	
1	Hiring of Excavator cum loader for excavation, removal of slips, removal of slips, removal of debris & dressing of berms with a mimimum capacity of 28.00 (Twenty Eight cubic meter) per hour minimum six hour per day including pay of operators, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibilities of the contractor. The work shall be executed as per the MORT&H specification and the direction of Engineer-In-Charge.	65.00 Hr	Per Hour	1100.00	Rupees One Thousand One Hundred Only	71500.00
2	Hiring of Tipper which shall include all expenses on A/C of establishment, POL, repair & other overhead charges etc. The tipper has to perform not less than as prescribed in the norms of HP. PWD. and as per direction of Engineer in Charge, including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	7.00 day	Per day	4000.00	Rupees Four Thousand Only	28000.00
	Total :-					99500.0
l in Words			Rupees Ninety Nine Thousand Five Hundred Only			
	% above/below to the DNIT amount i.e. Rs.					

T/S No. for the year 2025-26
DNITNo.672 for the year 2025-26

Draft Schedule of Quantity approved for Rs. 99500.0 only

Executive Engineer
B&R Division, HP.PWD.
Kasauli.

Scanned with OKEN Scanner

DRAFT SCHEDULE OF QUANTITY

Job No. :-	Estimated Cost: -	99682.00
	Earnest Money: -	2000.00
	Time limit : -	Two Month

Name of Work :- A/R & M/O Circuit house Building at Parwanoo . (SH:- Providing wood work etc).

Sr. No	Description of work	Qty.	Unit	Rate in		Amount
				Figures	Words	
1	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately). **Second class teak wood** as per the direction of Engineer-in-Charge including carriaghe of all labour equipments and materials to various location through all modes of transporation in all leads lifts and all incidental charges	0.15	Per Cubic Meter	140150.95	Rupees One Lakh Fourty Thousand One Hundred & Fifty Paise Ninety Five Only	21023.00
2	Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, excluding panelling which will be paid for separately, all complete as per direction of Engineer-incharge. **Second class teak wood 35 mm thick shutters** as per the direction of Engineer-in-Charge including carriaghe of all labour equipments and materials to various location through all modes of transporation in all leads lifts and all incidental charges	6.48	Per Square Meter	6297.50	Rupees Six Thousand Two Hundred & Ninety Seven Paise Fifty Only	40808.00
3	Providing and fixing wire gauge shutters using galvanized M.S. wire gauge of average width of aperture 1.4 mm in both directions with wire of dia 0.63 mm, for doors, windows and clerestory windows with hinges and necessary screws . **Second class teak wood 35 mm thick** as per the direction of Engineer-in-Charge including carriaghe of all labour equipments and materials to various location through all modes of transporation in all leads lifts and all incidental charges.	3.24	Per Square Meter	6097.60	Rupees Six Thousand &Ninety Seven - Paise Sixty Only	19756.00
4	Providing & fixing glass panes doors, windows, clerestory windows, all complete with **5.0 mm thick glass panes** as per the direction of Engineer-in-Charge including carriaghe of all labour equipments and materials to various location through all modes of transporation in all leads lifts and all incidental charges	5.40	Per Square Meter	908.00	Rupees Nine Hundred & Eight Only	4903.00
5	Providing and fixing aluminium sliding door bolts, antic color anodised (anodic coating not less than grade AC 10 as per IS 1868), transparent or dyed to required colour or shade with nuts and screws etc complete 300x16 mmcomplete as per the direction of Engineer-in-Charge including carriaghe of all labour equipments and materials to various location through all modes of transporation in all leads lifts and all incidental charges	1.00	Each	192.00	Rupees One Hundred & Ninety Two Only	192.00
6	Providing and fixing bright finished brass tower bolts (barrel type) with necessary screws etc as per the direction of Engineer-in-Charge including carriaghe of all labour equipments and materials to various location through all modes of transporation in all leads lifts and all incidental charges complete					

Scanned with OKEN Scanner

6.1	150X10 mm	12.00	Each	246.65	Rupees Two Hundred & Forty Six - Paise Sixty Five Only	2960.00
7	Providing and fixing bright finished brass handles with screws etc complete complete as per the direction of Engineer-in-Charge including carriage of all labour equipments and materials to various location through all modes of transportation in all leads lifts and all incidental charges.					
7.1	125 mm	18.00	Each	219.25	Rupees Two Hundred & Nineteen - Paise Twenty Five Only	3947.00
8	Providing and fixing aluminium die cast body tubular type universal hydraulic door closer (having ISI marking with ISI/IS: 3564, embossed on the body, door weight upto 35 kg and door width upto 750 mm) with necessary accessories and screws etc complete as per the direction of Engineer-in-Charge including carriage of all labour equipments and materials to various location through all modes of transportation in all leads lifts and all incidental charges	2.00	Each	1020.00	Rupees One Thousand &Twenty Only	2040.00
9	Providing and fixing 150 mm bright finished floor brass door stopper with rubber cushion, necessary brass screws etc to suit shutter thickness complete as per the direction of Engineer-in-Charge including carriage of all labour equipments and materials to various location through all modes of transportation in all leads lifts and all incidental charges	2.00	Each	267.60	Rupees Two Hundred & Sixty Seven - Paise Sixty Only	535.00
10	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.146 to 0.18 kg/ sqm over an under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture complete as per the direction of Engineer-in-Charge including carriage of all labour equipments and materials to various location through all modes of transportation in all leads lifts and all incidental charges.	28.00	Per Square Meter	125.65	Rupees One Hundred & Twenty Five Paise Sixty Five Only	3518.00
	Total :-					99682.00
in Words		Rupees Ninety Nine Thousand Six Hundred & Eighty Two Only				
	% above/below to the DNIT amount i.e. Rs.					

T/S No.71 for the year 2025-26
DNITNo.713 for the year 2025-26

Draft Schedule of Quantity approved for Rs. 99682.00 only

Executive Engineer
B&R Division HPPWD.
Kasauli.

Scanned with OKEN Scanner

DRAFT SCHEDULE OF QUANTITY

Job No. :-	Estimated Cost: -	99850.00
	Earnest Money: -	2000.00
	Time limit : -	Two Month

Name of Work :- A/R & M/O Rest house Building at Parwanoo . (SH:- Ceiling Paint and wood work etc).

Sr. No	Description of work	Qty.	Unit	Rate in		Amount
				Figures	Words	
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc complete as per the direction of Engineer-in-Charge including carriage of all labour equipments and materials to various location through all modes of transporation in all leads lifts and all incidental charges	115.21	Per Square Meter	15.80	Rupees Fifteen Paise Eighty Only	1820.00
2	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface with Murga Jaali where ever required of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer in Charge	38.20	Per Square Meter	562.65	[illegible] Sixty Five Only	21493.00
3	Providing and applying white cement based putty of average thickness 1 mm of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete complete as per the direction of Engineer-in-Charge including carriage of all labour equipments and materials to various location through all modes of transporation in all leads lifts and all incidental charges	115.21	Per Square Meter	121.65	[illegible] Hundred & Twenty One Paise Sixty Five Only	14015.00
4	Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade (Two or more coats on old work)complete as per the direction of Engineer-in-Charge including carriage of all labour equipments and materials to various location through all modes of transporation in all leads lifts and all incidental charges	115.21	Per Square Meter	133.50	[illegible]	15381.00
5	Finishing with rich textured exterior paint of required shade (New work) (two or more coat applied @ 1.25 ltr/10 sqm) over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)complete as per the direction of Engineer-in-Charge including carriage of all labour equipments and materials to various location through all modes of transporation in all leads lifts and all incidental charges	107.52	Per Square Meter	236.40	Rupees Two Hundred & Thirty Six [illegible] Only	25418.00

Scanned with OKEN Scanner

6	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately). **Second class teak wood** as per the direction of Engineer in-Charge including carriaghe of all labour equipments and materials to various location through all modes of transporation in all leads lifts and all incidental charges.	0.155	Per Cubic Meter	140150.95	Rupees One Lakh Fourty Thousand One Hundred & Fifty - Paise Ninety Five Only	21723.00
						99850.00
	Total :-					
in Words		Rupees Ninety Nine Thousand Eight Hundred & Fifty Only				
	% above/below to the DNIT amount i.e. Rs.					

T/S No. 712 for the year 2025-26
DNITNo. 714 for the year 2025-26

Draft Schedule of Quantity approved for Rs. 99850.00 only

Executive Engineer
B&R Division, KMVPWD,
Kasauli.

Scanned with OKEN Scanner

DRAFT SCHEDULE OF QUANTITY

Job No

Estimated Cost	99968.00
Earnest Money	2000.00
Time limit	Two Month

Name of Work :- A/R & M/O Rest house Building at Parwanoo . (SH:- Exterior Paint etc).

Sr No	Description of work	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Scraping, oil bound distemper, water proofing cement paint and the like by hand/power tool preparing and preparing the surface smooth including necessary repairs complete as per the direction of Engineer in Charge including carriage of all labour, equipments and materials to various location through all modes of conveyance, all leads lifts and all incidental charges	30.20	Per Square Meter	15.80	Rupees Fifteen Paise Eighty Only	477.00
2	Providing and applying white cement based putty of average thickness 1 mm of approved brand and manufacturer over the plastered wall surface to prepare the surface even and smooth complete complete as per the direction of Engineer in Charge including carriage of all Labour equipments and materials to various location through all modes of conveyance all leads lifts and all incidental charges	30.00	Per Square Meter	121.67	Rupees One Hundred & Twenty One Paise Sixty Five Only	3650.00
3	Painting walls with textured exterior paint of required shade New work (Two or more coats applied @ 1.28 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm) as per the direction of Engineer in Charge including carriage of all labour equipments and materials to various location through all modes of conveyance all leads lifts and all incidental charges	405.42	Per Square Meter	236.30	Rupees Two Hundred & Thirty Six Paise Thirty Only	95841.00
	Total :-					99968.00
in Words		Rupees Ninety Nine Thousand Nine Hundred & Sixty Eight Only				
	% above /below to the DNIT amount i.e. Rs					

T/S No.713 for the year 2025-26
DNIT No.715 for the year 2025-26

Draft Schedule of Quantity approved for Rs. 99968.00 only

Executive Engineer
B&R Division H.P.W.D.
Kasauli.

Scanned with OKEN Scanner

DRAFT SCHEDULE OF QUANTITY

Job No. :-

Estimated Cost: -	99942.00
Earnest Money: -	2000.00
Time limit : -	Two Month

Name of Work :- A/R & M/O Circuit house Building at Parwanoo . (SH:- Providing and Fixing wood & Steel work and Sanitary work etc).

Sr. No	Description of work	Qty.	Unit	Rate in		Amount
				Figures	Words	
1	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately). **Second class teak wood** as per the direction of Engineer-in-Charge including carriaghe of all labour equipments and materials to various location through all modes of transporation in all leads lifts and all incidental charges.	0.10	Per Cubic Meter	140150.95	Rupees One Lakh Fourty Thousand One Hundred & Fifty - Paise Ninety Five Only	**14015.00**
2	Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, excluding panelling which will be paid for separately, all complete as per direction of Engineer-incharge. **Second class teak wood 35 mm thick shutters** as per the direction of Engineer-in-Charge including carriaghe of all labour equipments and materials to various location through all modes of transporation in all leads lifts and all incidental charges.	1.80	Per Square Meter	6297.50	Rupees Six Thousand Two Hundred & Ninety Seven - Paise Fifty Only	**11336.00**
3	Providing and fixing wire gauge shutters using galvanized M.S. wire gauge of average width of aperture 1.4 mm in both directions with wire of dia 0.63 mm, for doors, windows and clerestory windows with hinges and necessary screws : **Second class teak wood 35 mm thick** as per the direction of Engineer-in-Charge including carriaghe of all labour equipments and materials to various location through all modes of transporation in all leads lifts and all incidental charges.	1.80	Per Square Meter	6097.60	Rupees Six Thousand &Ninety Seven - Paise Sixty Only	**10976.00**

Scanned with OKEN Scanner

4	Steel work in built up **tubular (round, square or rectangular hollow tubes etc.)** trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes.complete as per the direction of Engineer-in-Charge including carriaghe of all labour equipments and materials to various location through all modes of transporation in all leads lifts and all incidental charges.	245.00	Kg	136.50	Rupees One Hundred & Thirty Six - Paise Fifty Only	**33443.00**
5	Providing and fixing M.S. BP Sheet 1.66mm to 2mm thick in eaves board/ facia/ soffits/ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete as per the instruction of Engineer-in-charge (Base members of steel work shall be measured & paid separtely) complete as per the direction of Engineer-in-Charge including carriaghe of all labour equipments and materials to various location through all modes of transporation in all leads lifts and all incidental charges.	3.96	Per Square Meter	2314.85	Rupees Two Thousand Three Hundred & Fourteen - Paise Eighty Five Only	**9167.00**
6	Providing and fixing 600x120x5 mm glass shelf with edges round off, supported on anodised aluminium angle frame with C.P. brass brackets and guard rail complete fixed with 40 mm long screws, rawl plugs etc., complete.as per direction of Engineer-in-Charge including carriage of material through all modes of transportion with in all leads and lifts and other incidentials.	1.00	Each	1450.50	Rupees One Thousand Four Hundred & Fifty - Paise Fifty Only	**1451.00**
7	Providing and fixing 600x450 mm beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete.complete as per the direction of Engineer-in-Charge including carriaghe of all labour equipments and materials to various location through all modes of transporation in all leads lifts and all incidental charges.	1.00	Each	1623.25	Rupees One Thousand Six Hundred & Twenty Three - Paise Twenty Five Only	**1623.00**
8	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in Cement mortar 1:6 (1 cement : 6 coarse sand) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidental charges	0.90	Per Cubic Meter	6070.10	Rupees Six Thousand &Seventy Paise Ten Only	**5463.00**

Scanned with OKEN Scanner

9	Providing and fixing plastic seat (Solid / Hollow type) and cover for wash down water closet with C.P. Brass hinges and rubber butters . SOLID TYPE: white plastic seat and cover as per the direction of Engineer-in-Charge including carriaghe of all labour equipments and materials to various location through all modes of transporation in all leads lifts and all incidental charges.	2.00	Each	600.00	Rupees Six Hundred Only	1200.00
10	Supplying and fixing FRC cover with frame for manhole including carriage of material within all lead and lifts as per direction on Engineer of charge.The rate include octori, tovality, malkhana ,toll tax, Goods Service Tax, buildinga and other construction worker, welfare cess royalty or any other tax leavy or cess in respect of input or output by this contract shall be payable by the contractor and Goverment shall not entertain any calim whatsever in this respect of the same.					
10	600x600 mm with frame (heavy duty)	2.00	Each	5634.05	Rupees Five Thousand Six Hundred & Thirty Four - Paise Five Only	11268.00
	Total :-					99942.00
in Words					Rupees Ninety Nine Thousand Nine Hundred & Fourty Two Only	
	% above/below to the DNIT amount i.e. Rs.					

T/S No. for the year 2025-26
DNITNo.7/6 for the year 2025-26

Draft Schedule of Quantity approved for Rs. 99942.00 only

Executive Engineer
B&R Division, HP.PWD.
Kasauli.

Scanned with OKEN Scanner

DRAFT SCHEDULE OF QUANTITY

Job No. :-

Estimated Cost: -	99983.00
Earnest Money: -	2000.00
Time limit : -	Two Month

Name of Work :- A/R & M/O Circuit house Building at Parwanoo. (SH:- Providing Steel work etc).

Sr. No	Description of work	Qty.	Unit	Rate in		Amount
				Figures	Words	
1	Providing and fixing wooden moulded beading to door and window frames with iron screws, plugs and priming coat on unexposed surface etc. complete :2nd class teak wood 50x12 mm as per the direction of Engineer-in-Charge including carriaghe of all labour equipments and materials to various location through all modes of transporation in all leads lifts and all incidental charges	90.00	Rmt	278.65	Rupees Two Hundred & Seventy Eight - Paise Sixty Five Only	25079.00
2	Steel work in built up **tubular (round, square or rectangular hollow tubes etc.)** trusses etc , including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc complete. Hot finished welded type tubes complete as per the direction of Engineer-in-Charge including carriaghe of all labour equipments and materials to various location through all modes of transporation in all leads lifts and all incidental charges	422.40	Kg	136.50	Rupees One Hundred & Thirty Six - Paise Fifty Only	57658.00
3	Providing and fixing 0.60mm thick prepainted steel sheet **(TATA/DUROSHINE)** in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyster (RNP) organic coating of 20 microns over 5 microns primer coating to back coat of polyster of 5 microns over 5 microns primer coating i/c fixing with prepainted iron J or L hooks, bolts and nuts 6mm dia metre with prepainted limpet and rubber washers complete with all accessoriees as required as per the direction of Engineer-in-Charge including carriaghe of all labour equipments and materials to various location through all modes of transporation in all leads lifts and all incidental charges.	5.40	Per Square Meter	1496.20	Rupees One Thousand Four Hundred & Ninety Six - Paise Twenty Only	8079.00

Scanned with OKEN Scanner

4	Providing and fixing M S BP Sheet 1.66mm to 2mm thick in eaves board/ fascia/ soffits/ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete as per the instruction of Engineer-in-charge (Base members of steel work shall be measured & paid separtely) complete as per the direction of Engineer-in-Charge including carriaghe of all labour equipments and materials to various location through all modes of transporation in all leads litts and all incidental charges.	3.96	Per Square Meter	2314.85	Rupees Two Thousand Three Hundred & Fourteen - Paise Eighty Five Only	9167.00
	Total :-					99983.00
in Words		Rupees Ninety Nine Thousand Nine Hundred & Eighty Three Only				
	% above/below to the DNIT amount i.e. Rs.					

T/S No.710 for the year 2025-26
DNITNo.712 for the year 2025-26

Draft Schedule of Quantity approved for Rs. 99983.00 only

Executive Engineer
B&R Division U.S.PWD.
Kasauli.

Scanned with OKEN Scanner

DRAFT SCHEDULE OF QUANTITY

Job No. :-

Estimated Cost: -	99948.00
Earnest Money: -	2000.00
Time limit : -	Two Month

Name of Work :- A/R & M/O Circuit house & Rest house Building at Parwanoo . (SH:- Repair of plaster in patches and Supply of Double bed cover & Plastic lawn chair etc).

Sr. No	Description of work	Qty.	Unit	Rate in Figures	Rate in Words	Amount
1	Repair to plaster of thickness 12mm to 20 mm in patches of area 2 5 sqm and under, including cutting the patch in proper shape, raking out joints and preparing plastering the wall surface with white cement based polymer modified self curing mortar, including disposal of rubbish, all complete as per the direction of Engineer-In-Charge including carriage of all labour equipment and materials to various location of site through all modes of transportations in all leads lifts and all incidental charges.	45.00	Per Square Meter	579.50	Rupees Five Hundred & Seventy Nine - Paise Fifty Only	26078.00
2	Supplying of Double bed cover including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	20.00	Each	2830.00	Rupees Two Thousand Eight Hundred & Thirty Only	56600.00
3	Providing and Supplying Plastic lawn chairs including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	10.00	Each	1727.00	Rupees One Thousand Seven Hundred & Twenty Seven Only	17270.00
	Total :-					99948.00
	Rupees Ninety Nine Thousand Nine Hundred & Fourty Eight Only					
in Words						
	% above/below to the DNIT amount i.e. Rs.					

T/S No. for the year 2025-26

DNITNo.7/7 for the year 2025-26

Draft Schedule of Quantity approved for Rs. 99948.00 only

Executive Engineer
B&R Division, HPPWD.
Kasauli.

Scanned with OKEN Scanner

DRAFT SCHEDULE OF QUANTITY

Estimated Cost: -	99219.00
Earnest Money: -	2000.00
Time limit : -	Two Month

Job No. :-

Name of Work :- R/R damages to link road to Gharsi Brahmana in Km. 0/00 to 1/300. (SH:- C/o PCC R/Wall at Rd 0/670 to 0/674.30).

Sr.No	Description of work	Qty.	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibeted) as per drawing and technical specification true to lines and grades. Dimensions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) including trimming, dressing of sides and bottom, filling of unevenness blindages, backfilling in trenches with excavated suitable material and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	9.51 m3	Per Cubic Meter	277.50	Rupees Two Hundred & Seventy Seven Paise Fifty Only	2639.00
2	Providing and laying Plain Cement Concrete nominal mix 1:6:12 (one cement isto six sand isto twelve graded stone aggregate 40mm (fourty milimeters) nominal size) Mechanically mixed and vibrated for plain concrete in open foundations and plinths for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	0.96 m3	Per cubic meter	4039.45	Rupees Four Thousand &Thirty Nine Paise Fourty Five Only	3878.00

Scanned with OKEN Scanner

3	Providing and Laying concrete 1:4:8 (one cement isto four sand isto eight graded stoe aggregate 40 mm (fourty milimeters) nominal size for plain reinforced concrete mechanically mixed and viberated in open foundations including the cost of form work complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 (eight hundred two,eight hundred three,one thousand two hundred two & one thousand two hundred three) including carriage of all labour equipments and material to various location through all modes of transportation in all leads and lifts as per the direction of the Engineer-in-charge	18.95 m3	Per Cubic Meter	4537.20	Rupees Four Thousand Five Hundred & Thirty Seven · Paise Twenty Only	85980.00
4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia PVC pipe extending through the full width of the structure with slope of 1:20 (One verticle isto twenty horizontal) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7(six hundred fourteen, seven hundred nine, one thousand two hundred four point three point seven) as per MORD specification including carriage of all labour, equipment and material to various location through all modes of transportation in all leads lifts and all incidental charges.	8.00 No.	Each.	304.74	Rupees Three Hundred & Four · Paise Seventy Four Only	2438.00
5	Backfilling of Granular material behind abutment, wing wall and return wall, breast walls, retaining walls and parapets up to all heights, depths and levels complete as per drawings and MORD technical specification clause 1204.3.8 (one thousand two hundred four point three point eight) , including carriage of all labour equipment and materials to various location of site through all modes of transportations in all leads lifts and all incidental charges.	3.87 m3	Per Cubic Meter	1106.85	Rupees One Thousand One Hundred & Six · Paise Eighty Five Only	4284.00
						99219.0
		Rupees Ninety Nine Thousand Two Hundred & Nineteen Only				
	% above/below to the DNIT amount i.e. Rs.					

T/S No. 678 for the year 2025-26
DNITNo. 710 for the year 2025-26

Draft Schedule of Quantity approved for Rs. 99219.0 only

Executive Engineer
B&R Division, HP.PWD.
Kasauli.

Scanned with OKEN Scanner

DRAFT SCHEDULE OF QUANTITY

Job No. :-

Estimated Cost: -	99783.00
Earnest Money: -	2000.00
Time limit : -	Two Month

Name of Work :- R/R damages to link road to Gharsi Brahmana in Km. 0/00 to 1/300. (SH:- C/o PCC R/Wall at Rd 0/684 to 0/688.30).

Sr.No	Description of work	Qty.	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibeted) as per drawing and technical specification true to lines and grades. Dimensions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) including trimming, dressing of sides and bottom, filling of unevenness blindages, backfilling in trenches with excavated suitable material and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	9.83 m3	Per Cubic Meter	277.50	Rupees Two Hundred & Seventy Seven - Paise Fifty Only	2728.00
2	Providing and laying Plain Cement Concrete nominal mix 1:6:12 (one cement isto six sand isto twelve graded stone aggregate 40mm (fourty milimeters) nominal size) Mechanically mixed and vibrated for plain concrete in open foundations and plinths for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	0.96 m3	Per cubic meter	4039.45	Rupees Four Thousand &Thirty Nine - Paise Fourty Five Only	3878.00

Scanned with OKEN Scanner

3	Providing and Laying concrete 1:4:8 (one cement isto four sand isto eight graded stoe aggregate 40 mm (fourty milimeters) nominal size for plain reinforced concrete mechanically mixed and viberated in open foundations including the cost of form work complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 (eight hundred two,eight hundred three,one thousand two hundred two & one thousand two hundred three) including carriage of all labour equipments and material to various location through all modes of transportation in all leads and lifts as per the direction of the Engineer-in-charge	18.95 m3	Per Cubic Meter	4537.20	Rupees Four Thousand Five Hundred & Thirty Seven - Paise Twenty Only	85980.00
4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia PVC pipe extending through the full width of the structure with slope of 1:20 (One verticle isto twenty horizontal) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7(six hundred fourteen, seven hundred nine, one thousand two hundred four point three point seven) as per MORD specification including carriage of all labour, equipment and material to various location through all modes of transportation in all leads lifts and all incidental charges.	8.00 No.	Each.	304.74	Rupees Three Hundred & Four - Paise Seventy Four Only	2438.00
5	Backfilling of Granular material behind abutment, wing wall and return wall, breast walls, retaining walls and parapets up to all heights, depths and levels complete as per drawings and MORD technical specification clause 1204.3.8 (one thousand two hundred four point three point eight) , including carriage of all labour equipment and materials to various location of site through all modes of transportations in all leads lifts and all incidental charges.	4.30 m3	Per Cubic Meter	1106.85	Rupees One Thousand One Hundred & Six - Paise Eighty Five Only	4759.00
						99783.0
	Rupees Ninety Nine Thousand Seven Hundred & Eighty Three Only					
	% above/below to the DNIT amount i.e. Rs.					

T/S No. 677 for the year 2025-26
DNITNo. 709 for the year 2025-26

Draft Schedule of Quantity approved for Rs. 99783.0 only

Executive Engineer
B&R Division, HP.PWD.
Kasauli.

Scanned with OKEN Scanner

DRAFT SCHEDULE OF QUANTITY

Job No. :-

Estimated Cost: -	99973.00
Earnest Money: -	2000.00
Time limit : -	Two Month

Name of Work :- C/O Shardighat to Deora Guard Chewani Kamthanu via Parwat Raj Mandir road 0/00 to 2/500. (SH:-P/l 80mm thick interlocking tile pavement at various Rds between Kms. 0/00 to 2/500 (18 mtr length). DC Deposit.

Sr.No	Description of work	Qty.	Unit	Rate in		Amount
				Figures	Words	
1	Providing and laying cement concrete for plain concrete nominal mix 1:5:10 (One cement: five sand : ten graded crushed stone aggregate) 40 mm (forty millimetre) nominal size mechanical mixed, vibrated and curing complete including the cost of form work in open foundation for all type of structure complete as per drawing and technical specification clauses 802,803,1202 and 1203 as per direction of Engineer-in-Charge including carriage of material through all modes of transportion with in all leads and lifts and other incidentials.	5.49 m3	Per cubic meter	4205.40	Rupees Four Thousand Two Hundred & Five - Paise Fourty Only	23088.00
2	Providing and Laying of Interlocking Concrete Blcok Pavements having thickness 80 mm (eighty milimeters) as per drawing and Technical Specification Clause 1504, as per direction of Engineer in Charge including carriage of all labour equipment and materials to various location of site through all modes of transportations in all leads lifts and all incidental charges.	54.90 m2	Per square meter	1246.40	Rupees One Thousand Two Hundred & Fourty Six - Paise Fourty Only	68427.00
3	Providing and laying cement concrete work 1:2:4 (one cement two sand :four graded crust hard stone aggregate twenty milimetre nominal size) 20mm mechanically mixed and vibrated for compacting concrete required strength and curing complete including cost of form work and reinforcement for reinforced cement concrete work as per HPPWD specification 1990 (one thousand Nine hundred Ninety) volume-I inlcuding carriage of materials in all leads and lifts and as per the direction of Engineer-in-Charge. Foundations, and plinth in all depths and levels.	1.440 m3	Per cubic meter	5873.40	Rupees Five Thousand Eight Hundred & Seventy Three - Paise Fourty Only	8458.00
	Total :-					99973.0
l in Words	Rupees Ninety Nine Thousand Nine Hundred & Seventy Three Only					
	% above/below to the DNIT amount i.e. Rs.					

T/S No. 488 for the year 2025-26
DNITNo. 495 for the year 2025-26

Draft Schedule of Quantity approved for Rs. 99973.0 only

Executive Engineer
B&R Division, HP.PWD.
Kasauli

Scanned with OKEN Scanner

DRAFT SCHEDULE OF QUANTITY

Job No.

Estimated Cost: -	96800.00
Earnest Money: -	2000.00
Time: -	One Month

Name of Work :- R/R Damages on Joharji Mallah road in km 0/00 to 27/465 (SH:- Hiring of Excavator cum loader for removal of slips, Clearance of drain and dressing of berms in km 0/00 to 2/00)

Sr. No	Description of work	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Hiring of excavator cum loader for excavation, removal of slips, removal of debris & dressing of berms with a minimum capacity of 28.00 cum per hour minimum six hour per day including pay of operatore, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibilityu of the contractor. The work shall be executed as per the MORTH specification and the direction of Engineer-in-carge.	88.00	Per Hour	1100.00	Rupees One Thousand One Hundred Only	96800.00
	Total:-					96800.00
	Rupees Ninety Six Thousand Eight Hundred Only					

T/S No. for the year 2025-2026
Sr. No. 597 for the year 2025-2026

Executive Engineer
B&R Division, HP.PWD.
Kasauli

Scanned with OKEN Scanner

DRAFT SCHEDULE OF QUANTITY

Job No.

Estimated Cost: -	97900.00
Earnest Money: -	2000.00
Time: -	One Month

Name of Work :- R/R Damages on Jandauri Pratha Nabon road in km 0/00 to 8/00 (SH:- Hiring of Excavator cum loader for removal of slips, Clearance of drain and dressing of berms in km 5/00 to 8/00)

Sr. No	Description of work	Qty	Unit	Rate in Figures	Rate in Words	Amount
1	Hiring of excavator cum loader for excavation, removal of slips, removal of debris & dressing of berms with a minimum capacity of 28.00 cum per hour minimum six hour per day including pay of operatore, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibilityu of the contractor. The work shall be executed as per the MORTH specification and the direction of Engineer-in-carge.	89.00	Per Hour	1100.00	Rupees One Thousand One Hundred Only	97900.00
						97900.00
	Total:-				**Rupees Ninety Seven Thousand Nine Hundred Only**	

T/S No. for the year 2025-2026
Sr. No. 598 for the year 2025-2026

AE(P)

Executive Engineer
B&R Division, HP.PWD.
Kasauli

Scanned with OKEN Scanner

DRAFT SCHEDULE OF QUANTITY

Job No.

Estimated Cost: -	99000.00
Earnest Money: -	2000.00
Time: -	One Month

Name of Work :- R/R Damages on Joharji Kaba kalan road in km 0/00 to 5/270 (SH:- Hiring of Excavator cum loader for removal of slips, Clearance of drain and dressing of berms in km 0/00 to 5/270)

Sr. No	Description of work	Qty	Unit	Rate in Figures	Rate in Words	Amount
1	Hiring of excavator cum loader for excavation, removal of slips, removal of debris & dressing of berms with a minimum capacity of 28.00 cum per hour minimum six hour per day including pay of operatore, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibilityu of the contractor. The work shall be executed as per the MORTH specification and the direction of Engineer-in-carge.	90.00	Per Hour	1100.00	Rupees One Thousand One Hundred Only	99000.00
	Total:-					99000.00
					Rupees Ninety Nine Thousand Only	

T/S No. for the year 2025-2026
Sr. No. 599 for the year 2025-2026

Executive Engineer
B&R Division, HP.PWD.
Kasauli

Scanned with OKEN Scanner

Draft SCHEDULE OF QUANTITY

	AMOUNT
Estimated Cost: -	99000.00
Earnest Money: -	2000.00
Time Limit: -	One months.

Name of work:- Restoration of rain damages on various road under Chandi Sub Division Chandi Section (SH :- Hiring of JCB / loader cum-excavator for Removal of slips , berm dressing & clearance of drain. ~~Job- 8~~)

	Description of work	Qty.	Unit	RATE In Figures	RATE In Words	AMOUNT Rs.
	Hiring of JCB / loader cum-excavator.					
	Terms and Conditions :-					
1	Hire charges should include expenses on account of establishment POL Major and minor repairs /over hauling and replacement of tyres and batteries if reqd. Hire charges should also include insurance of machinery/vehicles and establishment and the department shall not be responsible for any fatal/non fatal accidents, The bucket and loader capacity of JCB cum-excavator should not be less than 0.24 cum and one, The machinery should be of latest modal not older than 1999 . quantity of excavated / removed material should not be less than 28 cum / per hour.	90.00	Per hour.	1100.00	Rupees One Thousand One Hundred Only	99000.00
	Total :-					99000.00

Total in Words Rupees Ninety Nine Thousand Only

Draft Schedule of Quantity Recommended for approval for Rs. **99000.00** only.

Assistant Engineer,
B&R Sub Division, HP.PWD. Chandi

TSNo. 577 for the year 25-26
Sr. No. 589 for the year 25-26

Draft Schedule of Quantity approved for Rs. 99000.00 only.

Executive Engineer
B&R Division, HP.PWD. Kasauli.

Scanned with OKEN Scanner

DRAFT SCHEDULE OF QUANTITY

Estimated Cost	40,000
Earnest Money	800
Time: -	1 Months

Name of Work : Construction of additional accomodation of Senior Secondary School building ~~and construction of Play ground including site development and Retaining walls~~ at Haripur in Tehsil and Distt. Solan (H.P.) under PMJVK (SH: Preparation of Detailed site plan and Contour Plan).

S.No.	Description of item	Unit	Amount (Inclusive of GST)
1	Preparation and submission of Detailed site plan and Contour Plan 3 No. Sets for Construction of additional accomodation of Senior Secondary School building and construction of Play ground including site development and Retaining walls at Haripur in Tehsil and Distt. Solan (H.P.) under PMJVK using DGPS in consultation with the Authority Engineer.	1	40,000
		Total	40,000

SCHEDULE OF PAYMENT

Sr. No.	Scope	Rates (In Percentage)
1	On successful submission of Detailed site plan and Contour Plan to Authority Engineer.	100%

Total in Words Forty Thousand Only DNIT No. 128 for the year 2025-26

Draft Schedule of Quantity Recommended for approval for Rs. 40,000

Assistant Engineer,
B&R Sub Division, HP.PWD. Subathu

40000.00 only.

Executive Engineer
B&R Division, HP.PWD. Kasauli

Scanned with OKEN Scanner