Himachal Pradesh
Public Works Department

No. PWP/Agr. Asstt./Tender/2025/ 2154-605 **Dated/** 20/3/26

To

The Executive Engineer (IT Cell),
Nirman Bhawan Nigam Vihar Shimla-2
Himachal Pardesh Shimla -2.

Subject:- **Publication of Tender Notice.**

Enclosed please find herewith Tender Notice of works as given in the Notice inviting Tenders alongwith schedule of quantities for uploading on departmental website as per Notification Secretary (PW) to the Govt. of HP letter NO. PBW (B) A (3) 1/2024 dated Shimla -03.01.2025

It is certified that the work mentioned in the Notice inviting tenders are urgent in nature and in Public interest.

DA/ Stated as above

Executive Engineer
Palampur Division
HPPWD Palampur

Copy along with copy of Tender Notice is forwarded to the following for information and necessary action:-

1. **The Superintending Engineer,5th Circle,HPPWD.,Palampur.**
2. **The Drawing /Accounts Branch in this office.**
3. **All Assistant Engineers working under this division.**
4. **Notice Board.**

Executive Engineer
Palampur Division
HPPWD Palampur

CERTIFICATE

Certified that the tenders invited vide this office NIT No. PWP/ Agr. Asstt/ NIT/ 2025/- 2159 4-605 Dated 20/3/2026 are urgent in nature and in public interest.

Executive Engineer
Palampur Division
HPPWD, Palampur

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
'NOTICE INVITING TENDERS'

Sealed item rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Palampur Division HP.PWD., Palampur on behalf of the Governor of H.P for the following work from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **27.03.2026** up to 11.00 AM. And the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Nonrefundable) on 25.03.2026 up to 4.00 P.M and the application for issue of tender form shall be received 24.03.2026 up to 12.00 noon.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

S. No.	Name of work.	Estimated Cost.	Earnest Money	Time Limit
1	C/o R/Wall on link road Ghuggar Lane No. 2 Ghogra Colony road (SW:- C/o R/Wall (M.C. Deposit)	Rs. 97,577.00	Rs. 2,000.00	Three Months
2	Link road from IPH Colony to Khilroo Bindraban Connencting Jamwal Colony Katoch Awadi CVD Khalet at Lekh Raj House KM RD 0/00 to 4/00 (SW:- P/L G.I Wire Crate work RHS Approaches)	Rs. 99,354..00	Rs. 2,000.00	Three Months
3	Link road from IPH Colony to Khilroo Bindraban Connencting Jamwal Colony Katoch Awadi CVD Khalet at Lekh Raj House KM RD 0/00 to 4/00 (SW:- P/L G.I Wire Crate work LHS Approaches)	Rs. 99,491.00	Rs. 2,000.00	Three Months
4	Link road Bindraban to Differ Patt road (SW:- U-Shape drain from Km 01/900 to 1/984.6) near Red Café **IPH Deposit)**	Rs. 99,783.00	Rs. 2,000.00	Three Months
5	Link road Bindraban to Differ Patt road (SW:- C/o R/Wall from KM 1/850 to 1/854 and U-Shape drain from Km RD 1/850 to 1/893(**IPH Deposit)**	Rs. 98,541.00	Rs. 2,000.00	Three Months
6	C/o Approach road towards Sharuti Hospital Palampur (SW:- C/o R/Wall (M.C Deposit)	Rs. 97,766.00	Rs. 2,000.00	Three Months
7	C/o Mahila Mandal Bhawan Saraswati Mahila Mandal GP Gopalpur Tehsil Palampur (Additional) (SW:- P/L Tile Work, Plaster Work & Fixing of door, Windows (MPLAD)	Rs.99,531.00	Rs. 2,000.00	Two Month
8	C/o R/Wall and House of Nitin Kumar House Band Vihar (Deposit) (SW:- C/o Edge Wall Km 0/000 to 0/025)	Rs. 99,910.00	Rs. 2,000.00	Three Month
9	Rain damage Bindraban Sidhpur Sarkari road Km 0/00 to 6/000 (SW:- C/o R/Wall from RD 5/850 to 5/856.40)	Rs. 97,555.00	Rs. 2,000.00	Three Month

`Terms & Conditions-

Following documents should accompany the application for tenders.

1. G.S.T. No.
2. Valid copy of Registration
3. Machinery will be of the contractor where required.
4. Certificate regarding possession of machinery.
5. Telegraphic/Fax tenders are not acceptable.
6. The tender documents can be received by registered/ Insured post which should be received in this office on or before the date of opening of tender by 11.00 A.M positively.
7. Contractor should have successfully executed two works of similar nature of 1/3 amount of estimated cost or similar single work of amount equal to estimated cost during the last preceding three years

Executive Engineer
Palampur Division
HPPWD Palampur

(1)

SCHEDULE OF QUANTITY

C/O R/Wall on link road Ghuggar Lane No.2 Ghogra colony road (SW:- C/O R/wall) (M.C-Deposit)

Estimated cost Rs.	97577.00
Earnest Money Rs.	2000.00
Time Limits	Three Month

No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	8.74			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specificationi section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equippments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the government.	20.83			Per cubic metre.	
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royality, GST, toll tax or other taxes imposed by the government.	11.00			Each	
4	Back filling with granular material behind abutment, wing wall and return wall to the full height compacted to a firm condition complete or as directed by the Engineer-in-Charge, including carriage of materials within all leads lifts and other incidental. The work should be done as per MORTH technical specification clauses 710.1.4 of IRC: 78 & 2200. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	3.81			Per cubic metre.	
	Total					

Executive Engineer,
Palampur Division
HP.PWD Palampur.

(2)

SCHEDULE OF QUANTITY

] - Link road from IPH Colony to Khilroo Bindraban Connecting Jamwal colony katoch awadi CVD Khalet at lekh raj house Km RD 0/00 to 4/00. (SW:- ire crate work RHS Approches)	Estimated cost Rs.	99354.00
	Earnest Money Rs.	2000.00
	Time Limits	Three Months

No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	5.30			Per cubic metre	
2	Providing and laying boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm (hundred millimeters into hundred millimeters) mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each in toe walls as per drawing and MORTH technical specifications Clause 2503 and as per direction of the Engineer- In –Charge including carriage of materials within all leads and lifts and other incidental. The rate includes octroi, royality Malkana Tol tax, GST or any other taxes imposed by the Government.	29.96			Per cubic metre	
3	Back filling with granular material behind abutment, wing wall and return wall to the full height compacted to a firm condition complete or as directed by the Engineer-in-Charge, including carriage of materials within all leads lifts and other incidental. The work should be done as per MORTH technical specification clauses 710.1.4 of IRC: 78 & 2200. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	11.75			Per cubic metre.	
	Total					

Executive Engineer,
Palampur Division
HP.PWD Palampur.

(3)

SCHEDULE OF QUANTITY

Name of work :- Link road from IPH Colony to Khilroo Bindraban Connecting Jamwal colony katoch awadi CVD Khalet at lekh raj house Km RD 0/00 to 4/00. (SW:- P/L G.I Wire crate work LHS Approches)

					Estimated cost Rs.	99491.00
					Earnest Money Rs.	2000.00
					Time Limits	Three Months
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is.including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	5.31			Per cubic metre	
2	Providing and laying boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm (hundred millimeters into hundred millimeters) mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each in toe walls as per drawing and MORTH technical specifications Clause 2503 and as per direction of the Engineer- In –Charge including carriage of materials within all leads and lifts and other incidental. The rate includes octroi, royality,Malkana,Tol tax, GST or any other taxes imposed by the Government.	30.00			Per cubic metre	
3	Back filling with granular material behind abutment, wing wall and return wall to the full height compacted to a firm condition complete or as directed by the Engineer-in-Charge, including carriage of materials within all leads lifts and other incidental. The work should be done as per MORTH technical specification clauses 710.1.4 of IRC: 78 & 2200. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	11.77			Per cubic metre.	
	Total					

Executive Engineer,
Palampur Division
HP.PWD Palampur.

4

SCHEDULE OF QUANTITY

Name of work : - Link road Bindraban to Differpatt road (SW :- U-Shape drain from Km RD 01/900 to 1/984.6) near Red café **I.P.H. DEPOSIT**

					Estimated cost Rs.	99783.00
					Earnest Money Rs.	2000.00
					Time Limits	Three Months
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	32.57			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (one cement :Three sand :Six graded crushed /broken stone aggregate including curing complete, pumping or bailing out water ,dewatering removal of slush as required at site which may arrisen at the time of laying under water complete for all heights/depths including the cost of form work, as per drawings and technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royality, Malkana, tolltax, or other taxes imposed by the government.	19.29			Per cubic metre.	
	Total					

Executive Engineer,
Palampur Division
HP.PWD Palampur.

SCHEDULE OF QUANTITY

Link road Bindraban to Differpatt road (SW :-C/o R/Wall from Km rd 1/850 TO 1/854 and U-Shape drain from Km RD 01/850 to 1/893) I.P.H. DEPOSIT

Estimated cost Rs.	98541.00
Earnest Money Rs.	2000.00
Time Limits	Three Month

Sl. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	20.64			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specificationi section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equippments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the government.	10.10			Per cubic metre.	
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royality, GST, toll tax or other taxes imposed by the government.	3.00			Each	
4	Back filling with granular material behind abutment, wing wall and return wall to the full height compacted to a firm condition complete or as directed by the Engineer-in-Charge, including carriage of materials within all leads lifts and other incidental. The work should be done as per MORTH technical specification clauses 710.1.4 of IRC: 78 & 2200. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	3.62			Per cubic metre.	
5	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (one cement :Three sand :Six graded crushed /broken stone aggregate including curing complete, pumping or bailing out water ,dewatering removal of slush as required at site which may arrisen at the time of laying under water complete for all heights/depths including the cost of form work, as per drawings and technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royality, Malkana, tolltax, or other taxes imposed by the government.	9.80			Per cubic metre.	
	Total					

Executive Engineer,
Palampur Division
HP.PWD Palampur.

SCHEDULE OF QUANTITY

Approach road towards Sharuti Hospital palampur (SW :- C/O R/wall) M.C DEPOSIT

				Estimated cost Rs.		97866.00
				Earnest Money Rs.		2000.00
				Time Limits		Three Month
	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	8.85			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specificationi section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equippments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the government.	21.11			Per cubic metre.	
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royality, GST, toll tax or other taxes imposed by the government.	7.00			Each	
4	Back filling with granular material behind abutment, wing wall and return wall to the full height compacted to a firm condition complete or as directed by the Engineer-in-Charge, including carriage of materials within all leads lifts and other incidental. The work should be done as per MORTH technical specification clauses 710.1.4 of IRC: 78 & 2200. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	3.86			Per cubic metre.	
	Total					

Executive Engineer,
Palampur Division
HP.PWD Palampur.

SCHEDULE OF QUANTITY

Name of work :- C/o Mahila Mandal Bhawan Saraswati Mahila Mandal G.P. Gopalpur Tehsil Palampur Distt. Kangra H.P. (Additional). SH:- P/L Tile work, Plaster work & fixing of door, windows). **MPLAD 1.00 Lacs**	Estimated cost Rs.	99531.00
	Earnest Money Rs.	2000.00
	Time Limits	Two Months

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	15 mm cement plaster on the rough side of single or half brick wall of mix : 1:6 (1 cement: 6 fine sand) and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government. .	148.34			Per square metre	
2	6 mm (six milimetre) cement plaster of mix: 1:3 (one cement : three fine sand) including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government. .	49.81			Per square metre	
3	Providing and laying 600x600 mm (six hundred into six hundred millimetre) Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm (twelve millimetre) thick bed of cement mortar 1:3 (one cement: three coarse sand), jointing with grey cement slurry @ 3.3 (three point three) Per Kilogram/ Per Square Metre including grouting the joint with white cement & matching pigments etc. complete including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government. .	36.87			Per square metre	
4	Providing and fixing ISI marked flush door shutters 35 mm thick including ISI marked Stainless Steel butt hinges with necessary screws conforming to IS : 2202 (Part I) decorative type, core of block board construction with frame of 1st class hard wood and well matched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	2.52			Per Square metre	
5	Providing and fixing 35 mm thick Kiln seasoned and chemically treated hollock wood glazed shutters for doors, windows and clerestory windows using 4 mm thick float glass panes, including ISI marked M.S. pressed butt hinges bright finished of required size with necessary screws. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government. .	1.80			Per Square Metre	
	Total					

Executive Engineer,
Palampur Division
HP.PWD Palampur.

Estimate No 623

(8)

Draft Schedule of Quantity

Name of work : - C/O R/Wall & House of Nitin Kumar House Band Vihar (Deposit)

Estimate Cost :- 99910/-
Earnest Money :- 2000/-
Time Limit : Three months.

Sub work :- C/O Edge Wall 0/000 to 0/025

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		Rs.
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantam of water including cleaning of slush which may arrise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi,royality,Mlakana,tolltax, Sale Tax or other taxes imposed by the government.	8.09 Cubic metre.			Per Cubic metre	
2	Providing Cement concrete 1:3:6 (One Cement : Three Sand : Six crushed stone aggregate) Nominal Mix P.C.C. grade M-10 (M-Ten) for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clasue 802,803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental.The rate including of octroi,royality,Mlakana,tolltax, Sale Tax or other taxes imposed by the government.	18.18 Cubic metre.			Per Cubic metre	
3	Providing weep holes in brick mansonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v) : 20 (H) towards drain face complete as per drawing and technical specification clause 614, 709, 1204.307 as per the direction of Engineer-in- Charge. The rate including of octroi, royality, malkana, tolltax, sale tax or other taxes imposed by the government.	14.00 Numbers			Each	
4	Back filling granular material behind R/Wall, abutment wing wall and return wall complete as per drawing and technical specifications clause 1204.3.8 as per the direction of Engineer-in- Charge. The rate including of octroi, royality, malkana, tolltax, sale tax or other taxes imposed by the government.	12.50 Cubic metre.			Per Cubic metre	

Executive Engineer
Palampur Division
HP.PWD Palampur

SCHEDULE OF QUANTITY

ork:- Rain Damage Bindraban Sidhpur Sarkari road Km 0/00 to 6/000. (SW:- C/O R/Wall from Km RD 5/850 TO 5/856.40)

Estimated cost Rs.	97555.00
Earnest Money Rs.	2000.00
Time Limits	Three Month

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	7.30			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specificationi section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equippments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the government.	21.06			Per cubic metre.	
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royality, GST, toll tax or other taxes imposed by the government.	9.00			Each	
4	Back filling with granular material behind abutment, wing wall and return wall to the full height compacted to a firm condition complete or as directed by the Engineer-in-Charge, including carriage of materials within all leads lifts and other incidental. The work should be done as per MORTH technical specification clauses 710.1.4 of IRC: 78 & 2200. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	3.71			Per cubic metre.	
	Total					

Executive Engineer,
Palampur Division
HP.PWD Palampur