

HIMACHAL PRADESH
PUBLIC WORK DEPARTMENT

No. PW/DT/TA/ NIT /2025-26- 12737 Dated:- 18-3-2026

To,

The Executive Engineer
IT Cell Nirman Bhawan Nigam Vihar
HP PWD Shimla

Subject:_ Regarding NIT for uploading on HP PWD website .

Enclosed please find herewith the Notice inviting tender Notice along with schedule of quantity for uploading on HP PWD website. This is for your kind information and necessary action at your end please.

Encls:- 06 Nos copy of Schedule of quantity.


Executive Engineer
Tanda Division HP PWD
Nagrotta Bagwan

CERTIFICATE

Certified that the tenders of works, called vide
this office letter No. PW-DT-NIT-2025-26- 12738 - 52 Dated:- 18-03-2026
are urgent nature.


Executive Engineer
Tanda Division HP PWD
at Nagrota Bagwan

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Sealed item rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, HP PWD Division Tanda at Nagrota Bagwan on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HP PWD (B & R) whose registration stood renewed as per revised rules so as to reach in his office on or before on 25.03.2026 up to 11:00 A.M. And the same shall be opened on the same day at 04:00 P.M. in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on 24.03.2026 up to 4:00 P.M and the application for issue of tender form shall be received on 23.03.2026 up to 12:00 noon. The applications for issue of tender forms accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates/Saving Account of the Post Office /Time Deposit account/FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP PWD Division Tanda at Nagrota Bagwan.

The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 120 days.

Sr. No.	Name of work	Estimated Cost	Earnest Money	Time limit
1.	Periodic Maintenance of Patch work under HP PWD Division Tanda at Nagrota Bagwan in Distt Kangra HP Under MMSRRY (.1. Thana Bargran Bussal road km 0/00 to 4/300(SH: Provding and laying patch work on various Rds in between km 0/00 to 0/650)	99170.00	2000.00	One Months
2	Periodic Maintenance of Patch work under HP PWD Division Tanda at Nagrota Bagwan in Distt Kangra HP Under MMSRRY (. 1. Link road to village Thana Lahar to Mualkar Jorian in G.P. Ratiyad km 0/00 to 1/00 (SH: Providing and laying patch work on various Rds in between km 0/00to 1/00)	99810.00	2000.00	One Months
3	Periodic Maintenance of Patch work under HP PWD Division Tanda at Nagrota Bagwan in Distt Kangra HP Under MMSRRY (. 1. Thana Bargran Bussal road km 0/00to 4/300 (SH: Providing and laying patch work on various Rds in between km 1/850 to 2/540).	99470.00	2000.00	One Months
4	Periodic Maintenance of Patch work under HP PWD Division Tanda at Nagrota Bagwan in Distt Kangra HP Under MMSRRY (. 1. Jalot Hardu mangrella road km 0/00 to 3/00 (SH: Providing and laying patch work on various Rds in between km 1/375 to 2/705)	99970.00	2000.00	One Months
5	Periodic Maintenance of Patch work under HP PWD Division Tanda at Nagrota Bagwan in Distt Kangra HP Under MMSRRY (. 1. Jalot Hardu mangrella road km 0/00 to 3/00 (SH: Providing and laying patch work on various Rds in between km 3/525 to 3/860).	99730.00	2000.00	One Months
6	Periodic Maintenance of Patch work under HP PWD Division Tanda at Nagrota Bagwan in Distt Kangra HP Under MMSRRY (. 1. Jalot Hardu mangrella road km 0/00 to 3/00 (SH: Providing and laying patch work on various Rds in between km 3/330 to 3/485).	99570.00	2000.00	One Months

Terms & Conditions:-)

- The contractor/firm should be registered as or dealer GST No.
- The intending contractor / firm have to produce the copy of latest enlistment and renewal enlisted in HPPWD.
- If any of the date mentioned above happened to be Gazetted Holidays the same shall be processed on next working day.
- The Executive Engineer reserves the right to accept/reject any tender/application or all tenders without assigning any reason.
- The Contractor will have to submit affidavit along with application for issue of tender form.
- Next tender will be issued only after completion of previous works in hand.

HIMSUCHANA AVAM & JAN SAMPARK

(On behalf of Governor of Himachal Pradesh)

No.PW/NBD/TA/Tender/NIT/2025-26- 12738-59

Dated/ 18-3-2026

Copy to the following for information and necessary action:-

- The Chief Engineer (KZ), HPPWD, Dharamshala.
- The Executive Engineer IT Cell Shimla HP PWD Shimla.
- The Superintending Engineer, 5th Circle, HPPWD, Palampur.
- The Deputy Commissioner, Kangra at Dharamshala.
- All the S.E.s/E.E.s under North Zone.
- The Sub-Divisional Officer(C) Nagrota Bagwan.
- All the Assistant Engineer under this Division.
- The Drawing /Accounts Branch in this office.
- Notice Board.

Executive Engineer
H.P.P.W.D. Tanda Division
at Nagrota Bagwan

Executive Engineer
H.P.P.W.D. Tanda Division
at Nagrota Bagwan

SCHEDULE OF QUANTITY

ESTIMATED COST :- Rs. 99170.00
 EARNEST MONEY :- Rs. 20000.00
 TIME LIMIT ONE MONTH

NAME OF WORK:- Periodic Maintenance of patch work under HPPWD Division Tanda at Nagrota Bagwan in Distt. Kangra (H.P.). (UNDER MMSRRY)

1.Thana Bargran Bussal road Km 0/000 to 4/300.

SUB-HEAD : Providing and laying patch work on various Rds in between Km 0/000 to 0/650

Sl. No.	Description of work	Quantity	RATES In		Unit	Amount
			Fig	Word		
1	Providing, laying, spreading and compacting stone aggregate of size 53mm to 22.4mm (Fifty three millimeter to Twenty two point four millimeter) Grading-III size [75mm (seventy five millimeters) compacted thickness] to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber applying and brooming, stone screening type-A of size 13.2mm (thirteen point two millimetres) nominal size at the rate of 0.22 cum (zero point twenty two) cubic metres per 10 sqm (per ten square metres) and binding material at the rate 0.06 cum (zero point zero six cubic metre) to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specifications clause No. 405 and as per drawing and HP.PWD technical specifications, as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	3.10 Cubic metres			Per cubic metre	
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.225 kgs (Zero decimal Two Two Five kilograms) per square metre on the prepared dry and hungry bituminous surface cleaned with Hydraulic broom as per MORD Technical Specification Clause 503 and as per direction of Engineer-In-charge including carriage of materials within all leads and lifts and other incidental. The rate inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government and rectifying defects noticed within two years as per clause 35 (III) of standard bidding document.	300.00 Square metre			Per square metre	
3	Providing, laying and rolling of close-graded Mix Seal Surfacing material of 20mm (Twenty millimetre) thickness composed of 11.2mm to 0.9mm (Eleven point two to Zero point Nine millimetre) (Type-A) @0.2704 Kg/10 Sqm (Zero point Two seven zero four kilogram per Ten square metre) aggregates using penetration grade bitumen @ i.e. binders content @ 22.00 Kg/10 Sqm (Twenty two point zero kilogram per Ten square metre) of 5.11% (Five point Eleven percent) by weight and minimum density of MSS (Mix Seal Surfacing) should be 2.10g (Two point ten grams) per CC to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN (Eight-Ten) static roller and finishing to required level and grades as per Technical Specification Clause 509 complete in all respect and as per direction of Engineer-In-charge including carriage of materials within all leads and lifts and other incidentals. The rate inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government and rectifying defects noticed within two years as per clause 35 (III) of standard bidding document.	300.00 Square metre			Per square metre	
Total :-						


 Executive Engineer,
 H.P.W.D. Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST :- Rs. 99810.00
 EARNEST MONEY :- Rs. 2000.00
 TIME LIMIT ONE MONTH

NAME OF WORK:- Periodic Maintenance of patch work under HPPWD Division Tanda at Nagrota Bagwan in Distt. Kangra (H.P.). (UNDER MMSRRY)
 I.Link road to village Thana Lahar to Mualkar Jorian in G.P. Ratiyad Km 0/000 to 1/000.

SUB-HEAD : Providing and laying patch work on various Rds in between Km 0/000 to 1/000.

Sl. No.	Description of work	Quantity	RATES In		Unit	Amount
			Fig	Word		
1	Providing, laying, spreading and compacting stone aggregate of size 53mm to 22.4mm (Fifty three millimeter to Twenty two point four millimeter) Grading-III size [75mm (seventy five millimeters) compacted thickness] to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber applying and brooming, stone screening type-A of size 13.2mm (thirteen point two millimetres) nominal size at the rate of 0.22 cum (zero point twenty two) cubic metres per 10 sqm (per ten square metres) and binding material at the rate 0.06 cum (zero point zero six cubic metre) to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specifications clause No. 405 and as per drawing and HP.PWD technical specifications, as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	3.42 Cubic metres			Per cubic metre	
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.225 kgs (Zero decimal Two Two Five kilograms) per square metre on the prepared dry and hungry bituminous surface cleaned with Hydraulic broom as per MORD Technical Specification Clause 503 and as per direction of Engineer-In-charge including carriage of materials within all leads and lifts and other incidental. The rate inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government and rectifying defects noticed within two years as per clause 35 (III) of standard bidding document.	300.00 Square metre			Per square metre	
3	Providing, laying and rolling of close-graded Mix Seal Surfacing material of 20mm (Twenty millimetre) thickness composed of 11.2mm to 0.9mm (Eleven point two to Zero point Nine millimetre) (Type-A) @0.2704 Kg/10 Sqm (Zero point Two seven zero four kilogram per Ten square metre) aggregates using penetration grade bitumen @ i.e. binders content @ 22.00 Kg/10 Sqm (Twenty two point zero kilogram per (Two point ten grams) per CC to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN (Eight-Ten) static roller and finishing to required level and grades as per Technical Specification Clause 509 complete in all respect and as per direction of Engineer-In-charge including carriage of materials within all leads and lifts and other incidentals. The rate inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government and rectifying defects noticed within two years as per clause 35 (III) of standard bidding document.	300.00 Square metre			Per square metre	
Total :-						


 Executive Engineer,
 H.P.W.D., Division,
 Tanda at Nagrota Bagwan.

2/900 to 2/952.50
 3/330 to 3/370

H.P.W.D. Engineer


SCHEDULE OF QUANTITY

ESTIMATED COST :- Rs. 99470.00
 EARNEST MONEY :- Rs. 2000.00
 TIME LIMIT ONE MONTH

NAME OF WORK:- Periodic Maintenance of patch work under HPPWD Division Tanda at Nagrota Bagwan in Distt. Kangra (H.P.). (UNDER MMSRRY)
 1.Thana Bargran Bussal road Km 0/000 to 4/300.

SUB-HEAD : Providing and laying patch work on various Rds in between Km 1/850 to 2/540.

Sl. No.	Description of work	Quantity	RATES In		Unit	Amount
			Fig	Word		
1	Providing, laying, spreading and compacting stone aggregate of size 53mm to 22.4mm (Fifty three millimeter to Twenty two point four millimeter) Grading-III size [75mm (seventy five millimeters) compacted thickness] to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber applying and brooming, stone screening type-A of size 13.2mm (thirteen point two millimetres) nominal size at the rate of 0.22 cum (zero point twenty two) cubic metres per 10 sqm (per ten square metres) and binding material at the rate 0.06 cum (zero point zero six cubic metre) to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specifications clause No. 405 and as per drawing and HP.PWD technical specifications, as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	3.25 Cubic metres			Per cubic metre	
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.225 kgs (Zero decimal Two Two Five kilograms) per square metre on the prepared dry and hungry bituminous surface cleaned with Hydraulic broom as per MORD Technical Specification Clause 503 and as per direction of Engineer-In-charge including carriage of materials within all leads and lifts and other incidental. The rate inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government and rectifying defects noticed within two years as per clause 35 (III) of standard bidding document.	300.00 Square metre			Per square metre	
3	Providing, laying and rolling of close-graded Mix Seal Surfacing material of 20mm (Twenty millimetre) thickness composed of 11.2mm to 0.9mm (Eleven point two to Zero point Nine millimetre) (Type-A) @0.2704 Kg/10 Sqm (Zero point Two seven zero four kilogram per Ten square metre) aggregates using penetration grade bitumen @ i.e. binders content @ 22.00 Kg/10 Sqm (Twenty two point zero kilogram per Ten square metre) of 5.11% (Five point Eleven percent) by weight and minimum density of MSS (Mix Seal Surfacing) should be 2.10g (Two point ten grams) per CC to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN (Eight-Ten) static roller and finishing to required level and grades as per Technical Specification Clause 509 complete in all respect and as per direction of Engineer-In-charge including carriage of materials within all leads and lifts and other incidentals. The rate inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government and rectifying defects noticed within two years as per clause 35 (III) of standard bidding document.	300.00 Square metre			Per square metre	
Total :-						


 Executive Engineer,
 H.P.W.D., Division,
 Tanda at Nagrota Bagwan.

.00
00
H I


SCHEDULE OF QUANTITY

ESTIMATED COST :- Rs. 99970.00
 EARNEST MONEY :- Rs. 2000.00
 TIME LIMIT ONE MONTH

NAME OF WORK:- Periodic Maintenance of patch work under HPPWD Division Tanda at Nagrota Bagwan in Distt. Kangra (H.P.). (UNDER MMSRRY)
 1.Jalot Hardu Mangrella road Km 0/000 to 3/000.

SUB-HEAD : Providing and laying patch work on various Rds in between Km 1/375 to 1/705.

Sl. No.	Description of work	RATES In		Unit	Amount
		Fig	Word		
1	Providing, laying, spreading and compacting stone aggregate of size 53mm to 22.4mm (Fifty three millimeter to Twenty two point four millimeter) Grading-III size [75mm (seventy five millimeters) compacted thickness] to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber applying and brooming, stone screening type-A of size 13.2mm (thirteen point two millimetres) nominal size at the rate of 0.22 cum (zero point twenty two) cubic metres per 10 sqm (per ten square metres) and binding material at the rate 0.06 cum (zero point zero six cubic metre) to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specifications clause No. 405 and as per drawing and HP.PWD technical specifications, as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	3.50	Cubic metres	Per cubic metre	
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.225 kgs (Zero decimal Two Two Five kilograms) per square metre on the prepared dry and hungry bituminous surface cleaned with Hydraulic broom as per MORD Technical Specification Clause 503 and as per direction of Engineer-In-charge including carriage of materials within all leads and lifts and other incidental. The rate inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government and rectifying defects noticed within two years as per clause 35 (III) of standard bidding document.	300.00	Square metre	Per square metre	
3	Providing, laying and rolling of close-graded Mix Seal Surfacing material of 20mm (Twenty millimetre) thickness composed of 11.2mm to 0.9mm (Eleven point two to Zero point Nine millimetre) (Type-A) @0.2704 Kg/10 Sqm (Zero point Two seven zero four kilogram per Ten square metre) aggregates using penetration grade bitumen @ i.e. binders content @ 22.00 Kg/10 Sqm (Twenty two point zero kilogram per Ten square metre) of 5.11% (Five point Eleven percent) by weight and minimum density of MSS (Mix Seal Surfacing) should be 2.10g (Two point ten grams) per CC to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN (Eight-Ten) static roller and finishing to required level and grades as per Technical Specification Clause 509 complete in all respect and as per direction of Engineer-In-charge including carriage of materials within all leads and lifts and other incidentals. The rate inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government and rectifying defects noticed within two years as per clause 35 (III) of standard bidding document.	300.00	Square metre	Per square metre	
Total :-					


 Executive Engineer,
 H.P.P.W.D., Division,
 Tanda at Nagrota Bagwan.

DRAFT SCHEDULE OF QUANTITY

ESTIMATED COST :- Rs. 99730.00
 EARNEST MONEY :- Rs. 2000.00
 TIME LIMIT ONE MONTH

ME OF Periodic Maintenance of patch work under HPPWD Division Tanda at Nagrota Bagwan in Distt. Kangra (H.P.). (UNDER MMSRRY)

DRK:- 1. Jalot Hardu Mangrella road Km 0/000 to 3/000.

B-HEAD : Providing and laying patch work on various Rds in between Km 3/525 to 3/860.

Description of work	Quantity	RATES In		Unit	Amount
		Fig	Word		
Providing, laying, spreading and compacting stone aggregate of size 53mm to 22.4mm (Fifty three millimeter to Twenty two point four millimeter) Grading-III size [75mm (seventy five millimeters) compacted thickness] to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber applying and brooming, stone screening type-A of size 13.2mm (thirteen point two millimetres) nominal size at the rate of 0.22 cum (zero point twenty two) cubic metres per 10 sqm (per ten square metres) and binding material at the rate 0.06 cum (zero point six cubic metre) to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specifications clause No. 405 and as per drawing and HP.PWD technical specifications, as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	3.38 Cubic metres	2000.00	Rupees Two thousand and paise Nil only.	Per cubic metre	6760.00
Providing and applying tack coat with Bitumen emulsion (RS-I) using emulsion distributor at the rate of 0.225 kgs (Zero decimal Two Two Five kilograms) per square metre on the prepared dry and hungry bituminous surface cleaned with Hydraulic broom as per MORD Technical Specification Clause 503 and as per direction of Engineer-In-charge including carriage of materials within all leads and lifts and other incidental. The rate inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government and rectifying defects noticed within two years as per clause 35 (III) of standard bidding document.	300.00 Square metre	19.00	Rupees Nineteen and paise Nil only.	Per square metre	5700.00
Providing, laying and rolling of close-graded Mix Seal Surfacing material of 20mm (Twenty millimetre) thickness composed of 11.2mm to 0.9mm (Eleven point two to Zero point Nine millimetre) (Type-A) @0.2704 Kg/10 Sqm (Zero point Two seven zero four kilogram per Ten square metre) aggregates using penetration grade bitumen @ i.e. binders content @ 22.00 Kg/10 Sqm (Twenty two point zero kilogram per Ten square metre) of 5.11% (Five point Eleven percent) by weight and minimum density of MSS (Mix Seal Surfacing) should be 2.10g (Two point ten grams) per CC to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN (Eight-Ten) static roller and finishing to required level and grades as per Technical Specification Clause 509 complete in all respect and as per direction of Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government and rectifying defects noticed within two years as per clause 35 (III) of standard bidding document.	300.00 Square metre	290.90	Rupees Two hundred ninety and paise ninety only.	Per square metre	87270.00

SCHEDULE OF QUANTITY

ESTIMATED COST :- Rs. 99570.00
 EARNEST MONEY :- Rs. 2000.00
 TIME LIMIT ONE MONTH

NAME OF WORK:- Periodic Maintenance of patch work under HPPWD Division Tanda at Nagrota Bagwan in Distt. Kangra (H.P.). (UNDER MMSRRY)
 1. Jafot Hardu Mangrella road Km 0/000 to 3/000.

SUB-HEAD : Providing and laying patch work on various Rds in between Km 3/330 to 3/485.

Sl. No.	Description of work	Quantity	RATES In		Unit	Amount
			Fig	Word		
1	Providing, laying, spreading and compacting stone aggregate of size 53mm to 22.4mm (Fifty three millimeter to Twenty two point four millimeter) Grading-III size [75mm (seventy five millimeters) compacted thickness] to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber applying and brooming, stone screening type-A of size 13.2mm (thirteen point two millimetres) nominal size at the rate of 0.22 cum (zero point twenty two) cubic metres per 10 sqm (per ten square metres) and binding material at the rate 0.06 cum (zero point zero six cubic metre) to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specifications clause No. 405 and as per drawing and HP.PWD technical specifications, as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	3.30 Cubic metres			Per cubic metre	
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.225 kgs (Zero decimal Two Two Five kilograms) per square metre on the prepared dry and hungry bituminous surface cleaned with Hydraulic broom as per MORD Technical Specification Clause 503 and as per direction of Engineer-In-charge including carriage of materials within all leads and lifts and other incidental. The rate inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government and rectifying defects noticed within two years as per clause 35 (III) of standard bidding document.	300.00 Square metre			Per square metre	
3	Providing, laying and rolling of close-graded Mix Seal Surfacing material of 20mm (Twenty millimetre) thickness composed of 11.2mm to 0.9mm (Eleven point two to Zero point Nine millimetre) (Type-A) @0.2704 Kg/10 Sqm (Zero point Two seven zero four kilogram per Ten square metre) aggregates using penetration grade bitumen @ i.e. binders content @ 22.00 Kg/10 Sqm (Twenty two point zero kilogram per Ten square metre) of 5.11% (Five point Eleven percent) by weight and minimum density of MSS (Mix Seal Surfacing) should be 2.10g (Two point ten grams) per CC to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN (Eight-Ten) static roller and finishing to required level and grades as per Technical Specification Clause 509 complete in all respect and as per direction of Engineer-In-charge including carriage of materials within all leads and lifts and other incidentals. The rate inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government and rectifying defects noticed within two years as per clause 35 (III) of standard bidding document.	300.00 Square metre			Per square metre	
Total :-						

Executive Engineer,
 H.P.W.D.I, Division,
 Tanda at Nagrota Bagwan.