Himachal Pradesh
Public Works Department
HP.PWD Division Shahpur Distt. Kangra (H.P)-176206
e-mail id: ee-shahpur-pwd@hp.gov.in
"NOTICE INVITING TENDERS"

Sealed percentage rate tenders on form 6 & 8 are hereby invited by the Executive Engineer Shahpur Division HP.PWD Shahpur on behalf of Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD (B&R) whose registration stood renewed as per revised rules and also registered under in H.P General Sales Tax Act 1968 so as to reach in his office on or before **27-03-2026 up to 11:00 AM.** and the same shall be opened on the same day at **11:30 AM.** in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable on **25-03-2026 up to 4:30** P.M and the application for issue of tender form shall be received on **25-03-2026 up to 12.00 Noon.**

The earnest money in the shape of NSC/FDR/Saving account of the Post office/ Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/incomplete tenders & tenders without earnest money will be summarily rejected. The offer of tender shall be kept open for 75 days.

Sr. No.	Name of work	Estimated Cost	Earnest Money	Time limit	Cost of tender form
1	Upgradation of Rirkaar to Kutharna road km 0/00 to 6/975 under PMGSY-III Batch -I Package No. HP-04-435 in Distt Kangra (HPP) (SH:- providing and laying of hot applied thermoplastic compound road marking paint-2.55 mm thick Edge line in km 5/101 to 5/500)	99051.00	2,000.00	One Month	350/-
2	Construction of Veer Shromani Maharana Partap Community Hall Lanjot Distt. Kangra (HP) (SH:- C/o Edge wall at RD 0/037 to 0/045)	98847.00	2,000.00	Two Month	350/-
3	Construction of Veer Shromani Maharana Partap Community Hall Lanjot Distt. Kangra (HP) (SH:- C/o Edge wall at RD 0/00 to 0/09)	99392.00	2,000.00	Two Month	350/-
4	A/R & M/O link road Har to Kuther road Km 0/00 to 1/500 (SH:- C/o Rain Shelter at Near Rajat Hotel at RD 0/015 (Steel Work)	99750.00	2,000.00	One Month	350/-
5	A/R & M/O link road Har to Kuther road Km 0/00 to 1/500 (SH:- C/o Rain Shelter at Near Rajat Hotel at RD 0/015 (P/F 0.60mm thick prepainted sheet, Ridge, Plastering & Puty)	99550.00	2,000.00	One Month	350/-
6	Construction of Veer Shromani Maharana Partap Community Hall Lanjot Distt. Kangra (HP) (SH:- C/o Edge wall at RD 0/09 to 0/18)	99665.00	2,000.00	Two Month	350/-
7	Upgradation of Rirkaar to Kutharna road km 0/00 to 6/975 under PMGSY-III Batch -I Package No. HP-04-435 in Distt Kangra (HPP) (SH:- providing and laying of hot applied thermoplastic compound road marking paint-2.55 mm thick Edge line in km 2/300 to 3/00)	97750.00	2,000.00	One Month	350/-
8	Construction of Veer Shromani Maharana Partap Community Hall Lanjot Distt. Kangra (HP) (SH:- C/o B wall at RD 0/00 to 0/04)	98124.00	2,000.00	Two Month	350/-
9	Upgradation of Rirkaar to Kutharna road km 0/00 to 6/975 under PMGSY-III Batch -I Package No. HP-04-435 in Distt Kangra (HPP) (SH:- providing and laying of hot applied thermoplastic compound road marking paint-2.55 mm thick Edge line in km 3/00 to 3/700)	99051.00	2,000.00	One Month	350/-
10	Construction of Veer Shromani Maharana Partap Community Hall Lanjot Distt. Kangra (HP) (SH:- C/o B wall at RD 0/05 to 0/08)	97720.00	2,000.00	Two Month	350/-

11	Upgradation of Rirkaar to Kutharna road km 0/00 to 6/975 under PMGSY-III Batch -I Package No. HP-04-435 in Distt Kangra (HPP) (SH:- providing and laying of hot applied thermoplastic compound road marking paint-2.55 mm thick Edge line in km 3/701 to 4/400)	99051.00	2,000.00	One Month	350/-
12	Annual Repair and Maintenance various road under Sub Division Gaggal (SH:- P/L Spreading and compacting G-III (53mm Ito 22.4mm)	99000.00	2,000.00	One Month	350/-
13	Upgradation of Rirkaar to Kutharna road km 0/00 to 6/975 under PMGSY-III Batch -I Package No. HP-04-435 in Distt Kangra (HPP) (SH:- providing and laying of hot applied thermoplastic compound road marking paint-2.55 mm thick Edge line in km 4/401 to 5/100)	99051.00	2,000.00	One Month	350/-
14	Annual Repair and Maintenance various road under Sub Division Gaggal (SH:- P/L Spreading and compacting G-II (65mm to 45mm)	98900.00	2,000.00	One Month	350/-
15	Repair of Primary Health Center at Lapiana under Health Block Shahpur Distt. Kangra (SH:- P/F 0.60mm Thick prepainted Sheet valley, Gutter, M.S. B.P. Sheet, Rain Pipe & Painting on steel work etc)	99780.00	2,000.00	One Month	350/-
16	Repair of Primary Health Center at Lapiana under Health Block Shahpur Distt. Kangra (SH:- P/F 0.60mm Thick prepainted Sheet Roofing Back Side (i)	99831.00	2,000.00	One Month	350/-
17	Repair of Primary Health Center at Lapiana under Health Block Shahpur Distt. Kangra (SH:- P/F 0.60mm Thick prepainted Sheet Roofing Back Side (ii)	99996.00	2,000.00	One Month	350/-
18	Repair of Primary Health Center at Lapiana under Health Block Shahpur Distt. Kangra (SH:- P/F 0.60mm Thick prepainted Sheet Roofing Back & Front side)	99914.00	2,000.00	One Month	350/-
19	Repair of Primary Health Center at Lapiana under Health Block Shahpur Distt. Kangra (SH:- P/F 0.60mm Thick prepainted Sheet Roofing Back & Ridge of main roof, Dormer, Porch & Back side stair Roof)	99434.00	2,000.00	One Month	350/-
20	Repair of Primary Health Center at Lapiana under Health Block Shahpur Distt. Kangra (SH:- P/F 0.60mm Thick prepainted Sheet Dormer (1st) (2nd) & Porch)	99963.00	2,000.00	One Month	350/-
21	Repair of Primary Health Center at Lapiana under Health Block Shahpur Distt. Kangra (SH:- P/F 0.60mm Thick prepainted Sheet Roofing Front side)	99897.00	2,000.00	One Month	350/-
22	C/o link road Rajol to Dianotu Road Km 0/00 to 3/125 (SH:- P/F Angle Grating for Cross Drainage at RD 0/325)	86256.00	2,000.00	One Month	350/-
23	C/o link road Ladwara Mundla Markoti road KM 0/00 to 3/800 (SH:- C/o U-shape drain at RD 1/790 to 1/810 and CC Pavement at Extended Portion 1/800 to 1/810)	75922.00	2,000.00	One Month	350/-
24	C/o link road Ladwara Mundla Markoti road KM 0/00 to 3/800 (SH:- C/o U-shape drain at RD 1/770 to 1/789 and CC Pavement at Extended Portion 1/790 to 1/800)	80276.00	2,000.00	One Month	350/-
25	Repair of Primary Health Center at Lapiana under Health Block Shahpur Distt. Kangra (SH:- Dismantling of Roofing , Celling & P/F 6mm Thick Cement fiber Board Celling)	99127.00	2,000.00	One Month	350/-
26	Annual Repair and Maintenance various road under Sub Division Gaggal (SH:- Supply & Stacking common burnt clay machine moulded perforated modular bricks)	98000.00	2,000.00	One Month	350/-

27	C/o link road Ladwara Mundla Markoti road KM 0/00 to 3/800 (SH:- C/o U-shape drain at RD 1/750 to 1/769 and CC Pavement at Extended Portion 1/780 to 1/790)	78559.00	2,000.00	One Month	350/-
28	Construction of Veer Shromani Maharana Partap Community Hall Lanjot Distt. Kangra (HP) (SH:- C/o Edge wall at RD 0/028 to 0/036)	99937.00	2,000.00	Two Month	350/-
29	Construction of Veer Shromani Maharana Partap Community Hall Lanjot Distt. Kangra (HP) (SH:- C/o B/ wall at RD 0/013 to 0/016)	98124.00	2,000.00	Two Month	350/-
30	Construction of Veer Shromani Maharana Partap Community Hall Lanjot Distt. Kangra (HP) (SH:- C/o Edge wall at RD 0/019 to 0/27)	99283.00	2,000.00	Two Month	350/-
31	Construction of Veer Shromani Maharana Partap Community Hall Lanjot Distt. Kangra (HP) (SH:- C/o B/ wall at RD 0/017 to 0/020.59)	99785.00	2,000.00	Two Month	350/-
32	A/R & M/O link road Har to Kuther road Km 0/00 to 1/500 (SH:- C/o Rain Shelter at Near Rajat Hotel at RD 0/015 (SH:- Excavation in Earth Work P/L 1:4:8, RR Masonry Stone Soilling, Cement Flooring & Steel Work)	99389.00	2,000.00	One Month	350/-
33	Construction of Veer Shromani Maharana Partap Community Hall Lanjot Distt. Kangra (HP) (SH:- C/o B/ wall at RD 0/09 to 0/12))	99973.00	2,000.00	Two Month	350/-
34	Repair of Primary Health Center at Lapiana under Health Block Shahpur Distt. Kangra (SH:- Dismantling of Roofing , Celling & P/F 6mm Thick Cement fiber Board Celling)	99960.00	2,000.00	One Month	350/-

Certified that tender of above works are being called of urgent nature in public interest.

Terms & Conditions: -

1. The contractor/firm should be produce the attested copy of latest enlistment and renewal enlistment in HP.PWD. GST No. and EPF No. with the application falling which their application will not be entertained.
2. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
3. The Earnest Money for the above works should be required at the time of sale of tender forms.
4. The Contractor/Firms should be quoted percentage rate in the tender both in figures and in words failing which tender is likely to be rejected.
5. The Executive Engineer reserves the right to accept/reject any tender/application or all tender without assigning any reason.

Executive Engineer
Shahpur Division
HP.PWD Shahpur.
(on behalf of Governor of Himachal Pradesh)

No.PWD/SD/Tender/NIT/2025-26/- 11307 - 11315 **Dated:** 19/03/2026

Copy to following for information and necessary action:-

1. The Superintending Engineer 5th Circle HPPWD Palampur.
2. The Executive Engineer (IT) Nigam Vihar Shimla. He is requested to upload the same on the department website.
3. All the Assistant Engineer under this Division.
4. The Drawing/Accounts Branch in this office.
5. Notice Board

Executive Engineer
Shahpur Division
HP.PWD Shahpur.

(1)

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 99051.00

EARNEST MONEY : - ₹ 2000.00

TIME LIMIT : One Month

NAME OF WORK :- Upgradation of Rirkmaar to Kutharna road km 0/000 to 6/975 under PMGSY-III Batch-I Package No: HP-04-435 in Distt Kangra (H.P.)

SUB-HEAD :- Providing and Laying of hot applied thermoplastic compound road marking paint 2.5mm thick Edge line in km 5/101 to 5/500.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and laying of hot applied thermoplastic compound 2.5mm (Two decimal five millimetres) thick including reflectorising glass @ 250 (two hundred fifty grams) per sqm area, thickness of 2.5 mm (two deciaml five millimetres) is exclusive of surface applied glass beads as per IRC -35(thirty five) The finished surface to be level, uniform and free from streaks and holes, as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royality, Malkana, toll tax, GST or any other taxes imposed by the Government.	144.60	685.00	Rupees Six Hundred Eighty Five Only	Per Square metre	99051.00
					TOTAL :-	99051.00
	Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)			
	Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)			

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

(1)

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 98847.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT : Two Months

NAME OF WORK :- Construction of Veer Shriomani Maharana Partap Community Hall Lanjot Distt Kangra (H.P).

SUB-HEAD :- C/o Edge wall at RD 0/037 to 0/045.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling /wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	9.72	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	3402.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arrise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etctera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royality, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	16.10	5450.00	Rupees Five Thousand Four Hundred Fifty Only	Per cubic metre	87745.00
3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope I(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government.	22.00	350.00	Rupees Three Hundred Fifty Only	Each	7700.00
					TOTAL :-	98847.00
	Quated Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quated Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 99392.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT : Two Months

NAME OF WORK :- Construction of Veer Shriomani Maharana Partap Community Hall Lanjot Distt Kangra (H.P).

SUB-HEAD :- C/o Edge wall at RD 0/000 to 0/09

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	9.72	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	3402.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arrise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etctera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royality, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	16.20	5450.00	Rupees Five Thousand Four Hundred Fifty Only	Per cubic metre	88290.00
3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope I(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government.	22.00	350.00	Rupees Three Hundred Fifty Only	Each	7700.00
					TOTAL :-	*99392.00*
	Quated Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quated Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 99750.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT :- One Month

NAME OF WORK : - A/R & M/O Link Road Har to Kuther Road km 0/00 to 1/500.

SUB-HEAD : - C/o Rain Shelter at Near Rajat Hotel at RD 0/015.(Steel Work.)

Sr. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Steel work welded in built up sections of TATA/SAIL joists channels, angles, tees with connection plates or angles, cleat as in trusses, trussed purlins main and cross beams, hips jack rafters, purlins connected to common rafters and the like in building including cutting, fixing, lifting, hoisting and; placing in position complete and applying a coat of red lead paint, within all leads, lifts of materials and other incidentals. as per approved architectural drawing, design and specification as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	950.00	105.00	Rupees One Hundred Five Only	Per Kilograme	99750.00
					TOTAL :-	*99750.00*
	Quated Rate in Figure (%)	**(Amount to be quoted by the contractor in Figure)**				
	Quated Rate in Words (%)	**(Amount to be quoted by the contractor in words)**				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur.

(3)

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 39550.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT :- One Month

NAME OF WORK : - A/R & M/O Link Road Har to Kuther Road km 0/00 to 1/500.

SUB-HEAD : - C/o Rain Shelter at Near Rajat Hotel at RD 0/015.(P/F 0.60mm thick prepainted Sheet, Ridge,Plastering & Putty.)

Sr. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and fixing 0.60mm (Zero decimal Six Zero milimetres) thick prepainted steel sheet ISI marked - Z 120 of Tata Durashine/ Sail / Reliance / Jindal steel in roofing with hot dipped metalic zinc coated sheet with top coat of regular modified polyster (RMP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating to back coat of polyster of 5 (five) microns over 5 (Five) microns primer fixing with prepainted iron J or L hooks,bolts and nuts with prepainted limpet and rubber washers complete with all accessories as required within all leads, lifts of materials and other. incidentals. as per approved architectural drawing, design and specification and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	26.92	1650.10	Rupees One Thousand Six Hundred Fifty And Paise Ten Only	Per square metre	44421.00
2	Providing and fixing ridges or hips 60 cm (Sixty centimetres) over all with 0.60mm (Zero decimal Sixty milimetres) thick prepainted steel sheet ISI marked - Z 120 of approved make in ridges of Sail / Relience / Jindal /Tata Durashine with hot dipped metallic Zinc coated sheet with top coat of regular modified polyester (RMP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating of back coat of polyester of 5 (Five) microns over 5 (Five) microns primer coating including fixing with prepainted iron J or L hooks, bolts and nuts 6mm (Six milimetres) diametres with prepainted G.I. limpet and bitumen washers complete with all accessories as required within all leads, lifts of materials and other. incidentals. as per approved architectural drawing, design and specification as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	7.80	850.40	Rupees Eight Hundred Fifty And Paise Forty Only	Per running metre	6633.00
3	Providing and fixing plain M.S. B.P. sheet of TATA/SAIL/JINDAL steel 2.00 mm (Two decimal zero millimeter) thick fixed in eaves board / facia / soffits /ceiling including cutting, fixing and welding to steel rafter, member and applying a coat of red lead primer with gas/ electric welding in position complete (frame work is to be measured and paid for separately) within all leads, lifts of materials and other. incidentals. as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	28.15	1490.00	Rupees One Thousand Four Hundred Ninety Only	Per square metre	41944.00
4	Painting two coats (excluding priming coat) on new steel and other metal surfaces with enamel paint brushing to give an even shade including cleaning the surface to remove all dirt,dust and other foregin matter with enamel paint other than white including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royality, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	28.15	65.00	Rupees Sixty Five Only	Per square metre	1830.00

SCHEDULE OF QUANTITY

1	2	3	4	5	6	7
5	Providing and applying 15mm (fifteen millimeters) thick cement plaster with cement mortar 1:6 (one cement isto six sand) in single coat on rough side of brick/concrete/ stone walls for interior plastering up to all floor level including arises, internal rounded angles, chamfers and/or rounded angles in all girth and finished even and smooth as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge.The rate is including octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government.	16.00	210.00	Rupees Two Hundred Ten Only	Per square metre	3360.00
6	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royality, malkana, toll tax, GST and all type of other taxes imposed by the Government.	16.00	85.10	Rupees Eighty Five And Paise Ten Only	Per square metre	1362.00
					TOTAL :-	***99550.00***
	Quated Rate in Figure (%)			**(Amount to be quoted by the contractor in Figure)**		
	Quated Rate in Words (%)			**(Amount to be quoted by the contractor in words)**		

Executive Engineer,
Shahpur Division,
HPPWD Shahpur.

SCHEDULE OF QUANTITY

(6)

ESTIMATED COST: - ₹ 99665.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT : Two Months

NAME OF WORK :- Construction of Veer Shriomani Maharana Partap Community Hall Lanjot Distt Kangra (H.P).

SUB-HEAD :- C/o Edge wall at RD 0/09 to 0/18.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	9.72	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	3402.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arrise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etctera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royality, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	16.25	5450.00	Rupees Five Thousand Four Hundred Fifty Only	Per cubic metre	88563.00
3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope I(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government.	22.00	350.00	Rupees Three Hundred Fifty Only	Each	7700.00
					TOTAL :-	*99665.00*
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

(7)

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 97750.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT : One Month

NAME OF WORK :- Upgradation of Rirkmaar to Kutharna road km 0/000 to 6/975 under PMGSY-III Batch-I Package No: HP-04-435 in Distt Kangra (H.P.)

SUB-HEAD :- Providing and Laying of hot applied thermoplastic compound road marking paint 2.5mm thick Edge line in km 2/300 to 3/00

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and laying of hot applied thermoplastic compound 2.5mm (Two decimal five millimetres) thick including reflectorising glass @ 250 (two hundred fifty grams) per sqm area, thickness of 2.5 mm (two deciaml five millimetres) is exclusive of surface applied glass beads as per IRC -35(thirty five) The finished surface to be level, uniform and free from streaks and holes, as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royality, Malkana, toll tax, GST or any other taxes imposed by the Government.	142.70	685.00	Rupees Six Hundred Eighty Five Only	Per Square metre	97750.00
					TOTAL :-	97750.00
	Quated Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quated Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

(8)

ESTIMATED COST: - ₹ 98124.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT : Two Months

NAME OF WORK :- Construction of Veer Shriomani Maharana Partap Community Hall Lanjot Distt Kangra (H.P).

SUB-HEAD :- C/o B/ wall at RD 0/00 to 0/04.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	7.20	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	2520.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty milimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government.	17.28	5050.00	Rupees Five Thousand Fifty Only	Per cubic metre	87264.00
3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope I(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in- charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government.	18.00	350.00	Rupees Three Hundred Fifty Only	Each	6300.00

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	*In words*		
1	*2*	*3*	*4*	*5*	*6*	*7*
4	Back filling with granular material behind abutments, wing walls, return walls and retaning walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royality, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	2.40	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	2040.00
					TOTAL :-	*98124.00*
	Quated Rate in Figure (%)	**(Amount to be quoted by the contractor in Figure)**				
	Quated Rate in Words (%)	**(Amount to be quoted by the contractor in words)**				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

(9)

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 99051.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT : One Month

NAME OF WORK :- Upgradation of Rirkmaar to Kutharna road km 0/000 to 6/975 under PMGSY-III Batch-I Package No: HP-04-435 in Distt Kangra (H.P.)

SUB-HEAD :- Providing and Laying of hot applied thermoplastic compound road marking paint 2.5mm thick Edge line in km 3/00 to 3/700.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and laying of hot applied thermoplastic compound 2.5mm (Two decimal five millimetres) thick including reflectorising glass @ 250 (two hundred fifty grams) per sqm area, thickness of 2.5 mm (two deciaml five millimetres) is exclusive of surface applied glass beads as per IRC -35(thirty five) The finished surface to be level, uniform and free from streaks and holes, as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royality, Malkana, toll tax, GST or any other taxes imposed by the Government.	144.60	*685.00*	Rupees Six Hundred Eighty Five Only	Per Square metre	*99051.00*
					TOTAL :-	*99051.00*
	Quated Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quated Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 97720.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT : Two Months

NAME OF WORK :- Construction of Veer Shriomani Maharana Partap Community Hall Lanjot Distt Kangra (H.P).

SUB-HEAD :- C/o B/ wall at RD 0/05 to 0/08.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	7.20	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	2520.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty milimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government.	17.20	5050.00	Rupees Five Thousand Fifty Only	Per cubic metre	86860.00
3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope I(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in- charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government.	18.00	350.00	Rupees Three Hundred Fifty Only	Each	6300.00

	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
	2	3	4	5	6	7
	Back filling with granular material behind abutments, wing walls, return walls and retaning walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royality, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	2.40	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	2040.00
					TOTAL :-	97720.00
	Quated Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)			
	Quated Rate in Words (%)		(Amount to be quoted by the contractor in words)			

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99052.00

EARNEST MONEY :- ₹ 2000.00

TIME LIMIT :- One Month

NAME OF WORK :- Upgradation of Rickmaar to Kuthana road km 0/000 to 6/575 under PMGSY-III Batch-I Package No: HP-04-425 in Distt Kangra (H.P.)

SUB-HEAD :- Providing and Laying of hot applied thermoplastic compound road marking paint 2.5mm thick Edge line in km 3/722 to 4/400.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			in fig.	in words		
1	2	3	4	5	6	7
1	Providing and laying of hot applied thermoplastic compound 2.5mm (Two decimal five millimetres) thick including reflectorising glass @ 250 (two hundred fifty grams) per sqm area, thickness of 2.5 mm (two decimal five millimetres) is exclusive of surface applied glass beads as per IRC -35(thirty five) The finished surface to be level, uniform and free from streaks and holes, as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	242.80	885.00	Rupees Six Hundred Eight Five Only	Per Square metre	99052.00
					TOTAL :-	99052.00
	Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in figure)			
	Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)			

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 99000.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT :- One Month

NAME OF WORK :- Annual Repair and Maintenance Various Road Under Sub -Division Gaggal .

SUB-HEAD :- Providing, laying, spreading and compacting G-III (53mm to 22.4mm)

Sr. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm(seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.16cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government	44.00	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	99000.00
					TOTAL :-	99000.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur.

DRAFT SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 97875.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT :- One Month

NAME OF WORK : - Annual Repair and Maintenance Various Road Under Sub -Division Gaggal .

SUB-HEAD : - Providing, laying, spreading and compacting G-III (53mm to 22.4mm)

Sr. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm(seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two milimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer–in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government	43.50	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	97875.00
					TOTAL : -	***97875.00***

Assistant Engineer,
HP.PWD Sub Division,
Gaggal.

Executive Engineer,
Shahpur Division,
HPPWD Shahpur.

(18)

SCHEDULE OF QUANTITY

NAME OF WORK :- Upgradation of Rirkmaar to Kutharna road km 0/000 to 6/975 under PMGSY-III Batch-I Package No: HP-04-435 in Distt Kangra (H.P.)

ESTIMATED COST: - ₹ 99051.00

EARNEST MONEY : - ₹ 2000.00

TIME LIMIT : One Month

SUB-HEAD :- Providing and Laying of hot applied thermoplastic compound road marking paint 2.5mm thick Edge line in km 4/401 to 5/100.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and laying of hot applied thermoplastic compound 2.5mm (Two decimal five millimetres) thick including reflectorising glass @ 250 (two hundred fifty grams) per sqm area, thickness of 2.5 mm (two deciaml five millimetres) is exclusive of surface applied glass beads as per IRC -35(thirty five) The finished surface to be level, uniform and free from streaks and holes, as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royality, Malkana, toll tax, GST or any other taxes imposed by the Government.	144.60	685.00	Rupees Six Hundred Eighty Five Only	Per Square metre	99051.00
	Quated Rate in Figure (%)				*TOTAL :-*	*99051.00*
	Quated Rate in Words (%)			(Amount to be quoted by the contractor in Figure)		
				(Amount to be quoted by the contractor in words)		

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

(19)

ESTIMATED COST: - ₹ 98900.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT :- One Month

NAME OF WORK :- Annual Repair and Maintenance Various Road Under Sub -Division Gaggal .

SUB-HEAD :- Providing, laying, spreading and compacting G-II (65mm to 45mm)

Sr. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing laying spreading and compacting by manual means of stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven decimal point two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required densityas per M.O.R.D. technical specifications clause 405 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royality, GST, toll tax or other taxes imposed by the Government.	46.00	2150.00	Rupees Two Thousand One Hundred Fifty Only	Per cubic metre	98900.00
					TOTAL :-	*98900.00*
	Quated Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quated Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur.

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99780.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT :- One Month

NAME OF WORK :- Repair of Primary Health Centre at Lapiana Under Health Block Shahpur ,District Kangra)

SUB-HEAD :- P/F 0.60mm Thick Prepainted Sheet Valley, Gutter, M.S. B.P. Sheet, Rain Pipe & Paiting on Steel work Etc.

Sr. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and fixing valleys 90 cm (ninety centimetres) over all over all with 0.60mm (Zero decimal Six zero milimetres) thick prepainted sheet ISI marked - Z 120 of Sail / TATA / Relience / Jindal steel roofing with hot dipped metallic Zinc coated sheet with top coat of regular modified polyester (RMP) organic coating of 20 (Twenty) microns over 5 (five) micron primer coating, back coat of polyster of 5 (Five) microns including fixing with prepainted iron J or L hooks, bolts and nuts 6mm (Six milimetres) diametres with prepainted G.I. limpet and bitumen washers complete with all accessories as required within all leads, lifts of materials and other incidentals. as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	11.00	950.00	Rupees Nine Hundred Fifty Only	Per running metre	10450.00
2	Providing and fixing 30cm (thirty centimeters) wide 25cm (twenty five centimeters) deep of Tata/ Sail / Jindal Steel 0.60mm (Zero decimal Six zero milimetres) thick plain G.I. gutter with iron brackets 40x3mm (Forty into Three milimetres) size bolts and nuts and washers etcetera including making necessary connections with rain water pipe and providing complete accesories within all leads, lifts of materials and other. incidentals. as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	36.30	825.60	Rupees Eight Hundred Twenty Five And Paise Sixty Only	Per running metre	29969.00
3	Providing and fixing plain M.S. B.P. sheet of TATA/SAIL/JINDAL steel 2.00 mm (Two decimal zero millimeter) thick fixed in eaves board / facia / soffits /ceiling including cutting, fixing and welding to steel rafter, member and applying a coat of red lead primer with gas/ electric welding in position complete (frame work is to be measured and paid for separately) within all leads, lifts of materials and other. incidentals. as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	6.36	1850.00	Rupees One Thousand Eight Hundred Fifty Only	Per square metre	11766.00
4	Providing and fixing flashing 38cm (Thirty eight centimetre) overall with 0.60mm (zero decimal six zero millimetre) thick prepainted sheet of Tata / sail / Reliance / Jindal with hot dipped metalic zinc coated sheet with top coat of regular modified polyster organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating + back coat of polyster of 5 (Five) microns over 5 (Five) microns primer coating i/c fixing with prepainted iron J or L hooks, bolts and nuts 6mm (Six millimetre) dia meter & prepainted G.I. limpet & bitumen washers complete. as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST and any other taxes imposed by the Government.	3.70	845.00	Rupees Eight Hundred Forty Five Only	Per running metre	3127.00
5	Providing and fixing high pressure PVC spigot and socket, waste and ventilating pipes light grade ISI marked of fenolex/vectus/price 4.6mm thick having pressure not less than 6kg /cm2 (six kilogramm per centimetre square) including fixing with approved adhesive etc complete including entire carriage of materials within all leads lifts and other incidentals. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government 150mm (One hundred fifty milimetres) diametres	18.00	510.25	Rupees Five Hundred Ten And Paise Twenty Five Only	Per running metre	9185.00

1	2	3	4	5	6	7
6	Providing and fixing P.V.C. I.S.I. marked plain bend of Finolex / Vectus / Prince including filling the joints with including fixing with approved adhesive within all leads, lifts of materials and other incidentals. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.150mm (One hundred fifty milimetres) diametres	15.00	280.10	Rupees Two Hundred Eighty And Paise Ten Only	Each	4202.00
7	Providing and fixing cast iron P.V.C. holder bat clamps ISI marked of approved drawing i/c/ steel screw and rawl plug etc. including entire carriage of materials within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.150mm (One hundred fifty milimetres) diametres	15.00	260.40	Rupees Two Hundred Sixty And Paise Forty Only	Each	3906.00
8	Providing and fixing glazing With float glass panes of 5 mm (Five milimetres) thickness (weight not less than 12.50kg/square metre) of modi guard/saint gobain/AIS/Atul/Gold Plus in door, windows, ventilators shutter and partitions with EPDM rubber/Neoprene gastet etcetera as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	18.50	1250.00	Rupees One Thousand Two Hundred Fifty Only	Per square metre	23125.00
9	Painting one coat (excluding priming coat) on previously painted steel and othermetal 103.50 surfaces with enamel paint brushing to give an even shade including cleaning the surface of all dirt, dust and other foreign matter with Enamel paint other than white complete as per direction of Engineer-In-Charge including entire carriage of materials within all leads, lifts and other incidentals.	90.00	45.00	Rupees Forty Five Only	Per square metre	4050.00
					TOTAL :-	***99780.00***
	Quated Rate in Figure (%)	**(Amount to be quoted by the contractor in Figure)**				
	Quated Rate in Words (%)	**(Amount to be quoted by the contractor in words)**				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur.

16

SCHEDULE OF QUANTITY

ESTIMATED COST : ₹ [illegible]

EARNEST MONEY : ₹ [illegible]

TIME LIMIT : [illegible]

NAME OF WORK : Repair of Primary Health Centre at Lapkana Under Health Block Dhalhpur District Kangra (

NAME HEAD : H.P. 7 Fifteen Third Programmed Grant Rooftop Rain Water (

Sr No	Description of Items	Quantity	Rates		Unit	Amount
			in Fig	in words		
1	2	3	4	5	6	7
1	Providing and fixing 1.25mm (Gen decimal for Gen nominal) thick prepainted steel sheet as per IS number 3 620 of 2 Gen (Thickness Size / Reference / Grade steel is roofing with hot dipped metallic zinc coated sheet with the coat of regular modified polyester (PMP) organic coating of 20 (Twenty) microns over a (Five) minimum primer coating to each coat of coatings of 2 (Two) minimum over a (Five) minimum prime fixing with prepainted nut / st c hooks bolts and nuts with prepainted limpet and rubber washers complete with all accessories as required either at basic site of materials and other consumables as per approved architectural drawing design and specification and as directed by the Engineer in Charge. The rate is inclusive of octroi, royalty, multipoint, VAT tax, web tax, CST or any other taxes imposed by the Government.	40.31	[illegible]	Rupees One Thousand Six Hundred Fifty And Paise Ten Only	Per square metre	[illegible]
					TOTAL	[illegible]
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
[illegible] Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 99996.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT :- One Month

NAME OF WORK : - Repair of Primary Health Centre at Lapiana Under Health Block Shahpur ,District Kangra)

SUB-HEAD : - P/F 0.60mm Thick Prepainted Sheet Roofing Back Side (ii)

Sr. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and fixing 0.60mm (Zero decimal Six Zero milimetres) thick prepainted steel sheet ISI marked - Z 120 of Tata Durashine/ Sail / Reliance / Jindal steel in roofing with hot dipped metalic zinc coated sheet with top coat of regular modified polyster (RMP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating to back coat of polyster of 5 (five) microns over 5 (Five) microns primer fixing with prepainted iron J or L hooks,bolts and nuts with prepainted limpet and rubber washers complete with all accessories as required within all leads, lifts of materials and other. incidentals. as per approved architectural drawing, design and specification and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	60.60	1650.10	Rupees One Thousand Six Hundred Fifty And Paise Ten Only	Per square metre	99996.00
					TOTAL :-	***99996.00***
	Quated Rate in Figure (%)	**(Amount to be quoted by the contractor in Figure)**				
	Quated Rate in Words (%)	**(Amount to be quoted by the contractor in words)**				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur.

SCHEDULE OF QUANTITY

18

ESTIMATED COST : ₹ 99914.00
EARNEST MONEY : ₹ 2000.00
TIME LIMIT :- One Month

NAME OF WORK :- Repair of Primary Health Centre at Lapiana Under Health Block Shahpur ,District Kangra)

SUB HEAD :- P/F 0.60mm Thick Prepainted Sheet Roofing Back & Front side

Sr. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and fixing 0.60mm (Zero decimal Six Zero millimetres) thick prepainted steel sheet (Si marked - Z 120 of Tata/ Durashine/ Sail / Reliance / Jindal steel in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyster (RMP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating to back coat of polyster of 5 (five) microns over 5 (Five) microns primer fixing with prepainted iron J or L hooks bolts and nuts with prepainted limpet and rubber washers complete with all accessories as required within all leads, lifts of materials and other incidentals, as per approved architectural drawing, design and specification and as directed by the Engineer in-Charge. The rate is inclusive of octroi, royalty, mukhiana, toll tax, sale tax, GST or any other taxes imposed by the Government.	60.55	1650.00	Rupees One Thousand Six Hundred Fifty And Paise Ten Only	Per square metre	99914.00
					TOTAL :-	99914.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur.

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 99434.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT :- One Month

NAME OF WORK : - Repair of Primary Health Centre at Lapiana Under Health Block Shahpur ,District Kangra)

SUB-HEAD : - P/F 0.60mm Thick Prepainted Sheet Roofing Front side & Ridge of Main Roof , Dormer, Porch & Back Side Stair Roof.

Sr. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and fixing 0.60mm (Zero decimal Six Zero milimetres) thick prepainted steel sheet ISI marked - Z 120 of Tata Durashine/ Sail / Reliance / Jindal steel in roofing with hot dipped metalic zinc coated sheet with top coat of regular modified polyster (RMP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating to back coat of polyster of 5 (five) microns over 5 (Five) microns primer fixing with prepainted iron J or L hooks,bolts and nuts with prepainted limpet and rubber washers complete with all accessories as required within all leads, lifts of materials and other. incidentals. as per approved architectural drawing, design and specification and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	41.50	1650.10	Rupees One Thousand Six Hundred Fifty And Paise Ten Only	Per square metre	68479.00
2	Providing and fixing ridges or hips 60 cm (Sixty centimetres) over all with 0.60mm (Zero decimal Sixty milimetres) thick prepainted steel sheet ISI marked - Z 120 of approved make in ridges of Sail / Relience / Jindal /Tata Durashine with hot dipped metallic Zinc coated sheet with top coat of regular modified polyester (RMP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating of back coat of polyester of 5 (Five) microns over 5 (Five) microns primer coating including fixing with prepainted iron J or L hooks, bolts and nuts 6mm (Six milimetres) diametres with prepainted G.I. limpet and bitumen washers complete with all accessories as required within all leads, lifts of materials and other. incidentals. as per approved architectural drawing, design and specification as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	36.40	850.40	Rupees Eight Hundred Fifty And Paise Forty Only	Per running metre	30955.00
					TOTAL :-	*99434.00*
	Quated Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)			
	Quated Rate in Words (%)		(Amount to be quoted by the contractor in words)			

Executive Engineer,
Shahpur Division,

(20)

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 99963.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT :- One Month

NAME OF WORK : - Repair of Primary Health Centre at Lapiana Under Health Block Shahpur ,District Kangra)

SUB-HEAD : - P/F 0.60mm Thick Prepainted Sheet Roofing Dormer (1st),(2nd) &Porch

Sr. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and fixing 0.60mm (Zero decimal Six Zero milimetres) thick prepainted steel sheet ISI marked - Z 120 of Tata Durashine/ Sail / Reliance / Jindal steel in roofing with hot dipped metalic zinc coated sheet with top coat of regular modified polyster (RMP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating to back coat of polyster of 5 (five) microns over 5 (Five) microns primer fixing with prepainted iron J or L hooks,bolts and nuts with prepainted limpet and rubber washers complete with all accessories as required within all leads, lifts of materials and other. incidentals. as per approved architectural drawing, design and specification and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	60.58	1650.10	Rupees One Thousand Six Hundred Fifty And Paise Ten Only	Per square metre	99963.00
					TOTAL :-	***99963.00***
	Quated Rate in Figure (%)	**(Amount to be quoted by the contractor in Figure)**				
	Quated Rate in Words (%)	**(Amount to be quoted by the contractor in words)**				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur.

SCHEDULE OF QUANTITY

(21)

ESTIMATED COST: - ₹ 99897.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT :- One Month

NAME OF WORK : - Repair of Primary Health Centre at Lapiana Under Health Block Shahpur ,District Kangra)

SUB-HEAD : - P/F 0.60mm Thick Prepainted Sheet Roofing Front side

Sr. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and fixing 0.60mm (Zero decimal Six Zero milimetres) thick prepainted steel sheet ISI marked - Z 120 of Tata Durashine/ Sail / Reliance / Jindal steel in roofing with hot dipped metalic zinc coated sheet with top coat of regular modified polyster (RMP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating to back coat of polyster of 5 (five) microns over 5 (Five) microns primer fixing with prepainted iron J or L hooks,bolts and nuts with prepainted limpet and rubber washers complete with all accessories as required within all leads, lifts of materials and other. incidentals. as per approved architectural drawing, design and specification and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	60.54	1650.10	Rupees One Thousand Six Hundred Fifty And Paise Ten Only	Per square metre	99897.00
					TOTAL :-	*99897.00*
	Quated Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)			
	Quated Rate in Words (%)		(Amount to be quoted by the contractor in words)			

Executive Engineer,
Shahpur Division,
HPPWD Shahpur.

SCHEDULE OF QUANTITY

22

ESTIMATED COST:- ₹ 86256.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT :- One Month

NAME OF WORK :- C/o Link road Rajol to Dianotu Road km 0/00 to 3/125.

SUB-HEAD :- SH:-P/F Angle Grating for Cross Drainage at RD 0/325.

Sr. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in charge .The rate is including Royality, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	4.95	1465.35	Rupees One Thousand Four Hundred Sixty Five And Paise Thirty Five Only	Per Cubic metre	7253.00
2	Steel work welded in built up sections,trusses and framed work,including cutting ,hoisting ,fixing in position and applying a priming coat of red lead paint In beams joists channels ,angles , tee ,flats with connecting plates or angle cleats as on main and cross beams,hip and jack rafters,purlins connected to common rafters and the like.complete as per specification, approved drawing , design, as per the entire satsifaction and direction of the Engineer-in-charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royality, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	713.75	105.00	Rupees One Hundred Five Only	Per koligram	74944.00
3	Providing and laying mechanically mixed and vibrated concrete for plain / reinforced concrete in sub structure for all types of structure of plain cement concrete grade M-20 (twenty) with minimum nominal mix 1:2:4 (one cement is to two sand is to four graded crushed stone aggregate 20mm (twenty millimetre) nominal size in or under water including curing complete for 14 (fourteen) days pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,804,806,807,1202 and 1204 as per the directions of Engineer-In-Charge including carriage of materials within all leads,lifts and other incidental. The rate including the octroi, royality, Malkana, toll tax, or any other taxes imposed by the Government..	0.660	6150.00	Rupees Six Thousand One Hundred Fifty Only	Per Cubic metre	4059.00
					TOTAL :-	86256.00
	Quated Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quated Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur.

DRAFT SCHEDULE OF QUANTITY

23

ESTIMATED COST: - ₹ 75922.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT :- One Month

NAME OF WORK : Construction of Link road Ladwara Mundla Makroti road KM 0/00 to 3/800

SUB-HEAD : - C/O U-Shape drain at RD 1/790to 1/810 and C.C. Pavement at Extended Portion 1/800 to 1/810.

Sr. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 1and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	18.32	350.00	Rupees Three Hundred Fifty Only	Per Cubic metre	6412.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arrise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etctera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royality, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	7.50	5380.00	Rupees Five Thousand Three Hundred Eighty Only	Per Cubic metre	40350.00
3	Providing laying spreading and compacting by manual means of stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven decimal point two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required densityas per M.O.R.D. technical specifications clause 405 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royality, GST, toll tax or other taxes imposed by the Government.	0.830	2150.00	Rupees Two Thousand One Hundred Fifty Only	Per Cubic metre	1785.00

1	2	3	4	5	6	7
4	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-II size [75mm(seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-3 of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	0.830	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per Cubic metre	1868.00
5	roviding and laying cement concrete 1:1.5 :3 (One cement: one & Half Sand: three graded/crushed stone aggregate) 20mm (twenty millimeter nominal size) for plain / reinforcement concrete in super structure complete including cost of form work steel plate as per drawing and technical specification clause No 802, 804, 805,806, 807, 1202 &1204 including entire carriage of material with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty malkana toll tax, sale tax or other taxes imposed by the Government	2.580	7150.00	Rupees Seven Thousand One Hundred Fifty Only	Per Cubic metre	18447.00
6	Steel work welded in built up sections,trusses and framed work,including cutting ,hoisting ,fixing in position and applying a priming coat of red lead paint in beams joists channels ,angles , tee ,flats with connecting plates or angle cleats as in main and cross beams,hip and jack rafters,purlins connected to common rafters and the like complete as per specification, approved drawing , design, as per the entire satisfaction and direction of the Engineer-in-charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	67.24	105.00	Rupees One Hundred Five Only	Per Kilogram	7060.00
					TOTAL :-	75522.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur.

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 80276.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT :- One Month

NAME OF WORK :- Construction of Link road Ladwara Mundla Makroti road KM 0/00 to 3/800

SUB-HEAD :- C/O U-Shape drain at RD 1/770 to 1/789 and C.C. Pavement at Extended Portion 1/790 to 1/800.

Sr. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	18.50	350.00	Rupees Three Hundred Fifty Only	Per Cubic metre	6475.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arrise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etctera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royality, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	7.70	5380.00	Rupees Five Thousand Three Hundred Eighty Only	Per Cubic metre	41426.00
3	Providing laying spreading and compacting by manual means of stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven decimal point two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required densityas per M.O.R.D. technical specifications clause 405 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royality, GST, toll tax or other taxes imposed by the Government.	1.300	2150.00	Rupees Two Thousand One Hundred Fifty Only	Per Cubic metre	2795.00

1	2	3	4	5	6	7
4	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm(seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two milimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer–in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government	1.300	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per Cubic metre	2925.00
5	roviding and laying cement concrete 1:1.5 :3 (One cement: one & Half Sand: three graded/crushed stone aggregate) 20mm (twenty millimeter nominal size) for plain / reinforcement concrete in super structure complete including cost of form work steel plate as per drawing and technical specification clause No 802, 804, 805,806, 807, 1202 &1204 including entire carriage of material with in all leads and lifts and other incidentals The rates are inclusive of octroi, royality malkana toll tax, sale tax or other taxes imposed by the Government	2.700	7150.00	Rupees Seven Thousand One Hundred Fifty Only	Per Cubic metre	19305.00
6	Steel work welded in built up sections,trusses and framed work,including cutting ,hoisting ,fixing in position and applying a priming coat of red lead paint In beams joists channels ,angles , tee ,flats with connecting plates or angle cleats as in main and cross beams,hip and jack rafters,purlins connected to common rafters and the like.complete as per specification, approved drawing , design, as per the entire satsifaction and direction of the Engineer-in-charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royality, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	70.00	105.00	Rupees One Hundred Five Only	Per koligram	7350.00
					TOTAL :-	***80276.00***
	Quated Rate in Figure (%)	**(Amount to be quoted by the contractor in Figure)**				
	Quated Rate in Words (%)	**(Amount to be quoted by the contractor in words)**				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur.

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 99127.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT :- One Months

NAME OF WORK : - Repair of Primary Health Centre at Lapiana Under Health Block Shahpur ,District Kangra)

SUB-HEAD : - Dismantling of Roofing , Ceiling & P/F 6mm Thick Cement fiber Board Ceiling.

Sr. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Dismantling roofing including ridges, hips, valleys and gutters etc., and stacking the material within 50 metres lead within all lead and lift. and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government	301.05	69.80	Rupees Sixty Nine And Paise Eighty Only	Per square metre	21013.00
2	Dismantling cement asbestos or other hard board ceiling or partition walls including stacking of serviceable material sand disposal of unservice able materials within 50 metres lead. within all lead and lift. and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government	180.66	28.50	Rupees Twenty Eight And Paise Fifty Only	Per square metre	5149.00
3	Providing and fixing 6 mm thick plain multipurpose cement fibre board with suitable screws for cement particle board in ceiling etc complete.within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	90.08	810.00	Rupees Eight Hundred Ten Only	Per square metre	72965.00
					TOTAL :-	*99127.00*
	Quated Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quated Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur.

SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 98000.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT :- One Month

NAME OF WORK :- Annual Repair and Maintenance Various Road Under Sub -Division Gaggal .

SUB-HEAD :- Supply & Stacking Common burnt clay machine moulded perforated modular bricks

Sr. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Supply & Stacking Common burnt clay machine moulded perforated modular bricks of class designation 12.5 as per direction Engineer in charge including carriage including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government..	3500.00	28.00	Rupees Twenty Eight Only	Per cubic metre	98000.00
					TOTAL :-	***98000.00***
	Quated Rate in Figure (%)	**(Amount to be quoted by the contractor in Figure)**				
	Quated Rate in Words (%)	**(Amount to be quoted by the contractor in words)**				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur.

SCHEDULE OF QUANTITY

27

ESTIMATED COST: - ₹ 78559.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT :- One Month

NAME OF WORK : - Construction of Link road Ladwara Mundla Makroti road KM 0/00 to 3/800

SUB-HEAD : - C/O U-Shape drain at RD 1/750 to 1/769 and C.C. Pavement at Extended Portion 1/780 to 1/790.

Sr. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	18.40	350.00	Rupees Three Hundred Fifty Only	Per Cubic metre	6440.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arrise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etctera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royality, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	7.60	5380.00	Rupees Five Thousand Three Hundred Eighty Only	Per Cubic metre	40888.00
3	Providing laying spreading and compacting by manual means of stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven decimal point two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required densityas per M.O.R.D. technical specifications clause 405 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royality, GST, toll tax or other taxes imposed by the Government.	1.250	2150.00	Rupees Two Thousand One Hundred Fifty Only	Per Cubic metre	2688.00

1	2	3	4	5	6	7
4	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm(seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two milimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer–in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government	1.250	2250.00		Per Cubic metre	2813.00
5	roviding and laying cement concrete 1:1.5 :3 (One cement: one & Half Sand: three graded/crushed stone aggregate) 20mm (twenty millimeter nominal size) for plain / reinforcement concrete in super structure complete including cost of form work steel plate as per drawing and technical specification clause No 802, 804, 805,806, 807, 1202 &1204 including entire carriage of material with in all leads and lifts and other incidentals The rates are inclusive of octroi, royality malkana toll tax, sale tax or other taxes imposed by the Government	2.600	7150.00		Per Cubic metre	18590.00
6	Steel work welded in built up sections,trusses and framed work,including cutting ,hoisting ,fixing in position and applying a priming coat of red lead paint in beams joists channels ,angles , tee ,flats with connecting plates or angle cleats as in main and cross beams,hip and jack rafters,purlins connected to common rafters and the like.complete as per specification, approved drawing , design, as per the entire satsifaction and direction of the Engineer-in-charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royality, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	68.00	105.00	Rupees One Hundred Five Only	Per koligram	7140.00
					TOTAL :-	***78559.00***
	Quated Rate in Figure (%)	**(Amount to be quoted by the contractor in Figure)**				
	Quated Rate in Words (%)	**(Amount to be quoted by the contractor in words)**				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur.

SCHEDULE OF QUANTITY

26

ESTIMATED COST: - ₹ 99937.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT : Two Months

NAME OF WORK :- Construction of Veer Shriomani Maharana Partap Community Hall Lanjot Distt Kangra (H.P).

SUB-HEAD :- C/o Edge wall at RD 0/028 to 0/036.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	9.72	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	3402.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arrise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etctera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royality, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	16.30	5450.00	Rupees Five Thousand Four Hundred Fifty Only	Per cubic metre	88835.00
3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope I(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government.	22.00	350.00	Rupees Three Hundred Fifty Only	Each	7700.00
					TOTAL :-	99937.00
	Quated Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quated Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 98124.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : Two Months

NAME OF WORK :- Construction of Veer Shriomani Maharana Partap Community Hall Lanjot Distt Kangra (H.P).

SUB-HEAD :- C/o B/ wall at RD 0/013 to 0/016.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	7.20	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	2520.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty milimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government.	17.28	5050.00	Rupees Five Thousand Fifty Only	Per cubic metre	87254.00
3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope I(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in- charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government.	18.00	350.00	Rupees Three Hundred Fifty Only	Each	6300.00

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
4	Back filling with granular material behind abutments, wing walls, return walls and retaning walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royality, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	2.40	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	2040.00
				TOTAL :-		98124.00
	Quated Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quated Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD, Shahpur

SCHEDULE OF QUANTITY

30

ESTIMATED COST: - ₹ 99283.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT : Two Months

NAME OF WORK :- Construction of Veer Shriomani Maharana Partap Community Hall Lanjot Distt Kangra (H.P).

SUB-HEAD :- C/o Edge wall at RD 0/019 to 0/27.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	9.72	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	3402.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arrise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etctera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royality, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	16.18	5450.00	Rupees Five Thousand Four Hundred Fifty Only	Per cubic metre	88181.00
3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope I(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government.	22.00	350.00	Rupees Three Hundred Fifty Only	Each	7700.00
					TOTAL :-	99283.00
	Quated Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quated Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

ESTIMATED COST:- ₹ 99785.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : Two Months

NAME OF WORK :- Construction of Veer Shriomani Maharana Partap Community Hall Lanjot Distt Kangra (H.P).

SUB-HEAD :- C/o B/ wall at RD 0/017 to 0/020.50

S. No.	Description of items	Quantity	RATES in		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	1.22	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	427.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty milimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government.	19.44	5050.00	Rupees Five Thousand Fifty Only	Per cubic metre	98172.00
3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope I(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in- charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government.	3.00	350.00	Rupees Three Hundred Fifty Only	Each	1050.00

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
6	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1500 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	0.16	830.00	Rupees Eight Hundred Fifty Only	Per cubic metre	136.50
					TOTAL :-	99785.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY ~ 32

ESTIMATED COST: - ₹ 99389.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT :- One Months

NAME OF WORK : - A/R & M/O Link Road Har to Kuther Road km 0/00 to 1/500.

SUB-HEAD : - C/o Rain Shelter at Near Rajat Hotel at RD 0/015.(Excavation in Earth Work,P/L 1:4:8, R.R Masonry ,Stone Soiling ,Cement Flooring & Steel Work.)

Sr. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	9.50	350.00	Rupees Three Hundred Fifty Only	Per Cubic Metre	3325.00
2	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	0.60	1450.60	Rupees One Thousand Four Hundred Fifty And	Per Cubic Metre	870.00
3	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty milimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the	1.30	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per Cubic Metre	6175.00
4	Random rubble masonry/polygonal rubble masonry (uncoursed/brought to courses) with hard stone of approved quality in foundation and plinth including leveling up with cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 20mm (twenty) millimeter nominal size mechanical mixed in cement mortor 1:6 (one cement six sand) as per the entire satsifaction and direction of the Engineer-in-charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government.	8.99	5250.10	Rupees Five Thousand Two Hundred Fifty And Paise Ten Only	Per Cubic Metre	47198.00
5	Stonework in plain ashlar in super structure up to floor five level in cement mortar 1:6 (1cement : 6coarse sand) includingpointingwithcementmortar1:2(1white cement : 2stonedust)with an admixture of pigment matching the stone shade One face dressed as per the entire satsifaction and direction of the Engineer-in-charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government.	5.62	6600.00	Rupees Six Thousand Six Hundred Only	Per Cubic Metre	37092.00

1	2	3	4	5	6	7
6	Stone soling properly handpacked filling interstices with spalls and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labouras per the entire satsifaction and direction of the Engineer-in-charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government.	0.80	850.00	Rupees Eight Hundred Fifty Only	Per Cubic Metre	680.00
7	Cement concrete flooring1:2:4 (1 cement : 2 coarse sand:4gradedstoneaggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete.40mmthickwith20mm nominal sizes tone aggregate as per the entire satsifaction and direction of the Engineer-in-charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government.	9.80	252.40	Rupees Two Hundred Fifty Two And Paise Forty Only	Per square metre	2474.00
8	Steel work welded in built up sections,trusses and framed work,including cutting ,hoisting ,fixing in position and applying a priming coat of red lead paint in beams joists channels ,angles , tee ,flats with connecting plates or angle cleats as in main and cross beams,hip and jack rafters,purlins connected to common rafters and the like.complete as per specification, approved drawing , design, as per the entire satsifaction and direction of the Engineer-in-charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royality, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	15.00	105.00	Rupees One Hundred Five Only	Per Kilogram	1575.00
					TOTAL :-	***99389.00***
	Quated Rate in Figure (%)	**(Amount to be quoted by the contractor in Figure)**				
	Quated Rate in Words (%)	**(Amount to be quoted by the contractor in words)**				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur.

SCHEDULE OF QUANTITY

33

ESTIMATED COST: - ₹ 97973.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT : Two Months

NAME OF WORK :- Construction of Veer Shriomani Maharana Partap Community Hall Lanjot Distt Kangra (H.P).

SUB-HEAD :- C/o B/ wall at RD 0/09 to 0/12.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	7.20	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	2520.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty milimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government.	17.25	5050.00	Rupees Five Thousand Fifty Only	Per cubic metre	87113.00
3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope I(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in- charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government.	18.00	350.00	Rupees Three Hundred Fifty Only	Each	6300.00

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
4	Back filling with granular material behind abutments, wing walls, return walls and retaning walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royality, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	2.40	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	2040.00
					TOTAL :-	97973.00
	Quated Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)			
	Quated Rate in Words (%)		(Amount to be quoted by the contractor in words)			

Executive Engineer.
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 99960.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT :- One Month

NAME OF WORK : - Repair of Primary Health Centre at Lapiana Under Health Block Shahpur ,District Kangra)

SUB-HEAD : - P/F 6mm Thick Cement fiber Board Ceiling, Steel Work & Back Side Stair Roofing.

Sr. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and fixing 6 mm thick plain multipurpose cement fibre board with suitable screws for cement particle board in ceiling etc complete.within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	90.40	810.00	Rupees Eight Hundred Ten Only	Per square metre	73224.00
2	Steel work welded in built up sections of TATA/SAIL joists channels, angles, tees with connection plates or angles, cleat as in trusses, trussed purlins main and cross beams, hips jack rafters, purlins connected to common rafters and the like in building including cutting, fixing, lifting, hoisting and; placing in position complete and applying a coat of red lead paint, within all leads, lifts of materials and other incidentals. as per approved architectural drawing, design and specification as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	152.00	107.50	Rupees One Hundred Seven And Paise Fifty Only	Per Kilograme	16340.00
3	Providing and fixing 0.60mm (Zero decimal Six Zero milimetres) thick prepainted steel sheet ISI marked - Z 120 of Tata Durashine/ Sail / Reliance / Jindal steel in roofing with hot dipped metalic zinc coated sheet with top coat of regular modified polyster (RMP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating to back coat of polyster of 5 (five) microns over 5 (Five) microns primer fixing with prepainted iron J or L hooks,bolts and nuts with prepainted limpet and rubber washers complete with all accessories as required within all leads, lifts of materials and other. incidentals. as per approved architectural drawing, design and specification and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	6.30	1650.10	Rupees One Thousand Six Hundred Fifty And Paise Ten Only	Per square metre	10396.00
					TOTAL :-	*99960.00*
	Quated Rate in Figure (%)	***0***	**(Amount to be quoted by the contractor in Figure)**			
	Quated Rate in Words (%)	***0***	**(Amount to be quoted by the contractor in words)**			

Executive Engineer,
Shahpur Division,
HPPWD Shahpur.