

Himachal Pradesh
Public Works Department

No. PWH/HD/CB/T-I/2025-26
To

14431-33

Dated: 30/03/2026


The Executive Engineer (IT Cell)
Nirman Bhawan, Nigam Vihar,
Shimla-2

Subject: - Publication of Notice inviting tender.

Sir,


Enclosed please find herewith copy of notice inviting tender for publishing on departmental website for favour of further necessary action please.

Encl: As above


Executive Engineer,
HPPWD Division Haroli,
Distt. Una (HP).


Copy along with copy of notice inviting tender is forwarded for information and necessary action to:-

1. The Superintending Engineer, 15th Circle, HP: PWD, Una.
2. Copy to Notice board.


Executive Engineer,
HPPWD Division Haroli,
Distt. Una (HP).

Certificate

Certified that the tenders for the works called vide this office letter No. PWH/HD
1/2025-26-14431-33 dated 30/3/2026 are required to be carried out immediately being emergent nat
work in public interest.


Executive Engineer,
Haroli Division, HPPWD
Haroli, Distt.Una HP).

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
" NOTICE INVITING TENDERS "

Percentage rate tender on PWD Form No. 6 & 8 are hereby invited by the Executive Engineer, Haroli Division H.P. on behalf of Governor of H.P. for the following works from the approved and eligible contractors/firms enlisted PWD Department as per latest instructions, so as to reach and open in his office as per time schedule given below. The offer of the tender will be open for 45 days from the date of opening of tenders. The undersigned reserves the right to reject any of the tenders without assigning any reasons.

1. Date of receipt of application for the tender form a/w requisite documents: - 06/04/2026 up to 10.30 (AM).
2. Date of issue/sale of tender forms against cash payment(non-refundable): - 07/04/2026 up to 3.00 PM
3. Date of receipt of tenders: - 08/04/2026 up to 10.30 AM
4. Date of opening of tenders: - 08/04/2026 at 11.00 AM

Sr. No.	Name of work	Estimate d cost	EMD	Time Limit	Cost of tender	Eligible class of contractor
1	2	3	4	5	6	7
1	Balance work for the upgradation of link road Umralli Dhilwan Heeran Thara Pubowal to Polian via Kuthar Beet km. 0/00 to 3/400(SH:-P/L CC in berm at RD. 0/426 to 0/496 BHS)under OTMNP	97020	2000/-	One Month	350/-	Class- C & D
2	C/O Driving Training Track and Traffic Park at Rora, Haroli Distt. Una (SH:-P/F curve stones in campus area of traffic park Phase-VII)-Deposit Work (Balance work)	86700	2000/-	One Month	350/-	Class- C & D
3	Balance work for the upgradation of link road Umralli Dhilwan Heeran Thara Pubowal to Polian via Kuthar Beet km. 0/00 to 3/400(SH:-P/L CC in berm at RD. 0/354 to 0/426 BHS)under OTMNP	99792	2000/-	One Month	350/-	Class- C & D
4	C/O Heliport at Rora, Haroli Tehsil Haroli Distt. Una (SH:-Filling of earth)Deposit Work	99810	2000/-	One Month	350/-	Class- C & D
5	C/O Driving Training Track and Traffic Park at Rora, Haroli Distt. Una (SH:-Beautification & Grassing at Traffic Park- Phase-XVII)-Deposit Work (Balance work)	98190	2000/-	One Month	350/-	Class- C & D
6	Balance work for the upgradation of link road Umralli Dhilwan Heeran Thara Pubowal to Polian via Kuthar Beet km. 0/00 to 3/400(SH:-P/L CC in berm at RD. 0/213 to 0/283 BHS)under OTMNP	99715	2000/-	One Month	350/-	Class- C & D
7	C/O Driving Training Track and Traffic Park at Rora, Haroli Distt. Una (SH:-Beautification & Grassing at Traffic Park- Phase-XIX)-Deposit Work (Balance work)	98190	2000/-	One Month	350/-	Class- C & D
8	Balance work for the upgradation of link road Umralli Dhilwan Heeran Thara Pubowal to Polian via Kuthar Beet km. 0/00 to 3/400(SH:-P/L CC in berm at RD. 0/141 to 0/213 BHS)under OTMNP	99792	2000/-	One Month	350/-	Class- C & D
9	Construction of link road Check Khad to Khad Khas via Tanda Panihar km. 0/00 to 2/200(SH:-P/L CC Pavement, R/wall for widening junction RHS at RD. 1/230) (Under Deposit-SCCP)	99429	2000/-	One Month	350/-	Class- C & D
10	Balance work for the upgradation of link road Umralli Dhilwan Heeran Thara Pubowal to Polian via Kuthar Beet km. 0/00 to 3/400(SH:-P/L CC in berm at RD. 0/070 to 0/141 BHS)under OTMNP	98406	2000/-	One Month	350/-	Class- C & D
11	Construction of link road Check Khad to Khad Khas via Tanda Panihar km. 0/00 to 2/200(SH:-P/L CC Pavement, R/wall in RD. 1/226 to 1/230) (Under Deposit-SCCP)	99180	2000/-	One Month	350/-	Class- C & D
12	Balance work for the upgradation of link road Umralli Dhilwan Heeran Thara Pubowal to Polian via Kuthar Beet km. 0/00 to 3/400(SH:-P/L CC in berm at RD. 0/00 to 0/070 BHS)under OTMNP	97020	2000/-	One Month	350/-	Class- C & D
13	Restoration of rain damages on link road Jongpur Chowk to Govt. Senior Secondary School Gondpur Bulla km. 0/00 to 1/200(SH:-C/O Slab over Existing U-shape drain at RD. 0/084.70 to 0/118.20 RHS)	98440	2000/-	One Month	350/-	Class- C & D

14	C/O Driving Training Track and Traffic Park at Rora, Haroli Distt. Una (SH:-Beautification & Grassing at Traffic Park- Phase-XVI)-Deposit Work (Balance work)	99084	2000/-	One Month	350/-	Class- C & D
15	Construction of link road Check Khad to Khad Khas via Tanda Panihar km. 0/00 to 2/200(SH:-P/L CC Pavement, R/wall in RD. 1/210 to 1/226) (Under Deposit-SCCP)	99540	2000/-	One Month	350/-	Class- C & D
16	Restoration of rain damages on link road Jongpur Chowk to Govt. Senior Secondary School Gondpur Bulla km. 0/00 to 1/200(SH:-C/O U-shape drain at RD. 0/100 to 0/138.40 LHS)	99183	2000/-	One Month	350/-	Class- C & D
17	Construction of link road Check Khad to Khad Khas via Tanda Panihar km. 0/00 to 2/200(SH:-P/L 80 mm thick paver blocks, R/wall in RD. 0/381 to 0/389.50) (Under Deposit-SCCP)	99923	2000/-	One Month	350/-	Class- C & D
18	C/O Driving Training Track and Traffic Park at Rora, Haroli Distt. Una (SH:-Providing and installation of solar light)-Deposit Work	99950	2000/-	One Month	350/-	Class- C & D
19	Restoration of rain damages on link road Jongpur Chowk to Govt. Senior Secondary School Gondpur Bulla km. 0/00 to 1/200(SH:-C/O U-shape drain at RD. 0/138.40 to 0/177 LHS)	99700	2000/-	One month	350/-	Class- C & D
20	Restoration of rain damages on link road Jongpur Chowk to Govt. Senior Secondary School Gondpur Bulla km. 0/00 to 1/200(SH:-C/O U-shape drain at RD. 0/177 to 0/180 LHS & Slab over Existing U-Shape drain at Rd. 0/020 to 0/051 RHS)	98843	2000/-	One month	350/-	Class- C & D
21	C/O Driving Training Track and Traffic Park at Rora, Haroli Distt. Una (SH:-Beautification & Grassing at Traffic Park- Phase-XVIII)-Deposit Work (Balance work)	97297	2000/-	One Month	350/-	Class- C & D
22	Restoration of rain damages on link road Jongpur Chowk to Govt. Senior Secondary School Gondpur Bulla km. 0/00 to 1/200(SH:-C/O Slab over Existing U-Shape drain at Rd. 0/051 to 0/084.70 RHS)	99028	2000/-	One month	350/-	Class- C & D
23	Restoration of rain damages on link road Jongpur Chowk to Govt. Senior Secondary School Gondpur Bulla km. 0/00 to 1/200(SH:-CC Pavement at Rd. 0/046.50 to 0/073.10)	98753	2000/-	One month	350/-	Class- C & D
24	Restoration of rain damages on link road Jongpur Chowk to Govt. Senior Secondary School Gondpur Bulla km. 0/00 to 1/200(SH:-CC Pavement at Rd. 0/073.10 to 0/099.80)	99124	2000/-	One month	350/-	Class- C & D
25	C/O Driving Training Track and Traffic Park at Rora, Haroli Distt. Una (SH:-P/F ACP Sheet under porch)-Deposit Work (Balance work)	97800	2000/-	One Month	350/-	Class- C & D
26	Restoration of rain damages on link road Jongpur Chowk to Govt. Senior Secondary School Gondpur Bulla km. 0/00 to 1/200(SH:-CC Pavement at Rd. 0/099.8 to 0/126.60)	99495	2000/-	One Month	350/-	Class- C & D
27	Restoration of rain damages on link road Jongpur Chowk to Govt. Senior Secondary School Gondpur Bulla km. 0/00 to 1/200(SH:-CC Pavement at Rd. 0/126.60 to 0/153.10)	98381	2000/-	One Month	350/-	Class- C & D
28	Construction of link road Check Khad to Khad Khas via Tanda Panihar km. 0/00 to 2/200(SH:-P/L 80 mm thick paver blocks, R/wall in RD. 0/390 to 0/400) (Under Deposit-SCCP)	99987	2000/-	One Month	350/-	Class- C & D
29	Restoration of rain damages on link road Jongpur Chowk to Govt. Senior Secondary School Gondpur Bulla km. 0/00 to 1/200(SH:-CC Pavement at Rd. 0/153.10 to 0/180)	99866	2000/-	One Month	350/-	Class- C & D

30	A/R & M/O on Panjwar bathri road km. 0/00 to 34/00(SH:- Repair of berms at Various RDs from km. 0/00 to 4/500)	99528	2000/-	One Month	350/-	Class- C & D
31	Restoration of rain damages on Polian Janani road km. 0/00 to 6/00(SH:-P/L CC Pavement at RD. 1/210 to 1/229.30)	98747	2000/-	One Month	350/-	Class- C & D
32	A/R & M/O on Panjwar bathri road km. 0/00 to 34/00(SH:- Repair of berms at Various RDs from km. 4/500 to 9/00)	98670	2000/-	One Month	350/-	Class- C & D
33	Restoration of rain damages on Polian Janani road km. 0/00 to 6/00(SH:-P/L CC Pavement at RD. 0/825 to 0/844.50)	99770	2000/-	One Month	350/-	Class- C & D
34	A/R & M/O PWD Non-Residential Building at Haroli(SH:- Painting of Division & Sub-Division Office etc.) Phase-II	99181	2000/-	One Month	350/-	Class- C & D

The earnest money in the shape of National Saving certificate/ time deposit/ saving account of any post office or FDR, Nationalized bank duly pledged in the name of undersigned must be accompanied with each tender. The conditional tender and tender not accompanying the earnest money in the proper mode of deposit will summarily be rejected. The tender documents to be sent should have invariably be waxed in sealed cover and in failure of that those will not be entertained. The copy of valid enlistment, GST registration No., Income Tax, Pan No. and epf no. must be attached with application.

SPECIAL CONDITION: -

1. The contractor/firm shall have his resignation and GST No. and copy of same be attached with the application.
2. The earnest money for the above work should be submitted duly pledged in favour of Executive Engineer, Haroli Division HPPWD with the application for the purchase of tender forms. The application received without earnest money shall summarily be rejected.
3. The contractor/firms are required to insert the rate in words as well as figures, failing which Executive Engineer reserves the right to accept/rejects any or all tenders. If any of the date mentioned above happens to be local/gazetted holidays, the same shall be process on next date.
4. The tender form will be issued to those contractors who have relevant machinery and equipment, the list of which may be attached with their application a/w proof of ownership of machinery/legal tie up arrangement).
5. The Executive Engineer reserves the right to reject or cancel any or all tenders without assigning any reasons.
6. The conditional/ambiguous/telegraphic tenders by fax shall not entertained/considered in any case.

HIM SUCHANA AVAM JAN SAMPARK.

Executive Engineer
HPPWD Division Haroli
Distt.Una(HP).Pin Code-177220
Email: ee-harolli-hp@hp.gov.in
On behalf of Governor of Himachal Pradesh

SCHEDULE OF QUANTITY

Estimated cost 97020

Earnest money 2000

Time limit One month

Name of Work: Balance work for the upgradation of link road Umraill Dhillwan Heeran Thara Pubowal to Pollian via Kuthar Beet Km 0/00 to 3/400 (SH:- P/L CC in berm at RD 0/426 to 0/496- BHS) under OTMNP

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundations/ for all type structure complete of plain cement concrete nominal mix 1:3:6 (One cement three sand six graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST labour cess or other taxes imposed by the Government.	25.20	Per cubic metre	3850.00	Rupees Three thousand eight hundred fifty only	97020
					Total	97020

NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)A(3)17/20212 dated 7.8.2018

2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt. of HP vide letter No.PBW(B) A(3)11/2020-1 dated 7.10.2021

Percentage quoted rate in Figures

Percentage quoted rate in words

Note:- Rate quoted in figures & words are mandatory by the contractor , otherwise the tender will be rejected.


 Executive Engineer
 Haroli Division
 HP.PWD.,Haroli

2

Schedule of quantity

Name of work :- C/O Driving Training Track and Traffic Park at Rora, Haroli Distt. Una.						Estimated Cost: Rs	₹ 86,700
						Time:-	One month
(SH:Providing & fixing curve stonicee in campus area of traffic park Phase-VII) -Deposit work (Balance work)						Earnest Money:-	2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount	
1	Providing and fixing to curve stone 80mm thick size 0.30m x0.30m including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	510.00	Each	170.00	Rupees one hundred seventy only	86700	
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				Total	86700	
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021						
	Percentage quoted rate in figures						
	Percentage quoted rate in words						
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected						

Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H.P.)

SCHEDULE OF QUANTITY

Estimated cost 99792
 Earnest money 2000
 Time limit One month

Name of Work: Balance work for the upgradation of link road Umrail Dhilwan Heeran Thara Pubowal to Pollian via Kuthar Beet Km 0/00 to 3/400 (SH:- P/L CC in berm at RD 0/354 to 0/426- BHS) under OTMNP

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Providing and laying mechanically mixed and vibrated concrete for plans/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:3:6 (One cement :three sand:six graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under wateror ground complete including pumping or hauling out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	25.92	Per cubic metre	3850.00	Rupees Three thousand eight hundred fifty only.	99792
					Total	99792

NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)A(3)17/20212 dated 7.8.2018

2) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021

Percentage quoted rate in Figures

Percentage quoted rate in words

Note:- Rate quoted in figures & words are mandatory by the contractor , otherwise the tender will be rejected.


Executive Engineer
 Haroli Division
 HP.PWD.,Haroli

5

Schedule of quantity

Name of work :- C/O Driving Training Track and Traffic Park at Rora, Haroli Distt. Una.		Estimated Cost: Rs		₹ 98,190		
		Time:-		One month		
(SH:Beautification & Grassing at Traffic Park-phase-XVII)-Deposit work (Balance work)		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Trenching in ordinary soil up to a depth of 60 cm including removal and stacking of serviceable materials and then disposing of surplus soil, by spreading and neatly levelling within a lead of 50 m and making up the trenched area to proper levels by filling with earth or earth mixed with sludge or / and manure before and after flooding trench with water . including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	52.80	Cum	285.00	Rupees Two Hundred EightyFive Only	15048
2	Supplying and stacking of good earth at site including cost of sludge, manure & including royalty and carriage upto any lead complete. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	52.80	Cum	880.00	Rupees Eight Hundred Eighty Only	46464
3	Rough dressing the trenched ground including breaking clods.including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	88.00	Sqm	17.00	Rupees Seventeen Only	1496
4	Uprooting weeds from the trenched area after 10 to 15 days of its flooding with water including disposal of uprooted vegetation. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	88.00	Sqm	70.00	Rupees Seventy Only	6160
5	Fine dressing of the ground. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	88.00	Sqm	35.00	Rupees ThirtyFive Only	3080

6	Spreading of sludge, dump manure and/or good earth in required thickness as per direction of officer-in-charge (cost of sludge, dump manure and/ or good earth to be paid separately. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	8.80	Cum	145.00	Rupees One Hundred FourtyFive Only	1276
7	Grassing with selection No. 1 grass including watering and maintenance of the lawn for 30 days or more till the grass forms a thick lawn, free from weeds and fit for mowing including supplying good earth, if needed (the grass and good earth shall be paid for separately). In rows 5 cm apart in both directions.including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	88.00	Sqm	130.00	Rupees One Hundred Thirty Only	11440
8	Preparation of beds for hedging and shrubbery by excavating 60 cm deep and trenching the excavated base to a further depth of 30 cm, refilling the excavated earth after breaking clods and mixing with sludge or manure in the ratio of 8:1 (8 parts of stacked volume of earth after reduction by 20% : one part of stacked volume of sludge or manure after reduction by 8%), flooding with water, filling with earth if necessary, watering and finally fine dressing, leveling etc. including stacking and disposal of materials declared unserviceable and surplus earth by spreading and leveling as directed, within a lead of 50 m, lift up to 1.5 m complete (cost of sludge, manure or extra earth to be paid for separately). including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	79.20	Cum	167.00	Rupees One Hundred SixtySeven Only	13226
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				Total	98190
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					


Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H.P.)

SCHEDULE OF QUANTITY

Estimated cost 99715
 Earnest money 2000
 Time limit One month
 in berm at RD

Name of work: Balance work for the upgradation of link road Umrahi Dhillwan Heeran Thara Pubowal to Pollian via Kuthar Beet Km 0/00 to 3/400 (SH:- P/L CC

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:3:6 (One cement three sand/six graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under wateror ground complete including pumping or hauling out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	25.90	Per cubic metre	3850.00	Rupees Three thousand eight hundred fifty only	99715
				Total		99715
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)A(3)1/2020 dated 7.8.2018					
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy,PW to the Govt of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor , otherwise the tender will be rejected.					

Executive Engineer
 Haroli Division
 HP,PWD.,Haroli

785

7

Schedule of quantity

Name of work :- C/O Driving Training Track and Traffic Park at Rora, Haroli Distt. Una.						Estimated Cost: Rs	₹ 98,190
						Time:-	One month
(SH:Beautification & Grassing at Traffic Park-phase-XIX)-Deposit work (Balance work)						Earnest Money:-	2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount	
1	Trenching in ordinary soil up to a depth of 60 cm including removal and stacking of serviceable materials and then disposing of surplus soil, by spreading and neatly levelling within a lead of 50 m and making up the trenched area to proper levels by filling with earth or earth mixed with sludge or / and manure before and after flooding trench with water . including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	52.80	Cum	285.00	Rupees Two Hundred EightyFive Only	15048	
2	Supplying and stacking of good earth at site including cost of sludge, manure & including royalty and carriage upto any lead complete. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	52.80	Cum	880.00	Rupees Eight Hundred Eighty Only	46464	
3	Rough dressing the trenched ground including breaking clods.including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	88.00	Sqm	17.00	Rupees Seventeen Only	1496	
4	Uprooting weeds from the trenched area after 10 to 15 days of its flooding with water including disposal of uprooted vegetation. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	88.00	Sqm	70.00	Rupees Seventy Only	6160	
5	Fine dressing of the ground. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	88.00	Sqm	35.00	Rupees ThirtyFive Only	3080	

6	Spreading of sludge, dump manure and/or good earth in required thickness as per direction of officer-in-charge (cost of sludge, dump manure and/ or good earth to be paid separately, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	8.80	Cum	145.00	Rupees One Hundred FortyFive Only	1276
7	Grassing with selection No. 1 grass including watering and maintenance of the lawn for 30 days or more till the grass forms a thick lawn, free from weeds and fit for mowing including supplying good earth, if needed (the grass and good earth shall be paid for separately). In rows 5 cm apart in both directions.including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	88.00	Sqm	130.00	Rupees One Hundred Thirty Only	11440
8	Preparation of beds for hedging and shrubbery by excavating 60 cm deep and trenching the excavated base to a further depth of 30 cm, refilling the excavated earth after breaking clods and mixing with sludge or manure in the ratio of 8:1 (8 parts of stacked volume of earth after reduction by 20% : one part of stacked volume of sludge or manure after reduction by 8%), flooding with water, filling with earth if necessary, watering and finally fine dressing, leveling etc. including stacking and disposal of materials declared unserviceable and surplus earth by spreading and leveling as directed, within a lead of 50 m, lift up to 1.5 m complete (cost of sludge, manure or extra earth to be paid for separately). including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	79.20	Cum	167.00	Rupees One Hundred SixtySeven Only	13226
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				Total	98190
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					

Executive-Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

SCHEDULE OF QUANTITY

Estimated cost 99792
 Earnest money 2000
 Time limit One month

Name of Work: Balance work for the upgradation of link road Umralli Dhiwan Heeran Thara Pubowal to Polian via Kuthar Beet Km 0/00 to 3/400 (SH:- P/L CC in berm at RD 0/141 to 0/213- BHS) under OTMNP

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundations/ for all type structure complete of plain cement concrete nominal mix 1:3:6 (One cement three sand:six graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803,1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental The rate includes sale tax octroi, royalty,matkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.,	25.92	Per cubic metre	3850.00	Rupees Three thousand eight hundred fifty only.	99792
					Total	99792
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)2(17)20212 dated 7.8.2018					
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy,PW to the Govt of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor , otherwise the tender will be rejected.					

Executive Engineer
 Haroli Division
 HP,PWD.,Haroli

786

Schedule of quantity

Name of work :-Construction of link road Check Khad to Khad Khas via Tanda Panihar km. 0/00 to 2/200)		Estimated Cost: Rs		₹ 99,429		
(SH: P/L CC Pavement , R/wall for widening junction RHS at RD 1/230) (Under Deposit-SCCP)		Time:-		One month		
DESCRIPTION		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana,toll tax,GST,labour cess or other taxes imposed by the Government..	7.34	Cum.	170.00	Rupees One Hundred Seventy Only.	1248.00
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,1202 & 1203.P.C.C. grade Nominal Mix 1 : 6 : 12 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkhana, toll tax , sale tax or other taxes imposed by the Government.	1.80	Cum.	2800.00	Rupees Two Thousand Eight Hundred Only.	5040.00
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,1202 & 1203.P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkhana, toll tax , sale tax or other taxes imposed by the Government.	18.51	Cum.	3300.00	Rupees Three Thousand Three Hundred Only.	61083.00
4	Providing and laying 900 mm dia RCC Non Pressure NP-3 class(Medium duty) R.C.C. pipes including collars/spigot jointed with stiff mixture of cement mortar in the proportion of 1:2(1 cement : 2 fine sand) including testing of joints etc. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	2.50	Cum.	4000.00	Rupees Four Thousand Only.	10000.00
5	Providing and laying reinforcement concrete work of grade M-25(M-twenty five)design mix to obtain the minimum crushing strength of 25 N/mm2 (twenty five Newton per millimeter square) with minimum cement content of 400 kg (Four hundred kilogramme) per cubic meter mechanically mixed and vibrated including curing complete including cost of form work and reinforced concrete work in suspended floors, roofs, landing and shelves and their supports balconies beams,girders, brussesmers and cantilevers upto all floor level/height including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkhana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	1.80	Cum.	5500.00	Rupees Five Thousand Five Hundred Only.	9900.00
6	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe (D-plast/Finolux having working pressure 4.00kg/cm2 extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty Horizontal) towards drawing face complete as per drawings and technical specification MORD 2014 clause 614,709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	6.00	Cum.	170.00	Rupees One Hundred Seventy Only.	1020.00

7	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specifications clause 1204.3.8 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	20.25	Cum.	550.00	Rupees Five Hundred Fifty Only.	11138.00
	Total					99429
	Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandantrly by the contractor, otherwise the tender will be rejected.					

Executive Engineer,
H.P.P.W.D. Division Haridwar,
Distt. Una (H.P.)

SCHEDULE OF QUANTITY

Estimated cost 98406
 Earnest money 2000
 Time limit One month
 Name of Work: Balance work for the upgradation of link road Umralli Dhiliwan Heeran Thara Pubowal to Polian via Kuthar Beet Km 0/00 to 3/400 (SH:- P/L CC in berm at RD

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:3:6 (One cement :three sand:six graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental*The rate includes sale tax octroi, royalty,malkhana ,oil tax,GST,labour cess or other taxes imposed by the Government..	25.56	Per cubic metre	3850.00	Rupees Three thousand eight hundred fifty only.	98406
					Total	98406
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)A(3)1/2020 dated 7.8.2018					
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy,PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor , otherwise the tender will be rejected.					

Executive Engineer
 Haroli Division
 HP.PWD.,Haroli

787

Schedule of quantity

Name of work :-Construction of link road Check Khad to Khad Khas via Tanda Panihar km. 0/00 to 2/200

(SH: P/L CC Pavement , R/wall in RD 1/226 to 1/230) (Under Deposit-SCCP)

		Estimated Cost: Rs		One month		
		Time:-		2000		
		Earnest Money:-		Amount		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material, including carriage of materials within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	12.60	Cum.	170.00	Rupees One Hundred Seventy Only.	2142.00
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203.P.C.C. grade Nominal Mix 1 : 6 : 12 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	6.30	Cum.	2800.00	Rupees Two Thousand Eight Hundred Only.	17640.00
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203.P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	13.56	Cum.	3300.00	Rupees Three Thousand Three Hundred Only.	44748.00
4	Providing and laying reinforcement cement concrete work of grade M-25 (M-twenty five) design mix to obtain the minimum crushing strength of 25 N/mm ² (twenty five Newton per millimeter square) with minimum cement content of 400 kg (Four hundred kilogramme) per cubic meter mechanically mixed and vibrated including curing complete including cost of form work and reinforced concrete work in suspended floors, roofs, landing and shelves and their supports balconies beams, girders, bressumers and cantilevers upto all floor level/height including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	6.30	Cum.	5500.00	Rupees Five Thousand Five Hundred Only.	34650.00
	Total					99180
Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandantry by the contractor, otherwise the tender will be rejected.						

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.R.)

SCHEDULE OF QUANTITY

Estimated cost 97020
 Earnest money 2000
 Time limit One month

12

Name of Work: Balance work for the upgradation of link road Umrahi Dhillwan Heeran Thara Pubowal to Polian via Kuthar Beet Km 0/00 to 3/400 (SH:- P/L CC in berm at RD 0/00 to 0/070- BHS) under OTMNP

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal max 1:3:6 (One cement ,three sand six, graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under wateror ground complete including pumping or hauling out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	25.20	Per cubic metre	3850.00	Ruppes Three thousand eight hundred fifty only	97020
					Total	97020

NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)(E)17/20212 dated 7.8.2018

2) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021

Percentage quoted rate in Figures

Percentage quoted rate in words

Note:- Rate quoted in figures & words are mandatory by the contractor , otherwise the tender will be rejected.

Executive Engineer
 Haroli Division
 HP.PWD.,Haroli

RZ

13

Schedule of quantity

Name of work :- Restoration of rain damages on link road Jongpur Chowk to Govt Senior Secondary School Gondpur Bulla Km 0/00 to 1/20 (SH: C/O Slab over Existing U-shape drain at Rd. 0/084.70 to 0/118.20 Rhs).						Estimated Cost: Rs	One month
						Time:-	
						Earnest Money:-	2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount	
1	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C grade M 25(1)nominal mix 1:1.5:3. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	7.54	CUM.	5500.00	Rupees Five Thousand Five Hundred Only	41456	
2	Supplying, fitting and placing TMT bar reinforcement in foundation complete as per drawings and technical specifications Clauses 1000 and 1202. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	633.15	Kg.	90.00	Rupees Ninety Only	56984	
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) (17) 2/02012 dated 07.08.2018				Total	98440	
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021						
	Percentage quoted rate in figures						
	Percentage quoted rate in words						
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected						

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

14

Schedule of quantity

Name of work :- C/O Driving Training Track and Traffic Park at Rora, Haroli Distt. Una.		Estimated Cost: Rs		₹ 99,084		
		Time:-		One month		
(SH:Beautification & Grassing at Traffic Park-phase-XVI)-Deposit work (Balance work)		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Trenching in ordinary soil up to a depth of 60 cm including removal and stacking of serviceable materials and then disposing of surplus soil, by spreading and neatly levelling within a lead of 50 m and making up the trenched area to proper level-by filling with earth or earth mixed with sludge or / and manure before and after flooding trench with water . including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	53.28	Cum	285.00	Rupees Two Hundred EightyFive Only	15185
2	Supplying and stacking of good earth at site including cost of sludge, manure & including royalty and carriage upto any lead complete. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	53.28	Cum	880.00	Rupees Eight Hundred Eighty Only	46886
3	Rough dressing the trenched ground including breaking clods.including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	88.80	Sqm	17.00	Rupees Seventeen Only	1510
4	Uprooting weeds from the trenched area after 10 to 15 days of its flooding with water including disposal of uprooted vegetation. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	88.80	Sqm	70.00	Rupees Seventy Only	6216
5	Fine dressing of the ground. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	88.80	Sqm	35.00	Rupees ThirtyFive Only	3108

6	Spreading of sludge, dump manure and/or good earth in required thickness as per direction of officer-in-charge (cost of sludge, dump manure and/ or good earth to be paid separately, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.88	Cum	145.00	Rupees One Hundred FortyFive Only	1288
7	Grassing with selection No. 1 grass including watering and maintenance of the lawn for 30 days or more till the grass forms a thick lawn, free from weeds and fit for mowing including supplying good earth, if needed (the grass and good earth shall be paid for separately). In rows 5 cm apart in both directions, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	88.80	Sqm	130.00	Rupees One Hundred Thirty Only	11544
8	Preparation of beds for hedging and shrubbery by excavating 60 cm deep and trenching the excavated base to a further depth of 30 cm, refilling the excavated earth after breaking clods and mixing with sludge or manure in the ratio of 8:1 (8 parts of stacked volume of earth after reduction by 20% : one part of stacked volume of sludge or manure after reduction by 8%), flooding with water, filling with earth if necessary, watering and finally fine dressing, leveling etc. including stacking and disposal of materials declared unserviceable and surplus earth by spreading and leveling as directed, within a lead of 50 m, lift up to 1.5 m complete (cost of sludge, manure or extra earth to be paid for separately). including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	79.92	Cum	167.00	Rupees One Hundred SixtySeven Only	13347
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				Total	99084
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					


Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

Name of work :-Construction of link road Check Khad to Khad Khas via Tanda Panihar km. 0/00 to 2/200

Schedule of quantity

(SH-P/L CC Pavement in RD 1/210 to 1/226)
(Under Deposit-SCCP)


		Estimated Cost: Rs		Time:-		
				One month		
				2000		
				Amount		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,1202 & 1203.P.C.C. grade Nominal Mix 1 : 6 : 12 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	9.48	Cum.	2800.00	Rupees Two Thousand Eight Hundred Only.	26544.00
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,1202 & 1203.P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	6.32	Cum.	3300.00	Rupees Three Thousand Three Hundred Only.	20856.00
3	Providing and laying reinforcement cement concrete work of grade M-25(M-twenty five)design mix to obtain the minimum crushing strength of 25 N/mm ² (twenty five Newton per millimeter square) with minimum cement content of 400 kg (Four hundred kilogramme) per cubic meter mechanically mixed and vibrated including curing complete including cost of form work and reinforced concrete work in suspended floors, roofs, landing and shelves and their supports balconies beams,girders, bressumers and cantilevers upto all floor level/height including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana, toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	9.48	Cum.	5500.00	Rupees Five Thousand Five Hundred Only.	52140.00
	Total					99540
Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandantary by the contractor, otherwise the tender will be rejected.						

Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H.P.)

Schedule of quantity

16

Name of work :- Restoration of rain damages on link road Jongpur Chowk to Govt Senior Secondary School Gondpur Bulla Km 0/00 to 1/200 (SH: C/O U-Shape Drain at RD. 0/100 to 0/138.40 Lhs).		Estimated Cost: Rs		₹ 99,183		
		Time:-		One month		
		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material. including entire carriage of material within all leads and lifts and other incidentals* and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	32.26	CUM.	160.00	(Rupees two hundred fifty only)	5161
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 4 : 8. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	4.61	CUM.	3400.00	(Rupees One hundred sixty only)	15667
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 3 : 6. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	20.35	CUM.	3850.00	(Rupees Three thousand nine hundred only)	78355
					Total	99183
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018					
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note - Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					


 Executive Engineer,
 H.P.W.D. Division Haroli
 Distt. Una (H.P.)


793

17

Schedule of quantity

Name of work :-Construction of link road Check Khad to Khad Khas via Tanda Panihar km. 0/00 to 2/200)		Estimated Cost: Rs		₹ 99,923		
(SH: P/L 80 mm thick paver blocks,R/walls in RD 0/381 to 0/389.50) (Under Deposit-SCCP)		Time:-		One month		
DESCRIPTION		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	11.57	Cum	170.00	Rupees One Hundred Seventy Only.	1967.00
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,1202 & 1203.P.C.C. grade Nominal Mix 1 : 6 : 12 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	3.19	Cum	2800.00	Rupees Two Thousand Eight Hundred Only.	8932.00
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,1202 & 1203.P.C.C. grade Nominal Mix 1 : 4 : 8 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	13.38	Cum	3300.00	Rupees Three Thousand Three Hundred Only.	44154.00
4	Providing and Laying of Interlocking Concrete Block Pavements having thickness 80 mm as per drawings and Technical Specification Clause 1504. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	43.35	Sqm	900.00	Rupees Nine Hundred Only.	39015.00
5	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,804,1202 & 1203 P.C.C. grade M 20 Nominal Mix 1 : 2 : 4 in foundation and plinth. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	0.51	Cum	4500.00	Rupees Four Thousand Five Hundred Only.	2295.00

6	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe (D-plast/Finolex having working pressure 4.00kg.per cm2 extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty Horizontal) towards drawing face complete as per drawings and technical specification MORD 2014 clause 6.14,709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	8.00	Each	170.00	Rupees One Hundred Seventy Only.	1360.00
7	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specifications clause 1.204.3.8 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	4.00	Cum	550.00	Rupees Five Hundred Fifty Only.	2200.00
	Total					99923
	Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandanthy by the contractor, otherwise the tender will be rejected.					



Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H.P.)

18

SCHEDULE OF QUANTITY

Estimated Cost 99950
Earnest Money 2000/-
Time limit One month

Name of work:- C/O Driving Training Track and Traffic Park at Rora, Haroli Distt. Una. (SH:- Providing and installation of solar light)- Deposit work

S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Providing and installation of SPV Street Lighting Systems for 25 watt LED Luminary, with 75 WP, RFID Type Module, 12.08 Volt, 30 Ah minimum, Lithium Ferro Phosphate Battery, Pole -6 Metre complete in all respect as per MNRE specification with installations, commissioning and inclusive all charges with 3 year guarantee of light and 25 year warranty of panel. The rates are inclusive octroi, royalty, maikana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government	5.00	each	19990.00	Rupees nineteen thousand nine hundred ninety only	99950
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@ (17)2/0212 dated 7.8.2018				Total	99950
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					

M

Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H.P.)

719

Schedule of quantity

Name of work :- Restoration of rain damages on link road Jongpur Chowk to Govt Senior Secondary School Gondpur Bulla Km 0/00 to 1/20 (SH: C/O U-Shape Drain at RD. 0/138.40 to 0/177 Lhs).		Estimated Cost: Rs		₹ 99,700		
		Time:-		One month		
		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material. including entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	32.42	CUM.	160.00	(Rupees two hundred fifty only)	5188
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203, P.C.C. grade M 10 Nominal Mix 1 : 4 : 8. including entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	4.63	CUM.	3400.00	THREE (Rupees One hundred sixty only THOUSAND ONLY	15749
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 3 : 6. including entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	20.46	CUM.	3850.00	(Rupees Three thousand eight hundred only)	78763
					Total	99700
Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018						
2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021						
Percentage quoted rate in figures						
Percentage quoted rate in words						
Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected						

Schedule of quantity

Name of work :- Restoration of rain damages on link road Jongpur Chowk to Govt Senior Secondary School Gondpur Bulla Km 0/00 to 1/20		Estimated Cost: Rs	₹ 98,843			
		Time:-	One month			
(SH: C/O U-Shape Drain at RD. 0/177 to 0/180 Lhs & Slab over Existing U-shape drain at rd. 0/020 to 0/051 Rhs).		Earnest Money:-	2000			
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material. Including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	2.52	CUM.	160.00	Rupees One Hundred Sixty Only	403
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203, P.C.C. grade M 10 Nominal Mix 1 : 4 : 8. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	0.36	CUM.	3400.00	Rupees Three Thousand Four Hundred Only	1224
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 3 : 6. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	1.59	CUM.	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	6122
4	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C grade M 25(nominal mix 1:1.5:3. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	6.98	CUM.	5500.00	Rupees Five Thousand Five Hundred Only	38363
5	Supplying, fitting and placing TMT bar reinforcement in foundation complete as per drawings and technical specifications Clauses 1000 and 1202. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	585.90	Kg.	90.00	Rupees Ninety Only	52731

20

	<p>Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) Z/02012 dated 07.08.2018</p> <p>2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021</p> <p>Percentage quoted rate in figures</p> <p>Percentage quoted rate in words</p> <p>Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected</p>		98843
		Total	


 Executive Engineer,
 H.P.P.W.D. Division Haroli
 Distt. Una (H.P.)

21

Schedule of quantity

Name of work :- C/O Driving Training Track and Traffic Park at Rora, Haroli Distt. Una.		Estimated Cost: Rs		₹ 97,297		
		Time:-		One month		
(SH: Beautification & Grassing at Traffic Park-phase-XVIII)-Deposit work (Balance work)		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Trenching in ordinary soil up to a depth of 60 cm including removal and stacking of serviceable materials and then disposing of surplus soil, by spreading and neatly levelling within a lead of 50 m and making up the trenched area to proper levels by filling with earth or earth mixed with sludge or / and manure before and after flooding trench with water , including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	52.32	Cum	285.00	Rupees Two Hundred EightyFive Only	14911
2	Supplying and stacking of good earth at site including cost of sludge, manure & including royalty and carriage upto any lead complete. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	52.32	Cum	880.00	Rupees Eight Hundred Eighty Only	46042
3	Rough dressing the trenched ground including breaking clods, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	87.20	Sqm	17.00	Rupees Seventeen Only	1482
4	Uprooting weeds from the trenched area after 10 to 15 days of its flooding with water including disposal of uprooted vegetation. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	87.20	Sqm	70.00	Rupees Seventy Only	6104
5	Fine dressing of the ground. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	87.20	Sqm	35.00	Rupees ThirtyFive Only	3052

6	Spreading of sludge, dump manure and/or good earth in required thickness as per direction of officer-in-charge (cost of sludge, dump manure and/ or good earth to be paid separately, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.72	Cum	145.00	Rupees One Hundred FortyFive Only	1264
7	Grassing with selection No. 1 grass including watering and maintenance of the lawn for 30 days or more till the grass forms a thick lawn, free from weeds and fit for mowing including supplying good earth, if needed (the grass and good earth shall be paid for separately). In rows 5 cm apart in both directions.including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	87.20	Sqm	130.00	Rupees One Hundred Thirty Only	11336
8	Preparation of beds for hedging and shrubbery by excavating 60 cm deep and trenching the excavated base to a further depth of 30 cm, refilling the excavated earth after breaking clods and mixing with sludge or manure in the ratio of 8:1 (8 parts of stacked volume of earth after reduction by 20% : one part of stacked volume of sludge or manure after reduction by 8%), flooding with water, filling with earth if necessary, watering and finally fine dressing, leveling etc. including stacking and disposal of materials declared unserviceable and surplus earth by spreading and leveling as directed, within a lead of 50 m, lift up to 1.5 m complete (cost of sludge, manure or extra earth to be paid for separately), including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	78.48	Cum	167.00	Rupees One Hundred SixtySeven Only	13106
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				Total	97297
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					



Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H.P.)

Schedule of quantity

Name of work :- Restoration of rain damages on link road Jongpur Chowk to Govt Senior Secondary School Gondpur Bulla Km 0/00 to 1/20 (SH: C/O Slab over Existing U-shape drain at Rd. 0/051 to 0/084.70 Rhs).		Estimated Cost: Rs		₹ 99,028		
		Time:-		One month		
		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C grade M 25(i) nominal mix 1:1.5:3, including entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	7.58	CUM.	5500.00	Rupees Five Thousand Five Hundred Only	41704
2	Supplying, fitting and placing TMT bar reinforcement in foundation complete as per drawings and technical specifications Clauses 1000 and 1202, including entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	636.93	Kg.	90.00	Rupees Ninety Only	57324
					Total	99028
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018					
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)(A)(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)(A)(3)1/2020-1 Dated 07.10.2021.					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					


 Executive Engineer,
 H.P.W.D. Division Haroli
 Distt. Una (H.P.K)

23

Schedule of quantity

Name of work :- Restoration of rain damages on link road Jongpur Chowk to Govt Senior Secondary School Gondpur Bulla Km 0/00 to 1/20		Estimated Cost: Rs		₹ 98,753		
(SH: C/O CC Pavement at Rd. 0/046.50 to 0/073.10).		Time:-		One month		
		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C grade M 25(i) nominal mix 1:1.5:3. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	17.96	CUM.	5500.00	Rupees Five Thousand Five Hundred Only	98753
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018				Total	98753
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					


 Executive Engineer,
 H.P.W.D. Division Haroli
 Distt. Una (H.P.)

Schedule of quantity

24

Name of work :- Restoration of rain damages on link road Jongpur Chowk to Govt Senior Secondary School Gondpur Bulla Km 0/00 to 1/20		Estimated Cost: Rs		₹ 99,124		
(SH: C/O CC Pavement at Rd. 0/073.10 to 0/099.80).		Time:-		One month		
		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C grade M 25 (nominal mix 1:1.5:3. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	18.02	CUM.	5500.00	Rupees Five Thousand Five Hundred Only	99124
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				Total	99124
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					


 Executive Engineer,
 H.P.P.W.D. Division Haroli
 Distt. Una (H.P.)

776

25

Schedule of quantity

Name of work :- C/O Driving Training Track and Traffic Park at Rora, Haroli Distt. Una.		Estimated Cost: Rs		₹ 97,800		
		Time:-		One month		
(SH: P/F ACP Sheet under porch) -Deposit work (Balance work)		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Providing, fabricating and supplying and fixing panels of aluminium composite panel cladding in pan shape in metallic colour of approved shades made out of 4mm thick aluminium composite panel material consisting of 3mm thick FR grade mineral core sandwiched between two Aluminium sheets (each 0.5mm thick). The aluminium composite panel cladding sheet shall be coil coated, with Kynar 500 based PVDF / Lumiflon based fluoropolymer resin coating of approved colour and shade on face # 1 and polymer (Service) coating on face # 2 as specified using stainless steel screws, nuts, bolts, washers, cleats, weather silicone sealant, backer rods etc. , including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	21.34	Sqm	4582.00	Rupees Four Thousand Five Hundred Eighty Two Only	97800
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				Total	97800
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(31)/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					


 Executive Engineer,
 H.P.W.D. Division Haroli
 Distt. Una (H.P.)

Schedule of quantity

Name of work :- Restoration of rain damages on link road Jongpur Chowk to Govt Senior Secondary School Gondpur Bulla Km 0/00 to 1/20						Estimated Cost: Rs	₹ 99,495
(SH: C/O C/Pavement at Rd. 0/099.8 to 0/126.60).						Time:-	One month
EARNST MONEY:-						Earnest Money:-	2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount	Amount
1	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C grade M 25(nominal mix 1:1.5:3. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government.	18.09	CUM.	5500.00	Rupees Five Thousand Five Hundred Only	99495	99495
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018				Total	99495	99495
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021						
	Percentage quoted rate in figures						
	Percentage quoted rate in words						
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected						


 Executive Engineer,
 H.P.P.W.D. Division Haroli
 Distt. Una (H.P.)

Schedule of quantity

27

Name of work :- Restoration of rain damages on link road Jongpur Chowk to Govt Senior Secondary School Gondpur Bulla Km 0/00 to 1/20 (SH: C/O CC Pavement at Rd. 0/126.60 to 0/153.10).		Estimated Cost: Rs		₹ 98,381		
		Time:-		One month		
		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C grade M 25(i) nominal mix 1:1.5:3, including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	17.89	CUM.	5500.00	Rupees Five Thousand Five Hundred Only	98381
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				Total	98381
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note - Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					


 Executive Engineer,
 H.P.W.D. Division Haroli
 Distt. Una (H.P.)

774

28

Schedule of quantity

Name of work :-Construction of link road Check Khad to Khad Khas via Tanda Panihar km. 0/00 to 2/200)		Estimated Cost: Rs		₹ 99,987		
(SH: P/L 80 mm thick paver blocks./walls in RD 0/390 to 0/400) (Under Deposit-SCCP)		Time:-		One month		
		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	10.55	Cum	170.00	Rupees One Hundred Seventy Only.	1794.00
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,1202 & 1203.P.C.C.grade Nominal Mix 1 : 6 : 12 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	3.75	Cum	2800.00	Rupees Two Thousand Eight Hundred Only.	10500.00
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,1202 & 1203.P.C.C.grade Nominal Mix 1 : 4 : 8 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	11.30	Cum	3300.00	Rupees Three Thousand Three Hundred Only.	37290.00
4	Providing and Laying of Interlocking Concrete Block Pavements having thickness 80 mm as per drawings and Technical Specification Clause 1504. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	51.00	Sqm	900.00	Rupees Nine Hundred Only.	45900.00
5	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,804,1202 & 1203 P.C.C.grade M 20 Nominal Mix 1 : 2 : 4 in foundation and plinth. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	0.60	Cum	4500.00	Rupees Four Thousand Five Hundred Only.	2700.00

6	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe (D-plast/Finolex having working pressure 4.00kg.per cm2 extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty Horizontal) towards drawing face complete as per drawings and technical specification MORD 2014 clause 614.709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax,octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	3.00	Each	170.00	Rupees One Hundred Seventy Only.	510.00
7	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specifications clause 1204.3.8 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax, octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	2.35	Cum	550.00	Rupees Five Hundred Fifty Only.	1293.00
Total						99987
Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandantary by the contractor, otherwise the tender will be rejected.						


 Executive Engineer,
 H.P.P.W.D. Division Harohi
 Distt. Una (H.P.)

Schedule of quantity

Name of work :- Restoration of rain damages on link road Jongpur Chowk to Govt Senior Secondary School Gondpur Bulla Km 0/00 to 1/20 (SH: C/O CC Pavement at Rd. 0/153.10 to 0/180).		Estimated Cost: Rs	₹ 99,866			
		Time:-	One month			
		Earnest Money:-	2000			
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C grade M 25(1)nominal mix 1:1.5:3, including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	18.16	CUM.	5500.00	Rupees Five Thousand Five Hundred Only	99866
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				Total	99866
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					


Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H.P.)

30

Schedule of quantity

Name of work: - A/R & M/O on Panjawar Bathri road km 0/00 to 34/00							Estimated Cost: Rs	₹ 99,528
(SH: Repair of Berms at Various RDs from km .0/00 to 4/500)							Time:-	One month
							Earnest Money:-	2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount		
1	Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per technical specification Clause 1903. The rate is including of octroi, royalty, GST, Malkana, toll tax , sale tax or other taxes imposed by the Government.	1809.60	Sqm	55.00	Rupees FiftyFive Only	99528		
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17)2/0212 dated 7.8.2018				Total:	99528		
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20							
	Percentage quoted rate in Figures							
	Percentage quoted rate in words							
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.							

Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H.P.)

31

Schedule of quantity

Name of work :-Restoration of rain damages on Pollan Janani road km. 0/00 to 5/00. (SH: P/L-CC Pavement at Rd. 1/210 to 1/229.30)		Estimated Cost: Rs		Time:-		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Earnest Money:- Rate in words	One month 2000 Amount
1	Loosening of the ground upto a level of 300 mm below the subgrade level, watered, graded and compacted in layers to meet requirement of Tables 300.1 and 300.2 for subgrade construction as per Technical Specification Clause 303.5.2., including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	23.16	Cum.	47.00	Rupees FortySeven Only	1089.00
2	Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401, including carriage of materials within all leads and lifts, and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	7.72	cum	1100.00	Rupees One Thousand One Hundred Only	8492.00
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,1202 & 1203.P.C.C, grade M 10 Nominal Mix 1 : 4 : 8 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkhana, toll tax, sale tax or other taxes imposed by the Government.	7.72	cum	3300.00	Rupees Three Thousand Three Hundred Only	25476.00
4	Providing & laying mechanically mixed and vibrated concrete for Plain/reinforced concrete in open foundations of cement concrete complete of Plain/reinforced concrete grade M-25 as per drawings and technical specification clause 802,803,1202 & 1203. M 25 Nominal Mix 1 : 1.5:3, and as per Direction of Engineer -in -charge, including carriage of material within all leads, including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	11.58	Cum.	900.00	Rupees Nine Hundred Only	10422.00
<p>Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) (17) 2/02012 dated 07.08.2018</p> <p>2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter no. PBW (B)A(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(31)/2020-1 Dated 07.10.2021</p>						
Percentage quoted rate in figures						
Percentage quoted rate in words						
Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected						
Total						45479

Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H/P)

32

Schedule of quantity

Name of work: - A/R & M/O on Panjavar Bathri road km 0/00 to 34/00		Estimated Cost: Rs		₹ 98,670		
(SH: Repair of Berms at Various RDs from km 4/500 to 9/00)		Time:-		One month		
		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per technical specification Clause 1903. The rate is including of octroi, royalty, GST, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1794.00	Sqm	55.00	Rupees FiftyFive Only	98670
					Total:	98670
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@1712/0212 dated 7.8.2018					
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					


Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

Schedule of quantity

Name of work :- Restoration of rain damages on Pollan Janani road km. 0/00 to 6/00.

[SH: P/L CC Pavement at Rd. 0/825 to 0/844.50]

33

		Estimated Cost: Rs		Time:-		One month	
		₹ 99,770		2000			
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount	
1	Loosening of the ground upto a level of 300 mm below the subgrade level, watered, graded and compacted in layers to meet requirement of Tables 300.1 and 300.2 for subgrade construction as per Technical Specification Clause 303.5.2., including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	23.40	Cum.	47.00	Rupees FourtySeven Only	1100.00	
2	Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401. Including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	7.80	cum	1100.00	Rupees One Thousand One Hundred Only	8580.00	
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malikhana, toll tax, sale tax or other taxes imposed by the Government.	7.80	cum	3300.00	Rupees Three Thousand Three Hundred Only	25740.00	
4	Providing & laying mechanically mixed and vibrated concrete for Plain/reinforced concrete in open foundations of cement concrete complete of Plain/reinforced concrete grade M-25 as per drawings and technical specification clause 802, 803, 1202 & 1203 M 25 Nominal Mix 1 : 1.5:3. and as per Direction of Engineer-in-charge including carriage of material within all leads, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	11.70	Cum.	5500.00	Rupees Five Thousand Five Hundred Only	64350.00	
Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW (B) @ (17) 2/022012 dated 07.08.2018							
2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter no. PBW (B)(A)(3)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)(A)(3)/2020-1 Dated 07.10.2021							
Percentage quoted rate in figures							
Percentage quoted rate in words							
Total						99770	
Note - Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected							


 Executive Engineer,
 H.P.P.W.D. Division Haroli
 Distt. Una (H.P.)

34

Schedule of quantity

Name of work :-A/R & M/O PWD Non residential building at Haroli.		Estimated Cost: Rs		One month		
[Sub Head -Painting of Division & Sub Division Office etc.] Phase-I]		Time-		2000		
S.NO	DESCRIPTION	Qty	Unit	T Rate	Earnest Money:- Rate in words	Amount
1	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour two coat, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	235.69	sqm	75.00	Rupees SeventyFive Only	17677
2	With ready mixed pink or Grey primer of approved brand and manufacture on wood work (hard and soft wood). The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	200.8566	sqm	40.00	Rupees Fourty Only	8034
3	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 hr/10 sqm over an under coat of primer applied @0.75 hr/10 sqm of approved brand and manufacture. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	200.8566	sqm	85.00	Rupees EightyFive Only	17073
4	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 hr/ 10 sqm over an under coat of primer applied @ 0.80 hr/ 10 sqm of approved brand and manufacture including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	200.8566	sqm	85.00	Rupees EightyFive Only	17073
5	Finishing walls with Acrylic Smooth exterior paint of required shade Old work (Two or more coat applied @ 1.67 hr/ 10 sqm) on existing cement paint surface, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	491.555	sqm	80.00	Rupees Eighty Only	39324
NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)@{(17)2/0212 dated 7.8.2018				Total:		99181
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy, PW to the Govt. of HP vide letter No PBW(B)/A/31/2020 dated 22.07.20						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.						

Executive Engineer,
P.P.W.D. Division Haroli
Distt. Una (H.P.)