



OFFICE OF THE EXECUTIVE ENGINEER

B & R DIVISION, HPPWD, SOLAN-173212

TEL.NO:- 01792-223811 E-MAIL:- ce-sol-hp@nic.com

No.PW-SD/CB-Tender/-2025-26-

19601-05

Dated:- 28/03/26


To

The Executive Engineer (IT Cell),
Nigam Vihar, Nirman Bhawan,
HPPWD, Shimla-2,
Email ID: ce-pwd-hp@nic.in

Subject: - Publication of e-Tender Notice.


Enclosed please find herewith the Tender Notice of the works as given in the Notice inviting Tender for uploading on departmental website as per Notification Pr. Secy(PW) to the Govt. of HP letter NO.PBW(B)A(3)1/2020 dated: 19th June, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

Encl: - Schedule of quantities.


Executive Engineer,
B&R Division,
HP.PWD, Solan.

Copy along with tender notice forwarded for information and necessary action please to:-

1. The Chief Engineer (S.Z), HP.PWD, Nirman Bhawan, Nigam Vihar, Shimla.
2. The Superintending Engineer, 3rd HP.PWD, Solan.
3. The Drawing Branch & Accounts Branch of this office.
4. Notice Board.


Executive Engineer,
B&R Division,
HP.PWD, Solan.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**

Exigency

Scaled item rate tenders are hereby invited on Form No.6 &8 by the Executive Engineer, Solan B&R Division, H.P. PWD, Solan (H.P.) on behalf of the Governor of Himachal Pradesh for the following works from the registered contractor of appropriate class enlisted in H.P.PWD, whose registrations stood renewed as per revised instructions and also registered dealers under the Himachal Pradesh, General Sales Tax Act.1968. The important dates of tender are as under:

Sr.No.	Tender Schedule	Dates	Time
1	The last date for receipt of application for tender form.	06.04.2026	Upto 3.00 P.M.
2	The last date sale of tender forms.	07.04.2026	Upto 4.00 P.M.
3	The date for receipt of tender forms.	08.04.2026	Upto 10.30 P.M.
4	The date of opening of tender	08.04.2026	At 11.00 A.M.

The tender shall be received upto 10.30 A.M. on 08.04.2026 and will be opened on the same day at 11.00 AM in the presence of office against cash payment as shown below (Non-refundable) during the working hours. The earnest money in the shape of National Saving Certificate, FDRs/Account/Saving account in any of the Post Office/ Nationalized Bank in H.P. duly intending contractors or their authorized representatives who may like to be present. The tender form can be had from the pledged in favour of the Executive Engineer, (B&R) Division, H.P.PWD, Solan must accompany with each tender, conditional tenders and the tenders received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 120 days. The Executive Engineer reserves the right to reject the tender without assigning any reason.

Sr. No	Name of work	Estimated Cost. (Rs.)	Earnest Money (Rs.)	Time	Cost Form
1.	Repair and maintenance of Circuit House at Chambaghat Solan (SH: Minor repair work including relaying paver block in parking area, relining wall tiles, P/F steel truss work and minor plumbing work)	492908/-	9900/-	Two Month	Rs.350
2	Repair and maintenance of Govt. Sanskrit college building at Solan (Deposit work) (SH: Providing and laying CC and tile works)	483883/-	9700/-	Two Month	Rs.350
3	Balance work of GSSS Gaura, Solan (Deposit Work) (SH: Construction of brick work, plaster and tile work)	329913/-	6600/-	Two Month	Rs.350
4	Construction of road from Jatoli Gadog road to Koti Kalan via Bawra from km 0/0 to 2/800 (SH: Preparation of detailed project report and CBR value test as per NABARD guidelines)	201000/-	4000/-	Two Month	Rs.350
5	C/o ambulance road from Brewery Solan (NH-05) to village Tikkar km 0/0 to 1/800 under MNP (SH: Improvement of grade by carrou excavation of road at RD 0/0 to 0/300)	79442/-	1600/-	One Month	Rs.350
6	Repair and maintenance of Meusium cabinet in Govt. women polytechnic college at Kandaghat Distt. Solan (Deposit work) (SH: Meusium cabinet along with aluminium frames, toughened glass i/c all necessary fittings etc.)	494435/-	9900/-	Two Month	Rs.350
7	Repair and maintenance of Non residential accommodation in Govt. Women polytechnic college at Kandaghat (Deposit work)(SH: Demolishing of floor, repair of plaster and patches, providing wood work in frames of doors, windows, shutters, repair of roof, whitewashing etc. C/o septic tank)	386039/-	7700/-	Two Month	Rs.350
8	C/o Toilet for transgender and specially abled at existing Distt. Solan court complex at Solan (SH: CC work, tile work and water supply and sanitary fittings etc.)	80489/-	1600/-	Two Month	Rs.350
09	Restoration of rain damages on Relidhar to Darahan road km 0/0 to 1/0 under PDNA (SH: Construction of PCC Retaining wall at RD 0/550 to 0/565)	497955/-	10000/-	Two Month	Rs.350

10	Construction of additional accommodation of Govt. Sr. Sec. School at Kotla tehsil & Distt. Solan HP (Deposit work) (SII: Construction of rain harvesting tank)	266391/-	5500/-	Two Month	Rs.3.00
----	--	----------	--------	-----------	---------

TERMS & CONDITIONS:-

1. The tender form will not be issued to those contractors whose performance has been found unsatisfactory.
2. The contractor should have submitted the proof of registration, EPF No. & GST No. at the time of tender application. Failure should not be issued tender forms.
3. Application without earnest money will not be entertained.
4. Executive Engineer reserves the right to reject or cancel any or all the tenders without assigning any reasons.


Executive Engineer
B&R Division
HPWD, Solan

Exigency Certificate

It is certified that the tenders which were invited vide this
Office NIT No. PW-SD/CB-Tender/20025-26-19601-05 Dated: 28/3/28, are of
emergent nature of work and in public interest the as per the provision at Sr. No. 5(I to IV) of
Govt. Notification No PBW(B) A(3)1/2020 dated 27.05.2021.

Dated:-

Place:- Solan

Executive Engineer
B&R Division
HPPWD, Solan

Schedule of Quantity

Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
					Estimated Cost:-	492908.00
					Earnest Money:-	9900.00
					Time limit :-	Two Months

Job No. :- 1

Name of work :- Repair and maintenance of Circuit House at Chambaghat Solan SH:- Minor repair works including relaying paver blocks in parking area, refixing wall tiles, P/F steel truss work and minor plumbing work)

1	Demolishing cement concrete 1:3:6 or richer mix (i.e. equivalent design mix) manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.	1.20	Per Cubic Meter	1004.45	Rupees Thousand Four and Paise Forty Five Only	1205.00
2	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead etc. complete as per direction of Engineer-in-charge.	77.00	Per Square meter	22.25	Rupees Twenty Two and Paise Twenty Five Only	1713.00
3	Taking out existing CC interlocking paver blocks from footpath/ central verge, including removal of rubbish etc., disposal of unserviceable material to the dumping ground, for which payment shall be made separately and stacking of serviceable material within 50 metre lead as per direction of Engineer-in-Charge.	213.50	Per Square Meter	54.40	Rupees Fifty Four and Paise Forty Only	11614.00
4	Reinforced cement concrete work in chimneys, shafts, upto floor level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (cement : 1.5 coarse sand) : 3 graded stone aggregate 20 mm nominal size) as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	2.81	Per Cubic Meter	774.80	Rupees Thousand Seven Hundred Forty Four and Paise Eighty Only	21763.00
5	Providing and laying cement concrete for plain concrete nominal mix 1:5:10 (One cement: five sand : ten graded crushed stone aggregate) 40 mm (forty millimetre) nominal size mechanical mixed, vibrated and curing complete including the cost of form work in open foundation for all type of structure complete as per drawing and technical specification clauses 802,803,1202 and 1203 as per direction of Engineer-in-Charge including carriage of material through all modes of transport with in all leads and lifts and other incidentals.	32.03	Per Cubic Meter	4685.75	Rupees Thousand Four Six Hundred Eighty Five and Paise Seventy Five Only	150085.00
6	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 40 mm nominal size) of specified grade excluding the cost of centering and shuttering all work up to plinth level as per H.P.PWD. Specification including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	1.50	Per Cubic Meter	5424.85	Rupees Thousand Four Hundred Twenty Four and Paise Eighty Five Only	8137.00
7	Supplying, filling, spreading & leveling stone boulders of size range 5 cm to 20 cm, in recharge pit, in the required thickness, for all leads & lifts, all complete as per direction of Engineer-in-charge.	10.68	Per Cubic Meter	1247.25	Rupees Thousand Hundred Forty	13321.00
8	Providing and fixing bright finished brass hanging over door stopper with necessary screws, etc. complete as per direction of Engineer-in-charge.	10.00	Each	105.65	Rupees Hundred Five and Paise Sixty Five Only	1057.00

9	Laying old cement concrete interlocking paver blocks of any design/ shape laid in required line, level, curvature, colour and pattern over and including 50 mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer in-charge. (Old CC paver blocks shall be supplied by the department free of cost).	108.50	Per square meter.	238.90	Rupees Hundred and Thirty Eight and Paise Only	Two Hundred and Thirty Paise	25921.00
10	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in stirring, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	77.00	Per Square meter	859.70	Rupees Hundred Fifty Nine and Paise Seventy Only	Eight Hundred and Paise	66197.00
11	Chequered precast Light shade pigment using white cement concrete tiles 22 mm thick in footpath & courtyard, jointed with neat cement slurry mixed with pigment to match the shade of tiles, including rubbing and cleaning etc. complete, on 20 mm thick bed of cement mortar 1:4 (1 cement: 4 coarse sand) as per H.P.P.W.D. Specification including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	18.72	Per Square meter	1047.65	Rupees Thousand Seven and Paise Sixty Five Only	One Hundred and Paise	19612.00
12	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works in position and applying a priming coat of approved steel primer using structural steel etc. as per HP.P.W.D. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	487.62	Per Kilogramme	107.45	Rupees Hundred Seven and Paise Forty Only	One Hundred and Paise	52395.00
13	Providing and fixing polycarbonaid transparent sheet 0.80mm thick to 1.20mm thick in roofing with galvanised J or L hooks bolts and nuts with G.I. Limpet and bitumen rubber washer complete with all accessories as required as per direction of Engineer-in-Charge. or as directed by the Engineer-in-Charge including carriage of materials with in all lead and lift and other incidentals.	45.00	Per Square Meter	1100.00	Rupees Thousand Hundred Only	One Hundred and Paise	49500.00
14	Finishing walls with Acrylic Smooth exterior paint of required shade New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm) as per direction of Engineer in charge including carriage of all labour, equipments and materials to various locations through all modes of transportation in all lead & lifts and all incidental charges.	186.45	Per Square Meter	128.75	Rupees Hundred Eight and Paise Seventy Five Only	One Hundred and Paise	24005.00
15	Polishing on New wood work with ready mixed wax polish of approved brand and manufacture as per direction of Engineer in charge including carriage of all labour, equipments and materials to various locations through all modes of transportation in all lead & lifts and all incidental charges.	14.44	Per Square Meter	92.95	Rupees Ninety Two and Paise Ninety Five Only	Two Hundred and Paise	1342.00
16	Painting on G.S. sheet with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade Old work (one or more coats) as per direction of Engineer in charge including carriage of all labour, equipments and materials to various locations through all modes of transportation in all lead & lifts and all incidental charges.	45.00	Per square meter.	45.00	Rupees Forty Five Only	Five	2025.
17	Finishing with Deluxe Multi surface paint system for interiors and exteriors using primer as per manufacturers specifications painting wood work with deluxe multi surface paint of required shade.Two or more coats applied on wall @ 1.25 ltr/10 sqm over and including one coat of Special primer applied @ 0.75 ltr/10 sqm of approved brand and manufacture as per HP.P.W.D. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	192.00	Per Square Meter	106.25	Rupees Hundred Six and Paise Twenty Five Only	One Hundred and Paise	20400
18	Providing and fixing pipes 110 mm dia on wall face PVC Emulox type B spigot and socket, waste and venting pipes of working pressure not less than 4.5 kg/sqm ISI marked including fixing with approved adhesive etc. complete as per HP.P.W.D specification including carriage of all labour, equipment and material to various location through all modes of transportation in all lead and lift, including all incidental charges.	26.00	Per Running Meter	272.30	Rupees Hundred Two and Paise Thirty Only	Two Hundred and Paise	708

19	Providing and fixing 110 mm dia PVC (Finolex) collars ISI marked including fixing with approved adhesive etc. complete including carriage of materials within all leads and lifts as per direction of Engineer-in-charge.	15.00	Each	174.90	Rupees Hundred Seventy Four and Paise Ninety Only	One	2624.00
20	Providing and fixing 110 mm dia PVC (Finolex) clamps ISI marked including fixing with approved adhesive etc. complete including carriage of materials within all leads and lifts as per direction of Engineer-in-charge.	12.00	Each	445.10	Rupees Hundred Forty Five and Paise Ten Only	Four	5341.00
21	Providing and fixing 110 mm dia PVC (Finolex) plain bend ISI marked including fixing with approved adhesive etc. complete including carriage of materials within all leads and lifts as per direction of Engineer-in-charge.	10.00	Each	176.60	Rupees Hundred Seventy Six and Paise Sixty Only	One	1766.00
22	Providing and fixing 110 mm dia PVC (Finolex) plain Tee ISI marked including fixing with approved adhesive etc. complete including carriage of materials within all leads and lifts as per direction of Engineer-in-charge.	5.00	Each	201.50	Rupees Hundred One and Paise Fifty Only	Two	1008.00
23	Cutting holes upto 15x15 cm in RCC floors for passing drain pipes ISI marked including fixing with approved adhesive etc. complete including carriage of materials within all leads and lifts as per direction of Engineer-in-charge.	20.00	Each	239.85	Rupees Hundred Nine and Paise Eighty Five Only	Two	4797.0
Total:-							
				Rupees Four Lakhs Ninety Two Thousand Nine Hundred Eight On			
				(+)	(-)		

Quoted Percentage rate upto Three Digits :-

T/S No. for the 2025-26
Sr. No. for the year 2025-26

Executive Engineer
B&R Division, HP.PWD. Solan.

Schedule of Quantity

Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
				Estimated Cost: -		483883.00
				Earnest Money: -		9700.00
				Time limit: -		Two months
Name of Work :- Repair and maintenance of Govt. Sanskrit College building at Solan (Deposit work) (SH: - Providing and laying CC and Tile works)						
1	Providing and laying cement concrete 1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) in position cement concrete of specified grade excluding the cost of centering and shuttering as per H.P. PWD. specification including carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts, including all incidental charges.	45.88	Per Cubic Meter	6294.15	Rupees Thousand Four and Paise Fifteen Only	Six Two Ninety Four Paise
2	Providing and laying Vitrified tiles in different sizes 600x600 mm (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joint with white cement & matching pigments etc. complete as per HP.PWD. Specification and as per direction of Engineer in Charge including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	132.78	Per square Meter	1469.40	Rupees Thousand Hundred Sixty Nine and Paise Forty Only	One Four Hundred Sixty Nine Paise
Total:-						288776.00
Rupees Four Lakhs Eighty Three Thousand Eight Hundred Eighty Three Only						483883.00
Quoted Percentage rate upto Three Digits :-					(+) / (-)	

T/S No. 304 for the 2025-26
Sr. No. 50 for the year 2025-26

Executive Engineer
B&R Division, HP.PWD. Solan.

Schedule of Quantity

Sr. No.	Description of work	Qty.	Unit	Rate in words		Amount
				Figures	words	
Name of Work :- Balance work of GSSS Gaura, Solan (Deposit work) (SH)- Construction of brick work, plaster & tile work)						
Job No. 3						
Time limit :- Two Months						
1	Demolishing brick in cement mortar work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge and HP.PWD. specification including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	18.00	Per Cubic Meter	975.15	Rupees Nine Hundred Seventy Five and Paise Fifteen Only	17553.00
2	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in Cement mortar 1:4 (1 cement :4 coarse sand in superstructure above plinth level up to floor level, superstructure above plinth level to up to all floor level including carriage of all labour equipment and material to various location through all modes of transportation in all lead, lift, other incidental charges and as per direction of engineer in charge.	90.00	Per square meter.	987.20	Rupees Nine Hundred Eighty Seven and Paise Twenty Only	88848.00
3	Providing and laying vitrified floor tiles in different sizes of tile 600X600 mm (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including erouting the joints with white cement and matching pigments etc., complete as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	126.31	Per square meter.	1437.15	Rupees Thousand Four Hundred Thirty Seven and Paise Fifteen Only	181526.00
4	15mm Cement plaster in single coat on the rough side of brick/ concrete/stone walls for interior/exterior plastering upto all floor level including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm in girth and finished even and smooth in Cement Mortar 1:6 (1 Cement:6 Sand) as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts	90.00	Per square meter.	260.25	Rupees Two Hundred Sixty and Paise Twenty Five Only	23423.00
5	Providing and applying white cement based putty of average thickness 1 mm. of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as per HP.PWD. Specification including carriage of all labour, equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	90.00	Per Square Meter	99.85	Rupees Nine and Paise Eighty Five Only	8987.00
6	Wall painting two coats with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacturer, including applying additional coats wherever required to achieve even shade and colour complete as per direction of Engineer in Charge and as per HP.PWD. Specification including carriage of all labour, equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	90.00	Per square meter.	106.40	Rupees One Hundred Six and Paise Forty Only	9576.00
Total:-						329913.00
Rupees Three Lakhs Twenty Nine Thousand Nine Hundred Thirteen Only						
Quoted Percentage rate upto Three Digits :-						
				(+)/(-)		

T/S No. **305** for the 2025-26

Sr. No. **501** for the year 2025-26

Executive Engineer
B&R Division, HP.PWD, Solan.

Schedule of Quantity

Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
<p>Job No. : 54</p> <p>Name of Work:- Construction of road from Jatoli Gadog road to Koti Kalan Via Bawra from Km.0/00 to 2/800 (SH : Preparation of Detailed project Report & CBR value test as per NABARD Guidelines)</p>						
Time limit :- Two months						
<p>Estimated Cost:- 201000.00</p> <p>Earnest Money:- 4000.00</p>						
1	Preparation of DPR, Topographical survey plan & Mark provisions on the Survey plan which include the following provision as given below:-	2.800	Per Kilometer	35000	Rupees Five Thousand Only	98000.00
	a) Topography survey by digital total station with two second accuracy, showing all features on survey plan like trees, culverts, bridges, electric poles, telephone poles, hand pumps, schools, Habitants villages etc.,					
	b) Draw cross-sections at 15m (fifteen meter) intervals, L-section & calculate the quantity of earth work in standard format of autocad showing all layer of pavement components as applicable.					
	c) Preparation of survey plan showing all provision on the topographical survey plan and preparation of detailed project report as per MORD Guidelines and submission of 5-set of DPR after manuscript.					
2	CBR-Value & Pavement design of crust as per IRC:SP-72-2015	8.000	Each	3500.00	Rupees Thousand Three Hundred Only	28000.00
3	Preparation of Working estimate and DNIT after sanction from NABARD and submission of 5-set of working estimate	1.000	Each	75000	Rupees Five Thousand Only	75000.00
	Total:-					
				Rupees Two Lakhs One Thousand Only		201000.00
	Quoted Percentage rate upto Three Digits :-		(+) / (-)			

Sr. No. **54** for the year 2025-26

Executive Engineer

B&R Division, HP PWD Solapur

Schedule of Quantity

Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
				Estimated Cost:-		79442.1
				Earnest Money:-		1600.
				Time limit :-		One Mon

Job No. :- **(5)**

Name of Work :- Construction of ambulance road from Brewery Solan (NH-05) to village Tikkar Km.0/00 to 1/800 under MNP (SH: Improvement of grade by carriout excavation of road at Rd.0/00 to 0/300)

1	Excavation for roadway in ordinary rock by deploying a dozer D-50 including cutting and pushing the cut earth to site of embankment upto a distance of 100 m (average lead 50 m), trimming bottom and side slopes in accordance with the requirements of lines, grades and cross-sections with lift upto 1.5 m.as per technical specification clause 302.3.5.	742.45	Per Cubic Meter	107.00	Rupees Hundred Seven Only	79442.1
Total:-						79442.1
Rupees Seventy Nine Thousand Four Hundred Forty Two On						
Quoted Percentage rate upto Three Digits :-						
			(+) / (-)			

T/S No. 314 for the 2025-26
Sr. No. 5/2 for the year 2025-26

Executive Engineer
B&R Division, HP.PWD. Solan.

Schedule of Quantity

Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
<p style="text-align: center;">Job No.: 6</p> <p style="text-align: center;">Name of work :- Repair and maintenance of Museum cabinet in Govt. Women Polytechnic college at Kandaghat Distt. Solan (Deposit work) (SH;- Museum cabinet along with aluminum frames, toughened glass i/c all necessary fitting etc.)</p>						
				Estimated Cost: -		494435.00
				Earnest Money: -		9900.00
				Time limit: -		Two Months
1	Providing Sal wood work in frames of false ceiling, partitions etc. sawn and fixed in position with necessary stainless steel screws etc.as per H.P.PWD. Specification, including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	0.175	Per Cubic Meter	91310.90	Rupees Hundred and Twenty Eight and Paise Eighty Five Only	15979.00
2	Providing and fixing panelling or panelling and glazing in panelled or panelled and glazed shutters for doors, window sand clerestory windows (Area of opening for panel inserts excluding portion in side groove sorr ebates to be measured). Panelling for panelled or panelled and glazed shutters 25 mm to 40 mm thick Decorative plywood one side decorative veneer and commercial veneer on other face(Type1) conforming to IS1328BWR Type as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	18.900	Per Cubic Meter	1986.25	Rupees Hundred and Twenty Eight and Paise Eighty Five Only	37540.00
3	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mirrored and jointed mechanically wherever required including clear angle, Aluminium snap beading for glazing / panelling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in charge. (Glazing, panelling and dash fasteners to be paid for separately) Polyester powder coated aluminium (minimum thickness of polyester powder coating 30 micron) as directed by the Engineer in-Charge including carriage of materials with in all leads and lifts and other incidentals.	413.78	Per Kilogramme	428.85	Rupees Hundred and Twenty Eight and Paise Eighty Five Only	177450.00
4	Providing and fixing aluminium work for doors, windows, Providing and fixing 12 mm thick prelaminated particle board with decorative lamination on both sides flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminium doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer- in-charge.	23.64	Per Square meter	949.20	Rupees Hundred Forty Nine and Paise Twenty Only	22439.00
5	Providing and fixing 12 mm thick frameless toughened glass door shutter of approved brand and manufacture, including providing and fixing top & bottom pivot & double action hydraulic floor spring type fixing arrangement and making necessary holes etc for fixing required door fittings, all complete as per direction of Engineer-in-charge (Door handle, lock and stopper etc to be paid separately)	17.55	Per Square Meter	4080.00	Rupees Thousand Only	71644.00
6	Providing and fixing aluminium tubular handle bar 32 mm outer dia, 30 mm thick, 2100 mm long with SS screws etc complete as per direction of Engineer-in Charge. Polyester powder coated aluminium thickness 50 micron aluminium tubular handle bar as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	21.00	Each	571.35	Rupees Hundred and Thirty Five Only	12098.40

	Providing laminated veneer lumber conforming to IS:14616 and TAD-15: 2001 (Part B) in factory made frames of doors, windows, clerestory windows and other frames, wrought framed and fixing in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately) as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	0.279	Per Cubic Meter	107736.40	Rupees One Lakh Seven Hundred Thirty Six and Paise Forty Only	30058.00
	Providing and fixing 510 X 19 mm stainless steel (SS 304 grade) adjustable friction windows stays of approved quality with necessary stainless steel screws etc. to the side hung windows as per direction of Engineer-in-charge complete.	21.00	Each	717.90	Rupees Seven Hundred Seventeen and Paise Ninety Only	15076.00
	Dismantling of G.S. Sheet roofing including ridges, hips, valleys and gutters etc., and stacking the material within 50 metres lead and lift, including all incidental charges.	69.00	Per Square meter.	69.80	Rupees Sixty Nine and Paise Eighty Only	4816.00
10	Providing corrugated G.S. sheet roofing 0.80mm thick with zinc coating not less than 275 gm/m ² including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	69.00	Per Square meter	984.10	Rupees Hundred Eighty Four and Paise Ten Only	67903.00
11	Providing ridges or hips of width 60 cm overall 0.80 mm thick with zinc coating not less than 275 gm/m ² width plain G.S. sheet fixed with polymer coated J or L hooks, bolts and nuts 8 mm dia G.I. limpet and bitumen washers complete as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	15.000	Per Running Meter	622.15	Rupees Hundred Twenty Two and Paise Fifteen Only	9332.00
12	Providing and fixing green grass mat, including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	37.800	Per Square meter	800.00	Rupees Hundred Only	30240.00
Total:-						
Rupees Four Lakhs Ninety Four Thousand Four Hundred Thirty Five Only						
Quoted Percentage rate upto Three Digits :-				(+) / (-)		

T/S No. 316 for the 2025-26
Sr. No. 509 for the year 2025-26

Executive Engineer
B&R Division, HP.PWD. Solan.

Schedule of Quantity

Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	

Job No. :- **(7)**

Estimated Cost: -	386039.00
Earnest Money: -	7700.00
Time limit: -	Two Months

Name of work :- Repair and maintenance of Non-Residential accommodation in Govt. Women Polytechnic College at Kandaghat (Deposit work) (SI); - Demolishing of floor, repair of plaster and patches, providing wood work in frames of doors, windows, shutters, repair of roof, whitewashing etc. c/o septic tank)

1	Demolishing cement concrete 1:3:6 or richer mix (1/c equivalent design mix) manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.	7.43	Per Cubic Meter	1004.45	Rupees Thousand Four and Paise Forty Five Only	One	7463.00
2	Dismantling doors, windows and clerestorey windows, ventilators (steel or wood) shutters including chauhats, architraves, hold fasts and other attachments etc. complete in all respects not exceeding 3.00 (three) square meter in area etc. as per direction of Engineer in Charge and as per HP.PWD. specification including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	8.00	Each	156.25	Rupees Hundred Fifty Six and Paise Twenty Five Only	One	1250.00
3	Providing and laying cement concrete 1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size), in position cement concrete of specified grade excluding the cost of centering and shuttering as per H.P. PWD. specification including carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts, including all incidental charges.	9.53	Per Cubic Meter	4955.20	Rupees Thousand Hundred Fifty Five and Paise Twenty Only	Four	47223.00
4	52mm thick cement concrete flooring with concrete hardener topping, under layer 40mm thick cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size) and top layer 12 mm thick cement hardener consisting of mix 1:2 (1 cement hardener ix:2 graded stone aggregate 6mm nominal size) by volume, hardening compound mixed @ 2 litre per 50kg of cement or as manufacturer's specifications. This includes cost of cement slurry but excluding the cost of nosing of steps etc. complete as per direction of Engineer in Charge and as per HP.PWD. Specification including carriage of all labour, equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	63.50	Per Square Meter	579.05	Rupees Hundred Seventy Nine and Paise Five Only	Five	36770.00
5	Repairs to plaster in patches of 2.50 sqm. (two point five zero square meter) and under and 10 to 15mm (ten to fifteen millimeter) thick with cement mortar 1:4 (one cement is to four sand) including cutting the patches in proper shape and re-plastering the surface of the wall including disposal of rubbish to the dumping ground within all lead as per direction of Engineer in Charge and as per HP.PWD. specification 1990 (One thousand Nine hundred Ninety) Volume-1 (One), including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	79.600	Per Square Meter	276.15	Rupees Hundred Six and Paise Fifteen Only	Two	21982.00
6	15mm Cement plaster in single coat on the south side of brick/ concrete stone walls for interior exterior plastering upto all floor level including providing and providing angles, chamfers and rounded angles not exceeding 80mm in girth and plastering of door and window frames and plastering of cement Mortar 1:4 (1 Cement 4 Sand) as per HP.PWD. Specification including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts.	79.60	Per square meter	200.45	Rupees Hundred and Paise Forty Five Only	Two	15956.00

7	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3 kg/sqm including pointing the joints with white cement and matching pigment etc., complete as per HP.PWD. specification including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	63.50	Per square meter.	856.85	Rupees Eight Hundred Fifty Six and Paise Eighty Five Only	54410.00
8	Providing and fixing 35 mm thick including ISI marked Stainless Steel butt hinges with necessary screws flush door shutters conforming to IS : 2202 (Part I) decorative type, core of block board construction with frame of 1st class hard wood and well matched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters as per H.P. PWD. specification including carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts, including all incidental charges.	4.00	Per Square meter	2832.75	Rupees Thousand Eight Hundred Thirty Two and Paise Seventy Five Only	11331.00
9	Providing & fixing 4.0 mm thick glass panes with putty and glazing clips in steel doors, windows, clerestory windows, all complete as per HP.PWD. Specification, including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts, including all incidental charges	18.00	Per Square Meter	847.55	Rupees Eight Hundred Seven and Paise Fifty Five Only	15256.00
10	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete as per HP.PWD. Specification including carriage of all labour, equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	102.32	Per Square Meter	8.50	Rupees Eight and Paise Fifty Only	870.00
11	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as per direction of Engineer in Charge and as per HP.PWD. Specification including carriage of all labour, equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	102.32	Per square meter.	85.10	Rupees Eighty Five and Paise Ten Only	8707.00
12	Painting One or more coats on old work with synthetic enamel paint on new wood and wood based surface with ready mixed paint, brushing to give an even shade including cleaning all dirt, dust and other foreign matter, sand papering and stopping as per HP.PWD. specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts, including all incidental charges and as per direction of engineer in charge.	104.50	Per Square Meter	53.85	Rupees Fifty Three and Paise Eighty Five Only	5627.00
13	Dispersing Two coats with 1st quality acrylic disperser having VOC (Volatile Organic Compound) content less than 50 grams/litre, of approved brand and manufacturer, including applying additional coats wherever required, to achieve even shade and colour as per direction of Engineer in Charge and as per HP.PWD) Specification including carriage of all labour, equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	102.32	Per Square Meter	51.00	Rupees Fifty One Only	5218.00
14	Finishing walls with Acrylic Smooth exterior paint of required shade Old work (Two or more coat applied to 1st lift) 10 sign on existing cement paint surface as per HP.PWD) Specification including carriage of all labour, equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	102.320	Per Square Meter	73.85	Rupees Three and Paise Eighty Five Only	7556.00
15	Taking up of floor with frame from R.C.C. top slab of specified thickness of various sizes including demolition of P.C.C. work manually/ by mechanical means and stacking of useful materials near the site and disposal of non-reusable materials within 50 metres had to per direction of Engineer-in-charge.	15.00	Each	174.80	Rupees Hundred Four and Paise Eighty Only	2622.00

<p>Constructing brick masonry manhole in cement mortar 1:4 (1 cement : 4 coarse sand) with R.C.C. top slab with 1:1.5:3 mix (1 cement : 1.5 coarse sand (zone- III) : 3 graded stone aggregate 20 mm nominal size), foundation concrete 1:4:8 mix (1 cement : 4 coarse sand (zone- III) : 8 graded stone aggregate 40 mm nominal size), inside plastering 12 mm thick with cement mortar 1:3 (1 cement : 3 coarse sand) Finished with floating coat of neat cement and making channels in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) finished with a floating coat of neat cement complete as per standard design :</p>	15.00	Each	9586.55	Rupees Thousand Hundred Eighty Six and Paise Fifty Five Only	143798.00
<p>16.1 Inside size 90x80 cm and 45 cm deep including C.I. cover with frame (light duty) 455x610 mm internal dimensions, total weight of cover and frame to be not less than 38 kg (weight of cover 23 kg and weight of frame 15 kg) : With common burnt clay F.P.S. (non modular) bricks of class designation 7.5</p>					
<p style="text-align: center;">Total:-</p>					
<p style="text-align: center;">Quoted Percentage rate upto Three Digits :-</p>					
<p>Rupees Three Lakhs Eighty Six Thousand Thirty Nine Only</p>					
<p>(+) / (-)</p>					
<p>386039.00</p>					

T/S No. 3 for the 2025-26
Sr. No. 568 for the year 2025-26

Executive Engineer
B&R Division, HP.PWD, Solan.

providing and fitting for including cover
including carriage of all labour, equipment and material to various location through road
all lead and lift including all incidental charges.

Schedule of Quantity

Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
					Estimated Cost:-	80489.00
					Earnest Money:-	1600.00
					Time limit :-	Two Months

Job No. : **(8)**

Name of work :- Construction of Toilet for Transgender and Specially abled at existing Distt. Solan Court Complex at Solan (SH:- CC work, tile work and water supply and sanitary fitting etc.)

1	Providing and laying cement concrete 1:2:4 (1 Cement : 2 coarse sand) : 4 Graded stone aggregate 20 mm nominal size) in position cement concrete of specified grade excluding the cost of centering and shuttering as per H.P. PWD. specification including carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts, including all incidental charges.	0.99	Per Cubic Meter	6294.16	Rupees Thousand Hundred Four and Sixteen Only	Six Two Ninety Four and Paise	6231.00
2	Providing and laying vitrified floor tiles in different sizes of tile 600x600 mm (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	3.99	Per square meter.	1437.15	Rupees Thousand Hundred Seven and Fifteen Only	One Four Thirty and Paise	5734.00
3	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge	2.00	Per Square Meter	296.75	Rupees Hundred Ninety Six and Paise Seventy Five Only	Two Hundred Thirty and Paise	594.00
3.1	20 mm nominal outer dia Pipes	2.00	Per Square Meter	296.75	Rupees Hundred Ninety Six and Paise Seventy Five Only	Two Hundred Thirty and Paise	594.00
3.2	25 mm nominal outer dia Pipes	5.00	Per Square Meter	234.50	Rupees Hundred Four and Fifty Only	Two Hundred Thirty and Paise	1173.00
4	Providing and fixing W.C. pan with ISI marked white solid plastic seat and lid white vitreous china pedestal type water closet (European type W.C. pan) for special disable person with seat and lid. 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (hand lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required as per HP.PWD specification including carriage of all labour, equipment and material to various location through all modes of transportation in all lead and lift, including all incidental charges.	2.00	Each	17500.00	Rupees Thousand Hundred Only	Seventeen Five	35000.00
5	Providing and fixing White Vitreous China Wash basin size 630x450 mm with a pair of 15 mm C.P. brass pillar taps 32mm (thru two millimeters) dia C.P. Brass waste for wash basin 1012 of (vra of equivalent or sink as per HP.PWD specification including carriage of all labour, equipment and material to various location through all modes of transportation in all lead and lift, including all incidental charges.	1.000	Each	2843.25	Rupees Thousand Hundred Three and Paise Twenty Five Only	Two Eight Forty and Paise	2843.00
6	Maintenance of G.I. distribution branch with G.I. main of following size : 25 to 40 mm nominal bore by providing and fixing the including cutting and threading the pipe etc. complete as per HP.PWD specification including carriage of all labour equipment and material to various location through all modes of transportation in all lead and lift, including all incidental charges.	1.00	Each	453.05	Rupees Hundred Three and Paise	Four	

7	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS:13983 with C.I. brackets and stainless steel plug 40mm, including painting of fittings and brackets, cutting and making good the walls wherever required 610x510mm bowl depth 200 mm as per HP.PWD specification including carriage of all labour equipments and materials to various location through all modes of transportation in all leads and lifts, including all incidental charges.	1.00	Each	4849.00	Rupees Thousand Hundred Forty Nine Only	Four Eight	4849.00
8	Providing and fixing 600mmx450mm (six hundred into four hundred fifty millimeter) beveled edge mirror of superior glass mounted on 6mm(six millimeters thick A.C. sheet or plywood sheet and fixed to wooden plugs with C.P. brass screws and washers as per HP.PWD specification including carriage of all labour equipments and materials to various location through all modes of transportation in all leads and lifts, including all incidental charges.	2.00	Each	1124.10	Rupees Thousand Hundred Twenty Four and Paise Ten Only	One	2248.00
9	Providing and fixing 600x120x5 mm (six hundred twenty into five millimeter) Glass Shelf with C.P. Brass bracket and guard rail complete, with 40 mm long screws, rawl plugs etc or equivalent as per HP.PWD specification including carriage of all labour, equipment and material to various location through all modes of transportation in all lead and lift, including all incidental charges.	2.000	Each	750.00	Rupees Hundred Fifty Only	Seven	1500.00
10	Providing and fixing toilet paper holder C.P. brass as per HP.PWD specification including carriage of all labour, equipment and material to various location through all modes of transportation in all lead and lift, including all incidental charge	2.000	Each	534.15	Rupees Hundred Four and Fifteen Only	Five Thirty Paise	1068.00
11	Providing and fixing PTMT soap Dish Holder having length of 138mm, breadth 102mm, height of 75mm with concealed fitting arrangements, weighing not less than 06 gms(Kent touchless sanitiser/ liquid soap dispenser/1000ml white) as per HP.PWD specification including carriage of all labour equipments and materials to various location through all modes of transportation in all leads and lifts, including all incidental charges.	2.000	Each	352.60	Rupees Hundred Fifty Two and Paise Sixty Only	Three Twenty Sixty	705.00
12	Providing and fixing uplasticised PVC connection pipe 45 cm length 15 mm nominal bore with brass unions as per HP.PWD specification including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges	2.000	Each	121.25	Rupees Hundred One and Twenty Five Only	One Twenty Paise	243.00
13	Providing and fixing PVC single equal branch 110 mm (one hundred ten millimeters) dia of required with oval access door insertion rubber washer 3mm thick bolts and nuts as per HP.PWD specification, including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	5.00	Each	312.25	Rupees Hundred and Paise Twenty Five Only	Three Twelve Twenty	1561.00
14	Providing and fixing 110 mm (One Hundred Ten millimeters) PVC plain bend ISI marked including fixing with approved adhesive etc. complete. as per HP.PWD specification including carriage of all labour, equipment and material to various location through all modes of transportation in all lead and lift, including all incidental charges.	5.00	Each	168.95	Rupees Hundred Eight and Ninety Five Only	One Sixty Paise	845.00
15	Providing and fixing 110 mm (One Hundred Ten millimeters) PVC door bend with oval access door, insertion rubber washer 3mm(three millimeter) thick bolts and nuts ISI marked complete including fixing with approved adhesive etc. complete. as per HP.PWD specification including carriage of all labour equipments and materials to various location through all modes of transportation in all leads and lifts, including all incidental charges.	5.00	Each	215.95	Rupees Hundred and Paise Ninety Five Only	Two Fifteen Ninety	1080.00
16	Providing and fixing 100 mm (One Hundred Ten millimeters) dia PVC Collars ISI marked including fixing with approved adhesive etc. complete as per HP.PWD specification including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	3.00	Each	176.20	Rupees Hundred Seven and Paise Twenty Only	One Seventy Paise	529.00
17	Providing and fixing Sand Cast iron 110 mm (One Hundred Ten millimeters) size 'P' or 'Strap for water closet (squatting pan) including joining the trap with the soil and soil pipe in cement mortar 1:1:4 cement : 1 sand as per HP.PWD specification including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	2.00	Each	722.00	Rupees Hundred Twenty and Paise Sixty Only	Seven Twenty Sixty	1445.00

18	Providing and fixing 32mm dia (Thirty Two millimeter) P.V.C. Flexible waste pipe for sink or wash basin including P.V.C. waste fittings complete as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	2.00	Each	116.60	Rupees One Hundred Sixteen and Paise Sixty Only	18
19	Providing and fixing 15 mm (fifteen millimeters) nominal bore C.P. brass long body bib cock of approved quality conforming to IS standards and weighing not less than 690 gms as per HP.PWD specification including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	3.000	Each	604.10	Rupees Hundred Four and Paise Ten Only	3
20	Providing and fixing PTMT pillar cock 15 mm nominal bore, 107 mm long, weighing not less than 110 gms of approved quality and colour as per HP.PWD specification including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	2.00	Each	195.45	Rupees Hundred Ninety Five and Paise Forty Five Only	6
21	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 as per HP.PWD specification including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	8.00	Each	750.00	Rupees Hundred Fifty Only	1
22	Providing and fixing Mixer for kitchen sink with casted swinging spout at top as per HP.PWD. Specification i/c carriage of all labour, equipment and material to various location through all modes of transportation in all lead and lift i/c all incidental charges.	1.00	Each	1735.48	Rupees Thousand Seven Hundred Thirty Five and Paise Forty Eight Only	
23	Providing and fixing 100 mm sand cast Iron grating for gully trap as per HP.PWD specification including carriage of all labour, equipment and material to various location through all modes of transportation in all lead and lift, including all incidental charges.	2.000	Each	105.35	Rupees Hundred Five and Paise Thirty Five Only	
24	Providing and fixing 75 mm diameter on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including joining with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	3.00	Per Running Meter	215.50	Rupees Hundred Fifteen and Paise Fifty Only	
Total:-						
Quoted Percentage rate upto Three Digits :-						
				(+)/(-)		
				Rupees Eighty Thousand Four Hundred Eighty Nin		

T/S No. 377 for the 2025-26
 Sr. No. 505 for the year 2025-26

Executive Engineer
 B&R Division, HP.PWD. Solan.

Schedule of Quantity

Sr. No.	Description of work	Qty.	Unit	Rate in words		Amount	
				Figures	words		
Name of Work :- Restoration of rain damages on Relidhar to Darahan road km.0/00 to 1/00 under PDNA (SH.- Construction of PCC Retaining wall at Rd.0/550 to 0/565)							
Job No. : 9							
Time limit :- Two months							
Estimated Cost :- 497955.00 Earnest Money :- 10000.00							
1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited). Dimensions and other particulars as per drawing and Technical Specification Clause 305 I (Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and its disposal including dressing of sides and bottom and backfilling in trenches with excavated suitable material, trimming, filling of unevenness blindages and finishing of the road to specified dimensions. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	50.41	Per Cubic Meter	392.00	Rupees Hundred Two Only	Three Ninety	19761.00
2	Providing and laying Plain Cement Concrete nominal mix 1:4:8 (one cement 150 four sand 150 eight graded stone aggregate 25mm (twenty five millimeters) nominal size) Mechanically mixed and vibrated for plain/reinforced concrete and curing complete in open foundations and plinths for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	93.29	Per Cubic Meter	4816.00	Rupees Thousand Hundred Only	Four Eight Sixteen	449285.00
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia PVC pipe extending through the full width of the structure with slope of 1:20 (One verticle 150 twenty horizontal) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204 3, 7, 15A hundred fourteen, seven hundred nine, one thousand two hundred four point three point seven) or as directed by the Engineer-in-Charge including carriage of materials with in all lead and lift and other incidentals.	46.00	Each	242.00	Rupees Hundred Two Only	Two Forty	11132.00

Backfilling behind abutment, wing wall and return wall, breast walls, retaining walls and parapets up to all heights, depths and levels complete as per HP.PWD. Specification clause 1204.3.8 (one thousand two hundred four point three point eight) Granular material, including carriage of all labour equipment and material to various locations through all modes of transportation in all lead and lift and all incidental charges.

	16.19	Per Cubic Meter	1098.00	Rupees Thousand Eight Only	One Ninety	17777.00
Total:-						497955.00
Rupees Four Lakhs Ninety Seven Thousand Nine Hundred Fifty Five Only						
Quoted Percentage rate upto Three Digits :-						
		(+) / (-)				

T/S No. 310 for the 2025-26
 Sr. No. 567 for the year 2025-26

Executive Engineer
 B&R Division, HP.PWD. Solan.

Schedule of Quantity

Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
				Estimated Cost :-		266391.00
				Earnest Money :-		5500.00
				Time limit :-		Two Months

Job No. :- **16**

Name of work :- Construction of Additional accommodation of Govt. Sr. Sec. School at Kotla tehsil and Distt. Solan HP (Deposit work)
(SH: - Construction of Rain Harvesting tank)

1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited). Dimensions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and its disposal including dressing of sides and bottom and backfilling in trenches with excavated suitable material, trimming, filling of unevenness blindages and finishing of the road to specified dimensions. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	50.82	Per Cubic Meter	392.00	Rupees Hundred Two Only	Three Ninety	19921.00
2	Providing and laying Plain Cement Concrete nominal mix 1:4:8 (one cement isto four sand isto eight graded stone aggregate 20mm (twenty five millimeters) nominal size Mechanically mixed and vibrated for plain/reinforced concrete and curing complete in open foundations and plinths for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	3.54	Per Cubic Meter	4816.00	Rupees Thousand Hundred Only	Four Eight Sixteen	17049.00
3	Providing and laying Reinforced cement concrete (1:1.5:3 (1 cement : 1.5 coarse sand) : 3 graded stone aggregate 20 mm nominal size) in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair case etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement as per H.P. PWD. specification including carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts, including all incidental charges.	2.90	Per Cubic Meter	7844.00	Rupees Thousand Hundred Forry Four Only	Seven Eight Four	22748.00
4	Centering and shuttering including strutting, propping etc. and removal of form work as per H.P. PWD. specification including carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts, including all incidental charges.						
4.1	Suspended floors, roofs, landings, balconies and access platform	17.71	Per Square meter	555.00	Rupees Hundred Fifty Five Only	Five	9829.00
4.2	Edges of slabs and breaks in floors and walls Under 20 cm wide.	23.20	Per running meter	129.00	Rupees Hundred Nine Only	One Twenty	2993.00

5	Steel reinforcement for R.C.C. Mild steel and Medium Tensile steel bars work including straightening, cutting, bending, placing in position and binding all complete upto plinth level as per H.P. PWD. specification including carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts, including all incidental charges.	522.00	Per Kilogramme	101.00	Rupees Hundred One Only	One	52722.00
6	Brick work with common burnt clay machine moulded with F.P.S.(non modular) perforated bricks of class designation 12.5 conforming to IS:2222 in superstructure above plinth level up to floor five level in cement mortar 1:6 (1 cement : 6 coarse sand) as per H.P. PWD. specification including carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts, including all incidental charges.	14.13	Per Cubic Meter	6822.00	Rupees Thousand Hundred Twenty Only	Six Eight Twenty	96395.00
7	15mm Cement plaster in single coat on the rough side of brick/ concrete/stone walls for interior/exterior plastering upto all floor level including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm in girth and finished even and smooth in Cement Mortar 1:6 (1Cement:6 Sand) as per H.P. PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts.	49.58	Per square meter.	262.00	Rupees Hundred Sixty Two Only	Two	12990.00
8	40 (Forty) millimeters thick with 20 mm nominal size stone aggregate Cement concrete flooring in 1:2:4 (One cement isto Two sand isto Four graded crushed hard stone aggregate 20 (twenty) millimeters nominal size) laid in One layer finished with floating coat of neat cement in all floors up to all heights, levels complete as per H.P. PWD. specification including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	10.57	Per Square meter	466.00	Rupees Hundred Sixty Six Only	Four	4926.00
9	Providing and fixing high pressure PVC spigot and socket, waste and ventilating pipes ISI marked including fixing with approved adhesive etc. complete as per HP PWD specification including carriage of all labour, equipment and material to various location through all modes of transportation in all lead and lift, including all incidental charges.						
9.1	110 mm (one hundred ten millimeters) dia.	50.00	Per Running Meter	373.00	Rupees Hundred Thirty Only	Three Seventy	18650.00
10	Providing and fixing in position pre-cast R.C.C. manhole Rectangular shape 610x455 mm internal dimensions cover and frame of required shape and approved quality as per HP PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	2.00	Each	838.00	Rupees Hundred Eight Only	Eight Thirty	1676.00
11	Providing and fixing in position precast reinforced cement concrete chamber cover with frame complete for man hole of internal dimension 300mmx300mm <i>Uc</i> carriage of materials with in all leads, lifts and other incidentials.	10.00	Each	431.00	Rupees Hundred One Only	Four Thirty	4310.00
12	Supply and filling broken/ crushed stone aggregate chipping of hard stone of 40 mm size complete as per HP PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	1.80	Per Cubic Meter	1212.00	Rupees Thousand Hundred Only	One Two Twelve	2182.00
Total:-							266391.00
Rupees Two Lakhs Sixty Six Thousand Three Hundred Ninety One Only							
Quoted Percentage rate upto Three Digits :-							
(+) / (-)							

T/S No. 321 for the 2025-26
Sr. No. 520 for the year 2025-26

Executive Engineer
B&R Division, HP.PWD, Solan.