

HIMACHAL PRADESH  
PUBLIC WORK DEPARTMENT

No. PW/DT/TA/ NIT /2025-26-

13540

Dated:- 30-03-2026

To,


The Executive Engineer  
IT Cell Nirman Bhawan Nigam Vihar  
HP PWD Shimla

Subject: \_

Regarding NIT for uploading on HP PWD website .


Enclosed please find herewith the Notice inviting tender Notice along with schedule of quantity for uploading on HP PWD website. This is for your kind information and necessary action at your end please.

Encls:- 18 Nos copy of Schedule of quantity.

  
Executive Engineer  
Tanda Division HP PWD  
at Nagrota Bagwan

CERTIFICATE

Certified that the tenders of works, called vide  
this office letter No. PW-DT-NIT-2025-26- 13540 - SS Dated:-30-03-2026  
are urgent nature.

  
Executive Engineer  
Tanda Division HP PWD  
at Nagrota Bagwan

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

Scaled item rate tender on form No. 6 & 8 are hereby invited by the **Executive Engineer, HP PWD Division Tanda at Nagrota Bagwan** on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HP PWD (B & R) whose registration stood renewed as per revised rules so as to reach in his office on or before on **10.04.2026** up to **11:00 A.M.** And the same shall be opened on the same day at **04:00 P.M.** in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on **09.04.2026** up to **4:00 P.M.** and the application for issue of tender form shall be received on **08.04.2026** up to **12:00 noon.** The applications for issue of tender forms accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates/Saving Account of the Post Office /Time Deposit account/FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP PWD Division Tanda at Nagrota Bagwan.

The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 120 days.

Sr. No.	Name of work	Estimated Cost	Earnest Money	Time limit
1.	Annual Repair and Maintenance of 500 Bedded Hospital at Dr. RP Govt. Medical College Tanda in Tehsil Nagrota Bagwan Distt. Kangra HP Deposit work (SH: Cleaning of Chocked Chamber Behind Medicine dispensary and Laundry).	95000.00	1900.00	One Months
2	Repair of CHW-1 and CHW-2 at Dr.R.P. Govt. Medial Collage Tanda in Distt. Kangra hP Deposit Work (SH: Painting and distempering CHW-l).	85285.00	1710.00	One Months
3	Construction of lecture Theatre Complex under EWS Scheme in Dr. R.P. govt. Medical College Kangra at Tanda in Distt. Kangra HP (SH Constnction of Pedestal for Shifting of Transformer form construction site stage -l).	75079.00	1550.00	One Month
4	Repair of Medical store Premises at Dr. R.P. Govt. Medical College tanda in Distt. Kangra HP Deposit work (SH:Painting and distempering part-l)	97074.00	1950.00	One Months
5	A/R & M/O to Internal roads in Dr. R.P. Govt. Medical College Kangra at Tanda in Distt. Kangra HP Deposit work (SH: Providing and fixing plastic speed braker speed bump).	85100.00	1700.00	One Months
6	Annual Repair and Maintenance of Internal roads in Dr. R.P. Govt. Medical College Kangra at Tanda in Distt. Kangra HP deposit work (SH: Providing and laying Kota stone, Repair to palster and painting on Railing).	99404.00	2000.00	One Months
7	Repair of Taruma Centre at Dr. R.P. Govt. Medical College Tanda in Distt. Kangra HP Deposit Work (SH: Providing and applying paint work curtain rod, providing and fixing aluminium work roof work & Glass panes etc part-l)	77071.00	1550.00	One Months
8	Annual Repair and Maintenance of Internal roads in Dr. R.P. Govt. Medical College Kangra at Tanda in Distt. Kangra HP deposit work (SH: Providing and laying Kota stone, Repair to palster and painting on Railing).	99382.00	2000.00	One Months
9	Repair of 500 bedded Hospital at Dr. RP. Govt. Medical College Kangra at Tanda in distt. Kangra HP Deposit work (SH: Providing and applying painting and aluminium work in Hospital Campus).	99691.00	2000.00	One Months
10	Repair of Mental Health Building at Dr. R.P. Govt. Medical College Kangra at Tanda in Distt. Kangra HP Deposit Work (SH: Providing and fixing aluminium partition, aluminium grill etc in Second floor).	99467.00	2000.00	One Months
11	Repair of Taruma Centre at Dr. R.P. Govt. Medical College Tanda in Distt. Kangra HP Deposit Work (SH: Providing and applying paint work,curtain rod, providing and fixing aluminium work, roof work & Glass panes etc Part-l)	77071.00	1550.00	One Months
12	Annual repair and maintanc of 500 Bedded Hospital in Dr. RP. Govt. Medical College Kangra at Tanda in Distt. Kangra HP Deposit work (SH: Providing and applying antifungal paint at ICU first Floor).	90506.0	1850.00	One Months
13	Repair of Main Entry Gate at Dr. R.P. Govt. Medical College Kangra at Tanda in Distt. Kangra HP Deposit Work (SH: Providing and fixing Golden Acrylic letters D/S Arc).	74575.00	1500.00	One Months
14	Repair of Guest House Toilet of Room No. 105 to 108 at Dr. R.P. Govt. Medical College Kangra at Tanda in Distt. Kangra HP Deposit work (SH: Providing and laying stone soling, C.c. 1:2:4 and C.c. 1:3:6 etc.).	89969.00	1800.00	One Months
15	Repair of OPD No.11 at Dr. RPGMC Kangra at Tanda in Distt. Kangra HP Deposit Work (SH: Painting distempering work W.S. & S.I. etc).	59234.00	1200.00	One Months
16	Repair of Guest House Toilet of Room No. 105 to 108 at Dr. R.P. Govt. Medical College Kangra at Tanda in Distt. Kangra HP Deposit work (SH: Dismantling C.C. work, providing and laying tiles etc).	87782.00	1800.00	One Months
17	Repair of Children Ward -1 in 500 Bedded Hospital at Dr. R.P. govt. Medical College Kangra at Tanda in Distt. Kangra HP Deposit Work (SH: Providing and laying tile work, W.S. & S.I. etc. Bath-l).	74036.00	1500.00	One Months
18	Balance work of Guest House Building at Dr. R.P. Govt. Medical College Kangra at Tanda in Distt. Kangra HP Deposit Work (SH: Providing and fixing glass panes, contruction of chamber, W.s. & S.I. work etc).	99961.00	2000.00	One Months

**Terms & Conditions:-)**

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor / firm have to produce the copy of latest enlistment and renewal enlisted in HPPWD.
3. If any of the date mentioned above happened to be Gazetted Holidays the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tenders without assigning any reason.
5. The Contractor will have to submit affidavit along with application for issue of tender form.
6. Next tender will be issued only after completion of previous works in hand.

**HIMSUCHANA AVAM & JAN SAMPARK**

(On behalf of Governor of Himachal Pradesh)

No.PW/NBD/TA/Tender/NIT/2025-26- **13541-55** Dated/ **30-03-2026**  
Copy to the following for information and necessary action:-

1. The Chief Engineer (KZ), HPPWD, Dharamshala.
2. The Executive Engineer IT Cell Shimla HP PWD Shimla.
3. The Superintending Engineer, 5<sup>th</sup> Circle, HPPWD, Palampur.
4. The Deputy Commissioner, Kangra at Dharamshala.
5. All the S.E.s/E.E.s under North Zone.
6. The Sub-Divisional Officer(C) Nagrota Bagwan.
7. All the Assistant Engineer under this Division.
8. The Drawing /Accounts Branch in this office.
9. Notice Board.

Executive Engineer  
H.P.P.W.D. Tanda Division  
at Nagrota Bagwan

Executive Engineer  
H.P.P.W.D. Tanda Division  
at Nagrota Bagwan

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

Sealed item rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, HP PWD Division Tanda at Nagrota Bagwan on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HP PWD (B & R) whose registration stood renewed as per revised rules so as to reach in his office on or before on 10.04.2026 up to 11:00 A.M. And the same shall be opened on the same day at 04:00 P.M. in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on 09.04.2026 up to 4:00 P.M and the application for issue of tender form shall be received on 08.04.2026 up to 12:00 noon. The applications for issue of tender forms accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates/Saving Account of the Post Office /Time Deposit account/FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP PWD Division Tanda at Nagrota Bagwan.

The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 120 days.

Sr. No.	Name of work	Estimated Cost	Earnest Money	Time limit
1.	Annual Repair and Maintenance of 500 Bedded Hospital at Dr. RP Govt. Medical College Tanda in Tehsil Nagrota Bagwan Distt. Kangra HP Deposit work (SH: Cleaning of Chocked Chamber Behind Medicine dispensary and Laundry).	95000.00	1900.00	One Months
2	Repair of CHW-1 and CHW-2 at Dr.R.P. Govt. Medial Collage Tanda in Distt. Kangra hP Deposit Work (SH: Painting and distempering CHW-l).	85285.00	1710.00	One Months
3	Construction of lecture Theatre Complex under EWS Scheme in Dr. R.P. govt. Medical College Kangra at Tanda in Distt. Kangra HP (SH Consturction of Pedestal for Shifting of Transformer form construction site stage -l).	75079.00	1550.00	One Month
4	Repair of Medical store Premises at Dr. R.P. Govt. Medical College tanda in Distt. Kangra HP Deposit work (SH:Painting and distempering part-l)	97074.00	1950.00	One Months
5	A/R & M/O to Internal roads in Dr. R.P. Govt. Medical College Kangra at Tanda in Distt. Kangra HP Deposit work (SH: Providing and fixing plastic speed braker speed bump).	85100.00	1700.00	One Months
6	Annual Repair and Maintenance of Internal roads in Dr. R.P. Govt. Medical College Kangra at Tanda in Distt. Kangra HP deposit work (SH: Providing and laying Kota stone, Repair to palster and painting on Railing).	99404.00	2000.00	One Months
7	Repair of Taruma Centre at Dr. R.P. Govt. Medical College Tanda in Distt. Kangra HP Deposit Work (SH: Providing and applying paint work curtain rod, providing and fixing aluminium work roof work & Glass panes etc part-l)	77071.00	1550.00	One Months
8	Annual Repair and Maintenance of Internal roads in Dr. R.P. Govt. Medical College Kangra at Tanda in Distt. Kangra HP deposit work (SH: Providing and laying Kota stone, Repair to palster and painting on Railing).	99382.00	2000.00	One Months
9	Repair of 500 bedded Hospital at Dr. RP. Govt. Medical College Kangra at Tanda in distt. Kangra HP Deposit work (SH: Providing and applying painting and aluminium work in Hospital Campus).	99691.00	2000.00	One Months
10	Repair of Mental Health Building at Dr. R.P. Govt. Medical College Kangra at Tanda in Distt. Kangra HP Deposit Work (SH: Providing and fixing aluminium partition, aluminium grill etc in Second floor).	99467.00	2000.00	One Months
11	Repair of Taruma Centre at Dr. R.P. Govt. Medical College Tanda in Distt. Kangra HP Deposit Work (SH: Providing and applying paint work,curtain rod, providing and fixing aluminium work, roof work & Glass panes etc Part-l)	77071.00	1550.00	One Months
12	Annual repair and maintanc of 500 Bedded Hospital in Dr. RP. Govt. Medical College Kangra at Tanda in Distt. Kangra HP Deposit work (SH: Providing and applying antifungal paint at ICU first Floor).	90506.0	1850.00	One Months
13	Repair of Main Entry Gate at Dr. R.P. Govt. Medical College Kangra at Tanda in Distt. Kangra HP Deposit Work (SH: Providing and fixing Golden Acrylic letters D/S Arc).	74575.00	1500.00	One Months
14	Repair of Guest House Toilet of Room No. 105 to 108 at Dr. R.P. Govt. Medical College Kangra at Tanda in Distt. Kangra HP Deposit work (SH: Providing and laying stone soling, C.c. 1:2:4 and C.c. 1:3:6 etc.).	89969.00	1800.00	One Months
15	Repair of OPD No.11 at Dr. RPGMC Kangra at Tanda in Distt. Kangra HP Deposit Work (SH: Painting distempering work W.S. & S.I. etc).	59234.00	1200.00	One Months
16	Repair of Guest House Toilet of Room No. 105 to 108 at Dr. R.P. Govt. Medical College Kangra at Tanda in Distt. Kangra HP Deposit work (SH: Dismantling C.C. work, providing and laying tiles etc).	87782.00	1800.00	One Months
17	Repair of Children Ward -1 in 500 Bedded Hospital at Dr. R.P. govt. Medical College Kangra at Tanda in Distt. Kangra HP Deposit Work (SH: Providing and laying tile work, W.S. & S.I. etc. Bath-l).	74036.00	1500.00	One Months
18	Balance work of Guest House Building at Dr. R.P. Govt. Medical College Kangra at Tanda in Distt. Kangra HP Deposit Work (SH: Providing and fixing glass panes, contruction of chamber, W.s. & S.I. work etc).	99961.00	2000.00	One Months

**Terms & Conditions:-)**

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor / firm have to produce the copy of latest enlistment and renewal enlisted in HPPWD.
3. If any of the date mentioned above happened to be Gazetted Holidays the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tenders without assigning any reason.
5. The Contractor will have to submit affidavit along with application for issue of tender form.
6. Next tender will be issued only after completion of previous works in hand.

**HIMSUCHANA AVAM & JAN SAMPARK**

(On behalf of Governor of Himachal Pradesh)

No.PW/NBD/TA/Tender/NIT/2025-26-13541-55 Dated/ 30-03-2026  
Copy to the following for information and necessary action:-

1. The Chief Engineer (KZ), HPPWD, Dharamshala.
2. The Executive Engineer IT Cell Shimla HP PWD Shimla.
3. The Superintending Engineer, 5<sup>th</sup> Circle, HPPWD, Palampur.
4. The Deputy Commissioner, Kangra at Dharamshala.
5. All the S.E.s/E.E.s under North Zone.
6. The Sub-Divisional Officer(C) Nagrota Bagwan.
7. All the Assistant Engineer under this Division.
8. The Drawing /Accounts Branch in this office.
9. Notice Board.

Executive Engineer  
H.P.P.W.D. Tanda Division  
at Nagrota Bagwan

Executive Engineer  
H.P.P.W.D. Tanda Division  
at Nagrota Bagwan

**Schedule of Quantity**

ESTIMATED COST: - ₹ 95000.00  
EARNEST MONEY :- ₹ 1900.00  
TIME LIMIT : ONE MONTH

**Name of Work:-** Annual Repair and Maintenance of 500 Bedded Hospital at Dr. R.P. Govt. Medical College Tanda in Tehsil Nagrota Bagwan, Distt. Kangra (H.P.) **(Deposit Work)**  
**Sub Head:-** Cleaning of Chocked Chamber Behind Medicine Dispensary and Laundry.

Sr. No	Description Of Item	Quantity	Rate		Unit	Amount
			In fig	In words		
1	Cleaning of Chocked Chanbers complete as per direction of Engineer-In-charge including carriage of material within all leads, lifts and other incidentals.	50 Numbers			Each	
<b>Total:-</b>						

Executive Engineer,  
HP PWD Division,  
Tanda at Nagrota Bagwan.

### Schedule of Quantity

ESTIMATED COST :- ₹ 85285.00  
EARNEST MONEY :- ₹ 1710.00  
TIME LIMIT : ONE MONTH

**Name of Work:-** Repair of CHW-1 and CHW-2 at Dr. R.P. Govt. Medical College Tanda in Dist. Kangra (H.P.) (Deposit Work)

**Sub Head:-** Painting and distempering. (Part)  
CHW-1

Sr. No	Description Of Item	Quantity	Rate		Unit	Amount
			In fig	In words		
1	Wall painting Two or more coats with acrylic emulsion paint of approved brand and manufacture to give an even shade complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	730.18			Per Square metre	
2	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	438.11			Per Square metre	
<b>Total:-</b>						

Executive Engineer  
HP PWD Division,  
Tanda at Nagrota Bagwan.


## Schedule of Quantity

ESTIMATED COST : - ₹ 75079.00  
 EARNEST MONEY : - ₹ 1550.00  
 TIME LIMIT : ONE MONTH

**Name of Work:-** Construction of Lecture Theatre Complex Under EWS Scheme in Dr. R.P. Govt. Medical College Kangra at Tanda in Distt. Kangra (H.P.)

**Sub Head:-** Construction of Pedestal for Shifting of Transformer form Construction site. **Stage I**

Sr. No	Description Of Item	Quantity	Rate		Unit	Amount
			In fig	In words		
1	Earthwork in excavation for structures as per drawing:Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms; lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed; within a lead of 50 m. Ordinary rock complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	4.75 Cubic metres			Per Cubic metre	
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 40 mm nominal size) complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	10.22 Cubic metres			Per Cubic metre	
3	Providing and Laying Stone soling under floor complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	6.30 Cubic metres			Per Cubic metre	
4	Centering and shuttering including strutting, propping etc. and removal of form for :Suspended floors; roofs, landings, balconies and access platform complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	14.50 Square metres			Per Square metre	
<b>Total:-</b>						

  
 Executive Engineer,  
 HP PWD Division,  
 Tanda at Nagrota Bagwan.

### Schedule of Quantity

ESTIMATED COST: - ₹ 97074.00  
EARNEST MONEY: - ₹ 1950.00  
TIME LIMIT: - ONE MONTH

**Name of Work:-** Repair of Medical store Premises at Dr. R.P. Govt. Medical College Tanda in Distt. Kangra (H.P.) (Deposit Work)  
**Sub Head:-** Painting and distempering.

Sr. No	Description Of Item	Quantity	Rate		Unit	Amount
			In fig	In words		
1	Wall painting Two or more coats with acrylic emulsion paint of approved brand and manufacture to give an even shade complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	831.11			Per Square metre	
2	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	498.67			Per Square metre	
<b>Total:-</b>						

Executive Engineer,  
HP PWD Division,  
Tanda at Nagrota Bagwan.

Schedule of Quantity

ESTIMATED COST :- ₹ 85100.00  
 EARNEST MONEY :- ₹ 1700.00  
 TIME LIMIT :- ONE MONTH

NAME OF WORK :- A/R & M/O on Internal Roads in Dr. R.P. Govt. Medical College Kangra at Tanda in Distt. Kangra (H.P.). Deposit work.  
SUB HEAD :- *Providing and fixing plastic speed breaker (speed bump)*

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In Fig.	In Words		
1	Speed Bump designed so dynamically and compact that it can bear maximum load on it. The body of the speed bump is made of ABS material. Two highly reflective reflectors moulded in PMMA material are welded with ABS base through ultrasonic welding process and then fixed on the speed bump so that dust and water cannot touch the reflector's inside area and thus it maintains its reflectivity for a long time. Size of the speed bump: Length=500mm (Five hundred millimetres) width 375mm (Three hundred seventy five millimetres) height 50 (Fifty millimeter) weight 2.7 Kg (Two point seven kilogram) per piece without filling as per direction by the Engineer-in-Charge including entire carriage of materials within all leads, lifts and other incidentals..	46.00 Running metres	4		Per running metre	
<b>TOTAL :-</b>						

Executive Engineer,  
 H.P.P. W.D. Division,  
 Tanda at Nagrota Bagwan.

## Schedule of Quantity

ESTIMATED COST: - ₹ 99404.00  
 EARNEST MONEY: - ₹ 2000.00  
 TIME LIMIT: ONE MONTH

**Name of Work:-** Annual Repair and Maintenance of Internal Roads in Dr. R.P. Govt. Medical College Kangra at Tanda in Distt. Kangra (H.P.) (Deposit Work)  
**Sub Head:-** Providing and Laying Kota stone, Repair to plaster and Painting on Railing.

Sr. No	Description Of Item	Quantity	Rate		Unit	Amount
			In fig	In words		
1	Kota stone slabs 20 mm thick in risers of steps, skirting, dado and pillars laid on 12 mm (average) thick cement mortar 1:3 (1 cement: 3 coarse sand) and jointed with grey cement slurry mixed with pigment to match the shade of the slabs, including rubbing and polishing complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	53.44	Square metres		Per Square metre	
2	Repair to plaster of thickness 12mm to 20 patches of area 2.5 sqm and under, including cutting the patch in proper shape, raking out joints and preparing plastering the wall surface with white cement based polymer modified self curing mortar, including disposal of rubbish complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	26.70	Square metres		Per Square metre	
3	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	128.40	Square metres		Per Square metre	
<b>Total:-</b>						

  
 Executive Engineer,  
 HP PWD Division,  
 Tanda at Nagerotia Bagwan.

## Schedule of Quantity

ESTIMATED COST: - ₹ 77071.00  
 EARNEST MONEY :- ₹ 1550.00  
 TIME LIMIT : ONE MONTH

**Name of Work:-** Repair of Taruma Centre at Dr. R.P. Govt. Medical College Tanda in Dist. Kangra (H.P.) (Deposit Work)

**Sub Head:-** Providing and applying paint work, curtain rod, providing and fixing aluminium work, roof work & Glass panes etc. (Part-1)

Sr. No	Description Of Item	Quantity	Rate		Unit	Amount
			In fig	In words		
1	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	13.00			Per Square metre	
2	Wall painting Two coats with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacturer, including applying additional coats wherever required to achieve even shade and colour complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	64.25			Per Square metre	
3	Providing and fixing 25 mm dia chromium plated brass curtain rod having wall thickness of 1.25mm with two chromium plated brass brackets fixed with C.P. brass screws and PVC sleeves etc., wherever necessary complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	18.00			Per Running metre	
4	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mired and jointed mechanically wherever required including clear angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15) complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	91.23			Per Kilogram	
5	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mired and jointed mechanically wherever required including clear angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC15) complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	22.79			Per Kilogram	
6	Providing and fixing 12 mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in paneling fixed in aluminium doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer- in-charge. Pre-laminated particle board with decorative lamination on both sides complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	6.39			Per Square metres	

2

Sr. No	Description Of Item	Quantity	Rate		Unit	Amount
			In fig	In words		
7	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item): With float glass panes of 5 mm thickness (weight not less than 12.50 kg/ sqm) complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and	3.12			Per Square metre	
8	Providing and fixing fly proof stainless steel grade 304 wire gauge, to windows and clerestory windows using wire gauge with average width of aperture 1.4 mm in both directions with wire of dia. 0.50 mm all complete With 12 mm mild steel U beading complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	2.25			Per Square metre	
<b>Total:-</b>						

  
 Executive Engineer,  
 HP PWD Division,  
 Tanda at Nagrota Bagwan.

## Schedule of Quantity

ESTIMATED COST: - ₹ 99382.00  
 EARNEST MONEY : - ₹ 2000.00  
 TIME LIMIT : ONE MONTH

**Name of Work:-** Annual Repair and Maintenance of Internal Roads in Dr. R.P. Govt. Medical College Kangra at Tanda in Dist. Kangra (H.P.) (Deposit Work)  
**Sub Head:-** Providing and Laying Kota stone, Repair to plaster and Painting on Railing.

Sr. No	Description Of Item	Quantity	Rate		Unit	Amount
			In fig	In words		
1	Kota stone slabs 20 mm thick in risers of steps, skirting, dado and pillars laid on 12 mm (average) thick cement mortar 1:3 (1 cement: 3 coarse sand) and jointed with grey cement slurry mixed with pigment to match the shade of the slabs, including rubbing and polishing complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	53.42			Per Square metre	
2	Repair to plaster of thickness 12mm to 20 patches of area 2.5 sqm and under, including cutting the patch in proper shape, raking out joints and preparing plastering the wall surface with white cement based polymer modified self curing mortar, including disposal of rubbish complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	26.72			Per Square metre	
3	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	128.45			Per Square metre	
<b>Total:-</b>						

Executive Engineer,  
 HP PWD Division,  
 Tanda at Nagrota Bagwan.

### Schedule of Quantity

ESTIMATED COST :- ₹ 99691.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT : ONE MONTH


**Name of Work:-** Repair of 500 Bedded Hospital at Dr. R. P. Govt. Medical College Kangra at Tanda in Distt. Kangra (H.P.) (Deposit Work)

**Sub Head:-** Providing and applying, painting and aluminium work in Hospital Campus.

Sr. No	Description Of Item	Quantity	Rate		Unit	Amount
			In fig	In words		
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scraping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	768.06			Per Square metre	
2	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	225.25			Per Square metre	
3	Wall painting Two coats with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacturer, including applying additional coats wherever required to achieve even shade and colour complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	768.06			Per Square metre	
4	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mired and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing/ paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC15) complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	21.78			Per kilogram	
5	Providing and fixing 12 mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in paneling fixed in aluminium doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer- in-charge. Pre-laminated particle board with decorative lamination on both sides complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	1.17			Per Square metre	
6	Providing and fixing 300 mm stainless steel handles with necessary screws etc. complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	4			Each	
7	Providing and fixing aluminium extruded section body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 36 kg to 89 kg and door width from 701 mm to 1000 mm), with double speed adjustment with necessary accessories and screws etc. complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	4			Each	

9

Sr. No	Description Of Item	Quantity	Rate		Unit	Amount
			In fig	In words		
8	Providing and fixing double action hydraulic floor spring of approved brand and manufacture conforming to IS : 6315, having brand logo embossed on the body / plate with double spring mechanism and door weight upto 125 kg, for doors, including cost of cutting floors, embedding in floors as required and making good the same matching to the existing floor finishing and cover plates with brass pivot and single piece M.S. sheet outer box with slide plate etc. complete as per the direction of Engineer-in-charge. With stainless steel cover plate minimum 1.25 mm thickness complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	2 Numbers			Per Running metre	
<b>Total:-</b>						

  
 Executive Engineer,  
 HP PWD Division,  
 Tanda at Nagrota Bagwan.

## Schedule of Quantity


ESTIMATED COST: - ₹ 99467.00  
EARNEST MONEY: - ₹ 2000.00  
TIME LIMIT: ONE MONTH

**Name of Work:-** Repair of Mental Health Building at Dr. R.P. Govt. Medical College Kangra at Tanda in Distt. Kangra (H.P.) (Deposit Work)

**Sub Head:-** Providing and fixing aluminium partition, aluminium grill etc. in Second floor.

Sr. No	Description Of Item	Quantity	Unit	Rate		Amount
				In fig	In words	
1	Providing and fixing 25 mm thick Pre-laminated flat pressed 3 layer (medium density) particle board or graded wood particle board IS : 3087 marked, with one side decorative and other side balancing lamination Grade I, Type II exterior grade IS : 12823 marked, in shelves with screws and fittings wherever required, edges to be painted with polyurethane primer (fittings to be paid separately) complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	30.60	Square metres			
2	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, milled and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing/ paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately). Powder coated aluminium (minimum thickness of powder coating 50 micron) complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	43.94	Kilogram			
3	Providing and fixing 12mm thick pre-laminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in paneling fixed in aluminium doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer- in-charge. Pre-laminated particle board with decorative lamination on both sides complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	3.85	Square metres			
4	Providing and fixing anodised aluminium grill (anodised transparent or dyed to required shade according to IS: 1868 with minimum anodic coating of grade AC 15) of approved design/pattern, with approved standard section and fixed to the existing window frame with C.P. brass/ stainless steel screws @ 200 mm centre to centre, including cutting the grill to proper opening size for fixing and operation of handles and fixing approved anodised aluminium standard section around the opening, all complete as per requirement and direction of Engineer-in- charge. (Only weight of grill to be measured for payment) complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	44.85	Kilogram			
5	Providing and fixing 125 mm aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	1	Numbers			
6	Providing and fixing aluminium extruded section body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 36 kg to 80 kg and door width from 701 mm to 1000 mm), with double speed adjustment with necessary accessories and screws etc. complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	1	Numbers			
7	Providing and fixing aluminium hanging floor door stopper, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade, with necessary screws etc. complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	1	Numbers			

Sr. No	Description Of Item	Quantity	Rate		Unit	Amount
			In fig	In words		
8	Providing and fixing 250x16 mm aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	1			Each	
9	Providing and fixing 250x10 mm aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868 ) transparent or dyed to required colour or shade, with necessary screws etc. complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	1			Each	
<b>Total:-</b>						

  
 Executive Engineer,  
 HP PWD Division,  
 Tanda at Nagrota Bagwan.

## Schedule of Quantity

**Name of Work:-** Repair of Trauma Centre at Dr. R.P. Govt. Medical College Tanda in Distt. Kangra (H.P.) **(Deposit Work)**

**Sub Head:-** Providing and applying paint work, curtain rod, providing and fixing aluminium work, roof work & Glass panes etc. (Part-I)

ESTIMATED COST. - ₹ 77071.00  
 EARNEST MONEY. - ₹ 1550.00  
 TIME LIMIT : ONE MONTH

Sr. No	Description Of Item	Quantity	Rate		Unit	Amount
			In fig	In words		
1	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	13.00 Square metres			Per Square metre	
2	Wall painting [Two coats with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	64.25 Square metres			Per Square metre	
3	Providing and fixing 25 mm dia chromium plated brass curtain rod having wall thickness of 1.25mm with two chromium plated brass brackets fixed with C.P. brass screws and PVC sleeves etc., wherever necessary complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	18.00 Running metres			Per Running metre	
4	Providing and fixing aluminium work for doors, windows, ventilators and partitions frame with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, milled and jointed mechanically wherever required including clear angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15) complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	91.23 Kilograms			Per Kilogram	
5	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, milled and jointed mechanically wherever required including clear angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC15) complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	22.79 Kilograms			Per Kilogram	
6	Providing and fixing 12 mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in paneling fixed in aluminium doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer- in-charge. Pre-laminated particle board with decorative lamination on both sides complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	6.39 Square metres			Per Square metre	

5

Sr. No	Description Of Item	Quantity	Rate		Unit	Amount
			In fig	In words		
7	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item): With float glass panes of 5 mm thickness (weight not less than 12.50 kg/ sqm) complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and	3.12	Square metres		Per Square metre	
8	Providing and fixing fly proof stainless steel grade 304 wire gauge, to windows and clerestory windows using wire gauge with average width of aperture 1.4 mm in both directions with wire of dia. 0.50 mm all complete With 12 mm mild steel U beading complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	2.25	Square metres		Per Square metre	
<b>Total:-</b>						


  
 Executive Engineer,  
 HP PWD Division,  
 Tanda at Nagrota Bagwan.

### Schedule of Quantity

ESTIMATED COST :- ₹ 90506.00  
EARNEST MONEY :- ₹ 1850.00  
TIME LIMIT : ONE MONTH  
(Deposit Work)

**Name of Work:-** Annual repair and maintenance of 500 Bedded Hospital in Dr. R.P. Govt. Medical College Kangra at Tanda in Dist. Kangra (H.P.)  
**Sub Head:-** Providing and applying antifungal paint at ICU First Floor.

Sr. No	Description Of Item	Quantity	Rate		Unit	Amount
			In fig	In words		
1	Finishing walls with 100% premium antifungal emulsion paint having VOC less than 50gm/litre and UV resistance, alkali & fungal resistance two or more coat and preparing the surface smooth to give an even surface complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	683.58			Per Square metre	
2	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	205.07			Per Square metre	
<b>Total:-</b>						

  
Executive Engineer,  
HP PWD Division,  
Tanda at Nagrota Bagawan.

### Schedule of Quantity

ESTIMATED COST: - ₹ 74575.00  
EARNEST MONEY: - ₹ 1500.00  
TIME LIMIT: ONE MONTH

**Name of Work:-** Repair of Main Entry Gate at Dr. R.P. Govt. Medical College Kangra at Tanda in Dist. Kangra (H.P.) (Deposit Work)

**Sub Head:-** Providing and fixing Golden Acrylic Letters: D/S Arc.

Sr. No	Description Of Item	Quantity	Rate		Unit	Amount
			In fig	In words		
1	Centering and shuttering including strutting, propping etc. and removal of form for scaffolding complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	32.50			Per Square metre	
2	Providing and fixing Golden Acrylic Letter with necessary screws and fitting complete including dismantling of old letters complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	29			Each	
<b>Total:-</b>						

Executive Engineer,  
HP PWD Division,  
Tanda at Nagrota Bagwan.

### Schedule of Quantity

ESTIMATED COST: - ₹ 89969.00  
EARNEST MONEY: - ₹ 1800.00  
TIME LIMIT : ONE MONTH

**Name of Work:-** Repair of Guest House Toilet of Room No. 105 to 108 at Dr. R.P. Govt. Medical College Kangra at Tanda in Distr. Kangra (H.P.) (Deposit Work)  
**Sub Head:-** Providing and laying stone soling, C.C. 1:2:4 and C.C. 1:3:6 etc.

Sr. No	Description Of Item	Quantity	Rate		Unit	Amount
			In fig	In words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	13.17			Per Cubic metre	
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	4.39			Per Cubic metre	
3	Providing and laying Stone soling under floor complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	7.06			Per Cubic metre	
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	11.87			Per Cubic metre	
<b>Total:-</b>						


Executive Engineer,  
HP PWD Division,  
Tanda at Nagrota Bagwan.

## Schedule of Quantity

ESTIMATED COST :- ₹ 59234.00  
EARNEST MONEY :- ₹ 1200.00  
TIME LIMIT : ONE MONTH

**Name of Work:-** Repair of OPD No. 11 at Dr. R.P. Govt. Medical College Kangra at Tanda in Dist. Kangra (H.P.) (Deposit Work)  
**Sub Head:-** Painting, distemperring work, W.S. & S.I. etc.

Sr. No	Description Of Item	Quantity	Rate		Unit	Amount
			In fig	In words		
1	Wall painting Two or more coats on new work with acrylic emulsion paint of approved brand and manufacture to give an even shade complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	143.37			Per Square metre	
2	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	86.02			Per Square metre	
3	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/e fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints 15 mm nominal outer dia Pipes complete complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	6.00			Per Running metre	
4	Providing and fixing 150 mm dia P.V.C Pipe including all fittings and adhesive complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	60.00			Per Running metre	
5	Providing and Fixing 150 mm dia P.V.C Bend including all fittings and adhesive complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	6			Per Running metre	
6	Providing and fixing 600x450 mm beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	2			Each	
7	Providing and fixing PTMT soap Dish Holder having length of 138mm, breadth 102mm, height of 75mm with concealed fitting arrangements, weighing not less than 106 gms complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	2			Each	
8	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require.White Vitreous China Wash basin size 630x450 mm with a pair of 15 mm C.P. brass pillar taps complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	2			Each	
9	Providing and fixing 32 mm dia P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	2			Each	
10	Providing and fixing 100 mm sand cast Iron grating for gully trap complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	2.00			Each	
11	Providing and fixing 15 mm nominal bore uplasticed PVC connection pipe with brass unions complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	4			Each	
12	Providing and fixing 15mm nominal bore C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	4			Each	
<b>Total:-</b>						


  
 Executive Engineer,  
 HP PWD Division,  
 Tanda at Nagrota Bagwan.

## Schedule of Quantity

ESTIMATED COST :- ₹ 87782.00  
 EARNEST MONEY :- ₹ 1800.00  
 TIME LIMIT : ONE MONTH

**Name of Work:-** Repair of Guest House Toilet of Room No. 105 to 108 at Dr. R.P. Govt. Medical College Kangra at Tanda in Distt. Kangra (H.P.) (Deposit Work)  
**Sub Head:-** Dismantling C.C. work, providing and laying tiles etc.

Sr. No	Description Of Item	Quantity	Rate		Unit	Amount
			In fig	In words		
1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles above 25 mm and up to 40 mm complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	63.92			Per Square metre	
2	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer-in-charge complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	18.77			Per Cubic metre	
3	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), Jointing with grey cement slurry @ 3.3 kg/sqm including pointing the joints with white cement and matching pigment etc. complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	16.92			Per Square metre	
4	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	8.56			Per Square metre	
5	Providing and laying 600x600 mm size of Tile vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc. complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	35.28			Per Square metre	
<b>Total:-</b>						

  
 Executive Engineer,  
 HP PWD Division,  
 Tanda at Nagrota Bagwan.

## Schedule of Quantity


ESTIMATED COST: - ₹ 74036.00  
 EARNEST MONEY: - ₹ 1500.00  
 TIME LIMIT : ONE MONTH

**Name of Work:-** Repair of Children Ward-I in 500 Bedded Hospital at Dr. R.P. Govt. Medical College Kangra at Tanka in Dist. Kangra (H.P.) (Deposit Work)  
**Sub Head:-** Providing and laying tile work, W.S. & S.I. etc. Bath-I

Sr. No	Description Of Item	Quantity	Rate		Unit	Amount
			In fig	In words		
1	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Flame Red Brown, laid on 20 mm thick bed of cement mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3 kg/sqm including pointing the joints with white cement and matching pigments etc. complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	13.26			Per Square metre	
2	Providing and fixing 1st quality ceramic glazed floor tiles of size 300x450mm conforming to IS : 15622 (thickness to be specified by the manufacturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of steps and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with pigment of matching shade complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	26.28			Per Square metre	
3	Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100 mm sand cast Iron P or S trap, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required white Vitreous china Orissa pattern W.C. pan of size 480x440 mm with integral type foot rests complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	1			Number	
4	Providing and fixing white vitreous china pedestal type water closet (European type) with seat and lid, 10 litre low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I. brackets, 40 mm flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid plastic seat and lid complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	1			Number	
5	Providing and fixing 8 mm dia C.P. / S.S. Jet with flexible tube upto 1 metre long with S.S. triangular plate to European type W.C. of quality and make as approved by Engineer - in - charge complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	1			Number	
6	Providing and fixing 10 litre capacity - White P.V.C. low level flushing cistern with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	2			Numbers	
7	Providing and fixing 15 mm nominal C.P. brass long nose bib cock of approved quality conforming to IS standards and weighing not less than 810 gms complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	3			Numbers	
8	Providing and fixing 100 mm inlet and 75 mm outlet trap of self cleansing design with screwed down or hinged grating with or without vent arm complete, including cost of cutting and making good the walls and floors : Hubless centrifugally cast (spun) iron epoxy coated inside & outside as per IS:15905 complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	2			Numbers	

3

Sr. No	Description Of Item	Quantity	Rate		Unit	Amount
			In fig	In words		
9	Providing and fixing 15mm diameters brass angle valve without nuts as per approved drawing and design directed by the Engineer-in-charge complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	5 Numbers			Each	
10	Providing and fixing 110 mm diameter on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (1) Single socketed pipes complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	19.00 Running metres			Per Running metre	
11	Providing and fixing Bend 87.5° 110 mm bend on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	3 Numbers			Each	
12	Providing and fixing 20 mm nominal outer dia Pipes Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/e fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls etc. complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	20.00 Running metres			Per Running metre	
<b>Total:-</b>						

  
 Executive Engineer,  
 HP PWD Division,  
 Tanda at Nagrota Bagwan.

### Schedule of Quantity


ESTIMATED COST :- ₹ 99961.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT : ONE MONTH

**Name of Work:-** Balance work of Guest House Building at Dr. R. P. Govt. Medical College Kangra at Tanda in Dist. Kangra (H.P.) (Deposit Work)

**Sub Head:-** Providing and fixing glass panes, construction of chamber, W.S. & S.I. work etc.

Sr. No	Description Of Item	Quantity	Rate		Unit	Amount
			In fig	In words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	48.00			Per Cubic metre	
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	3.00			Per Cubic metre	
3	Providing and fixing 150 mm PVC Pipe 6kg pressure including all adhesive and fitting complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	50.00			Per Running metres	
4	Providing and fixing 150 mm Tee 6kg pressure including all adhesive and fitting complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	6			Each	
5	Providing and fixing 150 mm PVC plain Bend 6kg pressure including all adhesive and fitting complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	6			Each	
6	Providing and fixing 15 mm nominal bore uplasticsed PVC connection pipe with brass unions complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	26			Each	
7	Providing and fixing PTMT soap Dish Holder having length of 138mm, breadth 102mm, height of 75mm with concealed fitting arrangements, weighing not less than 106 gms. complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	13			Each	
8	Providing and fixing 15mm nominal bore C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	10			Each	
9	Providing and fixing 600x450 mm beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	3			Each	
10	Providing and fixing Towel rail complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality and colour 600 mm long towel rail with total length of 645 mm, width 78 mm and effective height of 88 mm, weighing not less than 190 gms. complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	3			Each	

Sr. No	Description Of Item	Quantity	Rate		Unit	Amount
			In fig	In words		
11	Constructing masonry Chamber 60x60x75 cm inside, in brick work in cement mortar 1:4 (1 cement : 4 coarse sand) for sluice valve, with C.I. surface box 100mm top diameter, 160 mm bottom diameter and 180 mm deep ( inside) with chained lid and RCC top slab 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size ) , i/c necessary excavation, foundation concrete 1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40 mm nominal size) and inside plastering with cement mortar 1:3 (1 cement : 3 coarse sand) 12 mm thick, finished with a floating coat of neat cement complete as per standard design .With common burnt clay F.P.S.(non modular) bricks of class designation 7.5 complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	3	Numbers		Each	
12	Providing & fixing 5.5 mm thick glass panes with putty and glazing clips in steel doors, windows, clerestory windows, all complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	13.48	Square metres		Per Square metre	
<b>Total:-</b>						

  
 Executive Engineer,  
 HP PWD Division,  
 Tanda at Nagrota Bagwan.