



Office of the Executive Engineer
Tissa Division, HPPWD Bhanjraru, District Chamba (H.P.)-176316
Himachal Pradesh
Public Works Department

No. PWD-ID/TA/Tender/2025-26- 17337-39

Offline
Dated: - 30-03-2026

To


The Executive Engineer (IT Cell)
Nigam Bihar Shimla-2

Subject: - Publishing of Tender Notice.

Dear Sir,

Enclosed please find herewith the tender Notice of work as given in the Notice inviting Tender for uploading on department website as per notification Principal Secretary (PW) to the Govt. of Himachal Pradesh letter No. PBW-(B) A9 (3)1/2020 dated Shimla-2 the 16th July 2021 as the work mentioned in the tender notice are urgent in nature and public interest.

DA/ As above.


Executive Engineer,
Tissa Division, HPPWD,
Tissa.


Copy forwarded to the Superintending Engineer, 7th Circle, HPPWD, Dalhousie for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer, (IT Cell) Nigam Bihar Shimla-2 for information and further necessary action.


Executive Engineer,
Tissa Division, HPPWD,
Tissa.

Certificate

Certified that the tenders called vide this office letter No. PWD-TD/TA/Tender /2025-26:-17237-17336 dated. 30-3-2026 is emergent nature due to heavy rain and clouds burst on several places and in Public interest.


Executive Engineer,
Tissa Division, HPPWD,
Tissa.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
"NOTICE INVITING TENDERS"**

Sealed Percentage/Item rate tender(s) on PWD from No 6 & 7/8 are hereby invited by the Executive Engineer, Tissa Division, HPPWD, Tissa behalf of the Governor of HP for the following works from the approved and eligible contractor/firm of appropriate Class enlisted in HPPWD as per the latest instructions so as to reach in this office as per time schedule given below. The offer of the tender will be kept open for 90 days from the date of opening of the tender. The undersigned reserves the right to reject any or all the tender without assigning any reasons:-

Date of issued/sale of tender form against

07-04-2026.

Date of opening of Tender:-

09-04-2026.

The tender shall be received upto 11.00 AM on 09-04-2026. and will be opened on the same day at 12.00 PM in the presence of intending Contractor or their authorized representative who may like to be present. The tender can be had from this office against E-Challan as shown below (Nonrefundable) during the working hours on 06-04-2026.

The Earnest Money in the shape of National Saving Certificate/Deposit at call/Time deposit/Account/in any Post Office/Nationalized Bank in HP duly pledged in favour of Executive Engineer, Tissa Division, HPPWD, Tissa a must accompany with each application. Conditional tender and the tender received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 75 days. The XEN reserve the right to accept or reject the tender without assigning any reasons:-

Job No.	Name of Work	Estimated cost.	Earnest Money	Time Limit	Cost of Form	Eligible Class
1	Widening of link road to village Bhanjraru Km 0/0 to 1/650 (SH:-Providing R/wall at Rd 0/102.50 to 0/107.50)	96078.00	2000	Two Month	350	D/C
2	Widening of link road to village Bhanjraru Km 0/0 to 1/650 (SH:-Providing R/wall at Rd 0/107.50 to 0/112.50)	96813.00	2000	Two Month	350	D/C
3	Widening of link road to village Bhanjraru Km 0/0 to 1/650 (SH:-Providing R/wall at Rd 0/920 to 0/940)	97433.00	2000	Two Month	350	D/C
4	Widening of link road to village Bhanjraru Km 0/0 to 1/650 (SH:-Providing R/wall at Rd 0/940 to 0/960)	96503.00	2000	Two Month	350	D/C
5	Restoration of rain damages on various roads under Tissa Sub-Division (SH:- Hiring of JCB for removal of slips at various Rd's)	99910.00	2000	Two Month	350	D/C
6	Restoration of rain damages on various roads of Tissa-I Section under Tissa Sub-Division (SH:- Hiring of JCB for removal of slips at various Rd's)	99910.00	2000	Two Month	350	D/C
7	Restoration of rain damages on Bhadkwas to Bulwas road Km 0/0 to 2/500. (SH:-Providing crate work B/wall at Rd 1/32.15 to 1/37.50 & 1/39 to 1/44)	86035.00	2000	Two Month	350	D/C
8	Restoration of rain damages on Bhadkwas to Bulwas road Km 0/0 to 2/500. (SH:-Providing crate work B/wall at Rd 1/44 to 1/49, 1/259 to 1/264 & 1/386 to 390)	91961.00	2000	Two Month	350	D/C

	C/o Bhanjraru to Chachrot road Km 0/0 to 0/640 (SH:- Providing R/wall at Rd 0/497.375 to 0/504.25)	95178.00	2000	Two Month	350	D/C
	Restoration of rain damages on various roads of Kiani Section under Koti Sub Division (SH:-Hiring of JCB for removal of slips at various Rds)	98880.00	2000	Two Month	350	D/C
11	Restoration of rain damages on various roads of Pukhri Section under Koti Sub Division (SH:-Hiring of JCB for removal of slips at various Rds)	99910.00	2000	Two Month	350	D/C
12	Restoration of rain damages on various roads of Leswin Section under Nakrot Sub Division (SH:-Hiring of JCB for removal of slips at various Rds)	98880.00	2000	Two Month	350	D/C
13	Restoration of rain damages on Nakrot Tikri Bhagheigarh roads Nakrot Sub Division (SH:-Hiring of JCB for removal of slips at various Rds)	99425.00	2000	Two Month	350	D/C
14	Restoration of rain damages due to laying of OFC on Chamba Tissa road Km 5/0 to 32/250 (SH:-Providing R/wall at Rd 22/267 to 22/273)	32361.00	2000	Two Month	350	D/C
15	Restoration of rain damages due to laying of OFC on Chamba Tissa road Km 5/0 to 32/250 (SH:-Providing R/wall at Rd 22/904 to 22/910)	92758.00	2000	Two Month	350	D/C
16	Restoration of rain damages on various roads under Nakrot Sub Division (SH: -Hiring of Tipper for removal of slips at various Rds)	96000.00	2000	Two Month	350	D/C

1. The tender forms will not be issued to those Contractors whose performance is not found satisfactory.
2. The Contractor should have executed two similar types of works 1/3 of each amount put to tender or single work amount equal to the amount put to tender within list five year.
3. GST No/Earnest Money Tender Form cost, copy of enlistment should be accompanied with application.

Executive Engineer
Tissa Division HPPWD
Tissa at Bhanjraru

Dated:- 30-03-2026

No.PW.TD.CB.TA.Tender Notice/2025-26- 17237-17336

Copy to the following for information for information please: -

1. Engineer-in-Chief HPPWD Shimla.
2. Chief Engineer (KZ) HPPWD Dharamshala.
3. The Superintending Engineer 7th Circle HPPWD Dalhousie.
4. All Executive Engineers in HPPWD.
5. SDM Tissa.
6. All the Assistant Engineer working under Tissa Division.
7. Tehsildar/BDO Tissa.
8. SHO Tissa.
9. All the contractors.
10. Notice Board.

Executive Engineer
Tissa Division HPPWD
Tissa at Bhanjraru

**Percentage Book
PRICE SCHEDULE**

Name of Work:- Widening of link road to village Bhanjaru Km 0/0 to 1/650
(S.H.:- Providing retaining wall at Rd 0/102.50 to 0/107.50)

Sr. No.	Description /Items of work.	Quantity	Unit	Rate		Amount in figure	Amount in words
				Figures	Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORO technical specification clause 305 and 1603.4 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax GST or	22.63	Per Cubic Metre	310.00	Rupees Three Hundred Ten Only	7015.00	Rupees Seven Thousand Fifteen Only
2	Providing and laying of boulder apron or gabion walls laid in wire crates with 4mm (four millimeter) dia G.I. wire (Galvanized iron wire) conforming to IS: 280 (IS:two hundred eighty) and IS: 4826 (IS: four thousand eight hundred twenty six) in 100mmx100mm (one hundred millimeter into one hundred millimeter) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints, laid with stone boulders weighing not less than 25 kg (Twenty five kilogram) each as per drawing and technical specification clause 1301 or as per the directions of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals. he rate including the octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	31.25	Per Cubic Metre	2850.00	Rupees Two Thousand Eight Hundred Fifty Only	89063.00	Rupees Eighty Nine Thousand Sixty Three Only
				(To be quoted by Contractor)		96078.00	
				(To be quoted by Contractor)			
				Quoted Rate in figure (%)			
				Quoted Rate in Words (%)			

D.N.I.T. approved for Rs. 96078/- only.

[Signature]
Assistant Engineer
Public Works Department
UDAIPUR

Name of Work:- Widening of link road to village Bhanjaru Km 0/0 to 1/650
 (S.H.:- Providing retaining wall at Rd 0/107.50 to 0/112.50)

Percentage Bidding
 PRICE SCHEDULE

Sr. No.	Description /Items of work.	Quantity	Unit	Rate		Amount in figure	Amount in words
				Figures	Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305 and 1603.4 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax GST or	25.00	Per Cubic Metre	310.00	Rupees Three Hundred Ten Only	7750.00	Rupees Seven Thousand Seven Hundred Fifty Only
2	Providing and laying of boulder apron or gabion walls laid in wire crates with 4mm (four millimeter) dia G.I. wire (Galvanized iron wire) conforming to IS: 280 (IS:two hundred eighty) and IS: 4826 (IS: four thousand eight hundred twenty six) in 100mmx100mm (one hundred millimeter into one hundred millimeter) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints, laid with stone boulders weighing not less than 25 kg (Twenty five kilogram) each as per drawing and technical specification clause 1301 or as per the directions of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals, he rate including the octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	31.25	Per Cubic Metre	2850.00	Rupees Two Thousand Eight Hundred Fifty Only	89063.00	Rupees Eighty Nine Thousand Sixty Three Only
						96813.00	
				(To be quoted by Contractor)			
				(To be quoted by Contractor)			

D.N.I.T. approved for Rs. 96813/-only

*Engineer
 Bhanjaru Division
 BSSA*

Percentage BOQ

PRICE SCHEDULE

Name of Work:- Widening of link road to village Bhaniraru Km 0/0 to 1/650
(S.H.:- Providing crate work retaining wall at RD 0/920 to 0/940)

Sr. No.	Description /Items of work.	Quantity	Unit	Rate		Amount in figure	Amount in words
				Figures	Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305 and 1603.4 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto an lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeter) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana toll tax, sale tax GST or any other taxes imposed by the Government.	27.00	Per Cubic Metre	310.00	Rupees Three Hundred Ten Only	8370.00	Rupees Eight Thousand Three Hundred Seventy Only
2	Providing and laying of boulder apron or gabion walls laid in wire crates with 4mm (four millimeter) dia G.I. wire (Galvanized iron wire) conforming to IS: 280 (IS:two hundred eighty) and IS: 4826 (IS: four thousand eight hundred twenty six) in 100mmx100mm (one hundred millimeter into one hundred millimeter) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints, laid with stone boulders weighing not less than 25 kg (Twenty five kilogram) each as per drawing and technical specification clause 1301 or as per the directions of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals. he rate including the octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	31.25	Per Cubic Metre	2350.00	Rupees Two Thousand Eight Hundred Fifty Only	89063.00	Rupees Eighty Nine Thousand Sixty Three Only
				(To be quoted by Contractor)		97433.00	
				(To be quoted by Contractor)			
				Quoted Rate in figure (%)			
				Quoted Rate in Words (%)			

D.M.I.T. approved for B. 97433/- only

Executive Engineer
Bissa Division Highway
BSSA

**Percentage BOQ
PRICE SCHEDULE**

Name of Work:- Widening of link road to village Bhanjaru Km 0/0 to 1/650
(S.H):- Providing grate work retaining wall at RD 0/940 to 0/960

Sr. No.	Description /Items of work.	Quantity	Unit	Rate		Amount in figure	Amount in words
				Figures	Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305 and 1603.4 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax GST or	24.00	Per Cubic Metre	310.00	Rupees Three Hundred Ten Only	7440.00	Rupees Seven Thousand Four Hundred Forty Only
2	Providing and laying of boulder apron or gabion walls laid in wire crates with 4mm (four millimeter) dia G.I. wire (Galvanized iron wire) conforming to IS: 280 (IS:two hundred eighty) and IS: 4826 (IS: four thousand eight hundred twenty six) in 100mmx100mm (one hundred millimeter into one hundred millimeter) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints, laid with stone boulders weighing not less than 25 kg (Twenty five kilogram) each as per drawing and technical specification clause 1301 or as per the directions of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals. he rate including the octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	3125	Per Cubic Metre	2850.00	Rupees Two Thousand Eight Hundred Fifty Only	89063.00	Rupees Eighty Nine Thousand Sixty Three Only
				(To be quoted by Contractor)		95503.00	
				(To be quoted by Contractor)			
				Quoted Rate in figure (%)			
				Quoted Rate in Words (%)			

D.M.I.T. approved for R. 96503/- only.

Engineer
Sissa Division H.P.W.D
SISSA

D.N.I.T.

Name of work:- Restoration of rain damages on various roads under Tissa Sub-Division (SH:- Hiring of JCB for removal of slips at various Rd's

S.N.	Description of item	Quantity	Rate		Unit	Amount
			In Fig.	In words		
1	Hiring of J.C.B./Excavator cum loader for removal of soil of all kind i.e. hard/loose or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from road surface upto any leads and lifts up to any height and depth as per direction and entire satisfactions of Engineer-in-Charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The repair and spare, watch and ward of machinery also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or any other taxes imposed by the Government.	97.00	1030.00	One thousand thirty only	Per Hour	99910.00
Total						99910.00

Estimated Cost Rs.= 99910.00
 Earnest Money Rs.= 2000.00
 Time Limit = One Months

D.N.I.T. approved for Rs. 99910/- only

[Signature]
 EXECUTING ENGINEER
 TISSA Division HP/MD
 TISSA


D.N.I.T.

Name of work:- Restoration of rain damages on various roads of Tissa-I Section under Tissa
Sub-Division (SH):- Hiring of JCB for removal of slips at various Rd's

Estimated Cost Rs. = 99910.00
Earrest Money Rs. = 2000.00
Time Limit = One Months

S.N.	Description of item	Quantity	Rate		Unit	Amount
			In Fig.	In words		
1	Hiring of J.C.B./Excavator cum loader for removal of soil of all kind i.e. hard/loose or removal of slips in all kinds of soil and disposing of all excavated earth or un-servicable materials from road surface upto any leads and lifts up to any height and depth as per direction and entire satisfactions of Engineer-in-Charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The repair and spare, watch and ward of machinery also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or any other taxes imposed by the Government.	97.00	1030.00	One thousand thirty only	Per Hour	99910.00
Total						99910.00

D.N.I.T. approved for Rs. 99910/- only


Engineer
Tissa Division HP/DM/17

Percentage BoQ
PRICE SCHEDULE

Name of Work:-Restoration of rain damages on Bhadkwas to Bulwas road KM 0/0 to 2/500.

(S.H.:- Providing crate work breast wall at RD 1/32.15 to 1/37.50 and 1/39 to 1/44)

Sr. No.	Description /items of work.	Quantity	Unit	Rate		Amount in figure	Amount in words
				Figures	Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305 and 1603.4 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax GST or	11.75	Per Cubic Metre	330.00	Rupees Three Hundred Thirty Only	3878.00	Rupees Three Thousand Eight Hundred Seventy Eight Only
2	Providing and laying of boulder apron or gabion walls laid in wire crates with 4mm (four millimeter) dia G.I. wire (Galvanized iron wire) conforming to IS: 280 (IS:two hundred eighty) and IS: 4826 (IS: four thousand eight hundred twenty six) in 100mmx100mm (one hundred millimeter into one hundred millimeter) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints, laid with stone boulders weighing not less than 25 kg (Twenty five kilogram) each as per drawing and technical specification clause 1301 or as per the directions of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals. he rate including the octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	28.33	Per Cubic Metre	2900.00	Rupees Two Thousand Nine Hundred Only	82157.00	Rupees Eighty Two Thousand One Hundred Fifty Seven Only
				86035.00			
				(To be quoted by Contractor)			
				(To be quoted by Contractor)			

D.N.I.T. approved for Rs. 86035/- only.

Engineer
District Engineer
Mesa Division HPPWD
28355A

Percentage Bid

PRICE SCHEDULE

Name of Work:- Restoration of rain damages on Bhadkwas to Bulwas road KM 0/0 to 2/500.
 (S.H.:- Providing crate work breast wall at RD 1/44 to 1/49, 1/259 to 2/64 and 1/386 to 39)

Sr. No.	Description /Items of work.	Quantity	Unit	Rate		Amount in figure	Amount in words
				Figures	Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305 and 1603.4 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of sumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax sale tax GST or	16.88	Per Cubic Metre	330.00	Rupees Three Hundred Thirty Only	5570.00	Rupees Five Thousand Five Hundred Seventy Only
2	Providing and laying of boulder apron or gabion walls laid in wire crates with 4mm dia G.I. wire (Galvanized iron wire) conforming to IS: 280 (IS:two hundred eighty) and IS: 4826 (IS: four thousand eight hundred twenty six) in 100mmx100mm (one hundred millimeter into one hundred millimeter) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints, laid with stone boulders weighing not less than 25 kg (Twenty five kilogram) each as per drawing and technical specification clause 1301 or as per the directions of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals. he rate including the octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	29.79	Per Cubic Metre	2900.00	Rupees Two Thousand Nine Hundred Only	86391.00	Rupees Eighty Six Thousand Three Hundred Ninety One Only
(To be quoted by Contractor)							
91961.00							
Quoted Rate in figure (%)							
Quoted Rate in Words (%)							

D.N.S.T. approved for Rs. 91961/- only.


Engineer
 JISSA Division
 JISSA

**Percentage Boq
PRICE SCHEDULE**

Name of work:- C/o Bhanjiraru to Chachrot road KM 0/0 to 0/640
(SH:- Providing retaining wall at RD 0/497.375 to 0/504.25).

Sr. No.	Description /Items of work.	Quantity	Unit	Rate		Amount in figure	Amount in words
				Figures	Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORC technical specification clause 305 and 1603.4 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax GST or	11.17	Per Cubic Metre	300.00	Rupees Three Hundred Only	3351.00	Rupees Three Thousand Three Hundred Fifty One Only
2	Providing and laying of boulder apron or gabion walls laid in wire crates with 4mm (four millimeter) dia G.I. wire (Galvanized iron wire) conforming to IS: 280 (IS:two hundred eighty) and IS: 4826 (IS: four thousand eight hundred twenty six) in 100mmx100mm (one hundred millimeter into one hundred millimeter) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints, laid with stone boulders weighing not less than 25 kg (Twenty five kilogram) each as per drawing and technical specification clause 1301 or as per the directions of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals. he rate including the octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	32.22	Per Cubic Metre	2850.00	Rupees Two Thousand Eight Hundred Fifty Only	91827.00	Rupees Ninety One Thousand Eight Hundred Twenty Seven Only
				(To be quoted by Contractor)		95178.00	
				(To be quoted by Contractor)			
				Quoted Rate in figure (%)			
				Quoted Rate in Words (%)			

D.N.I.T. approved for Rs. 95178/- only.


Engineer
 Tissa Division, HP, PWD,
 Tissa at Bhanjiraru 176316

D.N.I.T.

Name Of Work :- Restoration of rain damages on various roads under Kiani section of Koti sub Division.

(SH:- Hiring of JCB for removal of slips at various Rd's)

S.No.	Description	Quantity	Rate		Unit	Amount.	Estimated cost	
			In word	In fig.			Earnest Money	Time Limit
1	Hiring of J.C.B./Excavator cum loader for cutting/widening work of road or removal of slips/snow in all kind of soil and disposing of all excavated earth or un-servieable materials from road surface upto any lead and lifts up to any hight and depth as per the direction and entire satisfactions of Engineer-in-Charge any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator cum loader owner which will have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The repair and spare, watch and ward of machinery also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	96.00	1030.00	Rupees One Thousand Thirty Only	Per hour	98880.00	98880.00	1977.60
Total:-						98880.00		

[Signature]
 Assistant Engineer,
 Koti Sub Division,
 HPPWD Koti,

2017 Approved for Rs 98880/-

Assistant Engineer
 Koti Sub Division
 HPPWD Koti

Executive Engineer
 Koti Sub Division
 HPPWD Koti

[Signature]

D.N.I.T.

Name Of Work :- Restoration of rain damages on various roads under Pukhri section of Koti sub Division.

(SH:- Hiring of JCB for removal of slips at various Rd's)

S.No.	Description	Quantity	Rate		Unit	Amount.	Estimated cost	
			In word	In fig.			Earnest Money	Time Limit
1	Hiring of J.C.B./Excavator cum loader for cutting/widening work of road or removal of slips/snow in all kind of soil and disposing of all excavated earth or un-servieable materials from road surface upto any lead and lifts up to any hight and depth as per the direction and entire satisfactions of Engineer-in-Charge any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator cum loader owner which will have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The repair and spare, watch and ward of machinery also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	97.00	1030.00	Ruppees One Thousand Thirty Only	Per hour	99910.00	1998.20	Two Months
Total:-						99910.00		

Owner approved for Rs 99910/-

Assistant Engineer,
Koti Sub Division,
HPPWD Koti,

[Signature]

Executive Engineer
Koti Sub Division
HPPWD Koti

[Signature]
Assistant Engineer,
Koti Sub Division,
HPPWD Koti

D.N.I.T.

Name of work:- Restoration of rain damages on various roads of Leswin section under Nakrot		Estimated Cost Rs. =		99910.00	
Sub-Division (SH):- Hiring of JCB for removal of slips at various Rd's		Earnest Money Rs. =		2000.00	
S.N.	Description of item	Quantity	Time limit =		One Month
			In Fig.	In words	
1	Hiring of J.C.B./Excavator cum loader for removal of soil of all kind i.e. hard/loose or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from road surface upto any leads and lifts up to any height and depth as per direction and entire satisfactions of Engineer-in-Charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The repair and spare, watch and ward of machinery also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or any other taxes imposed by the Government	97.00	1030.00	Rupees One Thousand Thirty Only	Per Hour
Total					99910.00

D.N.I.T approved for Rs = 99910/- only


[Signature]
 Tissa Division
 HPPVID TISSA

DNIT

Work: - Restoration of rain damages on Nakrot Tikri Bhagegarh road Km 0/0 to 15/0. (SH:- Hiring of JCB for removal of slips at DDs).

Estimated Cost: - Rs. 99425.00
 Earnest Money :- Rs. 1989.00
 Time Limit :- Two Month

Discription / Item of work	Qty.	Rate		Unit	Amount
		In fig.	In words		
Hiring of J.C.B/ Excavator-cum-loader for cutting/widening work of road or removal of slips in all kind of soil and disposing of all excavated earth or unserviable materials from road surface upto any leads and lifts up to any height and depth as per direction and entire satisfactions of Engineer in charge. Any loss to the public/private property or nay accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B/ Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The repair and spare, watch and ward of machinery also be borne by the contractor/owner. The dily log book will be maintained at site which should be duly verified by the Engineer in charge.	97.00	1025.00	One Thousand Twenty Five	Per Hour	99425.00
Total: -					99425.00


 Assistant Engineer
 Nakrot Sub Division
 HPPWD Nakrot.
With approved for Rs 99425.00




 Executive Engineer
 Kissa Division HPPWD
 KISSA

Percentage Bid

PRICE SCHEDULE

Name of work:- Restoration of damages due to laying OFC on Chambha Tissa road km 5/0 to 32/250 (SI:-Providing R/wall at Rd 22/267 TO 22/273)

Sr. No.	Description /Items of work.	Quantity	Unit	Figures	Estimated cost-		
					Rate	Amount in	
					Words	Month	words
					Time limit-	Three	Amount in
					limit-	Month	words
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305 and 1603.4 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government	8.76	Per Cubic Metre	300.00	Rupees Three Hundred Only	2628.00	Rupees Two Hundred Twenty Eight Only
2	Providing and laying mechanically mixed and vibrated concrete for plain / reinforced cement concrete in open foundation for all type of structure of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed stone aggregate 40 mm (forty millimetre) nominal size in or under water and curing complete for 14 (fourteen) days including pumping or bailing out water, (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying water complete for all heights and including removal cost of form work as per drawing and MORD technical specification clause 802,803,1202 and 1203 or as per direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax GST or other taxes imposed by the Government	15.66	Per Cubic Metre	5300.00	Rupees Five Thousand Three Hundred Only	82998.00	Rupees Eighty Two Thousand Nine Hundred Ninety Eight Only
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 and as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax GST or other taxes imposed by the Government	12.00	Each	280.00	Rupees Two Hundred Eighty Only	3360.00	Rupees Three Thousand Three Hundred Sixty Only

<p>4 Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sales tax GST or any other taxes imposed by the Government.</p>	4.50	Per Cubic Metre	750.00	Rupees Seven Hundred Fifty Only	3375.00	Rupees Three Thousand Three Hundred Seventy Five Only
				Total:-	92361.00	Rupees Ninety Two Thousand Three Hundred Sixty One Only
<p>Quoted Rate in figure (%)</p>	(To be quoted by Contractor)					
<p>Quoted Rate in Words (%)</p>	(To be quoted by Contractor)					

DNIT approved for Rs = 92361/- only


 Examining Engineer
 Tissa Division
 HPPWD Tissa

Percentage Bid
PRICE SCHEDULE

Name of work:- Restoration of damages due to laying OFC on Chamha Tissa road km 5/0 to 32/250 (SH:- Providing R/wall at Rd 22/904 to 22/910)

Sr. No.	Description /Items of work.	Quantity	Unit	Figures	Rate		Amount in figure	Amount in words
					Words	Amount in		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305 and 1603.4 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	870	Per Cubic Metre	300.00	Rupees Three Hundred Only	2610.00	Rupees Two Thousand Six Hundred Ten Only	
2	Providing and laying mechanically mixed and vibrated concrete for plain / reinforced cement concrete in open foundation for all type of structure of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed stone aggregate 40 mm (forty millimetre) nominal size in or under water and curing complete for 14 (fourteen) days including pumping or bailing out water, (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying water complete for all heights and depths including cost of form work as per drawing and MORD technical specification clause 802,803,1202 and 1203 or as per direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax GST or other taxes imposed by the Government.	15.66	Per Cubic Metre	5300.00	Rupees Five Thousand Three Hundred Only	82998.00	Rupees Eighty Two Thousand Nine Hundred Ninety Eight Only	
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 and as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax GST or other taxes imposed by the Government.	13.00	Each	280.00	Rupees Two Hundred Eighty Only	3640.00	Rupees Three Thousand Six Hundred Forty Only	

4	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORO technical specification clause 1204.3.8 or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sales tax GST or any other taxes imposed by the Government	4.68	Per Cubic Metre		750.00	Rupees Seven Hundred Fifty Only		3510.00	Rupees Three Thousand Five Hundred Ten Only
				Total:-				92758.00	Rupees Ninety Two Thousand Seven Hundred Fifty Eight Only
				(To be quoted by Contractor)				(To be quoted by Contractor)	
				Quoted Rate in figure (%)				Quoted Rate in Words (%)	

DIT approved for Rs = 92758/only


 TISSA DIVISION OFFICER
 HPPWMD TISSA

D.N.I.T.


Name of work:- Restoration of rain damages on various roads under Nakrot Sub-Division (SH:-

Hiring of Tipper for removal of slips.

S.N.	Description of item	Quantity	Rate		Unit	Amount
			In Fig.	In words		
1	Hiring of Tipper 5.5 cum capacity having lift system for carriage of material to different site of work with in all leads and lifts to the entire satisfaction of the Engineer-in-Charge. The Tipper should work minimum 8.00 hours (Eight hours) from 9.00 A.M. to 5.00 P.M. daily. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the owner which shall have to be fully compensated by him in all cases. The fuel of the Tipper, driver, repair work shall have to be born by the contractor/ owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or any other taxes imposed by the Government.	24.00	4000.00	Rupees Four Thousand Only	Per day	96000.00
Total						96000.00

Estimated Cost Rs. = 96000.00
 Earnest Money Rs. = 2000.00
 Time Limit = One Months

D.N.I.T approved for Rs = 96000/- only.


 Executive Engineer
 Tissa Division
 HPPWD Tissa