

Himachal Pradesh
Public Works Department

No. PW-KD- CTR- Tender-NIT/2025-2026-

10329-80

Dated:-

22/6/26

To


The Executive Engineer (IT Cell)
Nigam Vihar Shimla.

Subject :- Publication of Tender Notice.

Jai Hind


Enclosed please find herewith the tender Notice of work as given in the Notice Inviting tender for uploading on department website as per notification Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW (B)A(3)1/2024 dated Shimla-2 the 03-01-2024 and PWD-B-AO(3)/8/2025- 300858 dated 09-10-2025 as the works mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender & Schedule of Quantity and Certificate.


Executive Engineer,
HPPWD., Division Kasumpti
Shimla

Copy forwarded to for further necessary action please.

1. The Superintending Engineer 4th Circle HPPWD Shimla .


Executive Engineer,
HPPWD., Division Kasumpti
Shimla.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDERS**

Executive Engineer B&R Division Kasumpti HPPWD Shimla for the following works on behalf of the Government of Himachal Pradesh from the eligible contractors enlisted in HPPWD, so as to reach in the office as per time schedule given below:-

- | | |
|--|-----------------------------------|
| 1. Date of receipt of application for tender forms:- | 01-07-2026 10:00 AM upto 12:00 PM |
| 2. Dated of Issue /sale of tender forms:- | 01-07-2026 12:00 PM upto 4:00 PM |
| 3. Date of receipt of tender:- | 02-07-2026 .up to 10:30 AM |
| 4. Date of opening of tender:- | 02-07-2026 up to 11:00 AM |

Sr. No.	Name of Work	Estimate d cost	EMD(R s.)	Cost of Tender (Rs.)	Time Limit	Eligible class of Contractor
1	Constrction link road frokm Cheri Bifurication to Anu road km. 0/00 to 0/830 (SH:- ROFD Formation Cutting of road various RD.)	85142	1800	350	30 days	Class-D
2	A/R & M/O to Rest House Building at Fagu Shimla (SH:- Providing and Fixing Barhed wire fencing at RDst house).	99700	2000	350	30 days	Class-D
3	Special reair work of PWD rest House at Junga (SH:- Providing furniture material)	99725	2000	350	30 days	Class-D
4	Special repair work of PWD rest House at junga (SH:- Restuffing of furniture material).	99600	2000	350	30 days	Class-D
5	A/R & M/O to Ragyana to kanaina road km. 0/00 to 0/500 (SH:- ROFD/ Formation cutting of road front RD. 0/225 ot 0/300).	84946	1700	350	30 days	Class-D
6	A/R & M/O of Bisk to Tood road km. 0/00 to 1/720 (SH:- Formation cutting of road from RD. 0/00 to 0/050).	84602	1700	350	30 days	Class-D
7	Constrction link road from Bhont Bus stand to kudi shal road km. 0/00 to 0/410 (SH:- ROFD/Formation cutting RD 0/015 to 0/105).	83706	1700	350	30 days	Class-D
8	A/R & M/O on Shimla Mandi Tatapani road km. 6/00 to 22/00 (SH:- Remvoal of slips /Road slide Muck between RD. 16/00 to 2/00).	98499	2000	350	30 days	Class-D
9	A/R & M/O on Shimla Mandi Tatapani road km. 6/00 to 22/00 (SH:- Removal of slips /Road side Muck between Rd. 6/00 to 10/00).	97998	2000	350	30 days	Class-D
10	A/R & M/O of Mungar Nala to Mungar road km. 0/00 to 0/570 (SH:- ROFD/Foramtion cutting of road from RD. 0/060 to 0/167).	85915	1800	350	30 days	Class-D
11	A/R & M/O to Fagu to Cheog road in km. 0/00 to 5/600 Cheog to Dharech road in km. 0/00 to 7/400 (SH:- White washing to km. 0/00 to 5/600 & 0/00 to 7/400).	80000	1600	350	30 days	Class-D
12	A/R & M/O to Fagu to Cheog road to km. 0/00 to 5/600 Cheog to Dharech road in km. 0/00 to 7/400 (SH:- Trimming & Maintenance to km. 0/00 to 5/600 &0/00 to 7/400).	98952	2000	350	30 days	Class-D
13	A/R & M/O on Various road Fagu section under Mashobra sub Division (SH:- Supplying and stacking pot seal bags cold mix in various Rds).	99700	2000	350	30 days	Class-D
14	A/R & M/O on various roads Baldiyan section under Mashobra sub Division (SH:- Supplying and stacking pot seal bags cold mix in various Rds).	99750	2000	350	30 days	Class-D
15	A/R & M/O on various roads Junga section under junga sub Division (SH:- Supplying and stacking pot seal bags cold mix in various Rds	99225	2000	350	30 days	Class-D
16	A/R & M/O on various roads Challanda section under junga sub Division (SH:- Supplying and stacking pot seal bags cold mix in various Rds	99750	2000	350	30 days	Class-D
17	A/R & M/O on various roads Bharari section under sub Division No.1 (SH:- Supplying and stacking pot seal bags cold mix in various Rds	99750	2000	350	30 days	Class-D
18	A/R & M/O on various roads Lakkar Bazar section under sub Division No.1 (SH:- Supplying and stacking pot seal bags cold mix in various Rds	98175	2000	350	30 days	Class-D
19	Improvement of Bhattakuffer to AIMSS road km. 0/00 to 2/240 (SH:- Providing and fixing W-Metal beam crash barrier on various reaches/RDs from km. 0/340 to 0/510).	96204	2000	350	30 days	Class-D
20	Improvement of Bhattakuffer to AIMSS road km. 0/00 to 2/240 (SH:- Providing and fixing W-Metal beam crash barrier on various reaches/RDs from km. 0/680 to 0/850).	96284	2000	350	30 days	Class-D
21	Improvement of Bhattakuffer to AIMSS road km. 0/00 to 2/240 (SH:- Providing and fixing W-Metal beam crash barrier on various reaches/RDs from km. 0/510 to 0/680).	94444	2000	350	30 days	Class-D

22	Improvement of Bhattakuffer to AIMSS road km. 0/00 to 2/240 (SH:- Providing and fixing W-Metal beam crash barrier on various reaches/RDs from km. 0/850 to 1/000).	94444	2000	350	30 days	Class-D
----	--	-------	------	-----	---------	---------

It is certified that the above works are required to be carried out immediately being emergent nature of work in public interest.

The tender documents shall be issued only to those contractor/Firm who fulfill the following documents with the application.

1. The valid enlistment/Registration of contractor in Appropriate Class.
2. Permanent account No. (PAN NO).
3. G.S.T No.
4. Earnest Money in the shape of National saving certificate/time deposit account in the any of the post office in HP. F.D.R from any Nationalized Bank duly pleaded in favour of the Executive Engineer Division Kasumpti HPPWD Shimla.
5. The earnest & cost of tender form for the above works should be submitted with the application for the purchase of the tender form. The application received without earnest money & cost of tender form shall summarily be rejected.
6. The officer of the tender shall remain valid up to 75 days after the opening of tender.
7. Ambiguous/telephonic /conditional tenders or tender by fax/E mail shall not be considered and will be summarily be rejected.
8. Executive Engineer reserve the right to reject or cancel any or all tenders without assigning any reasons.
9. If the date given above happens to be holiday the same shall be processed on next working day.
10. The Contractor/firms must quote their rates in words as well as in figures failing which EXN reserve the right to accept/reject any or all tenders.
11. The tender forms shall not be issued to those contractors/firms whose previous performance is not found satisfactory and who have not executed the previous awarded works within the stipulated period of completion.
12. One contractor shall not have more than two major works in hand at a time.
13. Work should be completed by the contractor within stipulated period.

Executive Engineer,
Division Kasumpti.,
HPPWD. Shimla-3.

Dated :- 22-06-2026

No.PW-SD-I/CB-Tender/2026-2027- 10331-44
Copy forwarded to:-

1. Copy to the Deputy Commissioner Shimla Distt. Shimla.
2. Copy to the Executive Engineer Shimla Division No-III HPPWD Shimla.
3. Copy to the Sub Divisional Magistrate (U) Shimla.
4. Copy to the Sub Divisional Magistrate (R) Shimla.
5. Copy to Municipal committee Shimla Distt. Shimla.
6. Copy to Block Development officer Mashobra Distt. Shimla.
7. All the Assistant Engineers under this Division, HPPWD Shimla-3.
8. Superintendent / HDM /DAO.
9. Notice Board.

Executive Engineer,
Division Kasumpti.,
HPPWD Shimla.

149

DRAFT SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.							Estimated Cost:- 85,142.00	
Name of Work:--Construction of link road from Cheri Bifurcation to Anu road Km. 0/00 to 0/830.(SH-							Earnest Money :-1800 .00	
ROFD/ Formation cutting of road various Rd.)							Time:- One Month.	
Sr. No	Description of Work / Item (3)	No. of Qty.		Estimated Rate		Unit	Amount	
				In figures	In words			
1	Cutting and disposal of earth work in by mechanical in all heights and depths in all kinds of soils, including saturated soils comprising of pick work, jumper work and blasting work both in soft and hard rock with chiseling and wedging out of rock (where blasting is prohibited) and their intermediate classification of soils including, dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer -in-charge at site, according to the HP.PWD, specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site as per satisfaction of Engineer- in -charge through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required). All the surplus excavated earth to be dumped at dumping site(dumping sites will be arranged by the contractor on his own cost). Any loss to the public and private propriety, human being, machinery during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.	304.08	Cum.	280.00	Rupees Two Hundred Eighty Only	Per Cubic Metre	85142.00	
						Total	85142.00	
	Quoted rates Percentage in figures							
	Quoted rates Percentage in words							
						G.Total		

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

DNIT approved for Rs.85,142/- Only (Rupees eighty five Thousand one hundred forty two only) vide DNIT Register Sr.No. 149 the financial year 2026-27. T/S
 No. 100920 Dated 16/6/26 amounting to Rs. 87,696/-

Executive Engineer
 B&R Division Kasumpti,
 HPPWD, Winter Field Shimla-3

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-1, H.P.P.W.D., SHIMLA-3.					Estimated Cost:- 99,700.00		
Name of Work :- A/R & M/O to Rest House Building at Fagu Shimla. (SH:- Providing and fixing Barbed wire fencing at Rest House).					Earnest Money :- 2,000.00		
					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Cutting and disposal of earth work in by mechanical in all heights and depths in all kinds of soils, including saturated soils comprising of pick work, jumper work and blasting work both in soft and hard rock with chiseling and wedging out of rock (where blasting is prohibited) and their intermediate classification of soils including dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer -in-charge at site., according to the HP.PWD. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site as per satisfaction of Engineer- in -charge through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required). All the surplus excavated earth to be dumped at dumping site(dumping sites will be arranged by the contractor on his own cost). Any loss to the public and private propriety, human being, machinery during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.	6.00	Cum	225.00	Rupees Two Hundred Twenty Five Only	Per Cubic Metre	1350.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.(a) Cement Mortar 1:3:6(one cement:Three sand:Six graded stone aggregate 20mm(Twenty millimetre) nominal size).	5.00	Cum	5800.00	Rupees Five Thousand Eight Hundred Only	Per Cubic Meter	29000.00
3	Supplying at site Angle iron post & strut of requied size including bottem to be split and bent at right angle in opposite direction for 10cm length and drilling holes upto 10cm dia etc including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	170.00	Kgs	115.00	Rupees One Hundred Fifteen Only	Per Kilograms	19550.00

4	Fencing with angle iron post placed at required distance embedded in cement concrete blocks, every 15th post, last but one end post and corner post shall be strutted on both sides and end post on one side only and provided with horizontal lines and two diagonals interwoven with horizontal wires, of barbed wire weighing 9.38 kg per 100 m (minimum) between the two posts fitted and fixed with G.I. staples, turn buckles etc. complete. (Cost of posts, struts, earth work and concrete work to be paid for separately). Payment to be made per metre per metre cost of total length of barbed wire used. With G.I. barbed wire	150.00	Rmt	20.00	Rupees Twenty Only	Per Running Meter	3000.00
5	Disposal of muck excavated Earth /Removal of Slipes/ Malba/Similar unservicable, dismantle or waste materials by mechanical transport including loading, unloading & disposal up to all leads & lifts including arranging the dumping site at its own cost all taxes etc. The payment shall be made for dumping site by contractor for dumping site arranged by the contractor at private property or Govt. land as per the direction of Engineer-In- Charge.	156.00	Cum	300.00	Rupees Three Hundred Only	Per Cubic Meter	46800.00
						Total	99700.00
	Quoted rates Percentage in figures					G.Total	
	Quoted rates Percentage in words						

(T/S No. 10617-B Dated 16-6-26 Amount to Rs. 102641/-)

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer,
B&R Division Kasumpti,
HP.PWD. Winter Field, Shimla-3

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-					Estimated Cost:- 99,725.00		
Name of Work :- Special repair work of PWD rest House and AE office building at Junga (SH:- Providing furniture material).					Earnest Money :- 2000.00		
					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Providing and supplying Room door foot Mat of size .	8.00	Nos	1975.00	Rupees One Thousand Nine Hundred Seventy Five Only	Each	15800.00
2	Providing and supplying double bed bedsheet white stripe cloth.	15.00	Nos	1795.00	Rupees One Thousand Seven Hundred Ninety Five Only	Each	26925.00
3	Providing and supplying Astride ergofit heavy based regal wheel in all leads and lift.	3.00	Nos	13900.00	Rupees Thirteen Thousand Nine Hundred Only	Each	41700.00
4	Providing and supplying office table with two side drawer in all leads and lifts.	1.00	Nos	15300.00	Rupees Fifteen Thousand Three Hundred Only	Each	15300.00
						Total	99725.00
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer
B& R Division Kasumpti
HPPWD Winter Field Shimla -3

159/ote

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.					Estimated Cost:- 99,600.00		
Name of Work :- Special repair work of PWD rest House at Junga (SH:- Restuffing of furniture).					Earnest Money :- 2000.00		
					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Re-stuffing of sofa-set/chair using 3" thick korfoam band with superioir quality foam sheet in seat & back fixing padding with latex with superioir quality tapestry cloth (latherite material) in proper position. SINGLE SEATER SOFA CHAIRS.	8.00	Nos	5400.00	Rupees Five Thousand Four Hundred Only	Each	43200.00
2	Re-stuffing of Easy chairs (with arms) using 3" thick korfoam band with superioir quality foam sheet in seat & back fixing padding with latex with superioir quality tapestry cloth (latherite material) in proper position.	12.00	Nos	4700.00	Rupees Four Thousand Seven Hundred Only	Each	56400.00
						Total	99600.00
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer,
B& R Division Kasumpti
HPPWD Winter Field Shimla -3

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-1, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 84,946.00	
Name of Work:--A/R & M/O of Ragyana to Kanaina road km. 0/00 to 0/500.(SH:-ROFD/ Formation cutting of road from Rd. 0/225 to 0/300)						Earnest Money :-1700 .00	
						Time:- One Month.	
Sr. No.	Description of Work / Item (S)	No. of Qty		Estimated Rate		Unit	Amount
				In figures	In words		
1	Cutting and disposal of earth work in by mechanical in all heights and depths in all kinds of soils, including saturated soils comprising of pick work, jumper work and blasting work both in soft and hard rock with chiseling and wedging out of rock (where blasting is prohibited) and their intermediate classification of soils including dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer -in-charge at site, according to the H.P.P.W.D. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site as per satisfaction of Engineer- in -charge through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required). All the surplus excavated earth to be dumped at dumping site(dumping sites will be arranged by the contractor on his own cost). Any loss to the public and private propriety, human being, machinery during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.	303.38	Cum	280.00	Rupees Two Hundred Eighty Only	Per Cubic Metre	84946.00
						Total	84946.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standards.

Executive Engineer,
B&R Division Kasumpti,
HPPWD Winter Field Shimla-3


SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 84,602.00	
Name of Work:--A/R & M/O of Bisk to Tood road km. 0/00 to 1/720.(SH:-Formation cutting of road from Rd. 0/00 to 0/050)						Earnest Money :-1700.00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No. of Qty		Estimated Rate		Unit	Amount
				In figures	In words		
1	Cutting and disposal of earth-work in by mechanical in all heights and depths in all kinds of soils, including saturated soils comprising of pick work, jumper work and blasting work both in soft and hard rock with chiseling and wedging out of rock (where blasting is prohibited) and their intermediate classification of soils including dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer -in-charge at site, according to the HP.PWD. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site as per satisfaction of Engineer- in -charge through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required). All the surplus excavated earth to be dumped at dumping site(dumping sites will be arranged by the contractor on his own cost). Any loss to the public and private propriety, human being, machinery during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.	302.15	Cum	280.00	Rupees Two Hundred Eighty Only	Per Cubic Metre	84602.00
						Total	84602.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

CONDITION:-

CONDITION:-


1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.


 Executive Engineer,
 B&R Division Kasumpti,
 HPPWD, Winter Field Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-1, H.P.P.W.D., SHIMLA-3.					Estimated Cost:- 83,706.00		
Name of Work:--Construction of link road from Bhot Bus stand to Kudi Shal road km. 0/90 to 0/410.(SH:-					Earnest Money :-1700 .00		
ROFD/ Formation cutting of road Rd.0/015 to 0/105).					Time:- One Month.		
Sl. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Cutting and disposal of earth work in by mechanical in all heights and depths in all kinds of soils, including saturated soils comprising of pick work, junper work and blasting work both in soft and hard rock with chiseling and wedging out of rock (where blasting is prohibited) and their intermediate classification of soils including, dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer -in-charge at site., according to the HP.PWD. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site as per satisfaction of Engineer- in -charge through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required). All the surplus excavated earth to be dumped at dumping site(dumping sites will be arranged by the contractor on his own cost). Any loss to the public and private propriety, human being, machinery during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.	298.95	Cum	280.00	Rupees Two Hundred Eighty Only	Per Cubic Metre	83706.00
						Total	83706.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words					G.Total	

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.


 Executive Engineer
 B&R Division Kasumpti,
 HPPWD, Winter Field Shimla-3

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-						Estimated Cost:- 98,499.00	
Name of Work :- A/R & M/O on Shimla Mandi Tatapani road Km 6/000 to 22/000 (SH:- Removal of slips / Roads side Muck between Rd 16/000 to 20/00).						Earnest Money :- 2,000.00	
						Time:- One Month	
Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Removal of Slips and muck stacked on road side actual working will be accounted for payment and paper disposal slips debris by the contractor will be insured and including all lifts work shall be executed as per direction of the Engineer in charge (dumping site to be arranged by the contractor at his own cost).	328.33	Cum	300.00	Rupees Three Hundred Only	Per Cubic Meter	98499.00
						Total	98499.00

CONDITION:

1. All the P.O.L. Charges shall be borne by the contractor.
2. All the repair /maintenance of machineries shall be borne by the contractor.
3. For any minor /Major repair or any accident /damaged shall be the whole responsibility of contractor.
4. Any damages or loss to Govt./Private property during course of work shall have to be make good by the contractor.

Executive Engineer,
HPPWD Division,
Kasumpti Shimla

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-						Estimated Cost:- 97,998.00	
Name of Work :- A/R & M/O on Shimla Mandi Tatapani road Km 6/000 to 22/000 (SH:- Removal of slips / Roads side Muck between Rd 6/000 to 10/00).						Earnest Money :- 2,000.00	
						Time:- One Month	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Removal of Slips and muck stacked on road side actual working will be accounted for payment and paper disposal slips debris by the contractor will be insured and including all lifts work shall be executed as per direction of the Engineer in charge (dumping site to be arranged by the contractor at his own cost).	326.66	Cum	300.00	Rupees Three Hundred Only	Per Cubic Meter	97998.00
						Total	97998.00

CONDITION:

1. All the P.O.L. Charges shall be borne by the contractor.
2. All the repair /maintenance of machineries shall be borne by the contractor.
3. For any minor /Major repair or any accident /damaged shall be the whole responsibility of contractor.
4. Any damages or loss to Govt./Private property during course of work shall have to be make good by the contractor.

Executive Engineer
HPPWD Division,
Kasumpti Shimla

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 85,915.00	
Name of Work:--A/R & M/O of Mungar Nala to Mungar road km. 0/00 to 0/570.(SH:-ROFD/ Formation cutting of road from Rd. 0/060 to 0/167)						Earnest Money :-1800 .00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Cutting and disposal of earth work in by mechanical in all heights and depths in all kinds of soils, including saturated soils comprising of pick work, jumper work and blasting work both in soft and hard rock with chiseling and wedging out of rock (where blasting is prohibited) and their intermediate classification of soils including dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer in-charge at site, according to the HP.PWD. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site as per satisfaction of Engineer in-charge through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required). All the surplus excavated earth to be dumped at dumping site(dumping sites will be arranged by the contractor on his own cost). Any loss to the public and private propriety, human being, machinery during the course of execution and disposal of serviceable and unserviceable materials shall be the contractor's responsibility. A full and complete bill of materials to be submitted by him to all concerned authorities.	306.84	Cum	280.00	Rupees Two Hundred Eighty Only	Per Cubic Metre	85915.00
						Total	85915.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standards.

Executive Engineer
B&R Division Kasumpti,
HPPWD, Winter Field Shimla-3

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-1, H.P.P.W.D., SHIMLA-3.						Estimated Cost:-80,000.00	
Name of Work :- A/R & M/O to Fagu to Cheog road in KM. 0/00 to 5/600, Cheog to Dharech road in KM. 0/00 to 7/400. (SH:- White washing in KM. 0/00 to 5/600 & 0/00 to 7/400).						Earnest Money :- 1,600.00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	White washing two coats on parapets wall and tree trunks including preparation of surface by cleaning scraping etc. as per technical specification clause 1915 including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	2500.00	Sqm	32.00	Rupees Thirty Two Only	Per Square Meter	80000.00
						Total	80000.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

T/S No. 1024-25 Dated 16-6-26 Amount to
Rs. 82,400/-

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer,
B&R Division Kasumpti,
HP.PWD. Winter Field, Shimla-3

SCHEDULE OF QUANTITY							Estimated Cost:- 98,952.00	
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-L, H.P.P.W.D., SHIMLA-3.							Earnest Money :- 2,000.00	
Name of Work :- A/R & M/O to Fagu to Cheog road in KM. 0/00 to 5/600, Cheog to Dharech road in KM. 0/00 to 7/400. (SH:- Trimming & Maintenance in KM. 0/00 to 5/600 & 0/00 to 7/400).							Time:- One Month.	
Sr. No.	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount	
				In figures	In words			
1	Trimming of grass and weeds from the shoulders/ berms and disposing off the same to suitable locations as per technical specifications Clause 1914 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	11400.00	Sqm	4.08	Rupees Four and Paise Eight Only	Per Square Meter	46512.00	
2	Maintenance of drain including erosion, repair, cleaning, reshaping, regarding, deepening of side drain as well as per Technical specification Clause 1907 including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	11400.00	Rmt	4.60	Rupees Four and Paise Sixty Only	Per Running Meter	52440.00	
						Total	98952.00	
	Quoted rates Percentage in figures							
	Quoted rates Percentage in words					G.Total		

16-6-26 Amount to

(T/S No. 10022-23 Dated 16-6-26 Amount to Rs. 101221/-)

CONDITION:-
1. Rates should be quoted for all heights including all leads and lifts.

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer,
B&R Division Kasumpti,
HP.PWD. Winter Field, Shimla-3

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-					Estimated Cost:- 99,700.00		
NAME OF WORK:- A/R & M/O on Various roads Fagu section under Mashobra Sub Division					Earnest Money :-2,000.00		
(SH:- Supplying and Stacking Pot seal bags cold mix in Various Rds).					Time:- One Month		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Supplying and laying pot seal beg of 25 kgs cold mix including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	94.00	Nos	1050.00	Rupees One Thousand Fifty Only	Per Each	98700.00
						Total	98700.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						

RNo-179 TBN-10172-73 cl 19-6-26 RSLoket

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer,
HPPWD Division,
Kasumpti Shimla

PS 101661 /

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-					Estimated Cost:- 99,750.00		
NAME OF WORK:-A/R & M/O on Various roads Baldiyan section under Mashobra Sub					Earnest Money :-2,000.00		
Division (SH:- Supplying and Stacking Pot seal bags cold mix in Various Rds).					Time:- One Month		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Supplying and laying pot seal beg of 25 kgs cold mix including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	95.00	Nos	1050.00	Rupees One Thousand Fifty Only	Per Each	99750.00
						Total	99750.00
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						

R No. 180 TIS No. 10174-75 cl 14-6-26 Rs 102743/-

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer,
HPPWD Division,
Kasumpti Shimla

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-					Estimated Cost:- 99,225.00		
NAME OF WORK:- A/R & M/O on Various roads Junga section under Junga Sub Division (SH: Supplying and Stacking Pot seal bags cold mix in Various Rds).					Earnest Money :-2,000.00		
					Time:- One Month		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Supplying and laying pot seal beg of 25 kgs cold mix including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	94.50	No	1050.00	Rupees One Thousand Fifty Only	Per Each	99225.00
						Total	99225.00
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						

RNo.18/TKM.10173-77 ch 19626 RD 102202/-

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer,
HPPWD Division,
Kasumpti Shimla

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-						Estimated Cost:- 99,750.00	
NAME OF WORK:- A/R & M/O on Various roads Challanda section under Junga Sub Division						Earnest Money :-2,000.00	
(SH:- Supplying and Stacking Pot seal bags cold mix in Various Rds).						Time:- One Month	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Supplying and laying pot seal beg of 25 kgs cold mix including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	95.00	Nos	1050.00	Rupees One Thousand Fifty Only	Per Each	99750.00
						Total	99750.00
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						

Rate 102743 TUN 1017879 of 19-6-26 B 102743

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer,
HPPWD Division,
Kasumpti Shimla

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-					Estimated Cost:- 99,750.00		
NAME OF WORK:- A/R & M/O on Various roads Bharari section under Sub Division No.1 (SH: Supplying and Stacking Pot seal bags cold mix in Various Rds).					Earnest Money :-2,000.00		
					Time:- One Month		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Supplying and laying pot seal beg of 25 kgs cold mix including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	95.00	Nos	1050.00	Rupees One Thousand Fifty Only	Per Each	99750.00
						Total	99750.00
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						

RM-18375 No. 10166-6706 19-6-26 P0102743/

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer
HPPWD Division,
Kasumpti Shimla

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-						Estimated Cost:- 98,175.00	
NAME OF WORK:- A/R & M/O on Various roads Lakkar Bazar section under Sub Division No.1						Earnest Money :-2,000.00	
(SH:- Supplying and Stacking Pot seal bags cold mix in Various Rds).						Time:- One Month	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Supplying and laying pot seal beg of 25 kgs cold mix including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	93.50	Nos	1050.00	Rupees One Thousand Fifty Only	Per Each	98175.00
						Total	98175.00
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						

R No. 1847/SN. 1016E-69 ch 19/6/26 Rd 101120

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.


Executive Engineer,
HPPWD Division,
Kasumpti Shimla

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-1, H.P.P.W.D., SHIMLA-3.					Estimated Cost:- 96,204.00		
Name of Work :- Improvement of Bhattakuffer to AIIMS road Km. 0/000 to 2/240. (SH:- Providing and fixing W-metal beam crash barrier on various reaches/RDs from KM 0/340 to 0/510).					Earnest Money :-2,000.00		
					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Earth work in excavation by mechanical by manual means over areas (exceeding 30 cm (Thirty centimetre) in depth, 1.5 m (One point five metre) in width as well as 10 sqm (ten Square Metre) on plan) including getting out and disposal of excavated earth all lead and lift as directed by Engineer-in-charge and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site (To be arranged by the contractor) as per satisfaction of Engineer- in - charge through all modes of transportation including head load ,animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required) Any loss to the public and private propriety, human being, machinery during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges , within a lead of 50 m. (i)All kinds of soil.	3.33	Cum	400.00	Rupees Four Hundred Only	Per Cubic Metre	1332.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and Shuttering All work up to plinth level including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 1:2:4 (One cement :Two coarse sand): four graded stone aggregate 20mm (Twenty milimeter) nominal size).	3.33	Cum	6400.00	Rupees Six Thousand Four Hundred Only	Per Cubic Metre	21312.00

3	Providing and erecting a "W" metal beam crash barrier comprising of 3 mm thick corrugated sheet metal beam rail, 70 cm above road / ground level, fixing in ISMC series channel vertical posts, 150x75x5 mm spaced 2 m centre to centre, 1.8 m high, 1.1 m below ground / road level, all steel parts and fittings to be galvanised by hot dipped process all fittings to conform to IS: 1367 and IS: 1364, metal beam rail to be fixed on the vertical post with a spacer of channel section 150x75x5 mm, 330 mm long complete as per clause 810.) including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	18.39	Rmt	4000.00	Rupees Four Thousand Only	Per Running meter	73560.00
	Quoted rates Percentage in figures					Total	96204.00
	Quoted rates Percentage in words						
						G.Total	

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standards.


 Executive Engineer,
 B& R Division Kasumpti
 HPPWD Winter Field Shimla -3


DRAFT SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.					Estimated Cost:- 96,284.00		
Name of Work :- Improvement of Bhattakuffer to AIIMS road Km. 0/000 to 2/240. (SH:- Providing and fixing W-metal beam crash barrier on various reaches/RDs from KM 0/680 to 0/850).					Earnest Money :-2,000.00		
					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Earth work in excavation by mechanical by manual means over areas (exceeding 30 cm (Thirty centimetre) in depth, 1.5 m (One point five metre) in width as well as 10 sqm (ten Square Metre) on plan) including getting out and disposal of excavated earth all lead and lift as directed by Engineer-in-charge and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site (To be arranged by the contractor) as per satisfaction of Engineer- in-charge through all modes of transportation including head load ,animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required) Any loss to the public and private propriety, human being, machinery during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges , within a lead of 50 m. (i)All kinds of soil.	3.33	Cum	400.00	Rupees Four Hundred Only	Per Cubic Metre	1332.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and Shuttering All work up to plinth level including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 1:2:4 (One cement :Two coarse sand); four graded stone aggregate 20mm (Twenty milimeter) nominal size).	3.33	Cum	6400.00	Rupees Six Thousand Four Hundred Only	Per Cubic Metre	21312.00

3	Providing and erecting a "W" metal beam crash barrier comprising of 3 mm thick corrugated sheet metal beam rail, 70 cm above road / ground level, fixing in ISMC series channel vertical posts, 150x75x5 mm spaced 2 m centre to centre, 1.8 m high, 1.1 m below ground / road level, all steel parts and fittings to be galvanized by hot dipped process all fittings to conform to IS: 1367 and IS: 1364, metal beam rail to be fixed on the vertical post with a spacer of channel section 150x75x5 mm, 330 mm long complete as per clause 810.) including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	18.41	Rmt	4000.00	Rupees Four Thousand Only	Per Running meter	73640.00
	Quoted rates Percentage in figures					Total	96284.00
	Quoted rates Percentage in words						
						G.Total	

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standards.

DNIT approved for Rs. 96,284 /- Only vide DNIT Register Sr.No..... the financial year 2026-27.T/S NO.....DATE.....AMT 99,172 /- only


 Executive Engineer,
 B& R Division Kasumpti
 HPPWD Winter Field Shimla -3


DRAFT SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-1, H.P.P.W.D., SHIMLA-3.					Estimated Cost:- 96,324.00		
Name of Work :- Improvement of Bhattakuffer to AIIMS road Km. 0/000 to 2/240. (SH:- Providing and fixing W-metal beam crash barrier on various reaches/RDs from KM 0/510 to 0/680).					Earnest Money :-2,000.00		
					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Earth work in excavation by mechanical by manual means over areas (exceeding 30 cm (Thirty centimetre) in depth, 1.5 m (One point five metre) in width as well as 10 sqm (ten Square Metre) on plan) including getting out and disposal of excavated earth all lead and lift as directed by Engineer-in-charge and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site (To be arranged by the contractor) as per satisfaction of Engineer- in -charge through all modes of transportation including head load ,animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required) Any loss to the public and private propriety, human being, machinery during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges , within a lead of 50 m. (i)All kinds of soil.	3.33	Cum	400.00	Rupees Four Hundred Only	Per Cubic Metre	1332.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and Shuttering All work up to plinth level including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 1:2:4 (One cement :Two coarse sand): four graded stone aggregate 20mm (Twenty millimeter) nominal size).	3.33	Cum	6400.00	Rupees Six Thousand Four Hundred Only	Per Cubic Metre	21312.00

3	Providing and erecting a "W" metal beam crash barrier comprising of 3 mm thick corrugated sheet metal beam rail, 70 cm above road / ground level, fixing in ISMC series channel vertical posts, 150x75x5 mm spaced 2 m centre to centre, 1.8 m high, 1.1 m below ground / road level, all steel parts and fittings to be galvanized by hot dipped process all fittings to conform to IS: 1367 and IS: 1364, metal beam rail to be fixed on the vertical post with a spacer of channel section 150x75x5 mm, 330 mm long complete as per clause 810.) including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	18.42	Rmt	4000.00	Rupees Four Thousand Only	Per Running meter	73680.00
	Quoted rates Percentage in figures					Total	96324.00
	Quoted rates Percentage in words						
						G.Total	

CONDITION:-

DNIT approved for Rs. 96,324 /- Only vide DNIT Register Sr.No..... the financial year 2026-27.T/S NO.....DATE.....AMT 99,214 /- only

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.



 Executive Engineer,
 B& R Division Kasumpti
 HPPWD Winter Field Shimla -3

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.					Estimated Cost:- 94,444.00		
Name of Work :- Improvement of Bhattakuffer to AHMS road Km. 0/000 to 2/240. (SH:- Providing and fixing W-metal beam crash barrier on various reaches/RDs from KM 0/850 to 1/000).					Earnest Money :-2,000.00		
					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Earth work in excavation by mechanical by manual means over areas (exceeding 30 cm (Thirty centimetre) in depth, 1.5 m (One point five metre) in width as well as 10 sqm (ten Square Metre) on plan) including getting out and disposal of excavated earth all lead and lift as directed by Engineer-in-charge and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site (To be arranged by the contractor) as per satisfaction of Engineer-in-charge through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required) Any loss to the public and private propriety, human being, machinery during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges , within a lead of 50 m. (i) All kinds of soil.	3.33	Cum	400.00	Rupees Four Hundred Only	Per Cubic Metre	1332.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and Shuttering All work up to plinth level including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 1:2:4 (One cement :Two coarse sand): four graded stone aggregate 20mm (Twenty milimeter) nominal size).	3.33	Cum	6400.00	Rupees Six Thousand Four Hundred Only	Per Cubic Metre	21312.00

3	Providing and erecting a "W" metal beam crash barrier comprising of 3 mm thick corrugated sheet metal beam rail, 70 cm above road / ground level, fixing in ISMC series channel vertical posts, 150x75x5 mm spaced 2 m centre to centre, 1.8 m high, 1.1 m below ground / road level, all steel parts and fittings to be galvanised by hot dipped process all fittings to conform to IS: 1367 and IS: 1364, metal beam rail to be fixed on the vertical post with a spacer of channel section 150x75x5 mm, 330 mm long complete as per clause 810.) including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	17.95	Rmt	4000.00	Rupees Four Thousand Only	Per Running meter	71800.00
	Quoted rates Percentage in figures					Total	94444.00
	Quoted rates Percentage in words						
						G.Total	

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standards.


 Executive Engineer,
 B & R Division Kasumpti
 HPPWD Winter Field Shimla -3