



Office of
Executive Engineer Jaisinghpur Division HPPWD Jaisinghpur Himachal Pradesh
Works Department Jaisinghpur 176095 Phone No. 01894-228030
Email ee-jaipwd-hp@gov.in

No.PWD/JSPR/CB/Tenders/2026-27- 2054-61

Dated:- 11-6-26

To,


The Chief Engineer (KZ),
Himachal Pradesh, PWD,
Dharamshala (HP).

Subject:- Publication of Tender Notice on departmental website.

Sir,

Enclosed please find herewith tender notice for publication of the same on departmental website as per Notification issued by the worthy Principal Secretary (PW) to the Govt. of HP letter No. PBW-(B) A-(3) 1/2024 dated Shimla-2 dated 03.01.2025 and instructions issued by the worthy E-in-C, HPPWD Shimla letter No. PWD/ ICT Wing/ Website dated 22.05.2026. It is certified that the tenders are of urgent nature and in public interest.

DA/ As above.


Executive Engineer,
Jaisinghpur Division,
HPPWD Jaisinghpur.

Copy forwarded to the following for information and necessary please:-

1. The Superintending Engineer, 5th Circle. HPPWD, Palampur.
- 2-4. All the Assistant Engineers working under this Division.
- 5-6. The Drawings Branch and Accounts Branch in this office.
7. Notice Board.

DA/ As above.


Executive Engineer
Jaisinghpur Division,
HP.PWD., Jaisinghpur.



OFFICE OF

Executive Engineer Jaisinghpur Division HPPWD Jaisinghpur Himachal Pradesh
Works Department Jaisinghpur 176095 Phone No. 01894-228030

"CERTIFICATE"

Certified that the tenders are being called in exigency of works of public
interest vide this office letter No. PWD/JSD/TA/NIT/ 2026-27-2054-61 dated
11-6-26.

Executive Engineer
Jaisinghpur Division
HPPWD., Jaisinghpur.



"NOTICE INVITING TENDERS"

Sealed percentage rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, HP.PWD., Division Jaisinghpur on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rules so as to reach in his office on or before on **18.06.2026 up to 11:00 A.M.** and the same shall be opened on the same day at **11:30 A.M.** in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on **16.06.2026 up to 4:00 PM** and the application for issue of tender form shall be received on or before **15.06.2026 up to 4:00 PM**. The applications for issue of tender forms should accompanied with enlistment letter or renewal letter and the Earnest Money in the shape of National Saving Certificates / Saving Account of the Post Office / Time Deposit account / FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP.PWD., Division Jaisinghpur.

The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for **75 days**:-

Sr. No.	Name of Work	Estimated Cost (Rs.)	EMD	Time limit	Cost of tender form
1	Restoration of rain Damages on Alampur to Harsipattan road Km 0/00 to 7/800 (SH:-C/O R/wall at RD 4/120 to 4/133 and B/Wall at RD 0/625 to 0/635, 0/765 to 0/776) PDNA	499813.00	10000.00	Two Month	350/-
2	Restoration of rain Damages on Gander to Karonthi road Km 0/00 to 3/500 (SH:-Providing and fixing dual directional rumble strips) Deposit	98175.00	2000.00	Two Month	350/-
3	Restoration of rain Damages on Gander Siyara Kudana road Km 0/00 to 9/780 (SH:-P/L CC pavement at RD 2/00 to 2/081) PDNA	494728.00	9900.00	Two Month	350/-
4	A/R & M/O Deru Da bar to Dhar Bharampuri roadbetween km 0/00 to 1/00 (SH:-Repair of Pot Hole / patch work between Km 0/00 to 1/000)	99932.00	2000.00	One month	350/-
5	Restoration of rain Damages on Gander Siyara Kudana road Km 0/00 to 9/780 (SH:-P/L CC pavement at RD2/246 to 2/327) PDNA	494755.00	9900.00	Two Month	350/-

Terms & Conditions:-

1. The contractors will have to produce a copy of enlistment / renewal of valid class at time of application / tender form.
2. The contractors will have to produce a copy of GST, EPF and PAN.
3. The contractors are directed to insert the rate / percentage both in figures and words.
4. The tenders forms will not be issued to those contractors who have not completed their previous works / commitments or whose performance is not found satisfactory.
5. The Executive Engineer reserves the right to reject / cancel any or all the tenders without assigning any reason.

Executive Engineer
Jaisinghpur Division
HP.PWD., Jaisinghpur.

(On behalf of Governor of Himachal Pradesh)


(1)

SCHEDULE OF QUANTITY

ame of work :-Restoration of rain Damages on Alampur to Harsipattan road Km 0/00 to 7/800
 SH:-C/O R/wall at RD 4/120 to 4/133 and B/Wall at RD 0/625 to 0/635, 0/765 to 0/776) PDNA

				Estimated cost Rs.	499813.00	
				Earnest Money Rs.	10000.00	
				Time Limits	Two Month	
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	65.57	225.00	Rupees Two Hundred Twenty Five Only	Per cubic Metre	14753.00
2	Providing and laying cement concrete 1:4:8 (One cement: four sand: eight graded crushed/broken stone aggregate 40mm (forty millimetre) nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	107.95	4250.00	Rupees Four Thousand Two Hundred Fifty Only	Per Cubic Metre	458788.00


3	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700, 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	71.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	17750.00
4	Back filling with granular materials behind abutment, Retaining wall/Breast wall, Wing walls and the like complete as per drawings and MORD technical specification section 1200, 1600 and as per direction and entire satisfaction of the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	8.97	950.00	Rupees Nine Hundred Fifty Only	Per cubic Metre	8522.00
	Total					499813.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					


 Executive Engineer,
 Jaisinghpur Division,
 HP.PWD Jaisinghpur

(2)

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages on Gander to Karonthi road Km 0/00 to 3/500 (SH:- Providing and fixing dual directional rumble strips) PDNA						Estimated cost Rs.	98175.00
						Earnest Money Rs.	2000.00
						Time Limits	Two month
S. N.	Description of Item	Quantity	Rate		Unit	Amount	
			In Figures	In Word			
1	Providing and fixing dual directional rumble strips made of ABS (Acrylonitrile Butadiene styrene) material of size 250 mm x150 mm (Two hundred fifty to one hundred fifty millimetre) duly reflectorised with highly reflective glass panels on both sides and to be fixed with 2No. steel pins and suitable epoxy ncluding carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	77.000	1275.00	Rupees One Thousand Two Hundred Seventy Five Only	Each	98175.00	
	Total					98175.00	
	Quoted Rate (in Figures) Percentage	Excess (+)			%		
		Less (-)			%		
	G.Total in Figures						
	G.Total in Words						


 Executive Engineer,
 Jaisinghpur Division,
 HP.PWD Jaisinghpur

3

SCHEDULE OF QUANTITY


Name of work :-Restoration of rain Damages on Gander Siyara Kudana road Km 0/00 to 9/780
(SH:-P/L CC pavement at RD 2/00 to 2/081) PDNA

Estimated cost Rs.	494728.00
Earnest Money Rs.	9900.00
Time Limits	Two month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Scarifying the existing bituminous road surface to a depth of 50 mm and disposal of scarified material within all lifts and lead upto 1 Km (by mechanical means including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	259.200	6.71	Rupees Six And Paise Seventy One Only	Per square Metre	1739.00
2	Providing laying spreading and compacting by mechanical means 75 mm (seventy five millimetre) compacted thickness broken /crushed stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred) K.N. static roller in stages to proper grade and camber including applying and brooming, stone screening type B of size 11.2mm (eleven decimal two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per drawing and M.O.R.D. technical specifications section 400 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	19.44	2100.00	Rupees Two Thousand One Hundred Only	Per Cubic Metre	40824.00

3	Providing and laying design mix cement concrete of M-30(Thirty) grade, in roads using cement content as per design mix, using coarse sand and graded stone aggregate of 40 mm(forty millimetre) nominal size in appropriate proportions as per approved & specified design criteria, providing dowel bars with sleeve/ tie bars wherever required, laying at site, spreading and compacting mechanically by using needle and surface vibrators, levelling to required slope/ camber, finishing with required texture, including steel form work with sturdy M.S. channel sections, curing, making provision for contraction/ expansion, construction & longitudinal joints (10 mm wide x 50 mm)(ten millimetre wide into fifty millimetre deep) by groove cutting machine, providing and filling joints with approved joint filler and sealants, complete all as per direction of Engineerincharge (Item of joint fillers, sealants, dowel bars with sleeve/ tie bars to bepaid separately).Cement content considered in M-30(Thirty) is @ 340 kg/cum (at the rate three hundred forty kilograme per cubic metre). Excess/ less cement used as per design mix is payable/ recoverable separately.Cement concrete prepared with batch mixing machine.as per direction of Engineer-in- charge.and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	51.84	8200.00	Rupees Eight Thousand Two Hundred Only	Per Cubic Metre	425088.00
---	--	-------	---------	--	-----------------	-----------

4	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M ten) nominal mix 1:3:6 (one cement is to three sand is to six crushed stone aggregate 20mm(twenty millimetre) nominal size) on ground or under water including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work and curing complete in drain as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	5.47	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per Cubic Metre	27077.00
	Total					494728.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					


 Executive Engineer,
 Jaisinghpur Division,
 HP.PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-A/R & M/O Deru Da bar to Dhar Bharampuri roadbetween km 0/00 to 1/00 (SH:-
Repair of Pot Hole / patch work between Km 0/00 to 1/000)

Estimated cost Rs.	99932.00
Earnest Money Rs.	2000.00
Time Limits	One Month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Repairing of pot holes and removal of loose material trimming of sides by providing with Bitumen Rs-I tack coat at the rate of 0.225 kg. (zero point thirty kilograms) per Square metre,Open grades premix carpet of 20mm (twenty millimeter) thickness composed of 13.2mm (thirteen decimal two millimeter) to 5.6mm (five decimal six millimeter) aggregate @ 0.27 cum (zero decimal twenty seven cubic metres) mixed with using penetration grade bitumen VG-10(ten) @ 14.60 kg (fourteen point sixty kilogram) per ten square of road surface required line grade and level and seal coat sealing the voids in a bituminous surface laid to specified level grade and cross fall using type-B as per M.O.R.D. technical specification clause 510 premixed with 6.8 kg (six point eight) kilogram bitumen vg-10 (ten) 0.06 (zero point zero six) cubic metre of fine aggregate per 10 Sqm. (Ten square metre) heated in mini hot mix plant and laying manually of mixed material and rolling with power road roller 8-10 (eight to ten capacity) and as per directions of Engineer - in- Charge.	245.00	400.00	Rupees Four Hundred Only	Per Square Metre	98000.00

2	Providing laying spreading and compacting by mechanical means 75 mm (seventy five millimetre) compacted thickness broken /crushed stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred) K.N. static roller in stages to proper grade and camber including applying and brooming, stone screening type B of size 11.2mm (eleven decimal two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per drawing and M.O.R.D. technical specifications section 400 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	0.92	2100.00	Rupees Two Thousand One Hundred Only	Per Cubic Metre	1932.00
		Excess (+)			%	99932.00
	Quoted Rate (in Figures) Percentage	Less (-)			%	
	G.Total in Figures					
	G.Total in Words					


 Executive Engineer
 Jaisinghpur Division
 HPPWD Jaisinghpur



SCHEDULE OF QUANTITY


Name of work :-Restoration of rain Damages on Gander Siyara Kudana road Km 0/00 to 9/780
(SH:-P/L CC pavement at RD2/246 to 2/327) PDNA

Estimated cost Rs.	494755.00
Earnest Money Rs.	9900.00
Time Limits	Two month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Scarifying the existing bituminous road surface to a depth of 50 mm and disposal of scarified material within all lifts and lead upto 1 Km (by mechanical means including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	263.250	6.71	Rupees Six And Paise Seventy One Only	Per square Metre	1766.00
2	Providing laying spreading and compacting by mechanical means 75 mm (seventy five millimetre) compacted thickness broken /crushed stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred) K.N. static roller in stages to proper grade and camber including applying and brooming, stone screening type B of size 11.2mm (eleven decimal two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per drawing and M.O.R.D. technical specifications section 400 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	19.44	2100.00	Rupees Two Thousand One Hundred Only	Per Cubic Metre	40824.00

3	Providing and laying design mix cement concrete of M-30(Thirty) grade, in roads using cement content as per design mix, using coarse sand and graded stone aggregate of 40 mm(forty millimetre) nominal size in appropriate proportions as per approved & specified design criteria, providing dowel bars with sleeve/ tie bars wherever required, laying at site, spreading and compacting mechanically by using needle and surface vibrators, levelling to required slope/ camber, finishing with required texture, including steel form work with sturdy M.S. channel sections, curing, making provision for contraction/ expansion, construction & longitudinal joints (10 mm wide x 50 mm)(ten millimetre wide into fifty millimetre deep) by groove cutting machine, providing and filling joints with approved joint filler and sealants, complete all as per direction of Engineerincharge (Item of joint fillers, sealants, dowel bars with sleeve/ tie bars to be paid separately).Cement content considered in M-30(Thirty) is @ 340 kg/cum (at the rate three hundred forty kilograme per cubic metre). Excess/ less cement used as per design mix is payable/ recoverable separately.Cement concrete prepared with batch mixing machine.as per direction of Engineer-in- charge.and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	51.84	8200.00	Rupees Eight Thousand Two Hundred Only	Per Cubic Metre	425088.00
---	---	-------	---------	--	-----------------	-----------

4	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M ten) nominal mix 1:3:6 (one cement is to three sand is to six crushed stone aggregate 20mm(twenty millimetre) nominal size) on ground or under water including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work and curing complete in drain as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	5.47	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per Cubic Metre	27077.00
	Total					494755.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					


 Executive Engineer,
 Jaisinghpur Division,
 HP.PWD Jaisinghpur