



HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

Office of the Executive Engineer National Highway Division HPPWD Theog.

Email: eenh-theog-hp@gov.in Phone/ Fax No.: 01783-238900

NO.PW.TH.D/CB/TENDER/Tender Notice/2026 - 911-13
To

Dated:- 28.6.2026

The Executive Engineer,(IT)
Nigam Vihar Shimla 2

Subject:- Publication of tender Notice.

Enclose please find herewith the Tender Notice of the works as given in the Notice inviting Tender for uploading on department website as per Notification Pr. Secy. (PW)) to the Govt. of HP letter No PBW(B)A(3)1/2024 dated 03.01.2024 as the work mentioned in the tender notice are urgent in nature and in public interest.

Encl:- Schedule of Quantity.


Executive Engineer,
NH Division,
H.P.P.W.D., Theog

Copy forwarded to the Superintending Engineer NH Circle Shimla HP PWD for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer(IT) Cell), Nigam Vihar Shimla-2 for information and further necessary action please.


Executive Engineer,
NH Division,
H.P.P.W.D., Theog

Himachal Pradesh
Public Works Department
Notice Inviting Tender

Sealed Percent rates tender form No 7 & 8 are hereby invited by the Executive Engineer NH Division HP PWD Theog for the following works on behalf of the Governor of Himachal Pradesh from the eligible contractors enlisted in HP PWD so as to reach in this office as per time schedule Given below:-


1	Date of receipt of Applications for tender forms:	27.06.2026 upto 12:00 PM
2	Date of issue/sale of Tender forms:-	27.06.2026 upto 4:00 PM
3	Date of receipt of Tender:-	30.06.2026 upto 10:30 AM
4	Date of opening of Tender	30.06.2026 upto 11:00 AM

Sr. No	Job No.	Name of Works	Estimated Cost	Earnest Money	Cost of form	Time Period for completion
1	1	A/R and M/O Shimla bye Pass road km 13/00 to 24/250 .(SH:- Maintenance of Earthen shoulder and Clearing grass in km 22/00 to 24/00)	98945/-	2000/-	350/-	1 Month
2	2	A/R and M/O Shimla bye Pass road km 13/00 to 24/250 .(SH:- Maintenance of Earthen shoulder and Clearing grass in km 15/00 to 22/00)	426662/-	9000/-	350/-	1 Month
3	3	A/R and M/O Kalka Shimla Wangtoo road km 153/180 to 167/000.(SH:- Maintenance of Earthen shoulder ,Clearing grass , Drain and Culvert clearance in km 156/507 to 163/00)	497423/-	10000/-	350/-	1 Month
4	4	A/R and M/O Kalka Shimla Wangtoo road km 153/180 to 167/000.(SH:- Maintenance of Earthen shoulder ,Clearing grass , Drain and Culvert clearance in km 163/00 to 165/00)	290099/-	6000/-	350/-	1 Month
5	5	Maintenance on Shimla Bye Pass damages 13/00 to 24/250 and 153/180 to 167/00.(SH:- Hiring of JCB Excavator Cum loader and tipper for removal of slips & maintenance of earthen shoulder at various 13/00 to 16/00)	492692/-	10000/-	350/-	3 Months
6	6	Maintenance on Shimla Bye Pass damages 13/00 to 24/250 and 153/180 to 167/00.(SH:- Hiring of JCB Excavator Cum loader and tipper for removal of slips & maintenance of earthen shoulder at various 19/00 to 21/00)	498543/-	10000/-	350/-	3 Months
7	7	Maintenance of NH-22 (New NH 05) from Km 13/00 to 24/250 and 153/180 to 156/507 On Kalka-Shimla Wangtoo road (SH: Cutting of Grass and bushes, Prov.& applying White washing, Clearance of chowked drains,, Finishing with Epoxy paint between rd 18/00 to 19/00)	99747/-	2000/-	350/-	3 Months
8	8	Maintenance on Shimla Bye Pass road km 13/00 to 24/250 and 153/180 to 167/00. (SH:- Geological investigation for construction of box culvert at Rd 20/405)	73000/-	1500/-	350/-	3 Months
9	9	Maintenance on Shimla Bye Pass road (New Nh-05) km 13/00 to 24/250 . (SH:- Clearance of drain between rd 20/800 to 21/500)	90713/-	2500/-	350/-	3 Months
10	10	A/R and M/O Kalka Shimla Wangtoo road km 167/00 to 236/000.(SH:- Maintenance of Earthen shoulder ,Clearing grass and Drain clearance in km 193/00 to 195/000)	252060/-	5000/-	350/-	1 Month
11	11	A/R and M/O Kalka Shimla Wangtoo road km 167/00 to 236 /000.(SH:- Maintenance of Earthen shoulder ,Clearing grass and Drain clearance in km 177/00 to 181/00)	404866/-	8000/-	350/-	1 Month

12	12	Maintenance on Theog Kotkhai Hatkoti road NH-705 k.m. 0/000 to 69/0000 (SH:- (SH:- Hiring of machineries and manual labour between R.D 50/000 to 69/000).	498775/-	10000/-	350/-	3 Months
13	13	-Maintenance on Theog Kotkhai Hatkoti road 0/000 to 69/0000 (SH:- (SH:- Hiring of machineries and manual labour between R.D 39/00 to 46/00).	497675/-	10000/-	350/-	3 Months
14	14	Name of work:-Maintenance on Theog Kotkhai Hatkoti road 0/000 to 69/0000 (SH:- (SH:- Hiring of machineries and manual labour between R.D 30/00 to 35/00).	498775/-	10000/-	350/-	3 Months
15	15	Maintenance of Shimla Bye pass road RD 13/00 to 24/250(SH: Restoration of rain cuts, maintenance of earthan shoulder 18/800 to 19/00)	98700/-	2000/-	350/-	3 Months
16	16	Maintenance of Shimla Bye pass road RD 13/00 to 24/250(SH: Restoration of rain cuts, maintenance of earthan shoulder 19/00 to 20/00)	98700/-	2000/-	350/-	3 Months

Terms & Conditions:- The tender documents shall be issued to those contractors/firms who fulfill the following documents with the application:

- 1 The valid enlistment/ registration of contractor in appropriate class.
- 2 Permanent Account Number(PAN)
- 3 GST Number and EPF No.
- 4 Earnest Money in the shape of National saving certificate/Time deposit account in any of the Post office in HP FDR from Tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & Cost tender form shall summarily be rejected.
- 5 Ambiguous/telegraphic/Conditional tender of tender by fax/ E-mail shall not be entertained/considered and will summarily be rejected.
- 6 Executive Engineer reserves the right to reject or cancel any or all the tenders without assigning any reasons.
- 7 The offer of the tender shall remain valid upto 120 days after the opening of tender.
- 8 If the date given above happens to be a holiday, the same shall be processed on next working days.
- 9 The Contractors/firm must quote their rates in words as well as in figures failing which Xen reserves the right to accept/reject any or all tenders.
- 10 The Tender form will not be issued to those contractors/firms whose previous performance is not found satisfactory and who have not executed/completed the previous awarded works within the stipulated period of completion.
- 11 One Contractor should not have more than two works in hand at a time.
- 12 Works should be completed by the contractor within the stipulated period.


Executive Engineer,
NH Division,
H.P.P.W.D., Theog

Dated

No/PW/NH/CB/Tender/2026-27

Copy forwarded for information and necessary actions to:

- 1 The Superintending Engineer NH Circle HP PWD Shimla .
- 2 All the Assistant Engineer working under this Division
- 3 The Drawing Branch/Account Branch in this office.
- 4 Notice Board.


Executive Engineer,
NH Division,
H.P.P.W.D., Theog



NATIONAL HIGHWAY (NH-05)
HIMACHAL PRADESH PUBLIC WORKS DE
PARTMENT DIVISION THEOG

Certificate

Certified that the tenders of works as called
vide this office NIT No/PW/NH/CB/Tender/2026-27 903-10 Dated
20.3.2026 are urgent nature and public interest.


Executive Engineer,
NH Division,
H.P.P.W.D., Theog

SCHEDULE OF QUANTITY

		Estimated Cost:-		Rs:- 98945		
		Earnest Money		Rs:- Rs:-2000 only.		
		Time.		One Month		
Name of work:-A/R and M/O Shimla bye Pass road km 13/00 to 24/250 .(SH:- Maintenance of Earthen shoulder and Clearing grass in km 22/00 to 24/00)						
Sr. No	Description of item	Quantity	Unit	Rate	Rate In words	Amount
1	Maintenance of Earthen shoulder filling with soil making up loss material /irregularities on shoulder to the desired level by adding soil and ompacting it with appropriate equipment upto all leads and lifts as per technical specification clause 1903 as per the entire satisfaction and direction of the Engineer -in -Charge including carriage of materials by mechanical transport in all leads and lifts confirming with the MORTH Specificationand as per direction of the Engineer-in-Charge.	1514.00	Per Squire Meter	55.08	(Rs Fifty Five and Paisa Eight)Only	83391.12
2	Clearing Grass and Removal of Rubbish Clearing grass and removal of rubbish up to a distance of 50 metres outside the periphery of the area including carriage of materials in all leads and lifts confirming with the MORTH Specification and as per direction of the Engineer-in-Charge.	3020.00	Per Squire Meter	5.15	(Rs Five & Paisa Fifteen)Only	15553.00
Total						98944.12
(Quoted Rates in Figures)(+/-%)		(.....%)				
(Quoted Rates in words)(+/-%)		(.....%)				
Conditions						
1. Rate in						

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost


 Executive Engineer,
 NH Division HPPWD,
 Theog.

SCHEDULE OF QUANTITY

Estimated Cost:	Rs:- 426662
Earnest Money	Rs:- 9000 only.
Time.	One Month

Name of work:-A/R and M/O Shimla bye Pass road km 13/00 to 24/250 .(SH:- Maintenance of Earthen shoulder and Clearing grass in km 15/00 to 22/00)

Sr. No	Description of item	Quantity	Unit	Rate	Rate In words	Amount
1	Maintenance of Earthen shoulder filling with soil making up loss material /irregularities on shoulder to the desired level by adding soil and ompacting it with appropriate equipment upto all leads and lifts as per technical specification clause 1903 as per the entire satisfaction and direction of the Engineer -in -Charge including carriage of materials by mechanical transport in all leads and lifts confirming with the MORTH Specificationand as per direction of the Engineer-in-Charge.	6302.00	Per Squire Meter	55.08	(Rs Fifty Five and Paisa Eight)Only	347114.16
2	Clearing Grass and Removal of Rubbish Clearing grass and removal of rubbish up to a distance of 50 metres outside the periphery of the area including carriage of materials in all leads and lifts confirming with the MORTH Specification and as per direction of the Engineer-in-Charge.	15446.00	Per Squire Meter	5.15	(Rs Five & Paisa Fifteen)Only	79546.90
	Total					426661.06
	(Quoted Rates in Figures)(+/-%)				(.....%)	
	(Quoted Rates in words)(+/-%)				(.....%)	

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost


 Executive Engineer,
 NH Division HPPWD,
 Theog.

SCHEDULE OF QUANTITY

Estimated Cost:	Rs:- 497423
Earnest Money	Rs:- 10000 only.
Time.	One Month

Name of work:-A/R and M/O Kalka Shimla Wangtoo road km 153/180 to 167/000.(SH:- Maintenance of Earthen shoulder ,Clearing grass , Drain and Culvert clearance in km 156/507 to 163/00)

Sr. No	Description of item	Quantity	Unit	Rate	Rate In words	Amount
1	Maintenance of Earthen shoulder filling with soil making up loss material /irregularities on shoulder to the desired level by adding soil and ompacting it with appropriate equipment upto all leads and lifts as per technical specification clause 1903 as per the entire satisfaction and direction of the Engineer -in -Charge including carriage of materials by mechnical transport in all leads and lifts confirming with the MORTH Specificationand as per direction of the Engineer-in-Charge.	5357.00	Per Squire Meter	55.08	(Rs Fifty Five and Paisa Eight)Only	295063.56
2	Clearing Grass and Removal of Rubbish Clearing grass and removal of rubbish up to a distance of 50 metres outside the periphery of the area including carriage of materials in all leads and lifts confirming with the MORTH Specification and as per direction of the Engineer-in-Charge.	6122.00	Per Squire Meter	5.15	(RsFive & Paisa Fifteen)Only	31528.30
3	Removal of earth from the choked hill side drain and disposing it on the valley side manually including carriage of materials in all leads and lifts confirming with the MORTH Specificationand as per direction of the Engineer-in-Charge.	1860.00	Running Meter	77.65	(Rs Seventy Seven & Paisa Sixty Five)Only	144429.00
4	Clearing slab/ box type culverts and pipe culverts including clearing, cleaning and reshaping of upstream and downstream faces of these culverts within right of way. The job includes disposal of excess material recovered from site including vegetation outside ROW with all leads and lifts complete in all respects as per direction of Engineer-In- Charge and as per Maintenance Standards Clause 3.1 b) Pipe Culverts	9.00	Each	2933.50	(Rs Two Thousands Nine Hundred Thirty Three & Paisa Fifty)Only	26401.50
Total						497422.36
(Quoted Rates in Figures)(+/-)				%)		
(Quoted Rates in words)(+/-)				%)		

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost


 Executive Engineer,
 NH Division HPPWD,
 Theog.

SCHEDULE OF QUANTITY

Estimated Cost:	Rs:- 290099
Earnest Money	Rs:- Rs:-6000 only.
Time.	One Month

Name of work:-A/R and M/O Kalka Shimla Wangtoo road km 153/180 to 167/000.(SH:- Maintenance of Earthen shoulder ,Clearing grass , Drain and Culvert clearance in km 163/00 to 165/00)

Sr. No.	Description of item	Quantity	Unit	Rate	Rate In words	Amount
1	Maintenance of Earthen shoulder filling with soil making up loss material /irregularities on shoulder to the desired level by adding soil and ompacting it with appropriate equipment upto all leads and lifts as per technical specification clause 1903 as per the entire satisfaction and direction of the Engineer -in -Charge including carriage of materials by mechnical transport in all leads and lifts confirming with the MORTH Specificationand as per direction of the Engineer-in-Charge.	1823.00	Per Squire Meter	55.08	(Rs Fifty Five and Paisa Eight)Only	100410.84
2	Clearing Grass and Removal of Rubbish Clearing grass and removal of rubbish up to a distance of 50 metres outside the periphery of the area including carriage of materials in all leads and lifts confirming with the MORTH Specification and as per direction of the Engineer-in-Charge.	5940.00	Per Squire Meter	5.15	(RsFive & Paisa Fifteen)Only	30591.00
3	Removal of earth from the choked hill side drain and disposing it on the valley side manually including carriage of materials in all leads and lifts confirming with the MORTH Specificationand as per direction of the Engineer-in-Charge.	1860.00	Running Meter	77.65	(Rs Seventy Seven & Paisa Sixty Five)Only	144429.00
4	Clearing slab/ box type culverts and pipe culverts including clearing, cleaning and reshaping of upstream and downstream faces of these culverts within right of way. The job includes disposal of excess material recovered from site including vegetation outside ROW with all leads and lifts complete in all respects as per direction of Engineer-In- Charge and as per Maintenance Standards Clause 3.1 b) Pipe Culverts	5.00	Each	2933.50	(Rs Two Thousasnds Nine Hundred Thirty Three & Paisa Fifty)Only	14667.50
Total						290098.34
(Quoted Rates in Figures)(+/-)				(.....%)		
(Quoted Rates in words)(+/-)				(.....%)		

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost


 Executive Engineer,
 NH Division HPPWD,
 Theog.

SCHEDULE OF QUANTITY

Estimated Cost:	Rs:- 492692
Earnest Money	Rs:- 10000 only.
Time.	3 Months

Name of work:- Maintenance on Shimla Bye Pass damages 13/00 to 24/250 and 153/180 to 167/00. (SH:- Hiring of JCB Excavator Cum loader and tipper for removal of slips & maintenance of earthen shoulder at various 13/00 to 16/00)

Sr. N.	Description of item	Quantity	Unit	Rate	Rate In words	Amount
1	Hiring of JCB having loading bucket capacity of 0.90 cum to 1.00 cum and back hoe bucket capacity of 0.20 to 0.30 cum for removal of clearance of Slips in all leads and lifts and disposal of unserviceable material upto dumping site and stacking of serviceable material along road side and neatly dressing the road as per direction of the Engineer-in-Charge	88.00	Per Hours	2782.00	(Rs Two Thousands Seven Hundred Eighty Two)Only	244816.00
2	Hiring of Tipper for carriage of debris/Boulder and other construction materials from various location including wages of tipper driver, cleaner including P.O.L. Any repair/ damaged during the work will be absolute responsibility of the contractor/owner hours per day, the tipper has to work at least minimum 8 hours per day.	88.00	Per Hours	1681.00	(Rs One Thousand Six Hundred Eighty One and Paisa zero)Only	147928.00
3	Hiring of manual labour for clearing of drain, brooming of road surface etc including all leads and lifts as per the directions of Engineer-in-Charge. (5 Persons per day).	50.00	Per day	495.83	(Rs Four Hundred Ninty Five and Paisa	24792.00
	Total					417536.00
	Add 18 % GST					75156.00
						492692.00
	(Quoted Rates in Figures)(+/-)				(.....%)	
	(Quoted Rates in words)(+/-)				(.....%)	

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost


 Executive Engineer,
 NH Division HPPWD,
 Theog.

SCHEDULE OF QUANTITY

Estimated Cost:	Rs:- 498543
Earnest Money	Rs:- Rs:-10000 only.
Time.	3 Months

Name of work:- Maintenance on Shimla Bye Pass damages 13/00 to 24/250 and 153/180 to 167/00. (SH:- Hiring of JCB Excavator Cum loader and tipper for removal of slips & maintenance of earthen shoulder at various 19/00 to 21/00)

Sr. No	Description of item	Quantity	Unit	Rate	Rate In words	Amount
1	Hiring of JCB having loading bucket capacity of 0.90 cum to 1.00 cum and back hoe bucket capacity of 0.20 to 0.30 cum for removal of clearance of Slips in all leads and lifts and disposal of unserviceable material upto dumping site and stacking of serviceable material along road side and neatly dressing the road as per direction of the Engineer-in-Charge	88.00	Per Hours	2782.00	(Rs Two Thousands Seven Hundred Eighty Two)Only	244816.00
2	Hiring of Tipper for carriage of debris/Boulder and other construction materials from various location including wages of tipper driver, cleaner including P.O.L. Any repair/ damaged during the work will be absolute responsibility of the contractor/owner hours per day, the tipper has to work at least minimum 8 hours per day.	88.00	Per Hours	1681.00	(Rs One Thousand Six Hundred Eighty One and Paisa zero)Only	147928.00
3	Hiring of manual labour for clearing of drain, brooming of road surface etc including all leads and lifts as per the directions of Engineer-in-Charge. (5 Persons per day).	60.00	Per day	495.83	(Rs Four Hundred Ninty Five and Paisa Eighty Three	29750.00
	Total					422494.00
	Add 18 % GST					76049.00
						498543.00
	(Quoted Rates in Figures) (+/-)				(.....%)	
	(Quoted Rates in words) (+/-)				(.....%)	

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost


 Executive Engineer,
 NH Division HPPWD,
 Theog.

SCHEDULE OF QUANTITY

Estimated Cost:	Rs:- 99747
Earnest Money	Rs:- 2000 only.
Time.	3 Months

Name of work:- Maintenance of NH-22 (New NH 05) from Km 13/00 to 24/250 and 153/180 to 156/507 On Kalka-Shimla Wangtoo road (SH: Cutting of Grass and bushes, Prov.& applying White washing, Clearance of chowked drains,, Finishing with Epoxy paint between rd 18/00 to 19/00)

Sr. No	Description of item	Quantity	Unit	Rate	Rate In words	Amount
1	Clearing grass and removal of rubbish up to a distance of 50 metres outside the periphery of the area	4000.00	Sqm	4.96	(Rs Four and Paise Ninty Six)Only	19840.00
2	White washing with lime to give an even shade Old work (one or more coats) on Parapets, Trees, B/wall and V-shape drain etc. As per direction of Engineer-in-Charges.	600.00	RMT	26.88	(Rs Twenty Six and Paise Eighty eight)Only	16128.00
3	Removal of earth from the choked hill side drain and disposing it on the valley side	600.00	RMT	74.43	(Rs Seventy Four and Paise Forty Three)Only	44658.00
4	Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete. On concrete work	95.51	Sqm	200.20	(Rs Two Hundred and Paise twenty) only	19121.00
Total						99747.00
(Quoted Rates in Figures)(+/-)				(.....%)		
(Quoted Rates in words)(+/-)				(.....%)		

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost


 Executive Engineer,
 NH Division HPPWD,
 Theog.

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY						
			Estimated Cost:		Rs:- 73000	
			Earnest Money		Rs:- Rs:-1500 only.	
			Time.		3 Months	
Name of work:-Maintenance on Shimla Bye Pass road km 13/00 to 24/250 and 153/180 to 167/00. (SH:- Geological investigation for construction of box culvert at Rd 20/405)						
Sr. No	Description of item	Quantity	Unit	Rate	Rate In words	Amount
1	Sub Soil investigation in all types of soil/strata by drilling bore holes of NX size 75mm dia for investigation of soil rockconditions at site of work. The scope of work includes presevation of core including relevant tests and submission of geotechnical report of complex site of work including carriage of materials within all leads and as per directions of the Engineer-In-Charge.	10.00	Per Meter	7300.00	Rupees One thousand One Hundred Only	73000.00
Total						73000.00
(Quoted Rates in Figures)(+/-%)		(.....%)				
(Quoted Rates in words)(+/-%)		(.....%)				

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost



 Executive Engineer,
 NH Division HPPWD,
 Theog.

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY					Rs:- 90713	
				Estimated Cost:	Rs:- 2500 only.	
				Earnest Money	3 Months	
				Time.		
Name of work:-Maintenance on Shimla Bye Pass road (New Nh-05) km 13/00 to 24/250 . (SH:- Clearance of drain between rd 20/800 to 21/500)						
Sr. No	Description of item	Quantity	Unit	Rate	Rate In words	Amount
1	Removal of earth from the choked hill side drain and disposing it on the valley side manually complete or as per the direction of Engineer-In- Charge.	1250.00	Per Meter	72.57	Rupees Seventy Two and fifty seven Paisa Only	90713.00
	Total					90713.00
	(Quoted Rates in Figures)(+/-%)					(.....%)
	(Quoted Rates in words)(+/-%)					(.....%)

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost


 Executive Engineer,
 NH Division HPPWD,
 Theog.

SCHEDULE OF QUANTITY

Estimated Cost:	Rs:- 252060
Earnest Money	Rs:- Rs:-5000 only.
Time.	One Month

Name of work:-A/R and M/O Kalka Shimla Wangtoo road km 167/00 to 236/000.(SH:- Maintenance of Earthen shoulder ,Clearing grass and Drain clearance in km 193/00 to 195/000)

Sr. N	Description of item	Quantity	Unit	Rate	Rate In words	Amount
1	Maintenance of Earthen shoulder filling with soil making up loss material /irregularities on shoulder to the desired level by adding soil and ompacting it with appropriate equipment upto all leads and lifts as per technical specification clause 1903 as per the entire satisfaction and direction of the Engineer -in -Charge including carriage of materials by mechanical transport in all leads and lifts confirming with the MORTH Specificationand as per direction of the Engineer-in-Charge.	1671.00	Per Squire Meter	55.08	(Rs Fifty Five and Paisa Eight)Only	92038.68
2	Clearing Grass and Removal of Rubbish Clearing grass and removal of rubbish up to a distance of 50 metres outside the periphery of the area including carriage of materials in all leads and lifts confirming with the MORTH Specification and as per direction of the Engineer-in-Charge.	5440.00	Per Squire Meter	5.15	(Rs Five & Paisa Fifteen)Only	28016.00
3	Removal of earth from the choked hill side drain and disposing it on the valley side manually including carriage of materials in all leads and lifts confirming with the MORTH Specificationand as per direction of the Engineer-in-Charge.	1700.00	Running Meter	77.65	(Rs Seventy Seven & Paisa Sixty Five)Only	132005.00
Total						252059.68
				(Quoted Rates in Figures)(+/-(.....%)		
				(Quoted Rates in words)(+/-(.....%)		

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost


Executive Engineer,
NH Division HPPWD,
Theog.

SCHEDULE OF QUANTITY

				Estimated Cost:	Rs:-	404866
				Earnest Money	Rs:-	Rs:-8000 only.
				Time.		One Month
Name of work:-A/R and M/O Kalka Shimla Wangtoo road km 167/00 to 236 /000.(SH:- Maintenance of Earthen shoulder ,Clearing grass and Drain clearance in km 177/00 to 181/00)						
Sr. N	Description of item	Quantity	Unit	Rate	Rate In words	Amount
1	Maintenance of Earthen shoulder filling with soil making up loss material /irregularities on shoulder to the desired level by adding soil and ompacting it with appropriate equipment upto all leads and lifts as per technical specification clause 1903 as per the entire satisfaction and direction of the Engineer -in -Charge including carriage of materials by mechnical transport in all leads and lifts confirming with the MORTH Specificationand as per direction of the Engineer-in-Charge.	2952.00	Per Squire Meter	55.08	(Rs Fifty Five and Paisa Eight)Only	162596.16
2	Clearing Grass and Removal of Rubbish Clearing grass and removal of rubbish up to a distance of 50 metres outside the periphery of the area including carriage of materials in all leads and lifts confirming with the MORTH Specification and as per direction of the Engineer-in-Charge.	9650.00	Per Squire Meter	5.15	(Rs Five & Paisa Fifteen)Only	49697.50
3	Removal of earth from the choked hill side drain and disposing it on the valley side manually including carriage of materials in all leads and lifts confirming with the MORTH Specificationand as per direction of the Engineer-in-Charge.	2480.00	Running Meter	77.65	(Rs Seventy Seven & Paisa Sixty Five)Only	192572.00
Total						404865.66
(Quoted Rates in Figures)(+/-)				(.....%)		
(Quoted Rates in words)(+/-)				(.....%)		

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost


 Executive Engineer,
 NH Division HPPWD,
 Theog.

SCHEDULE OF QUANTITY

Estimated Cost:	Rs:- 498775
Earnest Money	Rs:- 10000 only.
Time.	3 Months

Name of work:-Maintenance on Theog Kotkhai Hatkoti road NH-705 k.m. 0/000 to 69/0000 (SH:- (SH:- Hiring of machineries and manual labour between R.D 50/000 to 69/000).

Sr. No	Description of item	Quantity	Unit	Rate	Rate In words	Amount
1	Hiring of JCB having loading bucket capacity of 0.90 cum to 1.00 cum and back hoe bucket capacity of 0.20 to 0.30 cum for removal of clearance of Slips in all leads and lifts and disposal of unserviceable material upto dumping site and stacking of serviceable material along road side and neatly dressing the road as per direction of the Engineer-in-Charge	244.00	Per Hours	1100.00	(Rs One Thousands One Hundred)Only	268400.00
2	Hiring of Tipper for carriage of debris/Boulder and other construction materials from various location including wages of tipper driver, cleaner including P.O.L. Any repair/ damaged during the work will be absolute responsibility of thecontractor/owner hours per day, the tipper has to work at least minimum 8 hours per day.	30.00	Per day	5200.00	(Rs Five Thousand Two Hundred Only	156000.00
3	Hiring of manual labour for clearing of drain, brooming of road surface etc including all leads and lifts as per the directions of Engineer-in-Charge. (5 Persons per day).	150.00	Per day	495.83	(Rs Four Hundred Ninty Five and Paisa Eighty Three)Only	74375.00
Total						498775.00
				(Quoted Rates in Figures)(+/=)	(.....%)	
				(Quoted Rates in words)(+/=)	(.....%)	

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost


Executive Engineer,
NH Division HPPWD,
Theog.

SCHEDULE OF QUANTITY

		Estimated Cost:	Rs:- 497675
		Earnest Money	Rs:- 10000 only.
		Time.	3 Months

Name of work:-Maintenance on Theog Kotkhai Hatkoti road 0/000 to 69/0000 (SH:- (SH:- Hiring of machineries and manual labour between R.D 39/00 to 46/00).

Sr. N	Description of item	Quantity	Unit	Rate	Rate In words	Amount
1	Hiring of JCB having loading bucket capacity of 0.90 cum to 1.00 cum and back hoe bucket capacity of 0.20 to 0.30 cum for removal of clearance of Slips in all leads and lifts and disposal of unserviceable material upto dumping site and stacking of serviceable material along road side and neatly dressing the road as per direction of the Engineer-in-Charge	243.00	Per Hours	1100.00	(Rs One Thousands One Hundred)Only	267300.00
2	Hiring of Tipper for carriage of debris/Boulder and other construction materials from various location including wages of tipper driver, cleaner including P.O.L. Any repair/ damaged during the work will be absolute responsibility of the contractor/owner hours per day, the tipper has to work at least minimum 8 hours per day.	30.00	Per day	5200.00	(Rs Five Thousand Two Hundred Only	156000.00
3	Hiring of manual labour for clearing of drain, brooming of road surface etc including all leads and lifts as per the directions of Engineer-in-Charge. (5 Persons per day).	150.00	Per day	495.83	(Rs Four Hundred Ninty Five and Paisa Eighty Three)Only	74375.00
Total						497675.00
(Quoted Rates in Figures)(+/ -)				(.....%)		
(Quoted Rates in words)(+/ -)				(.....%)		

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost


Executive Engineer,
NH Division HPPWD,
Theog.

SCHEDULE OF QUANTITY

Estimated Cost:

Rs:- 498775

Earnest Money

Rs:- 10000 only.

Time.

3 Months

Name of work:-Maintenance on Theog Kotkhai Hatkoti road 0/000 to 69/0000 (SH:- (SH:- Hiring of machineries and manual labour between R.D 30/00 to 35/00).

Sr. N	Description of item	Quantity	Unit	Rate	Rate In words	Amount
1	Hiring of JCB having loading bucket capacity of 0.90 cum to 1.00 cum and back hoe bucket capacity of 0.20 to 0.30 cum for removal of clearance of Slips in all leads and lifts and disposal of unserviceable material upto dumping site and stacking of serviceable material along road side and neatly dressing the road as per direction of the Engineer-in-Charge	244.00	Per Hours	1100.00	(Rs One Thousands One Hundred)Only	268400.00
2	Hiring of Tipper for carriage of debris/Boulder and other construction materials from various location including wages of tipper driver, cleaner including P.O.L. Any repair/ damaged during the work will be absolute responsibility of the contractor/owner hours per day, the tipper has to work at least minimum 8 hours per day.	30.00	Per day	5200.00	(Rs Five Thousand Two Hundred Only	156000.00
3	Hiring of manual labour for clearing of drain, brooming of road surface etc including all leads and lifts as per the directions of Engineer-in-Charge. (5 Persons per day).	150.00	Per day	495.83	(Rs Four Hundred Ninty Five and Paisa Eighty Three)Only	74375.00
Total						498775.00
(Quoted Rates in Figures)(+/ -)				(.....%)		
(Quoted Rates in words)(+/ -)				(.....%)		

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost


 Executive Engineer,
 NH Division HPPWD,
 Theog.

SCHEDULE OF QUANTITY

Name of work:- Maintenance of Shimla Bye Pass road R.D 13/00 to 24/250.(SH:- Restoration of rain cuts,maintenance of earthen shoulder 18/800 to 19/00)

Estimated Cost: Rs:- 98700

Earnest Money Rs:- 2000

Time. 3 Month.

Sr. No.	Description of item	Quantity	Unit.	Rate		Amount
				In figure	In words	
1	Restoration of rain cuts with soil, moorum, gravel or a mixture of these, clearing the loose soil, benching for 300 mm width, laying fresh material in layers not exceeding 250 mm and compacting with plate compactor or power rammers to restore the original alignment, levels and slopes	31.1	Cum	164.00	Rupees One Hundred Sixty Four	5100.4
2	Maintenance of Earthen Shoulder (filling with fresh soil) Making up loss of material/irregularities on shoulder to the design level by adding fresh approved soil and compacting it with appropriate equipment.	650	Sqm	144.00	Rupees one hundred forty four	93600
Total						98700
(Quoted Rates in Figures)(+/-)				%		
(Quoted Rates in words)(+/-)				%		

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost


Executive Engineer,
NH Division HPPWD,
Theog.

SCHEDULE OF QUANTITY

Name of work:- Maintenance of Shimla Bye Pass road R.D 13/00 to 24/250.(SH:- Restoration of rain cuts,maintenance of earthen shoulder 19/00 to 20/00)

Estimated Cost: Rs:- 98700

Earnest Money Rs:- 2000

Time. 3 Month.

Sr. No.	Description of item	Quantity	Unit.	Rate		Amount
				In figure	In words	
1	Restoration of rain cuts with soil, moorum, gravel or a mixture of these, clearing the loose soil, benching for 300 mm width, laying fresh material in layers not exceeding 250 mm and compacting with plate compactor or power rammers to restore the original alignment, levels and slopes	31.1	Cum	164.00	Rupees One Hundred Sixty Four	5100.4
2	Maintenance of Earthen Shoulder (filling with fresh soil) Making up loss of material/irregularities on shoulder to the design level by adding fresh approved soil and compacting it with appropriate equipment.	650	Sqm	144.00	Rupees one hundred forty four	93600
Total						98700
(Quoted Rates in Figures)(+/)				(.....%)		
(Quoted Rates in words)(+/)				(.....%)		

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost


Executive Engineer,
NH Division HPPWD,
Theog.