

Himachal Pradesh
Public Works Department

NO.PW- JDT-CB-EA-I- /Tender Notice/2026-27- 1573-76 Dated:- 23/06/2026
To

✓
The Chief Engineer (HZ),
HPPWD Hamirpur (HP).

SUBJECT: - Publication of Tender Notice.

Sir,

Jai Hind!

Enclosed please find herewith the Tender Notice for the work as given in the Notice Inviting Tender for uploading on department website as per Notification of Secretary (PW) to the Govt. of HP vide Notification No. PBW (B)A(3)1/2024 Dated 03/01/2025 and further in compliance of the Engineer-in-Chief, HPPWD Nigam Vihar Shimla-2 letter No.PWD/ICT Wing/website dated 22/5/2026 as the matter is of urgent nature and in public interest, you are requested to kindly get it published on departmental website before 16.06.2026.

DA:-As above.


Executive Engineer,
Jhandutta, Division.
HPPWD, Jhandutta.

On behalf of Governor of Himachal Pradesh

Copy along with copy of e-Procurement Notice forwarded to the following for information please: -

1. The Superintending Engineer, 10th Circle, HP.PWD., Bilaspur.
2. All the Assistant Engineer, working under this Division
3. Notice Board of this office.

DA:- As above.


Executive Engineer,
Jhandutta, Division.
HPPWD., Jhandutta.

On behalf of Governor of Himachal Pradesh



E-Mail ID - cepwd-jha-bil@hp.gov.in

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

"NOTICE INVITING TENDERS"

Scaled item / percentage rate tender(s) on PWD form No 6 & 7/8 are hereby invited by the Executive Engineer Jhandutta HPPWD Jhandutta on behalf of the Governor of HP for the following works from the approved and eligible contractors/firms of appropriate class enlisted in HPPWD as per latest instructions so as to reach in this office as per time schedule given below. The offer of the tender will be kept open for 90 days from the date of opening of the tenders. The undersigned reserves the right to accept / reject any application / tender or all the tenders without assigning any reasons.

Date of receipt of application for tender form
Date of issue/sale of Tender forms
Date of opening of tender

01/07/2026 upto 12:00 PM
01/07/2026 from 02:00 PM to 04:00 PM
02/07/2026 at 11:00AM

The tender shall be received up to **10:30AM on 02/07/2026** and will be opened on the same day at **11:00AM** in the presence of intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment (Non-refundable) on **01/07/2026** from 02:00 PM to 04:00 PM.

The Earnest money in the shape of National Saving Certificate/Deposit at call/ Time Deposit /Account/ in any of the Post-Office /Nationalized Bank in H.P. duly pledged in favour of Executive Engineer, Jhandutta Division, HP-PWD, Jhandutta must accompany with each application. Conditional tender and the tenders received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 90 days. The Executive Engineer reserves the right to accept or reject the tender without assigning any reasons.

Sr. No	Name of work	Estimated of cost	Earnest Money	Cost of form	Time limit
1	Repair of Marotan to Babkhal road at Km. 0/0 to 4/0 (SH: Removal of landslips & Restoration of rain cuts at various RD's) (SDF/2025/621)	95043.00	1901.00	350.00	One Month
2	Repair of link road to Lag to Chhat Gurnadi road Km. 0/0 to 2/0 (SH: Restoration of rain cuts at various RD's) (SDF/2025/622)	56225.00	1125.00	350.00	One Month
3	Repair of link road to Fufli Jhulwana road Km. 0/0 to 3/500 (SH: Restoration of rain cuts at various RD's) (SDF/2025/608)	94900.00	1898.00	350.00	One Month
4	Repair of link road to Kakraid Km. 0/0 to 2/0 (SH: Restoration of Rain cuts at various RD's) (SDF/2025/599)	85231.00	1705.00	350.00	One Month
5	Repair of link road to Bagdu Khurd at Km. 0/0 to 4/0 (SH: Restoration of rain cuts at various RD's) (SDF/2025/620)	94900.00	1898.00	350.00	One Month
6	Repair of link road to Lower Kharli road Km. 0/0 to 2/0 (SH: Restoration of rain cuts at various RD's) (SDF/2025/605)	71175.00	1424.00	350.00	One Month
7	Repair of link road to Chaillyan to Gurnadi at Km. 0/0 to 2/500 (SH: Restoration of rain cuts at various RD's) (SDF/2025/624)	61750.00	1235.00	350.00	One Month




8	Repair of Dhanaula to Sasota road Km. 0/0 to 5/0 (SH: Restoration of rain cuts at various RD's) (SDF/2025/602)	94900.00	1898.00	350.00	One Month
9	Repair of link road to Kangar Km. 0/0 to 1/0 and link road to Salwad Km. 0/0 to 1/0 (SH: Removal of landslips & Restoration of rain cuts at various RD's) (SDF/2025/600-601)	99450.00	1989.00	350.00	One Month
10	RRD on link road Darri Bhari to Harizan Basti road Km. 0/0 to 2/500 Mohal Nakhlehra (SH: Hiring of Excavator cum loader for removal of slips clearing of drains & other restoration works) (SDF/2025/425)	94500.00	1900.00	350.00	Two Month
11	C/o Govt. Primary School at Malraon Tehsil Jhandutta Distt. Bilaspur (HP) (SH: C/o Balance work on one room building with verandha i.e. framed structure work up to columns) BSP/2024/32)	228405.00	4568.00	350.00	Two Month
12	A/R & M/O on link road Talai Nain Ghatti Km. 0/0 to 2/500 (SH: Improvement of curve at RD 1/105 to 1/172)	99859.00	1997.00	350.00	One Month

Certificate:- Certified that tenders are being called for due to exigencies of works (landslide and road sinking etc.) in the public interest.

Terms and Conditions:-

1. The Contractor should produce a copy of enlistment/renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason.
3. The Contractor/firm must have his registration and GST No. The copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer, Jhandutta Division, HP.PVD, Jhandutta and cost of tender form for the above works should be submitted with the application for the purchase of tender forms. The application received without earnest money and cost of tender form shall be rejected straight way.
5. The contractor/ Firms are requested to insert the rate in percentage only both in words and in figures failing which XEN reserves the rights to accept/reject any tender without assigning any reason at any stage.

... HIM SUCHNA AVAM JAN SAMPARK...


Executive Engineer,
Jhandutta Division,
HP.PVD, Jhandutta.




Job No - 01

DRAFT SCHEDULE OF QUANTITY

Name of Work :- Repair of Marotan to Babkhal road at Km 0/00 to 4/00 (SH:- Removal of landslips & Restoration of Rain Cuts at various RD's) (SDF/2025/621)				Estimated Cost:- Rs. 95043.00		
				Earnest Money:- Rs. 1901.00		
				Time allowed:- One Month		
				Rate in		Unit
Sr. No.	Description of Items	Quantity	Figure	Words		
1	2	3	4	5	6	7
1	Restoration of rain cuts with soil, moorum gravel or a mixture of these, clearing the loose soil, benching for 300mm width laying fresh material in layers not exceeding 250 mm and compaction with plate compactor or power rammer to restore the original alignment, level and slopes as per drawings and technical specifications Clause 1902 including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax, Goods and Service Tax, building and other constreuction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	27.000	325.00	INR Three hundred twenty five point zero zero only.	Per Cubic meter	8775.00
2	Removal of landslides /slip clearance, Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all left and land as per technical specification 302.3.5 and 1611 including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other constreuction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	780.00	110.60	INR One hundred ten and Paise six zero only	Per Cubic Meter	86268.00
Total						95043.00

Estimate No. :- 16
 DNIT No. :- 16
 Head of Account :-

Draft schedule of quantity approved for Rs. 95043/only
Ver 20.20.27

Executive Engineer,
 Jhandutta Division,
 HPPWD, Jhandutta.



DRAFT SCHEDULE OF QUANTITY

Job No-02

Name of Work :- Repair of link road to Lag to Chhat Gurnadi road km 0/00 to 2/00 (SH: Restoration of Rain Cuts at various RD's) (SDF/2025/622)			Estimated Cost:- Rs. 56225.00			
			Earnest Money:- Rs. 1125.00			
			Time allowed:- One Month			
Sr. No.	Description of items	Quantity	Rate in		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Restoration of rain cuts with soil, moorum gravel or a mixture of these, clearing the loose soil, benching for 300mm width laying fresh material in layers not exceeding 250 mm and compaction with plate compactor or power rammer to restore the original alignment, level and slopes as per drawings and technical specifications Clause 1902 including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	173.000	325.00	Rs. Three hundred twenty five point zero zero only.	Per Cubic meter	56225.00
	Total					56225.00

Draft Schedule of quantity approved for Rs. 56225/only on 20.06.27

Estimate No. :- 17
DNIT No. :- 17
Head of Account :-

Executive Engineer,
Jhandutta Division,
HPPWD, Jhandutta

DRAFT SCHEDULE OF QUANTITY

Name of Work :- Repair of link road to Fufli Jhulwana road km 0/00 to 3/500 (SH:- Restoration of Rain Cuts at various RD's) (SDF/2025/608)			Estimated Cost:- Rs. 94900.00			
			Earnest Money:- Rs. 1898.00			
			Time allowed:- One Month			
Sr. No.	Description of items	Quantity	Rate in		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Restoration of rain cuts with soil, moorum gravel or a mixture of these, clearing the loose soil, benching for 300mm width laying fresh material in layers not exceeding 250 mm and compaction with plate compactor or power rammer to restore the original alignment, level and slopes as per drawings and technical specifications Clause 1902 including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	292.000	325.00	Rs. Three hundred twenty five point zero zero only.	Per Cubic meter	94900.00
	Total					94900.00

Estimate No. :- 18
DNIT No. :- 18
Head of Account :-

Executive Engineer,
Jhandutta Division,
HPPWD. Jhandutta.



DRAFT SCHEDULE OF QUANTITY

Jasrany

Name of Work :- Repair of link road to Kakraid km 0/00 to 2/00 (SH:- Restoration of Rain Cuts at various RD's) (SDF/2025/599)

Estimated Cost:- Rs. 85231.00

Earnest Money:- Rs. 1705.00

Time allowed:- One Month

Sr. No.	Description of Items	Quantity	Rate in		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Restoration of rain cuts with soil, moorum gravel or a mixture of these, clearing the loose soil, benching for 300mm width laying fresh material in layers not exceeding 250 mm and compaction with plate compactor or power rammer to restore the original alignment, level and slopes as per drawings and technical specifications Clause 1902 including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	262.250	325.00	Rs. Three hundred twenty five point zero zero only.	Per Cubic meter	85231.00
	Total					85231.00

Draft schedule of quantity approved for Rs. 85231/only. 28-27-19

Estimate No. :- 19

DNIT No. :- 19

Head of Account :-

Executive Engineer,
Jhandutta Division,
HPPWD, Jhandutta.



DRAFT SCHEDULE OF QUANTITY

Name of Work :- Repair of link road to Bagru Khurd at km 0/00 to 4/00 (SH:-
Restoration of Rain Cuts at various RD's) (SDF/2025/620)

Estimated Cost:- Rs. 94900.00

Earnest Money:- Rs. 1898.00

Time allowed:- One Month

Sr. No.	Description of items	Quantity	Rate in		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Restoration of rain cuts with soil, moorum gravel or a mixture of these, clearing the loose soil, benching for 300mm width laying fresh material in layers not exceeding 250 mm and compaction with plate compactor or power rammer to restore the original alignment, level and slopes as per drawings and technical specifications Clause 1902 including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	292.000	325.00	Rs. Three hundred twenty five point zero zero only.	Per Cubic meter	94900.00
	Total					94900.00

Estimate No. :- 20
DNIT No. :- 20
Head of Account :-

*Draft schedule of quantity approved
for Rs. 94,900/- only - 28-27*

Executive Engineer,
Jhandutta Division,
HPPWD, Jhandutta.



DRAFT SCHEDULE OF QUANTITY

Job No. 06

Name of Work :- Repair of link road to Lower Kharli road km 0/00 to 2/00 (SH:-
Restoration of Rain Cuts at various RD's) (SDF/2025/605)

Estimated Cost:- Rs. 71175.00

Earnest Money:- Rs. 1424.00

Time allowed:- One Month

Sr. No.	Description of items	Quantity	Rate in		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Restoration of rain cuts with soil, moorum gravel or a mixture of these, clearing the loose soil, benching for 300mm width laying fresh material in layers not exceeding 250 mm and compaction with plate compactor or power rammer to restore the original alignment, level and slopes as per drawings and technical specifications Clause 1902 including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	219.000	325.00	Rs. Three hundred twenty five point zero zero only.	Per Cubic meter	71175.00
	Total					71175.00

Draft schedule of quantity approved
for Rs. 71175/- only for 2020-27

Estimate No. :- 21

DNIT No. :- 21

Head of Account :-

Executive Engineer,
Jhandutta Division,
HPPWD, Jhandutta.



DRAFT SCHEDULE OF QUANTITY

Job No-07

Name of Work :- Repair of link road to Chaniliyan to Gurnadi at Km 0/00 to 2/500 (SH:-
Restoration of Rain Cuts at various RD's) (SDF/2025/624)

Estimated Cost:- Rs. 61750.00

Earnest Money:- Rs. 1235.00

Time allowed:- One Month

Sr. No.	Description of items	Quantity	Rate in		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Restoration of rain cuts with soil, moorum gravel or a mixture of these, clearing the loose soil, benching for 300mm width laying fresh material in layers not exceeding 250 mm and compaction with plate compactor or power rammer to restore the original alignment, level and slopes as per drawings and technical specifications Clause 1902 including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax, Goods and Service Tax, building and other constrction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	190.000	325.00	Rs. Three hundred twenty five point zero zero only.	Per Cubic meter	61750.00
	Total					61750.00

Draft Schedule of Quantity approved
for Rs. 61750/- only. 2026-27

Executive Engineer,
Jhandutta Division,
HPPWD. Jhandutta.

Estimate No. :- 22
DNIT No. :- 22
Head of Account :-



Tab No 08

DRAFT SCHEDULE OF QUANTITY

Name of Work :- Repair of Dhanaula to Sasota road km 0/00 to 5/00 (SH:- Restoration of Rain Cuts at various RD's) (SDF/2025/602)

Estimated Cost:- Rs. 94900.00

Earnest Money:- Rs. 1898.00

Time allowed:- One Month

Sr. No.	Description of items	Quantity	Rate in		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Restoration of rain cuts with soil, moorum gravel or a mixture of these, clearing the loose soil, benching for 300mm width laying fresh material in layers not exceeding 250 mm and compaction with plate compactor or power rammer to restore the original alignment, level and slopes as per drawings and technical specifications Clause 1902 including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	292.000	325.00	Rs. Three hundred twenty five point zero zero only.	Per Cubic meter	94900.00
	Total					94900.00

Draft schedule of quantity approved for Rs 94,900/- only. 26/27

Executive Engineer,
Jhandutta Division,
HPPWD. Jhandutta.

Estimate No. :- 23
DNIT No. :- 23
Head of Account :-



Job No 09

DRAFT SCHEDULE OF QUANTITY

Name of Work :- Repair of link road to Kangar km 0/00 to 1/00 and link road to Salwad km 0/00 to 1/00 (SH:- Removal of landslips & Restoration of Rain Cuts at various RD's) (SDF/2025/600-601)			Estimated Cost:- Rs. 99450.00			
			Earnest Money:- Rs. 1989.00			
			Time allowed:- One Month			
Sr. No.	Description of items	Quantity	Rate in		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Restoration of rain cuts with soil, moorum gravel or a mixture of these, clearing the loose soil, benching for 300mm width laying fresh material in layers not exceeding 250 mm and compaction with plate compactor or power rammer to restore the original alignment, level and slopes as per drawings and technical specifications Clause 1902 including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	306.00	325.00	Rs. Three hundred twenty five point zero zero only.	Per Cubic meter	99450.00
Total				01		99450.00

Draft schedule of quantity approved for Rs- 99450/- only
2025-27.

Executive Engineer,
Jhandutta Division,
HPPWD, Jhandutta.

Estimate No. :- 01
DNIT No. :- 01
Head of Account :-

RAFT SCHEDULE OF QUANTITY.

Job No -10

Name of work :- RRD on link roads Darri Bhari to Harizan Basti road Km. 0/00 to 2/500 Mohal Nakhlehra (SH:- Hiring of Excavator cum loader for removal of slips, clearing of drains & other restoration works) S.D.F. 12025/425		Estimated Cost:- Rs. 94500.00				
		Earnest Money:- Rs. 1900.00				
		Time allowed:- Two Month				
Sr No.	Description of items.	Quantity	Rate		Unit	Amount
			In Figure	In words.		
1	2	3	4	5	6	7
1	Providing of Excavator 0.90 (zero point nine) cum bucket capacity @ 40 Cum per hour for removal of landslides /slip clearance, ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left and land as per technical specification 302.3.5 and 1611 as per requirement including P.O.L. charges and other establishment required at site i.e. driver cleaner and other staff and other incidental charges complete as per the direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	90.00	1050.00	Rs. One thousand fifty and paisa zero zero only.	Per Hours	94500.00
Total						94500.00

Terms and Condition:-

- The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge.
- The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair during corresponding period.
- No extra charges will be payable to the contractor for any type of loss/repair of machinery during the execution of work.
- The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work.

Draft schedule of quantity No 14 for the year 2022
approved for Rs. 94500 only

Estimate No. 14
DNIT No. 14
Head of Account.

Executive Engineer,
Jharkhand Division
HPPWD, Jharkhand



Job No -11

DRAFT SCHEDULE OF QUANTITY

Name of Work :- C/o Govt. Primary School at Malroun Tehsil Jhandutta, Distt. Bilaspur (H.P.) (SH:- C/o Balance work on one room building with verandha i.e framed Structure work up to columns) BSP/2024/32

Estimated cost:- ₹ 228405.00

Earnest Money:- ₹ 4568.00

Time allowed:- Two Month

Sr. No.	Description of items	Quantity	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for foundation of structures in all type of soil by Manual /mechanical means as per drawing and technical specification including setting out construction of shoring and bracing, removal of stumps and other deleterious material, and disposal of material upto any lead and lift, dressing of sides and bottom and back filling with approved material and pumping and bailing out water (surface and sub-soil water) upto all depth and any quantum of water including cleaning of slush which may arise out during dewatering and carriage of materials and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidental. The rate includes octroi, royalty Malkana toll tax, Goods and service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.44	236.70	INR Two hundred thirty six and Paise seven zero Only	Per Cubic Meter	2945.00
2	Stone soling properly hand packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm (one hundred millimeter) spread thickness (finished work including materials and labour) including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.87	1452.85	INR One thousand four hundred fifty two and paise eight five only	Per Cubic Meter	7075.00
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level : 1:4:8 (one cement isto four coarse sand) isto eight graded crushed stone aggregate 40 mm (Fourty millimeter) nominal size) including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.60	4838.00	INR Four thousand eight hundred thirty eight and Paise zero zero Only	Per Cubic Meter	27093.00
4	Random rubble masonry with hard stone in superstructure above plinth level and upto floor five level, including leveling up with cement concrete 1:6:12 (one cement isto six coarse sand isto twelve graded stone aggregate) 20 mm (twenty millimeter nominal size) at window sills, ceiling level and the like Cement mortar 1:6 (one cement isto six coarse sand) including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.04	5345.30	INR Five thousand three hundred forty five and Paise three zero Only	Per Cubic Meter	10904.00

5	Centering and shuttering including strutting, propping etc. and removal of form work for Walls (any thickness) including attached pilasters, buttersses, plinth and string courses etc including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the	69.45	525.20	INR Five hundred twenty five and Paise two zero Only	Per Square Meter	36475.00
6	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement :1:1.5:3 (one cement isto one point five coarse sand) isto three graded stone aggregate 20 mm (twenty milimeter nominal size) including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8.09	7529.05	INR Seven thousand five hundred twenty nine and Paise zero five Only	Per Cubic Meter	60910.00
7	Steel reinforcement (TATA /SAIL / JINDAL PANTHER/RINL) for R.C.C. (reinforced cement concrete) work including straightening, cutting, bending, placing in position and binding all complete upto all floor level. Mild steel and Medium Tensile steel bars including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	970.80	85.50	INR Eighty Five and Paise five zero Only	Per Kilogram	83003.00
Total:-						228405.00

Estimate No. :- 03
DNIT No. :- 03
Head of account :-

Executive Engineer,
Jhandutta Division,
HP.PWD Jhandutta



Job No - 12

DRAFT SCHEDULE OF QUANTITY

Name of Work :- A/R & M/O on Link road Talai Nain to Ghatti km 0/00 to 2/500 (SH:- Improvement of curve at Rd 1/105 to 1/172)

Estimated cost:- ₹ 99859.00

Earnest Money:- ₹ 1997.00

Time allowed:- One Month

Sr. No.	Description of items	Quantity	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual /mechanical means including saturated soil comprising of ordinary soil , soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil, setting out true to the required line, grade width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification 2014 Clause 302;1603.1,1603.2, and sorting out useful material and stacking the same in all leads and lifts on acquired width of the road and transportation of useful material for filling in road ways, camber ,embankments for grade improvements and disposal of all surplus materials to the approved dumping sites, which shall be managed by the contractor / firm at their own, through all modes of transportation including head load or animals transport or mechanical means, alongwith its levelling fine dressing and carriage of machineries, materials, tools equipments and safety measures and other incidentals necessary to complete the work by mechanical means and/or labour if required. Any Loss to the public/private property during the execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him in all cases including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. A recovery of useful stones for 0 Cubic metre @ Rs.300/- per cubic metre shall be done on pro-rata basis from each running bill for this item.	554.00	180.25	INR One hundred eighty and Paise two five only	Per Cubic Meter	99859.00
Total:-						99859.00

Draft schedule of quantity approved for Rs. 99859/only on 2025-27

Executive Engineer,
Jhandutta Division,
HP.PWD Jhandutta.

Estimate No. :- 26
DNIT No. :- 26
Head of account :-