

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**

Sealed item rate / percentage rate tender are hereby invited on Form No. 6& 8 by the Executive Engineer, Bhoranj Division, HPPWD, Bhoranj on behalf of the Governor of Himachal Pradesh for the following works from the approved and eligible contractors/ firms of appropriate class enlisted in HPPWD (B&R) whose registration stood registered under the H.P. General Sales tax Act, 1968. As per latest instructions so as to reach and open in his office as per time schedule given below. The offer of the tender will be kept open for 20 days from the date of opening of the tenders. The undersigned reserves the right to reject any or all the tenders without assigning any reasons.

1. Date of receipt of Applications for tender form a/w requisite documents:- **23-06-2026 upto 10.00 AM to 11:00 AM.)**
2. Date of issue/Sale of tender forms against Cash payment (Non- refundable) **23-06-2026 (3:00 PM to 5.00 PM)**
3. Date of receipt of Tender:- **24-06-2026 at 10.30 AM.**
4. Date of opening of Tender:- **24-06-2026 at 11.30 AM.**

Sr. No.	Name of Road	Estimated Cost	Earnest Money	Time	Cost of Tender Form	Eligible class of Contractor
1	Restoration of rain damage on link road Vety Hospital Bhareri to Amroh via Fakruhi Hanoh Garli Bunga road km 0/00 to 2/400 (SH:- CC pavement at RD 1/230 to 1/253)	99780/-	2000/-	Two Months	Rs. 350/-	Class-D
2	Repair / Maintenance of Various roads Under Bhoranj Sub- Division (Section Chamboh)(SH:- Repair & Maintenance of earthen shoulder & Unlined Surface Drain at Various RDs.)	99876/-	2000/-	Two Months	Rs. 350/-	Class-D
3	Restoration / Repair on Mundkhar to Manoh via Nali Jamli road Km 0/00 to 5/00 (SH:- R/wall at RD 2/820 to 2/840& 3/500 to 3/513) PDNA	471990/-	9500/-	Two Months	Rs. 350/-	Class-D
4	C/O Link Veterinary Hospital Building near 132 KV Jahu towards Kot Side (SH:- C/O Cement Concrete Pavement at RD 0/00 to 0/060) (VKV/2024/648)	1,86000/-	2000/-	Two Months	Rs. 350/-	Class-D
5	Restoration / Repair on Mundkhar to Manoh via Nalli Jamli road Km 0/00 to 5/00 (SH:- C/O B/wall at RD 2/600 to 2/640 and R/wall at RD 2/900 to 2/925) (PDNA)	483607/-	10000/-	Two Months	Rs. 350/-	Class-D

6	Restoration of rain damages on link road Vety. Hospital Bhareri to Amroh via Fakruhi Hanoh Garli Bunga road km 0/00 to 2/400 (SH:- CC pavement at RD 1/260to 1/275, edge wall and V- shape drain)	99884/-	2000/-	Two Months	Rs. 350/-	Class-D
7	Repair / Maintenance of Various roads Under Bhoranj Sub- Division (Section Samirpur) (SH:- Repair & Maintenance of earthen shoulder & Unlined Surface Drain at Various RDs.)	99714/-	2000/-	Two Months	Rs. 350/-	Class-D
8	R/R Damages on Bassi Tikker road km. 0/00 to 9/00 (SH:- Formation cutting at Various RDs. Between KM. 0/00 to 1/00).	99575/-	2000/-	Two Months	Rs. 350/-	Class-D
9	Repair / Maintenance of Various roads Under Bhoranj Sub- Division (Section Bhareri) (SH:- Repair & Maintenance of earthen shoulder & Unlined Surface Drain at Various RDs.)	99876/-	2000/-	Two Months	Rs. 350/-	Class-D
10	R/R Damages on Bassi Tikker road km. 0/00 to 9/00 (SH:- Formation cutting at Various RDs. Between KM. 0/00 to 1/00).	98,239/-	2000/-	Two Months	Rs. 350/-	Class-D
11	Repair / Maintenance of Various roads Under Bhoranj Sub- Division (Section Bhoranj) (SH:- Repair & Maintenance of earthen shoulder & Unlined Surface Drain at Various RDs.)	99714/-	2000/-	Two Months	Rs. 350/-	Class-D
12	Restoration of rain damages on link road Vety. Hospital Bhareri to Amroh via Fakruhi Hanoh Garli Bunga road Km 0/00 to 2/400 (SH:- CC pavement at RD 1/200 to 1/223)	98438/-	2000/-	Two Months	Rs. 350/-	Class-D

The earnest money in the shape of National Saving Certificate/ Time Deposit/ saving account of any post office or FDR of Nationalized Bank duly pledged in the name of undersigned must be accompanied with each tender. The Conditional tender and tender not accompanying the earnest money in the proper mode of deposit with summarily be rejected.

The Tender documents to be sent should have invariably be waxed in sealed cover and in failure of that those will not be entertained.

The Copy of valid enlistment, GST Registration No. Income Tax PAN No. & EPF No. must be attached with application.

TERMS AND CONDITIONS:-

The tender form will be issued to those contractors who have relevant machinery and equipment, the list of which any be attached with their applications (The proof of ownership of machinery/ legal tie up arrangement).

The tender forms will not be issued to those contractors whose performance is not found satisfactory.

The tender form will not be issued to those contractors who have already two works in hand.

The earnest money for the above work should be submitted with the application for the purchase of the tender forms. The application received without earnest money shall summarily be rejected.

The conditional/ ambiguous/ telephonic tenders or tender by fax shall not entertain considered in any case.

- (i) No Violation of social distancing.
- (ii) Mandatorily wearing of face cover by everyone.
- (iii) It is further added that any violation of the National directives & guidelines of containment of pandemic Covid-19 is liable for prosecution under section of IPC 1860.

Certified that the above work is of emergent nature in exigency of Public interest.

Executive Engineer
Bhoranj Division
HPPWD Bhoranj

For and on behalf of Governor of HP.

Dated:- 16-06-2026

No:-PW/BHD/TA/NIT/2025- 3432-71

Copy forwarded for information & necessary action to:-

1. The Engineer-in-Chief, Nirman Bhawan Nigam Vihar, HP PWD., Shimla.
2. The Chief Engineer (HZ) HPPWD., Hamirpur.
3. The Superintending Engineer, 8th Circle HPPWD, Hamirpur.
4. All the Superintending Engineers/ Executive Engineers in HP.PWD.
5. The Deputy Commissioner, Hamirpur.
6. The Tehsildar, Bhoranj.
7. The B. D. O. Bhoranj.
8. The Municipal Committee, Bhoranj.
9. All the Assistant Engineers working under this Division.
10. Accounts Branch/ Drawing Branch/ Notice Board.
11. LokMitra, Bhoranj.
12. Various Contractors/ Firms.

Executive Engineer,
Bhoranj Division,
HPPWD, Bhoranj.

SCHEDULE OF QUANTITY

NAME OF WORK :- Restoration of rain Damage on Link Road Vely Hospital Bhareri to Amroh via Fakruhi Hanoh Garli Bunga Road Km 0/00 to 2/400
(SH:- CC Pavement at Rd 1/230 to 1/253)

Sr No	Description of Items	Quantity	Unit	Rate	Estimated Cost	
					Earnest Money Time Rates in Words	Rs. 99780/- Rs. 2000/- 2 month Amount
1	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structing and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.44	Per Cubic Meter			
2	Providing concrete for plain/ reinforced concrete in P.C.C. grade M-10 (M-ten) nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 20mm(twenty millimeters) nominal size in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.33	Per cubic metre			
3	Providing and laying in position specified grade of reinforced cement concrete, including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.44	Per Cubic Meter			
	Total					
	Terms and Condition:-					
	1. Work shall be executed as per PWD specification.					

3/
Executive Engineer
Bhoranj Division
HP PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- Repair /Maintenance of Various roads Under Bhorani Sub-Division (Section Chambh) (SH:-
Repair & Maintenance of earthen shoulder & Unlined Surface Drain at Various RDs.)

Estimated Cost Rs. 99876/-
Earnest Money Rs. 2000/-

Sr No	Description of Items	Time		Rates in Words	2Months Amount
		Quantity	Unit	Rate	
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregularity on shoulders to the design level by adding fresh approved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1120.00	Per square metre		
2	Construction of unlined surface drain of average cross sectional area 0.40 Sqm in soil to specified lines, grades, level and dimensions. Excavated material to be used in embankments with a lift up to 3 Mtr. and lead of 50 Mtr. (average lead 25 m) as per technical specification clause 307 as directed by the engineer in charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	220.00	Per Running Mtr.		
	Total				

Terms and Condition:-


1. Work shall be executed as per PWD specification.

Executive Engineer
Bhorani Division
H.P.W.D Bhorrani

NAME OF WORK:- Restoration / Repair on Mundkhar to Manoh via Nail Jamli Road Km 0/00 to 5/00 (SH:- RJwall at RD 2/820 to 2/840 & 3/500 to 3/513) (PDNA) SCHEDULE OF QUANTITY

Sr No	Description of Items	Quantity	Unit	Rate	Estimated Cost Earnest Money Time	Rates in Words	Rs. 4,71,990/- Rs. 9500/- 2 month
1	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring a structure and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	58.08	Per Cubic Meter				
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	104.09	Per Cubic Meter				
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vecus pipe having pressure 4kg per centimeter square. (four kilogramme per centimeter square) extending through the full width of the structures with slopes of (1V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	28.00	Each				
	Total						
	Terms and Condition:-						

1. Work shall be executed as per PWD specification.


 Executive Engineer
 Bhoranji Division
 HRPWD Bhoranji

SCHEDULE OF QUANTITY

NAME OF WORK :- C/O Link Veterinary Hospital Building near 132KV Jahu towards Kot Side (SH:- C/O Cement Concrete Pavement at Rd. 0/00 to 0/060)(MKV/2024/648)

Sr No	Description of Items	Quantity	Unit	Rate	Estimated Cost	
					Earnest Money Time	Rs. 1,86,000/- Rs. 2000/- 2 month Amount
1	Providing concrete for plain/ reinforced concrete in P.C.C. grade M-10 (M- ten)nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 40mm(forty millimeters) nominal size in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	18.60	Per cubic metre			
2	Providing and laying in position specified grade of reinforced cement concrete, including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size/as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	13.95	Per Cubic Meter			
Total						
Terms and Condition:-						

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK :- Restoration /Repair on Mundkhar to Manoh via Nalli Jamali Raod Km 0/00 to 5/00 (SH:- C/O B/wall in at Rd 2/600 to 2/640 and R/wall at Rd 2/900 to 2/925 (PDNA)

Sr No	Description of Items	Quantity	Unit	Rate	Estimated Cost	
					Earnest Money	Rs. 4.83.607/-
					Time	Rs. 10000/-
					Rates in Words	2 month
						Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structing and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	50.70	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	105.28	Per Cubic Meter			
4	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm (one hundred ten millimeter) dia PVC pipe De-plast/fnolex/ vecus pipe having pressure 4kg.per centimeter square. (four kilogramme per centimeter square) extending through the full width of the structures with slopes of (V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer-in -Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	60.00	Each			
Total						
Terms and Condition:-						

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK :- Restoration of rain Damages on Link Road Vety Hospital Bhateri to Amroh via Fakruhi Hanoh Garli Bunga Road Km 0/00 to 2/400 (SH:- CC Pavement at Rd 1/260 to 1/275, edge wall and V Shape drain)

Sr No	Description of Items	Quantity	Unit	Rate	Estimated Cost	
					Earnest Money	Rs. 99884/- Rs. 2000/- 2 month Amount
1	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring a structing and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	4.58	Per Cubic Meter			
2	Providing concrete for plain/ reinforced concrete in P.C.C. grade M-10 (M-ten) nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 20mm(twenty millimeters) nominal size in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	6.98	Per cubic metre			
3	Providing and laying in position specified grade of reinforced cement concrete, including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level 1:1.5:3 (1 cement : 1.5 coarse sand) : 3 graded stone aggregate 20 mm nominal size) as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	4.58	Per Cubic Meter			
4	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	7.50	Per Cubic Meter			
Total						
Terms and Condition:-						

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HRPWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- Repair /Maintenance of Various roads Under Bhorani Sub-Division (Section Samirpur) (SH:-
Repair & Maintenance of earthen shoulder & Unlined Surface Drain at Various RDs.)

Estimated Cost Rs. 99714/-
Earnest Money Rs. 2000/-

Sr No	Description of Items	Quantity	Unit	Rate	Time	
					Rates in Words	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregularity on shoulders to the design level by adding fresh approved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	1005.25	Per square metre			
2	Construction of unlined surface drain of average cross sectional area 0.40 Sqm in soil to specified lines , grades, level and dimensions . Excavated material to be used in embankments with a lift up to 3 Mtr. and lead of 50 Mtr. (average lead 25 m) as per technical specification clause 307 as directed bythe engineer in charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	540.00	Per Running Mtr.	20000		
	Total					

Terms and Condition:-

1. Work shall be executed as per PWD specification.


Executive Engineer
Bhorani Division
H.P. PWD Bhorani

SCHEDULE OF QUANTITY

Name of Work:-R/R Dmages on Bassi Tikker Road Km. 0/00 to 9/00 (SH:- Formation cutting at various Rds. Between KM. 0/00 to 1/00).

Estimated cost:- 99,575/-
Earnest Money:- 2000/-
Time:- 2 months

Sr. No.	Description of item	Qty.	Rate	Rate in words	Unit	Amount
1	Excavation in earth work in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, Water pollution, etc and to protect soil stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to line, grades, stops, width, camber, super elevation and level as shown on the drawing as per direction of Engineer in Charge in conformity with the requirement of technical specification for rural roads august 2004 clause 16.2 of general conditions of contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and stage, disposal of unsuitable cut material in specified manner, trimming/gilling of unevenness blinding and finishing of the road to specified dimensions or as directed by Engineer in charge for smooth riding. The recovery of useful stones shall be made from the contractor and recovery of 34.16 cubic meter useful stones shall be made @ 300/-per cubic meter on pro rata basis in each running bill. Any loss to the public and private property during the course of excavation shall be resorted by the contractor what so ever the nature of the same may be. The serviceable material will be stacked out specified dimension in all leads and lifts as per the direction of Engineer in Charge.	205.000	485.73		Per Cubic meter	
Total						

Terms and Condition:-

1. Work shall be executed as per PWD specification.

Done by me on this date.....
Cutting.....
Over writing.....
Condition.....
E.B.

Executive Engineer
Bhorahj Division
H.R. PWD Bhorahj

SCHEDULE OF QUANTITY

NAME OF WORK:- Repair /Maintenance of Various roads Under Bhorani Sub-Division (Section Bhareli) (SH:-
Repair & Maintenance of earthen shoulder & Unlined Surface Drain at Various RDs.)

Estimated Cost Rs. 99876/-
Earnest Money Rs. 2000/-

Sr No	Description of Items	Quantity	Unit	Rate	Time	
					Rates in Words	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregularity on shoulders to the design level by adding fresh approved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire cartage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1120.00	Per square metre			
2	Construction of unlined surface drain of average cross sectional area 0.40 Sqm in soil to specified lines, grades, level and dimensions. Excavated material to be used in embankments with a lift up to 3 Mtr. and lead of 50 Mtr. (average lead 25 m) as per technical specification clause 307 as directed by the engineer in charge including entire cartage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	220.00	Per Running Mtr.			
	Total					

Terms and Condition:-

1. Work shall be executed as per PWD specification.


Executive Engineer
Bhorani Division
HPPWD Bhorani

SCHEDULE OF QUANTITY

Name of Work:-R/R Dmages on Bassi Tikker Road Km. 0/00 to 9/00 (SH:- Formation cutting at various Rds. Between KM. 0/00 to 1/00).

Estimated cost:- 98,239/-
Earnest Money:- 2000/-
Time:- 2 months

Sr. No.	Description of item	Qty.	Rate	Rate in words	Unit	Amount
1	Excavation in earth work in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, Water pollution, etc and to protect soil stability of hill side rock shall be excavated with chiseling and wedging our rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to line, grades, stops, width, camber, super elevation and level as shown on the drawing as per direction of Engineer in Charge in conformity with the requirement of technical specification for rural roads august 2004 clause 16.2 of general conditions of contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and stage. disposal of unsuitable cut material in specified manner, trimming/filling of unevenness, blinding and finishing of the road to specified diamensions or as directed by Engineer in charge for smooth riding. The recovery of useful stones shall be made from the contractor and recovery of 33.70 cubic meter useful stones shall be made @ 300/- per cubic meter on pro rata basis in each running hill. Any loss to the public and private property during the course of excavation shall be resorted by the contractor what so ever the nature of the same may be. The serviceable material will be stacked out specified dimension in all leads and lifts as per the direction of Engineer in Charge.	202.250			Per Cubic meter	
Total						

Terms and Condition:-

1. Work shall be executed as per PWD specification.

Open by me on dt.....
Cutting.....
Over writing.....
Condition.....
E.B

Executive Engineer
Bhorani Division
(Hd) PWD Bhorani

SCHEDULE OF QUANTITY

NAME OF WORK:- Repair /Maintenance of Various roads Under Bhorani Sub-Division (Section Bhorani) (SH:-
Repair & Maintenance of earthen shoulder & Unlined Surface Drain at Various RDs.)

Estimated Cost Rs. 99714/-
Earnest Money Rs. 2000/-

Sr No	Description of Items	Quantity	Unit	Rate	Time	
					Rates In Words	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregularity on shoulders to the design level by adding fresh approved soil and compacting with appropriate equipment as per technical specification clause no 1903. Including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1005.25	Per square metre			
2	Construction of unlined surface drain of average cross sectional area 0.40 Sqm in soil to specified lines, grades, level and dimensions. Exacavated material to be used in embankments with a lift up to 3 Mtr. and lead of 50 Mtr. (average lead 25 m) as per technical specification clause 307 as directed by the engineer in charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	540.00	Per Running Mtr.			
	Total					

Terms and Condition:-

1. Work shall be executed as per PWD specification.


Executive Engineer
Bhorani Division
A/P PWD Bhorani

SCHEDULE OF QUANTITY

NAME OF WORK :- Restoration of rain Damage on Link Road Vety Hospital Bhaveri to Amroh via Fakruhi Hanoh Gari Bungla Road Km 0/00 to 2/400
(S4):- CC Pavement at Rd 1/200 to 1/223)

Sr No	Description of Items	Quantity	Unit	Rate	Estimated Cost	
					Earnest Money	Rs. 98,438/-
					Time	Rs. 2000/-
					Rates in Words	2 month
						Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structing and pumping and bailing out water (surface and sub sol water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	6.24	Per Cubic Meter			
2	Providing concrete for plain/ reinforced concrete in P.C.C. grade M-10(Nr- ten)nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 20mm(twenty millimeters) nominal size in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	8.33	Per cubic metre			
3	Providing and laying in position specified grade of reinforced cement concrete, including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level 1:1.5:3 (1 cement : 1.5 coarse sand) : 3 graded stone aggregate 20 mm nominal size)as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	8.33	Per Cubic Meter			
Total						
Terms and Condition:-						
1. Work shall be executed as per PWD specification.						

Executive Engineer
Bhoranj Division
HR PWD Bhoranj