

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No.PW-AD-EA-I-Tender-2026-27-

3431-39

Dated-23/1/2024

To

The Executive Engineer (IT Cell)
H.P.P.W.D. Nigam Vihar Shimla-2.

Subject:- Notice Inviting Tender for uploading the same on departmental website.

Enclosed please find herewith Notice Inviting Tender (NIT) of various works in respect of this office as per notification Pr. Secy.(PW) to the Govt. of Himachal Pradesh letter no. PBW(B)A(3)1/2024 dated shimla-2 the 03.01.2024 as the works mentioned in the tender notice are uploading the same on departmental website at the earliest please.

Encl:-Copy of NIT


Executive Engineer,
Arki Division
H.P.P.W.D. Arki
Ph. 01796-220743

Copy forwarded for the following for information and necessary action to:-

1. The Engineer-in-Chief, HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-2
2. The Chief Engineer, (SZ) HPPWD., Nirman Bhawan, Nigam Vihar, Shimla.
3. The Superintending Engineer, 3rd Circle, HPPWD., Solan.
4. The Deputy Commissioner Solan, Distt. Solan.
5. The Sub Divisional Magistrate Arki.
6. All the Executive Engineers in HPPWD, (SZ).
7. All the Assistant Engineer, working under this division.
8. All the heads of the branches in this office.
9. Notice Board.


Executive Engineer,
Arki Division
H.P.P.W.D. Arki
Ph. 01796-220743

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDER

Sealed percentage tenders on PWD Form 6 & 7/8 are hereby invited by the Executive Engineer Arki Division H.P.P.W.D. Arki on behalf of Governor of Himachal Pradesh for the followings works from the eligible contractors enlisted in H.P.PWD. (B&R) whose registration stood renewed as per revised rules and also registered under the Central Goods and Service Tax Act, 2017 so as to reach in this office on before **01.07.2026 up to 11:30 AM** and the same shall be opened on the same day at **12:00 A.N.** in the presence of intending contractors or their authorized representative who may like to be present. The Tenders documents can be had from this office against cash payment (Non-refundable) on **30.06.2026 up to 4:30 PM** and the application for issue of tender form shall be received on **30.06.2026 up to 5:00 PM.**


The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/Bank duly pledged in favour of Executive Engineer Arki Division HPPWD Arki must be accompanied with the application for tender documents. Please not no exemption order of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 75 days. The Executive Engineer reserve right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on next working day at the same time and venue.

Sr. No	Name of Work	Estimated Cost	Earnest Money	Time	Cost of Form
1	R/R Damages on Talab (Rau Khad) Behli road km. 0/00 to 2/170 (SH:- C/o R/wall at RD 1/535 to 1/555) PDNA	4,52,415/-	9,200/-	1 Month	350/-
2.	Balance work of R/R damages on Talab (Rau Khad) Behli road km. 0/00 to 2/170 (SH:- C/o R/wall at RD 0/649 to 0/659 Balance work) PDNA 2023	1,59,198/-	3,200/-	1 Month	350/-
3	C/o link road Delag to Shivghatti Gram Panchyat Sanan km. 0/00 to 1/500(SH:- Formation cutting in km. 1/150 to 1/250)DMFT Deposit.	1,06,385/-	2,200/-	1 Month	350/-
4	Construction of Ambulance road Outer Gate Rouri to Meera Mahajan Cow Shed in km. 0/00 to 0/350 G.P. Rouri (SH:- Formation Cutting in kmm. 0/00 to 0/350, Hume Pipe culvert & wing wall at various RD's and C/o unlined surface drain in km. 0/0 to 0/350) Under DMFT	4,81,913/-	10,000/-	2 Months	350/-
5.	R/R damages on Talab (Rau khad)Behli road km. 0/0 to 2/170(SH:-C/o R/wall at Rd 1/555 to 1/574)PDNA	4,30,347/-	9,000/-	1 Months	350/-

6	C/o under Ground Chanalization fromm Ambuja Chowk Darlaghat to Shiv Mandir(Ist phase)DMFT deposit	4,90,333/-	10,000/-	1 Months	350/-
7	A/R & M/o Chandi Rudal Harsang Dhar road km. 0/0 to 8/300(SH:-Balance work of C/o R/wall at end point for development of Bus Stand Job No.5)DMFT	4,85,060/-	10,000/-	1 Months	350/-
8	C/o Ambulance link road from Rudal to Harijan Basti Kathalu km. 0/0- to 0/325(SH:-Formation cutting in km. 0/250 to 0/325)DMFT Deposit	97,509/-	2000/-	1 Months	350/-
9	Restoration of rain damages on Arki Sub-Division HP,PWD, Arki under Arki section(SH:-Removal of slips/dressing of roads by hiring of JCB)Job No.1	99,000/-	2000/-	1 Months	350/-
10	A/R & M/o Chandi Rudal Harsang Dhar road km. 0/0 to 8/300(SH:-Balance work of C/o R/wall at end point for development of Bus Stand Job No.4)DMFT	4,85,060/-	10,000/-	1 Months	350/-
11	C/o Abulance road from Pukhar to Daseran km. 0/0 to 0/300(SH:-C/o R/wall at Rd 0/283 to 0/295.15 and R.C.C. Hume pipe Culvert at Rd 0/280)DMFT	4,96,923/-	10,000/-	2 Months	350/-
12	C/o Abulance road from Pukhar to Daseran km. 0/0 to 0/300(SH:-C/o R/wall at Rd 0/283 to 0/295.15 and R.C.C. Hume pipe Culvert at Rd 0/280)DMFT	4,91,964/-	10,000/-	1 Months	350/-

Followings documents should be attached with the application for tenders:-

- The Contractors are requested to be produced a copy of their PAN No. GST No. copy of enlistment renewed letter and EPF certificate alongwith FDR against earnest money.
- Special care would be taken to write the rates both in figures and in word failing which tender is likely to be rejected.



Executive Engineer
Arki Division,
H.P.P.W.D. Arki.

No: PW-AD-EA-I-Tender-2026-27- 3431-39

Dated:- 23/06/2026


Copy forwarded for the following for information and necessary action to:-

- The Superintending Engineer 3rd Circle HPPWD Solan.
- The all Assistant Engineer working under this division for information and necessary action.
- All the heads of the branches in this office.
- Notice Board.


Executive Engineer
Arki Division
H.P.P.W.D. Arki.

Certificate

Certified that the tenders called vide this notice inviting tender for 12 (twelve) jobs are due to exigencies/emergency of works in the larger public interest.


Executive Engineer
Arki Division
H.P.P.W.D. Arki.

SCHEDULE OF QUANTITY

Name of Work:- R/R Damages on Talab (Rau Khad) Behli Road Km 0/00 to 2/170. (SH:- C/o R/wall at Rd 1/535 to 1/555) PDNA

Estimated Cost: -Rs4,52,415/- only

Earnest Money :-Rs9,200/-Only

Time :-One Month

S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	60.00	171.40	Rupees One hundred seventy one and paise forty only	P.Cum.	10284
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts, and as per the direction of Engineer-In- Charge	94.50	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	414912
3	Backfilling Granular materials behind abutment, wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts.and as per the direction of Engineer-In- Charge	13.80	1203.30	Rupees one thousand two hundred three and paise thirty only	P.Cum.	16606
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	38.70	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	10613
					Total	452415

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY						Estimated Cost: -Rs159198/- only
Name of Work:- Balance Work of R/R Damages on Talab (Rau Khad) Behli road km 0/00 to 2/170 [SH:- C/O R/ Wall at RD 0/649 to 0/659 Balance work] PDNA 2023						Earnest Money :-Rs3200/-Only
						Time :-One Month
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
1	2		Figure	Words		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	11.66	171.40	Rupees one hundred seventy one and paise fourty only	P.Cum.	1999
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803,1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	33.07	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	145197
3	Back filling behind abutment wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts.and as per the direction of Engineer-In- Charge	8.06	1203.30	Rupees one thousand two hundred three and paise thirty only	P.Cum.	9699
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	8.40	274.25	Rupees two hundred seventy four and paise twenty five only	Rmt	2304
					Total	159198

Quoted Rate Percentage in Figure
Quoted Rate Percentage in Words


Executive Engineer
Arki Division HPPWD
Arki

SCHEDULE OF QUANTITY

Name of Work:- C/o Link Road Delag to Shivghati Gram Panchyat Sanan Km 0/00 to 1/500. (SH:- Formation Cutting in Km 1/150 to 1/250.)DMFT Deposit

Estimated Cost: -Rs 1,06,385/- only


Earnest Money :-Rs2,200/-Only

Time :- One Month

S.No	Sub head and items of work	Qty.	Unit	Rate		Amount
				Figure	Words	
1	Excavation in earthwork in hilly area by mechanical means all hights and depth, in all kind of soil including saturated soil comprising of mixed soil , ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side,water pollution , etc. and to protect stabality of hill side . Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting / excavation , including rock excavation shall be carried out true to lines grades , side slopes, width, chamber, super elevation and level as shown on the drawings or as directed by the Engineer-in - Charges, in conformity with the requirement of techanical specification for Rural Road, August 2004 and clause 16.2 of General Conditions for Contract to achieve designed formation wodth including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut matereial inspecified manner,tremming, filling of unevenness, blindage and finishing of the road to specified dimensions or as dirrected by the Engineer-in -Charge for smooth riding. The recovery of useful stone that is 11.95 cubic meter in all cases falling which recovery @ Rupees 300/- only (Rupees three hundereed only) per cubic metre shall be effected on prorata basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	597.50	Per. Cum.	178.05	Rupees one hundred seventy eight and paise five only .	106385
					Total	106385

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 B&R Division HPPWD
 Arki

SCHEDULE OF QUANTITY

Name of Work:-C/o Ambulance Road Outer Gate Rouri to Meera Mahajan Cow Shed in Km 0/00 to 0/350 G. P. Rpuri (SH:- Formation Cutting in Km 0/00 to 0/350 ,Hume Pipe Culvert & wing wall at Various RD,s and C/o Upline Surface Drain in Km 0/00 to 0/350) Under DMFT						Estimated Cost: -Rs4,81,913/-- only
						Earnest Money :-Rs10,000/-only
						Time :- Two Months
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
1	2	3	Figure	Words	5	6
1	Excavation in earthwork in hilly area by mechanical means all hights and depth, in all kind of soil including saturated soil comprising of mixed soil , ordinaryrock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side,water pollution , etc. and to protect stabality of hill side . Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting / excavation , including rock excavation shall be carried out true to lines grades , side slopes, width, chamber, super elevation and level as shown on the drawings or as directed by the Engineer-in - Charges, . The recovery of useful stone that is 95.11 cubic meter in all cases falling which recovery @ Rupees 300/- only (Rupees three hundereed only) per cubic metre shall be effected on prorata basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	1337.30	165.04	Rupees one hundred sixty five and paise four only	P.Cum.	220708
2	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In-Charge	35.64	171.40	Rupees One hundred seventy one and paise forty only	P.Cum.	6109
3	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	7.38	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	32403
4	Providing and Laying concrete for plain/reinforced concrete 1:4:8 (one cement : four sand: eight graded stone aggregate 20mm (Twenty millimeter) nominal size in open foundations and curing complete including cost of form work plain/ reinforced concrete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials within all leads and	18.11	4955.20	Rupees four thousand nine hundred fifty five and paise twenty only	P.Cum.	89739
5	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803,1202 &1203 including carriage of materials in all leads and lifts. a)P.C.C 1:3:6.(1 Cement :3 sand : 6 Agg. 20mm nominal Size) i/c carriage of material within all leads & lifts As per the direcion of Engineer In-Charge.	13.92	5291.95	Rupees. five thousand two hundred ninety one and paise ninety five only	P.Cum.	73664
6	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation protection work, back filling concrete and masonry work in head walls and parapets clause 1108. 900 mm dia pipe including carriage of materials in all leads and lifts. and as per the direction of	7.50	3851.55	Rupees three thousand eight hundred fifty one and paise twenty only	P.Rmt	28887

S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
7	Backfilling Granular materials behind abutment, wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts and as per the direction of Engineer-In- Charge	5.40	1203.30	Rupees one thousand two hundred three and paise thirty only	P.Cum.	6498
8	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	10.60	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	2907
9	Construction of unlined surface drain of average cross sectional area 0.40sqm in ordinary rock to specified lines grades, levels and dimensions. Excavated Material to be used in embankment with salify up to 3.00meter and lead of 50 Mtrs(average Lead 25 mtrs) as per approved design and technical specification clause 307 as per MORD Specification directed by Engineer-In- Charge	350.00	60.00	Rupees sixty and paise zero only	P.Rmt	21000
					Total	481913

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY

Name of Work:- R/R Damages on Talab (Rau Khad) Behli Road Km 0/00 to 2/170. (SH:- C/o R/wall at Rd 1/555 to 1/574) PDNA

Estimated Cost: -Rs4,30,347/- only

Earnest Money :-Rs9,000/-Only

Time :-One Month

S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	57.00	171.40	Rupees One hundred seventy one and paise forty only	P.Cum.	9770
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	89.78	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	394188
3	Backfilling Granular materials behind abutment, wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts.and as per the direction of Engineer-In- Charge	13.11	1203.30	Rupees one thousand two hundred three and paise thirty only	P.Cum.	15775
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	38.70	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	10613
					Total	430347

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words

Executive Engineer
Arki Division HPPWD
Arki

SCHEDULE OF QUANTITY						Estimated Cost: -Rs4,90,333/- only	
Name of Work:-C/o Under Ground Chanalization from Ambuja Chowk Darlaghat to Shiv Mandir (1st Phase) DMFT Deposit)						Earnest Money :-Rs10,000/-Only	
						Time :-One Month	
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount	
1	2	3	Figure	Words	5	6	
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	41.58	171.40	Rupees One hundred seventy one and paise fourty only	P.Cum.	7127	
2	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour) and as directed by Engineer-In- Charge	11.88	1425.25	Rupees one thousand four hundred twenty five and paise twenty five only	P.Cum.	16932	
3	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803,1202 &1203 including carriage of materials in all leads and lifts. a)P.C.C 1:3:6.(1 Cement :3 sand : 6 Agg. 20mm nominal Size) i/c carriage of material within all leads & lifts As per the direcion of Engineer In-Charge.	88.11	5291.95	Rupees five thousand two hundred ninety one and paise ninety five only	P.Cum.	466274	
					Total	490332	

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY					Estimated Cost: -Rs4,85,060/- only	
Name of Work:- A/R & M/O Chandi Rudal Harsang Dhar Road Km 0/00 to 8/300.(SH:-Balance work of C/o R/wall at end point for development of Bus stand Job No. 5) DMFT					Earnest Money :-Rs10,000/-Only	
					Time :-One Month	
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	35.10	171.40	Rupees One hundred seventy one and paise forty only	P.Cum.	6016
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	95.42	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	418951
3	Backfilling Granular materials behind abutment, wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts.and as per the direction of Engineer-In- Charge	39.00	1203.30	Rupees one thousand two hundred three and paise thirty only	P.Cum.	46929
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	48.00	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	13164
					Total	485060

Quoted Rate Percentage in Figure


Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY						
Name of Work:-C/o Ambulance Link Road from Rudal to Harijan Basti Kathalu Km 0/00 to 0/325. (SH:- Formation Cutting in Km 0/250 to 0/325.)DMFT Deposit				Estimated Cost: -Rs 97,509/- only		
				Earnest Money :-Rs2,000/-Only		
				Time :- One Month		
S.No	Sub head and items of work	Qty.	Unit	Rate		Amount
				Figure	Words	
1	Excavation in earthwork in hilly area by mechanical means all hights and depth, in all kind of soil including saturated soil comprising of mixed soil , ordinaryrock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side,water pollution , etc. and to protect stabality of hill side . Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting / excavation , including rock excavation shall be carried out true to lines grades , side slopes, width, chamber, super elevation and level as shown on the drawings or as directed by the Engineer-in - Charges, in conformity with the requirement of technical specification for Rural Road, August 2004 and clause 16.2 of General Conditions for Contract to achieve designed formation wothd including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut matereial inspecified manner,tremming, filling of unevenness, blindage and finishing of the road to specified dimensions or as dirrected by the Engineer-in -Charge for smooth riding. The recovery of useful stone that is 38.34 cubic meter in all cases falling which recovery @ Rupees 300/- only (Rupees three hundereed only) per cubic metre shall be effected on prorata basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	547.65	Per. Cum.	178.05	Rupees one hundred seventy eight and paise five only .	97509
					Total	97509

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


Executive Engineer
B&R Division HPPWD
Arki

SCHEDULE OF QUANTITY						Estimated Cost: -Rs99000/- only	
Name of Work:-Restoration of Rain Damages of Arki Sub Division HP,PWD Arki Under Arki Section . (SH:-Removal of Slips/dressing of roads by hiring of JCB) Job No-1						Earnest Money :-Rs2000/-Only	
						Time :-One Month	
S. No.	Sub head and items of work	Qty.		Rate In		Unit	Amount
				Figure	Words		
		3		4		5	6
1	2	99.00	Hour	1000.00	Rupees One Thousand and paise nil only	P.Hour.	99000
1	Hiring of JCB Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 1611.)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge						
						Total	99000

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


Executive Engineer
Arki Division HPPWD
Arki

SCHEDULE OF QUANTITY					Estimated Cost: -Rs4,85,060/- only	
Name of Work:- A/R & M/O Chandi Rudal Harsang Dhar Road Km 0/00 to 8/300.(SH:-Balance work of C/o R/wall at end point for development of Bus stand Job No. 4) DMFT Deposit					Earnest Money :-Rs10,000/-Only	
					Time :-One Month	
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3		4	5	6
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	35.10	171.40	Rupees One hundred seventy one and paise forty only	P.Cum.	6016
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	95.42	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	418951
3	Backfilling Granular materials behind abutment, wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts.and as per the direction of Engineer-In- Charge	39.00	1203.30	Rupees one thousand two hundred three and paise thirty only	P.Cum.	46929
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	48.00	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	13164
					Total	485060

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY					Estimated Cost: -Rs4,96,923/-- only	
Name of Work:-C/o Ambulance Road from Pukhar to Daseran Km 0/00 to 0/300. (SH:- C/o R/wall at Rd 0/283 to 0/295.15 and R.C.C. Hume Pipe Culvert at Rd0/280.) DMFT Deposit					Earnest Money :-Rs10,000/-Only	
					Time :- Two Months	
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
2	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	69.32	171.40	Rupees One hundred seventy one and paise forty only	P.Cum.	11881
3	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	84.56	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	371269
4	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803,1202 &1203 including carriage of materials in all leads and lifts. a)P.C.C 1:3:6.(1 Cement :3 sand : 6 Agg. 20mm nominal Size) i/c carriage of material within all leads & lifts As per the direcion of Engineer In-Charge.	11.85	5291.95	Rupees. five thousand two hundred ninety one and paise ninety five only	P.Cum.	62710
5	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation protection work, back filling concrete and masonry work in head walls and parapets clause 1108. 900 mm dia pipe including carriage of materials in all leads and lifts. and as per the direction of Engineer-	5.00	3851.55	Rupees three thousand eight hundred fifty one and paise twenty only	P.Rmt	19258
6	Backfilling Granular materials behind abutment, wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts.and as per the direction of Engineer-In- Charge	14.58	1203.30	Rupees one thousand two hundred three and paise thirty only	P.Cum.	17544
7	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	52.00	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	14261
					Total	496923

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY					Estimated Cost: -Rs4,91,964/- only	
Name of Work:-C/o Ambulance Road from Pukhar to Daseran Km 0/00 to 0/300. (SH:- P/L Cement Conc. 1:4:8. and 1:2:4 at Rds 0/00 to 0/120.) DMFT Deposit					Earnest Money :-Rs10,000/-Only	
					Time :-One Month	
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Surface dressing of Ground including removing of Vegetation and in-equalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5 m. all kinds of soil and as directed by Engineer-In- Charge	360.00	14.00	Rupees fourteen and paise zero only	P.Sqm.	5040
2	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour) and as directed by Engineer-In- Charge	36.00	1425.25	Rupees one thousand four hundred twenty five and paise twenty five only	P.Cum.	51309
3	Providing and Laying concrete for plain/reinforced concrete 1:4:8 (one cement : four sand: eight graded stone aggregate 20mm (Twenty millimeter) nominal size in open foundations and curing complete including cost of form work plain/ reinforced concrete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials within all leads and lifts and as directed by Engineer-In- Charge	36.00	4955.20	Rupees four thousand nine hundred fifty five and paise twenty only	P.Cum.	178387
4	Providing and laying cement concrete work 1:2:4 (one cement : two sand : four graded stone aggregate 20mm nominal size) mechanically mixed and compecting with vibrator and curing complete including the cost of centering and shuttering - All work up to plinth level carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge	43.20	5954.35	Rupees five thousand nine hundred fifty four and paise thirty five only	P.Cum.	257228
					Total	491964

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki