

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
No.PW-AD-EA-I-Tender-2026-27 2924-32

Dated:- 06/06/2026

To

The Executive Engineer (IT Cell)
H.P.P.W.D. Nigam Vihar Shimla-2.

Subject:- Notice Inviting Tender for uploading the same on departmental website.

Enclosed please find herewith Notice Inviting Tender (NIT) of various works in respect of this office as per notification Pr. Secy.(PW) to the Govt. of Himachal Pradesh letter no. PBW(B)A(3)1/2024 dated shimla-2 the 03.01.2024 as the works mentioned in the tender notice are uploading the same on departmental website at the earliest please.

Encl:-Copy of NIT


Executive Engineer,
Arki Division
H.P.P.W.D. Arki
Ph. 01796-220714

Copy forwarded for the following for information and necessary action to:-

1. The Engineer-in-Chief, HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-2
2. The Chief Engineer, (SZ) HPPWD., Nirman Bhawan, Nigam Vihar, Shimla.
3. The Superintending Engineer, 3rd Circle, HPPWD., Solan.
4. The Deputy Commissioner Solan, Distt. Solan.
5. The Sub Divisional Magistrate Arki.
6. All the Executive Engineers in HPPWD, (SZ).
7. All the Assistant Engineer, working under this division.
8. All the heads of the branches in this office.
9. Notice Board.


Executive Engineer,
Arki Division
H.P.P.W.D. Arki
Ph. 01796-220714

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDER

Sealed percentage tenders on PWD Form 6 & 7/8 are hereby invited by the Executive Engineer Arki Division H.P.P.W.D. Arki on behalf of Governor of Himachal Pradesh for the followings works from the eligible contractors enlisted in H.P.PWD. (B&R) whose registration stood renewed as per revised rules and also registered under the Central Goods and Service Tax Act, 2017 so as to reach in this office on before **18.06.2026 up to 11:30 AM** and the same shall be opened on the same day at **12:00 A.N.** in the presence of intending contractors or their authorized representative who may like to be present. The Tenders documents can be had from this office against cash payment (Non-refundable) on **16.06.2026 up to 4:30 PM** and the application for issue of tender form shall be received on **16.06.2026 up to 5:00 PM.**

The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/Bank duly pledged in favour of Executive Engineer Arki Division HPPWD Arki must be accompanied with the application for tender documents. Please not no exemption order of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 75 days. The Executive Engineer reserve right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on next working day at the same time and venue.

Sr. No	Name of Work	Estimated Cost	Earnest Money	Time	Cost of Form
1	C/o Link Road from Jabloo Kanswala to Village Khata G.P. Rouri km. 0/00 to 1/500 (SH:- F/c in km. 0/360 to 0/685) DMFT Deposit.	4,88,360/-	10,000/-	1 Month	350/-
2.	R/R damages on Suhani Basyana Chamrol Falodan Kangridhar Road km. 0/00 to 8/240 (SH:- C/o R/wall at RDs 1/790 to 1/820 and 2/495 to 2/504) PDNA	4,72,972/-	9,500/-	1 Month	350/-
3	A/R & M/o Chandi Rudal Harsang Dhar Road km. 0/00 to 8/300 (SH:- Balance work of C/o R/wall at end point for development of Bus stand Job No. 3) DMFT	4,76,641/-	10,000/-	1 Month	350/-
4	C/o Link road Nawin-Karyah to Village Nawin km. 0/00 to 1/150 (SH:- F/c in km. 0/165 to 0/390) DMFT Deposit	4,95,246/-	10,000/-	1 Month	350/-
5	C/o Rain Shelter at Village Chandpur, G.P. Bakhalag. (Under DMFT)	3,03,722/-	6,100/-	1 Month	350/-
6	Channelization of Nallah at Pokhtu in G.P. Batal Tehsil Arki, Distt. Solan HP. (SH:- P/L PCC 1:3:6 and stone soling at RDs 0/00 to 0/060) Under DMFT	4,92,080/-	10,000/-	1 Month	350/-

Following documents should be attached with the application for tenders:-

- (i) The Contractors are requested to be produced a copy of their PAN No. GST No. copy of enlistment renewed letter and EPF certificate alongwith FDR against earnest money.
- (ii) Special care would be taken to write the rates both in figures and in word failing which tender is likely to be rejected.


Executive Engineer
Arki Division,
H.P.P.W.D. Arki.

No: PW-AD-EA-I-Tender-2026-27- 2924-32

Dated:- 06/06/2026

Copy forwarded for the following for information and necessary action to:-

- 1.The Superintending Engineer 3rd Circle HPPWD Solan.
- 2.The all Assistant Engineer working under this division for information and necessary action.
- 3.All the heads of the branches in this office.
- 4.Notice Board.


Executive Engineer
Arki Division
H.P.P.W.D.Arki.

Certificate

Certified that the tenders called vide this notice inviting tender for
6 (Six) jobs are due to exigencies/emergency of works in the larger public interest.


Executive Engineer
Arki Division
H.P.P.W.D. Arki.

SCHEDULE OF QUANTITY

Name of Work:- C/o Link Road from Jabloo Kanswala to Village Khata G.P. Rouri Km 0/00 to 1/500 (SH:- F/C in Km 0/360 to 0/685) DMFT Deposit

Estimated Cost: -Rs 4,88,360/- only

Earnest Money :-Rs10,000/-Only

Time :- One Month

S.No	Sub head and items of work	Qty.	Unit	Rate		Amount
				Figure	Words	
1	Excavation in earthwork in hilly area by mechanical means all hights and depth, in all kind of soil including saturated soil comprising of mixed soil , ordinaryrock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side,water pollution , etc. and to protect stabality of hill side . Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting / excavation , including rock excavation shall be carried out true to lines grades , side slopes, width, chamber, super elevation and level as shown on the drawings or as directed by the Engineer-in - Charges, in conformity with the requirement of technical specification for Rural Road, August 2004 and clause 16.2 of General Conditions for Contract to achieve designed formation wodth including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut matereial inspecified manner,tremming, filling of unevenness, blindage and finishing of the road to specified dimensions or as dirrected by the Engineer-in -Charge for smooth riding. The recovery of useful stone that is 199.88 cubic meter in all cases falling which recovery @ Rupees 300/- only (Rupees three hundereed only) per cubic metre shall be effected on prorata basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	2702.30	Per. Cum.	180.72	Rupees one hundred eighty and paise seventy two only .	488360
					Total	488360

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 B&R Division HPPWD
 Arki

SCHEDULE OF QUANTITY					
Name of Work:- R/R Damages on Suhani Basyana Chamrol Falodan Kangaridhar Road Km 0/00 to 8/240.(SH:- C/o R/wal ar Rd 1/790 to 1/820 and 2/495 to 2/504.) PDNA				Estimated Cost: -Rs4,72,972/- only	
				Earnest Money :-Rs9,500/-Only	
				Time :-One Month	
S. No.	Sub head and items of work	Qty.	Rate In	Unit	Amount
1	2	3	Figure	Words	6
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	52.02	171.40	Rupees One hundred seventy one and paise forty only	P.Cum. 8916
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	96.33	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum. 422946
3	Backfilling Granular materials behind abutment, wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts.and as per the direction of Engineer-In- Charge	22.86	1203.30	Rupees one thousand two hundred three and paise thirty only	P.Cum. 27507
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	49.60	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt 13603
				Total	472972

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words

Executive Engineer
Arki Division HPPWD
Arki

SCHEDULE OF QUANTITY					Estimated Cost: -Rs4,76,641/- only	
Name of Work:- A/R & M/O Chandi Rudal Harsang Dhar Road Km 0/00 to 8/300.(SH:-Balance work of C/o R/wall at end point for development of Bus stand Job No. 3) DMFT					Earnest Money :-Rs10,000/-Only	
					Time :-One Month	
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
1	2	3	Figure	Words	5	6
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	43.94	171.40	Rupees One hundred seventy one and paise fourty only	P.Cum.	7531
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	95.42	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	418951
3	Backfilling Granular materials behind abutment, wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts and as per the direction of Engineer-In- Charge	31.20	1203.30	Rupees one thousand two hundred three and paise thirty only	P.Cum.	37543
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	46.00	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	12616
					Total	476641

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY

Name of Work:- C/o Link Road Nawin- Karyah to Village Nawin Km 0/00 to 1/150.(SH:- F/C in Km 0/165 to 0/390) DMFT Deposit

Estimated Cost: -Rs 4,95,246/- only


Earnest Money :-Rs10,000/-Only

Time :- One Month

S.No	Sub head and items of work	Qty.	Unit	Rate		Amount
				Figure	Words	
1	Excavation in earthwork in hilly area by mechanical means all hights and depth, in all kind of soil including saturated soil comprising of mixed soil , ordinaryrock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side,water pollution , etc. and to protect stabality of hill side . Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting / excavation , including rock excavation shall be carried out true to lines grades , side slopes, width, chamber, super elevation and level as shown on the drawings or as directed by the Engineer-in - Charges, in conformity with the requirement of techanical specification for Rural Road, August 2004 and clause 16.2 of General Conditions for Contract to achieve designed formation wodth including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut matereial inspecified manner,tremming, filling of unevenness, blindage and finishing of the road to specified dimensions or as dirrected by the Engineer-in -Charge for smooth riding. The recovery of useful stone that is 83.45 cubic meter in all cases falling which recovery @ Rupees 300/- only (Rupees three hundereed only) per cubic metre shall be effected on prorata basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	2781.50	Per. Cum.	178.05	Rupees one hundred seventy eight and paise five only .	495246
					Total	495246

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 B&R Division HPPWD
 Arki

SCHEDULE OF QUANTITY

Name of Work:-C/o Rain shelter at Village Chandpur, G.P. Bakhalag. (Under DMFT)

Estimated Cost: -Rs3,03,722/- only

Earnest Money :-Rs6,100/-Only

Time :-One Month

S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	10.52	171.40	Rupees One hundred seventy one and paise forty only	P.Cum.	1803
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	2.87	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	12601
3	Providing and laying cement concrete work 1:2:4 (one cement : two sand : four graded stone aggregate 20mm nominal size) mechanically mixed and compecting with vibrator and curing complete excluding cost of form work and reinforced concrete work including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge .	2.30	5954.35	Rupees five thousand nine hundred fifty four and paise thirty five only	P.Cum.	13695
4	Random rubble masonry with hard stone in foundation andplinth including levelling up with cement concrete 1:6:12 (1cement : 6 coarse sand : 12graded stone aggregate 20 mm nominal size) upto plinth level with : Cement mortar 1:6 (1 cement : 6 coarse sand) including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge .	3.38	5002.35	Rupees five thousand two and paise thirty five only	P.Cum.	16908
5	Providing and fixing 0.60mm thick prepainted steel sheet of Tata/Reliance / Jindal Sheets in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyster (RNP) organic coating of 20 microns over 5 microns primer coating to back coat of polyster of 5 microns over 5 microns primer coating i/c fixing with prepainted iron J or L hooks, bolts and nuts 6mm dia metre with prepainted limpet and rubber washers complete with all accesoriees as required as per the direction of Engineer-in-charge.	40.51	1321.05	Rupees one thousand three hundred twenty one and paise five only	P.Sqm.	53516
6	Providing ridges or hips of width 60 cm overall width plain G.S. sheet fixed with polymer coated J or L hooks, bolts and nuts 8 mm dia G.I. limpet and bitumen washers complete.0.63 mm thick with zinc coating not less than 275 gm/m ² including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	33.76	550.90	Rupees five hundred fifty and paise ninety only	P.Rmt	18598
7	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	1265.33	86.65	Rupees Eighty six and paise sixty five only	P.Kg	109641

S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
8	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint. In beams joists channels, angles, tee, flats with connecting plates or angle cleats as in main and cross beams, hip and jack rafters, purlins connected to common rafters and the like. including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	235.80	107.45	Rupees one hundred seven and paise forty five only	P.Kg	25337
9	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) : 25 mm thick including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge .	14.88	1215.70	Rupees one thousand two hundred fifteen and paise seventy only	P.Sqm.	18090
10	Supplying and filling in plinth with stone under floors, including watering, ramming, consolidating and dressing complete. i/c all leads, lifts & carriage of material and as per direction of Engineer-in- Charge	2.14	1200.00	Rupees one thousand two hundred and paise zero only	P.Cum	2568
11	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture complete and as per the direction of Engineer-In- Charge	26.15	94.30	Rupees ninety four and paise thirty only.	P.sqm.	2466
12	Providing supplying and fixing garden benche deluxe model 1.60 meter long setting of 4 person capacity with ornamental legs and arm of cast iron & back and feet rectangular hollow section 65mmx25mm eight nos. strips including welding & finished painted with all accesses as per stranded specifications with all leads, lifts and other incidental charges of site of work with all direction of Engineer-in-Charge at site including all incidentals and taxes imposed by the Government.	3.000	9500.00	Rupees nine thousand five hundred and paise zero only	Nos.	28500
				Total		303722

Quoted Rate Percentage in Figure
Quoted Rate Percentage in Words


Executive Engineer
Arki Division HPPWD
Arki

SCHEDULE OF QUANTITY					Estimated Cost: -Rs4,92,080/- only	
Name of Work:- Channelization of Nallah at Pokhtu in G.P. Batal Tehsil Arki Distt. Solan (H.P.) (SH:- P/L PCC 1:3:6 and Stone Soling at Rd 0/00 to 0/060) Under DMFT					Earnest Money :-Rs10,000/-Only	
					Time :-One Month	
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	99.08	171.40	Rupees One hundred seventy one and paise forty only	P.Cum.	16982
2	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour)	21.60	1200.00	Rupees one thousand two hundred and paise zero only	P.Cum.	25920
3	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803,1202 &1203 including carriage of materials in all leads and lifts. a)P.C.C 1:3:6.(1 Cement :3 sand : 6 Agg. 20mm nominal Size) i/c carriage of material within all leads & lifts As per the direcion of Engineer In-Charge.	82.80	5424.85	Rupees five thousand four hundred twenty four and paise eighty five only	P.Cum.	449178
					Total	492080

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki