

REGISTERED

Office of the Executive Engineer, B&R Division, HP PWD Kalpa District Kinnaur (HP)

Web:- www.hppwd.gov.in E mail:- hp-kin@nic.in

Phone No:- 01786-226027 Fax:- 01786-226027.

No:- PW/KNR-E-Tender/2026-
To

2178-80

Dated:- 27/6/2026


The Executive Engineer (IT Cell),
HP.PWD. Shimla-2.

Subject:-

Publication of Tender Notice (OFFLINE)

Enclosed please find herewith the Tender of works costing above 1 upto 5.00 Lakh as given in the Notice Inviting Tender for uploading on the departmental website as per notification vide Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW(B). 1/2020 dated 16-07-2021 and even file No. 1/2024 dated 03-01-2024, 03-01-2025 and 1/2024-241828 dated 17-07-2025 and PWD-B-A 0(3)/8/2025-300858 dated 09-10-2025, even file No. 300858 dated 13-11-2025, 08-12-2025 and even file No. 241828 dated 02-02-2026. The works mentioned in the tender notice are urgent in nature and public interest.

Encl:- NIT, Schedule of Quantity
& Certificate.


Executive Engineer,
Kalpa Division,
HP.PWD. Kalpa.

Copy forwarded for information to:-

1. The Superintending Engineer, 11th Circle, HP.PWD. Rampur Bushahr.
2. Copy to Drawing Branch in this office.

Executive Engineer,
Kalpa Division,
HP. PWD, Kalpa.

HP.P.W.D. TENDER NOTICE (offline)

Sealed item rate offline tender on form PWD-6 & 8 are hereby invited on behalf of Governor of Himachal Pradesh by the Executive Engineer, Kalpa Division, HP,PWD; Kalpa for the following works from the approved and eligible contractors enlisted in HP.PWD; so as to reach in the office of the Executive Engineer Kalpa Division HP.PWD. Kalpa on or before **04-07-2026 up to 11.00 A.M.** and shall be opened on the same day at **11:30 AM** in presence of intending contractors or their authorized representatives. The tender form documents can be had from this office (Kalpa Division, HPPWD Kalpa) against cash payment (Non-refundable) on **03-07-2026 upto 4:00 P.M.** No application for issue of tender forms will be received on **03-07-2026 after 4:00 PM.** If the office happens to be closed on the above mentioned dates, the tenders will be sold/opened on the next working day at the same time and venue. The Earnest Money in the shape of National Saving Certificate, F.D.R,s any Post office/Bank in H.P. duly pledged in the name of Executive Engineer, Kalpa Division, HP.PWD. Kalpa must accompany with each tenders. Conditional tenders and application (For purchase of tender forms) received without Earnest Money summarily be rejected. The officer of the tenders shall be kept open for 120 days. The Executive Engineer Reserves (Right to accept or to reject any) or all the tenders without assigning any reasons.

Sr. No	Name of work	Estimated cost	Earnest Money	Time allowed	Cost of form	Eligible class of contractor
1	R/R damages (PDNA) on Peo Kalpa C.P. road Km. 0/00 to 6/765 (SH:- C/O B/wall in R.R. Masonry at RD. 0/993 to 0/997 and M/T work near ITDP office)	4,99,908/-	10,000/-	One Month	350/-	"C" & "D" Class
2	R/R damages (PDNA) on Peo Karchham Shilti road Km. 0/00 to 11/635 (SH:- C/O R/wall at various RDs between Km. 3/022 to 3/034)	4,96,653/-	10,000/-	One Month	350/-	"C" & "D" Class
3	R/R damages (PDNA) on Peo Karchham Shilti road Km. 0/00 to 11/635 (SH:- C/O R/wall at various RDs between Km. 6/586 to 6/598)	4,80,034/-	10,000/-	One Month	350/-	"C" & "D" Class
4	R/R damages (PDNA) on Peo Karchham Shilti road Km. 0/00 to 11/635 (SH:- C/O R/wall at various RDs between Km. 6/846.60 to 6/863)	4,99,033/-	10,000/-	One Month	350/-	"C" & "D" Class
5	R/R damages (PDNA) on NH-22 to Taitty Valley road Km. 0/00 to 4/445 (SH:- C/O R/wall and crash barrier between Km. 0/00 to 0/250)	4,89,169/-	10,000/-	One Month	350/-	"C" & "D" Class
6	R/R damages (PDNA) on NH-22 to Taitty Valley road Km. 0/00 to 4/445 (SH:- C/O R/wall and crash barrier between Km. 0/250 to 0/500)	4,89,169/-	10,000/-	One Month	350/-	"C" & "D" Class

Terms and conditions:-


Following documents should accompany the application for tenders:-

1. Copy of valid enlistment/renewal order.
2. Copy of GST Registration No.
3. Proof of Valid E.P.F accounts Number allotted by the Provident Fund Commissioner Shimla and copy of PAN Number.
4. Ambiguous/Telegraphic/conditional tenders or tenders by fax/E-Mail shall not be entertained/considered in any case.
5. The contractors should quote the rates of each items in words as well as figures in the Schedule of quantity.

6. The earnest money must also accompany with the application for the tender documents.
7. The tender shall be issued to those contractors who have not more than two works in Hand.

No.: PW/KNR-E-Tender/NIT/2026-

2163-77


Executive Engineer,
Kalpa Division,
HP. PWD. Kalpa.

Dated:-

27/5/2026



Copy forwarded for information to:-

1. The Engineer-in-Chief, HP.PWD. Shimla-2.
2. The Deputy Commissioner, Kinnaur District at Reckong Peo.
3. The Sub Divisional Officer (Civil) Kalpa at Reckong Peo.
4. The Superintending Engineer, 11th Circle, HP.PWD. Rampur Bushahr.
5. The Block Development Officer, Kalpa at Reckong Peo.
6. The Chairman, Zila Parishad, Kinnaur District at Reckong Peo.
7. The Chairman, Panchayat Samiti Kalpa at Reckong Peo.
8. Drawing Branch in this office.
9. All the Contractors under this Division.
10. Notice Board.


Executive Engineer,
Kalpa Division,
HP. PWD. Kalpa.

CERTIFICATE

Certified that the Tender for works called vide this office Letter No. PW/KNR/E-Tender/2026- 2163-77 dated 27-6-2026 and Six numbers of works are of urgent nature and essential for public safety or restoration of infrastructure and public interest.


**Executive Engineer,
Kalpa Division,
HP.PWD, Kalpa.**


SCHEDULE OF QUANTITY

Name of work:-		Restoration of rain damages (PDNA) on Peo Kalpa C.P. road Km. 0/00 to 6/765		Estimated Cost :-		4,99,908/-
		(SH:- C/O B/Wall in RR Masonry at RD 0/993 to 0/997) and MIT work near ITDP office		Earnest Money :-		10,000/-
				Time		One Month
Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill- up the interstices of coarse aggregate, watering and compacting to the required density Grading-2 as per technical specification clause 405. By Manual Means. 63 to 40mm size, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge.	29.37	₹ 3,220.25	Rupees Thousand Hundred Paise Only Three Two Twenty TwentyFive	Per Cubic meter	₹ 94,579.00
2	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill- up the interstices of coarse aggregate, watering and compacting to the required density Grading-3 as per technical specification clause 405. By Manual Means. 53 to 22.4 mm size, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge.	29.37	₹ 3,750.85	Rupees Thousand Hundred Fifty Paise EightyFive Only Three Seven	Per Cubic meter	₹ 110,162.00
3	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.25 to 0.30 kg per sqm (Zero point twenty five to zero point thirty kilogram per square metre) on the prepared dry and hungry bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge.	391.60	₹ 35.20	Rupees Paise Twenty Only ThirtyFive	Per Square meter	₹ 13,784.00
4	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg/sqm using mechanical means as per Technical Specification Clause 502, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge.	391.60	₹ 102.00	Rupees One Hundred Two Only	Per Square meter	₹ 39,943.00


5	Providing, laying and rolling of open-graded premix carpet of 20mm (millimeter) thickness composed of 13.2mm (millimeter) to 5.6mm (millimeter) aggregate using VG-10 to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 80/100 KN static roller capacity, finished to required level and grades to be followed by seal coat of Type B as per technical specifications Clause 508. By manual means, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge.	391.60	₹ 325.25	Rupees Hundred Paise Only Three Hundred Twenty Five Paise	Per Square meter	₹ 127,368.00
6	Providing and laying seal coat sealing the voids in bituminous surface laid to the specified levels, grade and cross fall using Type B as per technical specification clause 510. By manual means VG-10, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge.	391.60	₹ 110.15	Rupees One Hundred Ten Paise Only	Per Square meter	₹ 43,135.00
7	Earth work in excavation by mechanical means (Hydraulic excavator). / manual means in foundation trenches or drains, including dressing of sides and ramming of bottoms, with in all lifts, including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads in all kind of soil, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	18.72	₹ 261.70	Rupees Two Hundred Sixty One Paise Seventy Only	Per Cubic meter	₹ 4,899.00
8	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203. PCC 1:6:12 (one Cement : six coarse sand) : twelve graded stone aggregate), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	0.94	₹ 4,211.70	Rupees Thousand Hundred Eleven Paise Seventy Only Four Two	Per Cubic meter	₹ 3,959.00
9	Stone masonry in cement mortar for substructure complete as per drawing & technical specification Clauses 702, 704, 1202 and 1204. Random rubble masonry in cement mortar 1:6 (One cement: Six sand,) including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	11.84	₹ 5,150.20	Rupees Thousand Hundred Fifty Paise Twenty Only Five One	Per Cubic meter	₹ 60,978.00

2

SCHEDULE OF QUANTITY

Name of work:-		Restoration of rain damages (PDNA) on Peo Karchham Shilti road Km 0/00 to 11/635 (SH:- C/O R/Wall at various RD's between Km. 3/022 to 3/034).		Estimated Cost :- 4,96,653/-	
				Earnest Money :- 10,000/-	
				Time :- One Month	
Sr. No.	Description of items	Qty.	Rate		Amount
			In Fig.	In Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains, including dressing of sides and ramming of bottoms, with in all lifts, including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads in all kind of soil, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	13.68	₹ 270.05	Rupees Two Hundred Seventy Paise Only	₹ 3,694.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering -All work up to plinth level 1:4:8 (One cement : Four coars sand) : Eight graded stone aggregate 40 mm (Forty millimeter) nominal size), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	78.72	₹ 5,152.65	Rupees Five Thousand One Hundred Fifty Two Paise Sixty Five Only	₹ 405,617.00
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification clause 1204.3.8. Granular material (For R/wall), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	21.60	₹ 595.80	Rupees Five Hundred Ninety Five Paise Eighty Only	₹ 12,869.00
4	Providing weep holes in brick masonry /stone masonry/plain reinforced concrete abutments, wing wall, return wall, with 100mm (One hundred millimeter) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 (For R/wall) including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	27.00	₹ 290.35	Rupees Two Hundred Ninety Thirty Five Paise Only	₹ 7,839.00

5	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level Thermo-Mechanically Treated bars of grade Fe-500D or more, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	652.00	₹ 102.20	Rupees One Hundred Two Paise Only	Per Kilogram	₹ 66,634.00
	Total in figures:-					₹ 496,653.00
	Total in Words:-	Rupees Four Lakh Ninety Six Thousand Six Hundred Fifty Three Only				
	Quoted Percentage rate upto three Digits :-	(+)/(-)				


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD; Kalpa.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages (PDNA) on Peo Karchham Shilti road Km 0/00 to 11/635 (SH:- C/O R/Wall at various RD's between Km. 6/586 to 6/598).							Estimated Cost :- 4,80,034/-
							Earnest Money :- 10,000/-
							Time :- One Month
Sr. No.	Description of items	Qty.	Rate		Unit	Amount	
			In Fig.	In Words			
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains, including dressing of sides and ramming of bottoms, with in all lifts, including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads in all kind of soil, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	9.60	₹ 270.05	Rupees Two Hundred Seventy Paise Five Only	Per Cubic meter	₹ 2,592.00	
2	Providing and laying in position cement concrete of seecified grade exluding the cost of centering and shutteringg -All work up to plinth level :1:4:8 (One cement : Four coars sand) : Eight graded stone aggregate 40 mm (Forty millimeter) nominal size), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	84.00	₹ 5,152.65	Rupees Five Thousand One Hundred FiftyTwo Paise SixtyFive Only	Per Cubic meter	₹ 432,823.00	
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification clause 1204.3.8. Granular material (For R/wall), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	23.76	₹ 595.80	Rupees Five Hundred NinetyFive Paise Eighty Only	Per Cubic meter	₹ 14,156.00	
4	Providing weep holes in brick masonry /stone masonry/plain reinforced concrete abutments, wing wall, return wall,with 100mm (One hundred millimeter) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614.709,1204.3.7 (For R/wall) including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	31.00	₹ 290.35	Rupees Two Hundred Ninety ThirtyFive Only	Each	₹ 9,001.00	


5	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level Thermo-Mechanically Treated bars of grade Fe-500D or more, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	210.00	₹ 102,220	Rupees One Hundred Two Paise Only	Per Kilogram	₹ 21,462.00
	Total in figures:-		1			₹ 480,034.00
	Total in Words:-		Rupees Four Lakh Eighty Thousand ThirtyFour Only			
	Quoted Percentage rate upto three Digits :-	(+)/(-)				


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD; Kalpa.

SCHEDULE OF QUANTITY


Name of work:- Restoration of rain damages (PDNA) on Peo Karchham Shilti road Km 0/00 to 11/635 (SH:- C/O R/Wall at various RD's between Km. 6/846.60 to 6/863).						
Estimated Cost :- 4,99,033/-						
Earnest Money :- 10,000/-						
Time :- One Month						
Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains, including dressing of sides and ramming of bottoms, with in all lifts, including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads in all kind of soil, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	24.44	₹ 270.05	Rupees Two Hundred Seventy Paise Five Only	Per Cubic meter	₹ 6,600.00
2	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203. PCC 1:6:12 (one Cement : six coarse sand) : twelve graded stone aggregate), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	4.43	₹ 4,211.70	Rupees Four Thousand Two Hundred Eleven Paise Seventy Only	Per Cubic meter	₹ 18,658.00
3	Providing and laying in position cement concrete of seecified grade exluding the cost of centering and shutteringg -All work up to plinth level 1:4:8 (One cement : Four coars sand) : Eight graded stone aggregate 40 mm (Forty millimeter) nominal size) . . including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	18.2	₹ 5,152.65	Rupees Five Thousand One Hundred FiftyTwo Paise SixtyFive Only	Per Cubic meter	₹ 93,778.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification clause 1204.3.8. Granular material (For R/wall), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	29.52	₹ 595.80	Rupees Five Hundred NinetyFive Paise Eighty Only	Per Cubic meter	₹ 17,588.00

5	Providing weep holes in brick masonry /stone masonry/plain reinforced concrete abutments, wing wall, return wall,with 100mm (One hundred millimeter) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614.709,1204.3.7 (For R/wall) including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	26.00	₹ 290.35	Rupees Two Hundred Ninety Paise ThirtyFive Only	Each	₹ 7,549.00
6	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter) diameter GI wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (Hundred millimeter into hundred millimeter) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighting not less than 25kg (twenty five kilogram) each as per drawing and technical specification Clause 1301, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	118.08	₹ 3,005.25	Rupees Thousand Three Hundred Fifty Paise TwentyFive Only	Per Cubic meter	₹ 354,860.00
Total in figures:-						₹ 499,033.00
Total in Words:-						
Quoted Percentage rate upto three Digits :-						
		(+)/(-)		Rupees Four Lakh NinetyNine Thousand ThirtyThree Only		


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD, Kalpa.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages (PDNA) on NH-22 to Taity Valley road Km 0/00 to 4/445 (SH:- C/O R/Wall and Crash barrier between Km. 0/00 to 0/250).		Estimated Cost :- 4,89,169/-				
		Earnest Money :- 10,000/-				
		Time :- One Month				
Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203. P.C.C (Mechanical mix and vibrated graded crushed stone aggregate) 1:4:8 (40 mm (Forty millimeter) aggregates), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	51.10	₹ 5,152.65	Rupees Five Thousand Hundred FiftyTwo Paise SixtyFive Only	Per Cubic meter	₹ 263,300.00
2	Providing erecting type "A" W metal Crash barrier comprising of 3mm corrugated sheet metal beam rail 70cm above road/ ground level , fixed an ISMC series chanel Vertical post 150x75x5 mm spaced 2 mtr c/c 1.80mtr high 1.1 mtr below ground level all steel parts and fitment to be galvenised by hot dip process, all fittings to conform to IS 1364 metal beam rail to be fixed on the vertical post with a space of channel section 150x75x5 mm 330 mm long complete as per clause 810, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	70.00	₹ 3,226.70	Rupees Three Thousand Hundred TwentySix Paise Seventy Only	Per Running meter	₹ 225,869.00
Total in figures:-						₹ 489,169.00
Total in Words:-		Rupees Four Lakh EightyNine Thousand One Hundred SixtyNine Only				
Quoted Percentage rate upto three Digits :-		(+)/(-)				


 Executive Engineer
 Kalpa Division (B&R),
 HP.PWD, Kalpa.

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITIES						
Name of work:-		Restoration of rain damages (PDNA) on NH-22 to Taity Valley road Km 0/00 to 4/445 (SH:- C/O R/Wall and Crash barrier between Km. 0/250 to 0/500).			Estimated Cost :-	4,89,169/-
					Earnest Money :-	10,000/-
					Time :-	One Month
Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203. P.C.C (Mechanical mix and vibrated graded crushed stone aggregate) 1:4:8 (40 mm (Forty millimeter) aggregates), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royaltyti, malkana, toll tax, GST or other taxes imposed by the Government.	51.10	₹ 5,152.65	Rupees Thousand Hundred Paise SixtyFive Only	Five One Two FiftyTwo	₹ 263,300.00
2	Providing erecting type "A" W metal Crash barrier comprising of 3mm cerrugated sheet metal beam rail 70cm above road/ ground level , fixed an ISMC series chanel Vertical post 150x75x5 mm spaced 2 mtr c/c 1.80mtr high 1.1 mtr below ground level all steel parts and fitment to be galvenised by hot dip process, all fittings to conform to IS 1364 metal beam rail to be fixed on the vertical post with a space of channel section 150x75x5 mm 330 mm long complete as per clause 810, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royaltyti, malkana, toll tax, GST or other taxes imposed by the Government.	70.00	₹ 3,226.70	Rupees Thousand Hundred Paise Seventy Only	Three Two SixtySix	₹ 225,869.00
Total in figures:-						₹ 489,169.00
Total in Words:-			Rupees Four Lakh EightyNine Thousand One Hundred SixtyNine Only			
Quoted Percentage rate upto three Digits :-			(+)/(-)			

Executive Engineer,
Kalpa Division (B&R),
HP.PWD; Kalpa.