

Himachal Pradesh
Public Works Department

No. PW-KD- CTR- Tender-NIT/2025-2026- - 1256-97 Dated:-

31/7/25

To


The Executive Engineer (IT Cell)
Nigam Vihar Shimla.

Subject :- Publication of Tender Notice.

Jai Hind


Enclosed please find herewith the tender Notice of work as given in the Notice Inviting tender for uploading on department website as per notification Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW (B)A(3)1/2024 dated Shimla-2 the 03-01-2024 and PWD-B-A0(3)/8/2025- 300858 dated 09-10-2025 as the works mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender & Schedule of Quantity and Certificate.


Executive Engineer,
HPPWD., Division Kasumpti
Shimla.

Copy forwarded to for further necessary action please.

1. The Superintending Engineer 4th Circle HPPWD Shimla .


Executive Engineer,
HPPWD., Division Kasumpti
Shimla.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDERS**

Executive Engineer B&R Division Kasumpti HPPWD Shimla for the following works on behalf of the Government of Himachal Pradesh from the eligible contractors enlisted in HPPWD, so as to reach in the office as per time schedule given below:-

- | | |
|--|-----------------------------------|
| 1. Date of receipt of application for tender forms:- | 13-07-2026 10:00 AM upto 12:00 PM |
| 2. Dated of Issue /sale of tender forms:- | 13-07-2026 12:00 PM upto 4:00 PM |
| 3. Date of receipt of tender:- | 14-07-2026 .up to 10:30 AM |
| 4. Date of opening of tender:- | 14-07-2026 up to 11:00 AM |

Sr. No.	Name of Work	Estimated cost	EMD(Rs.)	Cost of Tender (Rs.)	Time Limit	Eligible class of Contractor
1	A/R & M/O on Jablanda to Kiarkoti road Km. 0/00 to 8/200 (SH:- Trimming of grass and clening of drain, cleaning of hume pipe & Maintenance of earth shoulder 0/00 to 4/00).	99278/-	2000/-	350/-	30 days	Class-D
2	A/R & M/O various residential Qtrs. Type-I to Type-VI GAD Residential Qtrs. at, Kasumpti, Shimla-9 (SH:- P/F Chajja in type-III, set No.120,109, Repair of Toilet in Type-III set no 160, P/F rain pipes in various sets under Kasumpti Section).	99532/-	2000/-	350/-	30 days	Class-D
3	A/R & M/O on Shimla Mandi road Km. 6/00 to 22/00 (SH:- Trimming of grass and cleaning of drain, cleaning of hume pipe & Maintenance of earth shoulder 14/500 to 18/00).	98112/-	2000/-	350/-	30 days	Class-D
4	A/R & M/O on Jablanda to Kiarkoti road Km. 0/00 to 8/200 (SH:- Trimming of grass and cleaning of drain, cleaning of hume pipe & Maintenance of earth shoulder 4/200 to 8/200).	99320/-	2000/-	350/-	30 days	Class-D
5	A/R & M/O on Shimla Mandi road Km. 6/00 to 22/00 (SH:- Trimming of grass and cleaning of drain, cleaning of hume pipe & Maintenance of earth shoulder 11/00 to 14/500).	98027/-	2000/-	350/-	30 days	Class-D
6	A/R & M/O on Shimla Mandi road Km. 6/00 to 22/00 (SH:- Trimming of grass and cleaning of drain, cleaning of hume pipe & Maintenance of earth shoulder 9/00 to 11/00).	99594/-	2000/-	350/-	30 days	Class-D
7	A/R & M/O on Shimla Mandi road Km. 6/00 to 22/00 (SH:- Trimming of grass and cleaning of drain, cleaning of hume pipe & Maintenance of earth shoulder 6/00 to 8/500).	99510/-	2000/-	350/-	30 days	Class-D

It is certified that the above works are required to be carried out immediately being emergent nature of work in public interest.

The tender documents shall be issued only to those contractor/Firm who fulfill the following documents with the application.

1. The valid enlistment/Registration of contractor in Appropriate Class.
2. Permanent account No. (PAN NO).
3. G.S.T No.
4. Earnest Money in the shape of National saving certificate/time deposit account in the any of the post office in HP. F.D.R from any Nationalized Bank duly pleaded in favour of the Executive Engineer Division Kasumpti HPPWD Shimla.
5. The earnest & cost of tender form for the above works should be submitted with the application for the purchase of the tender form. The application received without earnest money & cost of tender form shall summarily be rejected.
6. The officer of the tender shall remain valid up to 75 days after the opening of tender.
7. Ambiguous/telephonic /conditional tenders or tender by fax/E mail shall not be considered and will be summarily be rejected.
8. Executive Engineer reserve the right to reject or cancel any or all tenders without assigning any reasons.
9. If the date given above happens to be holiday the same shall be processed on next working day.
10. The Contractor/firms must quote their rates in words as well as in figures failing which EXN reserve the right to accept/reject any or all tenders.
11. The tender forms shall not be issued to those contractors/firms whose previous performance is not found satisfactory and who have not executed the previous awarded works within the stipulated period of completion.
12. One contractor shall not have more than two major works in hand at a time.
13. Work should be completed by the contractor within stipulated period.

Executive Engineer,
Division Kasumpti.,
HPPWD. Shimla-3.

No.PW-SD-I/CB-Tender/2026-2027-
Copy forwarded to:-

1. Copy to the Deputy Commissioner Shimla Distt. Shimla.
2. Copy to the Executive Engineer Shimla Division No-III HPPWD Shimla.
3. Copy to the Sub Divisional Magistrate (U) Shimla.
4. Copy to the Sub Divisional Magistrate (R) Shimla.
5. Copy to Municipal committee Shimla Distt. Shimla.
6. Copy to Block Development officer Mashobra Dsitt. Shimla.
7. All the Assistant Engineers under this Division, HPPWD Shimla-3.
8. Superintendent / HDM /DAO.
9. Notice Board.

Dated : 31/7/26

Executive Engineer,
Division Kasumpti.,
HPPWD Shimla.

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., **Estimated Cost:- 99,278.00**

Name of Work :- A/R & M/O on Jublanda to Kiarkoti Road Km. 0/00 to 8/200. (SH:- Trimming of glass and cleaning of drain , cleaning of hume pipe & maintainance of earth shoulder 0/00 to 4/00) **Earnest Money :- 2,000.00**

Time:- One Month.


Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Cutting of Branches of trees shrubs and trimming of glass and weeds Trimming of glass and weeds from the shoulder / berms and disposing off the same to suitable location as per technical specification Clause 1914. including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	4000.00	Sqm	4.08	Rupees Four and Paise Eight Only	Per Square metre	16320.00
2	Maintenance of Drain The maintenance of drain include erosion , repair , clearing , cleaning, reshaping ,regarding , deepening of side drain as well as catch water drain as per technical specification Clause 1907. including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	4000.00	Rmt	4.60	Rupees Four and Paise Sixty Only	Per Running Metre	18400.00
3	The maintenance of Hume pipe Culvert by way of clearing , cleaning, Erosion, repairs to cracks , parapet wall and protection work as per drawing and technical specification Clause 1908. including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	8.00	Nos	2128.00	Rupees Two Thousand One Hundred Twenty Eight Only	Each	17024.00

228
o/c

4	Maintenance of Earth shoulder (felling with free slection soil) making and loose material / irregularities on shoulders to the design level by adding fresh approved selection soil and compecting it with approved equipment at OMC upto a lead of 1000 mts as per drawing and technical specification Clause 1603. including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	1124.00	Sqm	42.29	Rupees Forty Two and Paise Twenty Nine Only	Per Square metre	47534.00
						Total	99278.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per indian standard in the market should confirm to bureau of indian standars.


 Executive Engineer,
 B& R Division Kasumpti
 HPPWD Winter Field Shimla -3

228

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA- Estimated Cost:- 99,532.00
Name of Work :- A/R & M/O various residential Qtrs Type- I to Type-VI GAD Residential Qtrs at, Kasumpti, Shimla-9. (SH:- P/F Chajja in Type-III , set no 120, 109, Repair of Toilet in Type- III set no 160, P/F rain pipes in various sets under Kasumpti Section). Earnest Money :- 2,000 .00
Time:- One Month

Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and back filling with approved material. Hard Roack blasting prohibited and their intermediate classification of soils including dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer - in-charge at site, according to the HP.PWD. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site (To be arranged by the contractor) including payment of prescribed charges of dumping to the owner of dumping site as per satisfaction of Engineer-in-Charge through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour. (if required).All useful material such as stones, shingles aggregate and slates shall be properly stacked at site to the maximum possible extent in all leads and lifts through all modes of transportation the usefull stones as per the direction of the Engineer-in-Charge. Any loss to the public and private propriety during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.	2.03	Cum	550.00	Rupees Five Hundred Fifty Only	Per Cubic Metre	1117.00

2	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 1:3:6 (One cement : Three coarse sand) : Six graded stone aggregate 20 mm nominal size)	0.45	Cum	5700.00	Rupees Five Thousand Seven Hundred Only	Per Cubic Metre	2565.00
2.1	(ii) 1:5:10 (One cement : five coarse sand) : ten graded stone aggregate 40 mm nominal size)	0.45	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per Cubic Metre	2070.00
3	Steel work welded in built up sections, trusses and framed work including cutting hoisting fixing in position and applying a priming coat of red lead paint including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) In gratings, framed guards bars ladders, railing, brackets and similar work.	180.00	Kgs	115.00	Rupees One Hundred Fifteen Only	Per Kilogram	20700.00
4	Painting two coats (excluding coat) on new wood and wood based surface with enamel paint to give an even shade including cleaning the surface of dirt, dust and other foreign matter, sand papering & stopping including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) With white enamel paint.	3.15	Sqm	80.00	Rupees Eighty Only	Per Square meter	252.00
5	Providing and fixing high pressure PVC spigot and socket, waste and ventilating pipes ISI marked including fixing with approved adhesive etc. including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 110 mm dia.	45.00	Rmt	380.00	Rupees Three Hundred Eighty Only	Per Running Meter	17100.00
5.1	(ii) 90 mm dia.	15.00	Rmt	350.00	Rupees Three Hundred Fifty Only	Per Running Meter	5250.00

6	Providing and fixing PVC door bend with oval access door, insertion rubber washer 3 mm thick bolts and nuts ISI marked complete including fixing with approved adhesive etc. including carriage of materials in all leads as per directions of the Engineer-in-Charge. (i) 110 mm dia.	2.00	Nos.	280.00	Rupees Two Hundred Eighty Only	Each	560.00
6.1	(iii) 150 mm dia.	2.00	Nos.	250.00	Rupees Two Hundred Fifty Only	Each	500.00
7	Providing and fixing PVC single equal branch plain ISI marked including fixing with approved adhesive etc. complete. (i) 110 mm dia.	2.00	Nos.	250.00	Rupees Two Hundred Fifty Only	Each	500.00
7.1	(ii) 90 mm dia.	2.00	Nos.	230.00	Rupees Two Hundred Thirty Only	Each	460.00
8	Providing and fixing PVC collars ISI marked including fixing with approved adhesive etc including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 110 mm dia.	2.00	Nos.	230.00	Rupees Two Hundred Thirty Only	Each	460.00
8.1	(ii) 90 mm dia.	2.00	Nos.	210.00	Rupees Two Hundred Ten Only	Each	420.00
9	Providing and fixing PVC plain bend ISI marked including fixing with approved adhesive etc. including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 110 mm dia.	2.00	Nos.	250.00	Rupees Two Hundred Fifty Only	Each	500.00
9.1	(ii) 90 mm dia.	2.00	Nos.	230.00	Rupees Two Hundred Thirty Only	Each	460.00
10	Providing and fixing PVC single equal branch with oval access door ,ISI marked insertion rubber washer 3 mm thick bolts and nuts complete ,including fixing with approved adhesive etc. complete. (i) 110 mm dia.	2.00	Nos.	250.00	Rupees Two Hundred Fifty Only	Each	500.00

10.1	(ii) 90 mm dia	2.00	Nos.	230.00	Rupees Two Hundred Thirty Only	Each	460.00
11	Providing and laying stone soling , including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	0.60	Cum	1400.00	Rupees One Thousand Four Hundred Only	Per Cubic Metre	840.00
12	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. (i)Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix)	0.29	Cum	1250.00	Rupees One Thousand Two Hundred Fifty Only	Per Cubic Metre	360.00
13	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) For thickness of tiles 10 mm to 25 mm	1.44	Sqm	50.00	Rupees Fifty Only	Per Square Meter	72.00
14	Providing and laying rectified Glazed Ceramic floor tiles of size 300x300 mm or more (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick Cement Mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including pointing the joints with white cement and matching pigments etc., including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	1.44	Sqm	1300.00	Rupees One Thousand Three Hundred Only	Per Square Meter	1872.00
15	Tile work in skirting, risers of steps and dado up to 2 m height over 12 mm thick bed of cement mortar 1:3 (1 cement :3 coarse sand) and jointed with grey cement slurry @ 3.3 kg/sqm, including pointing in white cement mixed with pigment of matching shade including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. Size 300x600 mm .	1.20	Sqm	1300.00	Rupees One Thousand Three Hundred Only	Per Square Meter	1560.00


16	Providing and fixing vitreous China wash down, water closet (European type. W.C. pan) with integral 'P' or 'S' trap including jointing the trap with soil pipe in cement mortar 1:1(1 cement : 1 sand) (Seat and over to be measured and paid for separately) including carriage of materials in all leads as per directions of the Engineer-in-Charge (i) European type seat Make Ess Ess	1.00	Nos.	3400.00	Rupees Three Thousand Four Hundred Only	Each	3400.00
17	Providing and fixing plastic seat (solid / Hallow type) and cover for wash down water closet with C.P. Brass hinges and rubber buffers. including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. White plastic seat and Cover MAKE ESSCO or Equivalent	1.00	Nos.	1100.00	Rupees One Thousand One Hundred Only	Each	1100.00
18	Providing and fixing P.V.C. low level flushing cistern with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 10 litre capacity - White MAKE ESSCO or Equivalent	1.00	Nos.	2600.00	Rupees Two Thousand Six Hundred Only	Each	2600.00
19	Providing and fixing hand faucet including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	1.00	Nos.	1050.00	Rupees One Thousand Fifty Only	Each	1050.00
20	Providing and fixing scaffolding in building side, including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	90.00	Sqm	120.00	Rupees One Hundred Twenty Only	Per Square Meter	10800.00
21	Providing corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 0.63 mm thick sheet with zinc coating not less than 275 gm/m ²	3.15	Sqm	1450.00	Rupees One Thousand Four Hundred Fifty Only	Per Square Meter	4568.00

22	Providing and fixing of 40 cm overall width plain G.S sheet fixed with polymer coated J or L hooks , bolts and nuts , G.I limpet and bitumen washer complete , bent to shape and fixed in wall with cement mortar 1:3(1 cement : 3 coarse sand) , including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 1.00 mm thick with zinc coating not less than 275 gm/m ²	9.00	Rmt	600.00	Rupees Six Hundred Only	Per Running metre	5400.00
23	Providing and fixing PVC degree bend ISI marked including fixing with approved adhesive etc. including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 110 mm dia.	2.00	Nos.	250.00	Rupees Two Hundred Fifty Only	Each	500.00
23.1	(i) 90 mm dia	2.00	Nos.	200.00	Rupees Two Hundred Only	Each	400.00
24	Providing and fixing M.S. holder - bat clamps of approved design to Sand Cast iron/cast iron (spun)/ PVC pipe embedded in and including cement concrete blocks 10x10x10 cm of 1:2:4 mix (1: cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) , including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) For 110 mm dia pipe	20.00	Nos.	200.00	Rupees Two Hundred Only	Each	4000.00
25	Chequerred precast cement concrete tiles 20 mm thick in footpath & courtyard, jointed with neat cement slurry mixed with pigment to match the shade of tiles, including rubbing and cleaning etc complete, on 20 mm thick bed of cement mortar 1:4 (One cement: Four coarse sand)including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) Medium shade pigment using 50% white cement 50% grey cement.	3.60	Sqm	1400.00	Rupees One Thousand Four Hundred Only	Per Square Metre	5040.00
26	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) For thickness of tiles 10 mm to 25 mm	3.60	Sqm	80.00	Rupees Eighty Only	Per Square Meter	288.00

27	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. (i)Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	0.72	Cum	1400.00	Rupees One Thousand Four Hundred Only	Per Cubic Metre	1008.00
28	Providing and fixing Bambi in chajja , including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	2.00	Nos.	400.00	Rupees Four Hundred Only	Each	800.00
						Total	99532.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						G. Total	

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.


 Executive Engineer
 B& R Division Kasumpti
 HPPWD Winter Field Shimla -3

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., **Estimated Cost:- 98,112.00**

Name of Work :- A/R & M/O on Shimla Mandi Road Km. 6/00 to 22/00. (SH:- Trimming of glass and cleaning of drain , cleaning of hume pipe & maintenance of earth shoulder 14/500 to 18/00) **Earnest Money :- 2,000.00**


Time:- One Month.

Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Cutting of Branches of trees shrubs and trimming of glass and weeds Trimming of glass and weeds from the shoulder / berms and disposing off the same to suitable location as per technical specification Clause 1914. including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	3500.00	Sqm	4.08	Rupees Four and Paise Eight Only	Per Square metre	14280.00
2	Maintenance of Drain The maintenance of drain include erosion , repair , clearing , cleaning, reshaping ,regarding , deepening of side drain as well as catch water drain as per technical specification Clause 1907. including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	3500.00	Rmt	4.60	Rupees Four and Paise Sixty Only	Per Running Metre	16100.00
3	The maintenance of Hume pipe Culvert by way of clearing , cleaning, Erosion, repairs to cracks , parapet wall and protection work as per drawing and technical specification Clause 1908. including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	5.00	Nos	2128.00	Rupees Two Thousand One Hundred Twenty Eight Only	Each	10640.00

4	Maintenance of Earth shoulder (felling with free selection soil) making and loose material / irregularities on shoulders to the design level by adding fresh approved selection soil and compacting it with approved equipment at OMC upto a lead of 1000 mts as per drawing and technical specification Clause 1603. including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	1350.00	Sqm	42.29	Rupees Forty Two and Paise Twenty Nine Only	Per Square metre	57092.00
						Total	98112.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.


 Executive Engineer,
 B& R Division Kasumpti
 HPPWD Winter Field Shimla -3

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D.,							
Name of Work :- A/R & M/O on Jublanda to Kiarkoti Road Km. 0/00 to 8/200. (SH:- Trimming of glass and cleaning of drain , cleaning of hume pipe & maintanance of earth shoulder 4/200 to 8/200)						Estimated Cost:- 99,320.00	
						Earnest Money :- 2,000.00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Cutting of Branches of trees shrubs and trimming of glass and weeds Trimming of glass and weeds from the shoulder / berms and disposing off the same to suitable location as per technical specification Clause 1914. including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	4000.00	Sqm	4.08	Rupees Four and Paise Eight Only	Per Square metre	16320.00
2	Maintenance of Drain The maintenance of drain include erosion , repair , clearing , cleaning, reshaping ,regarding , deepening of side drain as well as catch water drain as per technical specification Clause 1907. including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	4000.00	Rmt	4.60	Rupees Four and Paise Sixty Only	Per Running Metre	18400.00
3	The maintenance of Hume pipe Culvert by way of clearing , cleaning, Erosion, repairs to cracks , parapet wall and protection work as per drawing and technical specification Clause 1908. including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	8.00	Nos	2128.00	Rupees Two Thousand One Hundred Twenty Eight Only	Each	17024.00

229

4	Maintenance of Earth shoulder (felling with free selection soil) making and loose material / irregularities on shoulders to the design level by adding fresh approved selection soil and compacting it with approved equipment at OMC upto a lead of 1000 mts as per drawing and technical specification Clause 1603. including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	1125.00	Sqm	42.29	Rupees Forty Two and Paise Twenty Nine Only	Per Square metre	47576.00
						Total	99320.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer
B& R Division Kasumpti
HPPWD Winter Field Shimla -3


SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D.,					Estimated Cost:- 98,027.00		
Name of Work :- A/R & M/O on Shimla Mandi Road Km. 6/00 to 22/00. (SH:- Trimming of glass and cleaning of drain , cleaning of hume pipe & maintanance of earth shoulder 11/00 to 14/500)					Earnest Money :- 2,000.00		
					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Cutting of Branches of trees shrubs and trimming of glass and weeds Trimming of glass and weeds from the shoulder / berms and disposing off the same to suitable location as per technical specification Clause 1914. including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	3500.00	Sqm	4.08	Rupees Four and Paise Eight Only	Per Square metre	14280.00
2	Maintenance of Drain The maintenance of drain include erosion , repair , clearing , cleaning, reshaping ,regarding , deepening of side drain as well as catch water drain as per technical specification Clause 1907. including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	3500.00	Rmt	4.60	Rupees Four and Paise Sixty Only	Per Running Metre	16100.00
3	The maintenance of Hume pipe Culvert by way of clearing , cleaning, Erosion, repairs to cracks , parapet wall and protection work as per drawing and technical specification Clause 1908. including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	5.00	Nos	2128.00	Rupees Two Thousand One Hundred Twenty Eight Only	Each	10640.00

4	Maintenance of Earth shoulder (felling with free selection soil) making and loose material / irregularities on shoulders to the design level by adding fresh approved selection soil and compacting it with approved equipment at OMC upto a lead of 1000 mts as per drawing and technical specification Clause 1603. including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	1348.00	Sqm	42.29	Rupees Forty Two and Paise Twenty Nine Only	Per Square metre	57007.00
						Total	98027.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.


 Executive Engineer,
 B& R Division Kasumpti
 HPPWD Winter Field Shimla -3


SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D.,				Estimated Cost:- 99,594.00			
Name of Work :- A/R & M/O on Shimla Mandi Road Km. 6/00 to 22/00. (SH:- Trimming of glass and cleaning of drain , cleaning of hume pipe & maintanance of earth shoulder 9/00 to 11/00)				Earnest Money :- 2,000.00			
				Time:- One Month.			
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Cutting of Branches of trees shrubs and trimming of glass and weeds Trimming of glass and weeds from the shoulder / berms and disposing off the same to suitable location as per technical specification Clause 1914. including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	3000.00	Sqm	4.08	Rupees Four and Paise Eight Only	Per Square metre	12240.00
2	Maintenance of Drain The maintenance of drain include erosion , repair , clearing , cleaning, reshaping ,regarding , deepening of side drain as well as catch water drain as per technical specification Clause 1907. including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	3000.00	Rmt	4.60	Rupees Four and Paise Sixty Only	Per Running Metre	13800.00
3	The maintenance of Hume pipe Culvert by way of clearing , cleaning, Erosion, repairs to cracks , parapet wall and protection work as per drawing and technical specification Clause 1908. including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	4.00	Nos	2128.00	Rupees Two Thousand One Hundred Twenty Eight Only	Each	8512.00

4	Maintenance of Earth shoulder (felling with free selection soil) making and loose material / irregularities on shoulders to the design level by adding fresh approved selection soil and compacting it with approved equipment at OMC upto a lead of 1000 mts as per drawing and technical specification Clause 1603. including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	1538.00	Sqm	42.29	Rupees Forty Two and Paise Twenty Nine Only	Per Square metre	65042.00
						Total	99594.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.


 Executive Engineer,
 B& R Division Kasumpti
 HPPWD Winter Field Shimla-3


SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D.,						Estimated Cost:- 99,510.00	
Name of Work :- A/R & M/O on Shimla Mandi Road Km. 6/00 to 22/00. (SH:- Trimming of glass and cleaning of drain , cleaning of hume pipe & maintainance of earth shoulder 6/00 to 8/500)						Earnest Money :- 2,000.00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Cutting of Branches of trees shrubs and trimming of glass and weeds Trimming of glass and weeds from the shoulder / berms and disposing off the same to suitable location as per technical specification Clause 1914. including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	2500.00	Sqm	4.08	Rupees Four and Paise Eight Only	Per Square metre	10200.00
2	Maintenance of Drain The maintenance of drain include erosion , repair , clearing , cleaning, reshaping ,regarding , deepening of side drain as well as catch water drain as per technical specification Clause 1907. including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	2500.00	Rmt	4.60	Rupees Four and Paise Sixty Only	Per Running Metre	11500.00
3	The maintenance of Hume pipe Culvert by way of clearing , cleaning, Erosion, repairs to cracks , parapet wall and protection work as per drawing and technical specification Clause 1908. including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	6.00	Nos	2128.00	Rupees Two Thousand One Hundred Twenty Eight Only	Each	12768.00

4	Maintenance of Earth shoulder (felling with free slection soil) making and loose material / irregularities on shoulders to the design level by adding fresh approved selection soil and compecting it with approved equipment at OMC upto a lead of 1000 mts as per drawing and technical specification Clause 1603. including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	1538.00	Sqm	42.29	Rupees Forty Two and Paise Twenty Nine Only	Per Square metre	65042.00
						Total	99510.00
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.


 Executive Engineer
 B& R Division Kasumpti
 HPPWD Winter Field Shimla-3