

Himachal Pradesh
Public Works Department

No. PW-KD- CTR- Tender-NIT/2026-2027-

13620-21

Dated:-

31/7/20

To

The Executive Engineer (IT.Cell)
Nigam Vihar Shimla.


Subject :-

Publication of Tender Notice.

Jai Hind

Enclosed please find herewith the tender Notice of work as given in the Notice Inviting tender for uploading on department website as per notification Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW (B)A(3)1/2024 dated Shimla-2 the 03-01-2024 and PWD-B-A0(3)/8/2025- 300858 dated 09-10-2025 as the works mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender & Schedule of Quantity and Certificate.


Executive Engineer,
HPPWD, Division Kasumpti
Shimla.

Copy forwarded to for further necessary action please.

1. The Superintending Engineer 4th Circle HPPWD Shimla .


Executive Engineer,
HPPWD., Division Kasumpti
Shimla.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDERS**

Executive Engineer B&R Division Kasumpti HPPWD Shimla for the following works on behalf of the Government of Himachal Pradesh from the eligible contractors enlisted in HPPWD, so as to reach in the office as per time schedule given below:-

- | | |
|--|----------------------------------|
| 1. Date of receipt of application for tender forms:- | 10-8-2026 10:00 AM upto 12:00 PM |
| 2. Dated of Issue /sale of tender forms:- | 10-08-2026 12:00 PM upto 4:00 PM |
| 3. Date of receipt of tender:- | 11-08-2026 upto 10:30 AM |
| 4. Date of opening of tender:- | 11-08-2026 upto 11:00 AM |

Sr. No.	Name of Work	Estimated cost	EMD(Rs.)	Cost of Tender (Rs.)	Time Limit	Eligible class of Contractor
1	A/R & M/O on various various roads lakkar Bazar section under sub Division No-I (SH:- Supplying and stacking pot seal bags cold mix in various Rds)	83199/-	1700/-	350/-	30 days	Class-D
2	A/R & M/O Residetnial Building at GAD Colony kasumpti Shimla 9 (SH:- Conducting of surevey & preparation of contour plan with X-section of jammu caste building at kasumpti under sub Division VIII Shimla)	68500/-	1400/-	350/-	30 days	Class-D
3	A/R & M/O to kelti Barmu under Shimla sub Division No.1 (SH:- Maintenance of drain culvert shoulders)(Excluding GST)	82217/-	1700/-	350/-	30 days	Class-D
4	A/R & M/O on various various roads Beolia section under Junga sub Division (SH:- Supplying and stacking pot seal bags cold mix in various Rds)(without GST)	84534/-	1700/-	350/-	30 days	Class-D
5	A/R & M/O on various various roads Dhalli section under sub Division No-I (SH:- Supplying and stacking pot seal bags cold mix in various Rds) without GST)	83644/-	1700/-	350/-	30 days	Class-D
6	A/R & M/O on various various roads Bharari section under sub Division No-I (SH:- Supplying and stacking pot seal bags cold mix in various Rds) without GST)	84534/-	1700/-	350/-	30 days	Class-D
7	A/R & M/O on various roads janedghat section under junga sub Division (SH:- Supplying and stacking pot seal bags cold mix in various Rds)(without GST)(without GST)	83644/-	1700/-	350/-	30 days	Class-D
8	A/R & M/O on various roads Chllanda section under janga sub Division (SH:- Supplying and stacking pot seal bags cold mix in various Rds). (without GST)	83644/-	1900	350/-	30 days	Class-D
9	Restoation of Rain Damages on Shoghi mehli Junga sadhupul road in km. 12/375 to 48/925 (SH:- Constrction of R/wall between Rd. 38/370 to 38/388)(Under PDNA)	498923/-	10000/-	350/-	30 days	Class-D

It is certified that the above works are required to be carried out immediately being emergent nature of work in public interest.

The tender documents shall be issued only to those contractor/Firm who fulfill the following documents with the application.

- The valid enlistment/Registration of contractor in Appropriate Class.
- Permanent account No. (PAN NO).
- G.S.T No.
- Earnest Money in the shape of National saving certificate/time deposit account in the any of the post office in HP. F.D.R from any Nationalized Bank duly pleaded in favour of the Executive Engineer Division Kasumpti HPPWD Shimla.
- The earnest & cost of tender form for the above works should be submitted with the application for the purchase of the tender form. The application received without earnest money & cost of tender form shall summarily be rejected.
- The officer of the tender shall remain valid up to 75 days after the opening of tender.
- Ambiguous/telephonic /conditional tenders or tender by fax/E mail shall not be considered and will be summarily be rejected.
- Executive Engineer reserve the right to reject or cancel any or all tenders without assigning any reasons.
- If the date given above happens to be holiday the same shall be processed on next working day.
- The Contractor/firms must quote their rates in words as well as in figures failing which EXN reserve the right to accept/reject any or all tenders.
- The tender forms shall not be issued to those contractors/firms whose previous performance is not found satisfactory and who have not executed the previous awarded works within the stipulated period of completion.
- One contractor shall not have more than two major works in hand at a time.
- Work should be completed by the contractor within stipulated period.

Executive Engineer,
Division Kasumpti,
HPPWD. Shimla-3.

No.PW-SD-I/CB-Tender/2026-2027-

Copy forwarded to:-

- Copy to the Deputy Commissioner Shimla Distt. Shimla.
- Copy to the Executive Engineer Shimla Division No-III HPPWD Shimla.
- Copy to the Sub Divisional Magistrate (U) Shimla.
- Copy to the Sub Divisional Magistrate (R) Shimla.
- Copy to Municipal committee Shimla Distt. Shimla.
- Copy to Block Development officer Mashobra Dsitt. Shimla.
- All the Assistant Engineers under this Division, HPPWD Shimla-3.
- Superintendent / HDM /DAO.
- Notice Board.

Dated :-

31/3/28

Executive Engineer,
Division Kasumpti,
HPPWD Shimla.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-						Estimated Cost:- 83,199.00	
NAME OF WORK:- A/R & M/O on Various roads Lakkar Bazar section under Sub Division						Earnest Money :-1,700.00	
No.1 (SH:- Supplying and Stacking Pot seal bags cold mix in Various Rds).						Time:- One Month	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Supplying and laying pot seal beg of 25 kgs cold mix The rate including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government But Excluding GST, including hauling of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in- Charge.as per direction of Engineer-In-Charge	93.50	Nos	889.83	Rupees Eight Hundred Eighty Nine and Paise Eighty Three Only	Per Each	83199.00
						Total	83199.00
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						
SA No- 377 T/SNO-13383-84 RS 10/120/-D+30							

SA No: 372T/SNO-13383-84 RS 101120/-D+30-7-26

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.


Executive Engineer,
HPPWD Division,
Kasumpti Shimla

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.					Estimated Cost:- 68,500.00		
Name of Work :- A/R & M/O Residential Building at GAD Colony Kasumpti, Shimla- 171009. (SH:- Conducting of Survey & Preparation of Contour plan with X-section of Jammu castle building at Kasumpti under Sub-Division VIII Shimla.)					Earnest Money :- 1,400.00		
					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Conducting of preparation survey & Preparation of Contour plan with X-section ,Topo sheet and SHP file with preparation of 2 sets, complete in all respect up to final approval as per directions of the Engineer-in-Charge in Jammu castle building. (Excluding GST)	1.00	Per Case	68500.00	Rupees Sixty Eight Thousand Five Hundred Only	Per Case	68500.00
						Total	68500.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

SR No ÷ 365 T/S No - 13397-98 Rs. 83,255/- Dt 30/7/26

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standards.


 Executive Engineer,
 B& R Division Kasumpti
 HPPWD Winter Field Shimla -3

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.							
Name of Work :---A/R & M/O to Kelti Barmu under shimla sub division No 1. (SH:, Maintenance of drain culvert shoulders) (Excluding GST)						Estimated Cost:-82,217.00	
						Earnest Money :1700.00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	The maintenance of drains include erosion, repair, clearing, reshaping, regarding, deepening of side drains as well as catch water drains as per technical specification Clause 1907 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (Excluding GST)	4000.00	cum	3.81	#NAME?	Per Cubic Metre	15240.00
2	Mainteance of Hume pipe culvert by way of cleaning, Erosion repair to cracks parapets wall and protection work as per drawing and technical specification Clause 1908 including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge. Excluding GST	8.00	No	1949.15	#NAME?	Per Cubic Metre	15593.00
3	Cutting of branches of trees shrubs and trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per technical specifications Clause 1914 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. Excluding GST	16250.00	Sqm	2.97	#NAME?	Per Cubic Metre	48263.00
4	White washing two coats on parapets wall and tree trunks including preparation of surface by cleaning scraping etc. as per technical specification clause 1915 including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge. Excluding GST	86.40	Sqm	36.12	#NAME?	Per Cubic Metre	3121.00
	Quated rates Percentage in figures					Total	82217.00
	Quoted rates Percentage in words						
						G.Total	

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

SR No : 370 T/5 No-13387-88 Rs. 99,927/- 8130-7-2

Executive Engineer,

B & R Division Kasumpti

HPPWD Winter Field Shimla -3

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-						Estimated Cost:- 84,534.00	
NAME OF WORK:- A/R & M/O on Various roads Beulia section under Junga Sub Division						Earnest Money :-1,700.00	
(SH:- Supplying and Stacking Pot seal bags cold mix in Various Rds). .(Without GST)						Time:- One Month	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Supplying and laying pot seal beg of 25 kgs cold mix The rate including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government But Excluding GST, including hauling of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in- Charge.as per direction of Engineer-In-Charge	95.00	Nos	889.83	Rupees Eight Hundred Eighty Nine and Paise Eighty Three Only	Per Each	84534.00
						Total	84534.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						

SR No-373 T/S No-13381-82 Rs.102742/- Dt 30-7-26

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer,
HPPWD Division,
Kasumpti Shimla

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-					Estimated Cost:- 83,644.00		
NAME OF WORK:- A/R & M/O on Various roads Dhalli section under Sub Division No.1 (SH:-					Earnest Money :-1,700.00		
Supplying and Stacking Pot seal bags cold mix in Various Rds).					Time:- One Month		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Supplying and laying pot seal beg of 25 kgs cold mix The rate including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government But Excluding GST, including hauling of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in- Charge.as per direction of Engineer-In-Charge	94.00	Nos	889.83	Rupees Eight Hundred Eighty Nine and Paise Eighty Three Only	Per Each	83644.00
						Total	83644.00
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						

SON 3748 No-13379-80 Rs.101661/- Dt 30-7-26

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standards

Executive Engineer,
HPPWD Division,
Kasumpti Shimla

SCHEDULE OF QUANTITY						
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-				Estimated Cost:- 84,534.00		
NAME OF WORK:- A/R & M/O on Various roads Bharari section under Sub Division No.1				Earnest Money :-1,700.00		
(SH:- Supplying and Stacking Pot seal bags cold mix in Various Rds). (Without GST)				Time:- One Month		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit
				In figures	In words	
1	Supplying and laying pot seal beg of 25 kgs cold mix The rate including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government But Excluding GST, including hauling of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in- Charge.as per direction of Engineer-In-Charge	95.00	Nos	889.83	Rupees Eight Hundred Eighty Nine and Paise Eighty Three Only	Per Each
						Total
						84534.00
	Quated rates Percentage in figures					
	Quoted rates Percentage in words					

SAN-375 T/S No-13377-78 Rs.102742/- Dt 30-7-26

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.


Executive Engineer,
HPPWD Division,
Kasumpti Shimla

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-						Estimated Cost:- 83,644.00	
NAME OF WORK:- A/R & M/O on Various roads Janedghat section under Junga Sub Division						Earnest Money :-1,700.00	
(SH:- Supplying and Stacking Pot seal bags cold mix in Various Rds). (Without GST)						Time:- One Month	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Supplying and laying pot seal beg of 25 kgs cold mix The rate including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government But Excluding GST, including hauling of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in- Charge.as per direction of Engineer-In-Charge	94.00	Nos	889.83	Rupees Eight Hundred Eighty Nine and Paise Eighty Three Only	Per Each	83644.00
						Total	83644.00
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						

SR No-376 T/S No-13378-76 Rs. 101661/- Dt 29-7-26

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.


Executive Engineer,
HPPWD Division,
Kasumpti Shimla

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-						Estimated Cost:- 83,644.00	
NAME OF WORK:- A/R & M/O on Various roads Challanda section under Junga Sub Division						Earnest Money :-1,900.00	
(SH:- Supplying and Stacking Pot seal bags cold mix in Various Rds)..(Without GST)						Time:- One Month	
Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Supplying and laying pot seal beg of 25 kgs cold mix The rate including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government But Excluding GST, including hauling of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in- Charge.as per direction of Engineer-In-Charge	94.00	Nos	889.83	Rupees Eight Hundred Eighty Nine and Paise Eighty Three Only	Per Each	83644.00
						Total	83644.00
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						

SR No-377 TIS No 13373-74 Rs. 101661/- Dt 29-7-26

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer,
HPPWD Division,
Kasumpt Shimla

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER KASUMPTI DIVISION , H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 498923.00	
Name of Work :-Restoration of Rain Damages on Shoghi Mehli Junga Sadhupul road in Km. 12/375 to 48/925. (SH:- Construction of R/Wall between Rd 38/370 to 38/388) (Under PDNA).						Earnest Money :- 10000.00	
						Time:- Two Month:	
Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Cutting and disposal of earth work in by mechanical in all heights and depths in all kinds of soils, including saturated soils comprising of pick work, jumper work and blasting work both in soft and hard rock with chiseling and wedging out of rock (where blasting is prohibited) and their intermediate classification of soils including, dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer -in-charge at site., according to the HP.PWD. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site as per satisfaction of Engineer- in -charge through all modes of transportation including head load ,animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required). All the surplus excavated earth to be dumped at dumping site(dumping sites will be arranged by the contractor on his own cost). Any loss to the public and private propriety, human being, machinery during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.	30.78	Cum	325.00	Rupees Three Hundred Twenty Five Only	Per Cubic Metre	10004.00
2	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and back filling with approved material. Hard Roack blasting prohibited and their intermediate classification of soils including, dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer -in-charge at site, according to the HP.PWD. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site (To be arranged by the contractor) including payment of prescribed charges of dumping to the owner of dumping site as per satisfaction of Engineer-in-Charge through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical	24.30	Cum	400.00	Rupees Four Hundred Only	Per Cubic Metre	9720.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Cement Mortar 1:5:10 (One cement: five sand: Ten graded stone agg.40mm nominal size).	6.84	Cum	3800.00	Rupees Three Thousand Eight Hundred Only	Per Cubic Metre	25992.00
4	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.(a) Cement Mortar 1:4:8(One cement:Four sand:Eight graded stone aggregate40 mm(forty milimetre) nominal size).	97.60	Cum	4300.00	Rupees Four Thousand Three Hundred Only	Per Cubic Metre	419680.00

5	Providing weep holes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm(One hundred milimetre) dia PVC pipe extending through the full with of the structures with stop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	64.00	Rmt	200.00	Rupees Two Hundred Only	Per Runing metre	12800.00
6	Backfilling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Granular material.	17.28	Cum	1200.00	Rupees One Thousand Two Hundred Only	Per Cubic Metre	20736.00
					Total		498932.00

SR No-364 T/S No-13399-400 RS-51,4000/- Dt 30/7/26

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer,
HPPWD Division,
Kasumpti Shimla