

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No. PWD-BHR-C.B/Tender/2026-27-

8740-47

Dated: 6/7/26

To

The Chief Engineer (KZ)
HPPWD Dharmshala

Subject: - Publication of Tender Notice

Respected Sir,

Enclosed please find herewith tender Notice of works as given in the Notice Inviting Tenders along with schedule of quantities for uploading on departmental Website as per direction received through e-mail dated-22.05.2026 of Worthy Engineer-in-Chief , HPPWD Nigam Vihar Shimla.

It is certified that the work mentioned in the Notice Inviting tenders are urgent in nature and in public interest.

DA: State as above.

Your's Faithfully,


Executive Engineer,
Bharmour Division,
HPPWD, Bharmour

DA/As above.

Copy forwarded to the following for information please :-

1. The Superintending Engineer 7th Circle HPPWD Dalhousie.
2. The Drawing Branch/Account Branch in this office
3. All the Assistant Engineers working under this Division
4. Notice Board of this office


Executive Engineer,
Bharmour Division,
HPPWD, Bharmour

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

"SHORT TERM NOTICE INVITING TENDERS"

Sealed procuring rate tenders on form 6 & 8 are hereby invited by the Executive Engineer Bharmour Division HPPWD Bharmour on behalf of the Governor of HP for the following works from the approved and eligible contractors enlist with HPPWD under revised rules:-

Tender Schedule:-

Date and time of receipt of application for tender form:-	10.07.2026. Time Up to 1:00 PM
Date and time of issue/Sale of tender form:-	10.07.2026. Time Up to 2:00 PM to 4:30 PM
Date and time of receipt of tender form:-	10.07.2026 Time Up to 11:30 AM
Date and time of opening tender form:-	14.07.2026 Time Up to 3:30 PM

The tender form can be had from the office of the Executive Engineer against Cash (Non-refundable). The earnest money should be in shape of Fixed Deposit duly pledge in favour of the Executive Engineer Bharmour Division HPPWD Bharmour must accompany each tender. Conditional tender and the tender received without earnest money summarily be rejected. The offer will be kept open for 75 days. The Executive Engineer reserves the right to reject on or all tenders without assigning any reason.

Sr. No.	Name of work	Estimate d cost	EMD	Cost of tender	Time allowed	Class of Contractor
1	Special repair of Chambers at ITDP Colony at Bharmour Tehsil-Bharmour Distt.-Chamba HP SH: P/L brick Chamber P.V.C. pipe etc.	69209/-	1384/-	350/-	Three month	C & D
2	C/O Balance work science block at Khani SH: P/L kota stone flooring CC and gate.	458877/-	9178/-	350/-	Three month	C & D
3	C/O Andround to Gadyara road SH: F/C from Rd 0/00 to 0/260	498266/-	10000/-	350/-	Three month	C & D
4	Restoration of rain damage on various roads under Rakh Sub-Division Sub-Head- Hiring of JCB for removal of slips at various Rds	499460/-	10000/-	350/-	Three month	C & D
5	Restoration of rain damage on various roads under Rakh Sub-Division Sub-Head- Hiring of crawler for removal of slips at various Rds	497700/-	10000/-	350/-	Three month	C & D
6	Restoration of Rain damage on Dadima to Garima road Km 0/00 to 6/00 under PDNA SH: C/O R/wall at Rd 2/134 to 2/500 portion 0/680 to 0/691	489317	9786/-	350/-	Three month	C & D
7	Improvement of Hadsar to Manimahesh mule road Km 0/00 to 13/00 SH: F/C of mule road at Rd 2/210 to 2/260 & 7/300 to 7/340	195536/-	3911/-	350/-	Three month	C & D
8.	Restoration of rain damage under Holi Sub-Division for Monsoon Sub-Head: Hiring to Tipper for removal of slips at various Rds.	474000/-	10000/-	350/-	Three month	C & D
9.	Restoration of rain damage on various roads under Holi Sub-Division for Monsoon Sub-	495690/-	10000/-	350/-	Three month	C & D

	Head: Hiring to J.C.B for removal of slips at various Rds.					
10.	Restoration of rain damage on various roads under Holi Sub-Division for Monsoon Sub-Head: Hiring to J.C.B for removal of slips at various Rds.	496920/-	10000/-	350/-	Three month	C & D
11.	Restoration of rain damage on various roads under Rakh Sub-Division for Monsoon Sub-Head: Hiring to J.C.B for removal of slips at various Rds.	493230	10000/-	350/-	Three month	C & D
12.	Restoration of rain damage on various roads under Rakh Sub-Division for Monsoon Sub-Head: Hiring to J.C.B for removal of slips at various Rds.	496920	10000/-	350/-	Three month	C & D
13.	Restoration of rain damage on various roads under Rakh Sub-Division for Monsoon Sub-Head: Hiring to J.C.B for removal of slips at various Rds.	494460	10000/-	350/-	Three month	C & D
14.	Restoration of rain damage on various roads under Rakh Sub-Division for Monsoon Sub-Head: Hiring of Tractor for shifting of material	476000/-	10000/-	350/-	Three month	C & D
15.	Restoration of rain damages under Rakh Sub-Division for monsoon SH: Hiring of Tipper for removal of slip at various Rds.	474000/-	10000/-	350/-	Three month	C & D
16.	Restoration of rain damage on various roads under Garola Sub-Division for Monsoon Sub-Head: Hiring to J.C.B for removal of slips at various Rds.	498150/-	10000/-	350/-	Three month	C & D
17.	Restoration of rain damage on various roads under Garola Sub-Division for Monsoon Sub-Head: Hiring to J.C.B for removal of slips at various Rds.	499380/-	10000/-	350/-	Three month	C & D
18.	Restoration of rain damage on various roads under Garola Sub-Division for Monsoon Sub-Head: Hiring to J.C.B for removal of slips at various Rds.	498150/-	10000/-	350/-	Three month	C & D
19.	Restoration of rain damage on various roads under Garola Sub-Division for Monsoon Sub-Head: Hiring of tractor for shifting of materials.	476000/-	10000/-	350/-	Three month	C & D
20.	Restoration of rain damage on various roads under Garola Sub-Division for Monsoon Sub-Head: Hiring of Tipper for removal of slips at various Rds.	474000/-	10000/-	350/-	Three month	C & D
21.	Restoration of rain damage on various roads under Garola Sub-Division for Monsoon Sub-Head: Hiring of J.C.B. for removal of slips at various Rds.	495690/-	10000/-	350/-	Three month	C & D
22.	Restoration of rain damage on various roads under Bharmour Sub-Division for Monsoon Sub-Head: Hiring of J.C.B. for removal of slips at various Rds.	498150/-	9963/-	350/-	Three month	C & D

23.	Restoration of rain damage on various roads under Bharmour Sub-Division for Monsoon Sub-Head: Hiring of J.C.B. for removal of slips at various Rds.	494460/-	10000/-	350/-	Three month	C & D
24.	Restoration of rain damage on various roads under Bharmour Sub-Division for Monsoon Sub-Head: Hiring of J.C.B. for removal of slips at various Rds.	495690/-	10000/-	350/-	Three month	C & D
25.	Restoration of rain damage on various roads under Bharmour Sub-Division for Monsoon Sub-Head: Hiring of J.C.B. for removal of slips at various Rds.	493230/-	10000/-	350/-	Three month	C & D
26.	Restoration of rain damage on various roads under Bharmour Sub-Division for Monsoon Sub-Head: Hiring of J.C.B. for removal of slips at various Rds.	493230/-	10000/-	350/-	Three month	C & D
27.	Restoration of rain damage on various roads under Bharmour Sub-Division for Monsoon Sub-Head: Hiring of J.C.B. for removal of slips at various Rds.	498150/-	9963/-	350/-	Three month	C & D
28.	A/R & M/O on Nichali Kugati to upar Kugati km 0/00 to 2/00 SH: c/o B/Wall at Rd 0/575 to 0/582.50	448721/-	8974/-	350/-	Three month	C & D
29.	A/R & M/O on Nichali Kugati to upar Kugati km 0/00 to 2/00 SH: c/o R/Wall at Rd 0/476 to 0/481	315986/-	6320/-	350/-	Three month	C & D
30.	A/R & M/O on Nichali Kugati to upar Kugati km 0/00 to 2/00 SH: c/o R/Wall at Rd 0/470 to 0/481	315379/-	6308/-	350/-	Three month	C & D
31.	A/R & M/O on Nichali Kugati to upper Kugati Road Km 0/00 to 2/00 SH: C/O B/wall at Rd 0/583 to 0/590.50	448175/-	8964/-	350/-	Three month	C & D
32.	Restoration of rain damage on Galthan Massu road Km 0/00 to 4/500 SH: Removal of slips including boulders at various Rd's	276274/-	5525/-	350/-	Three month	C & D
33.	C/O Batot to Almi road (Portion Batot to Gailu Kasrodi Km 0/00 to 2/500 under BASP SH: c/o R/Wall from Rd 1/090 to 1/105	499845/-	9997/-	350/-	Three month	C & D
34.	C/O Batot to Almi road (Portion Batot to Gailu Kasrodi Km 0/00 to 2/500 under BASP SH: c/o R/Wall from Rd 1/040 to 1/054.50	484939/-	9699/-	350/-	Three month	C & D
35.	Restoration of rain damage on Kandi to Kuthed road Km 0/00 to 9/00 SH: Hiring of Tipper for removal of slips at various rd's	476000/-	10000/-	350/-	One month	C & D
36.	A/R & M/O on Bharmour Badagram road km 0/00 to 26/00 SH: C/O R/wall at RD 0/225 to 0/228.52	498779/-	9976/-	350/-	Three month	C & D
37.	A/R & M/O on Bharmour Badagram road km 0/00 to 26/00 SH: C/O R/wall at RD 0/240 to 0/243.52	498399/-	9968/-	350/-	Three month	C & D

38.	A/R & M/O on Bharmour Badgram road km 0/00 to 26/00 SH: C/O R/wall at RD 0/235.80 TO 0/239.31	497404/-	9948/-	350/-	Three month	C & D
39.	Restoration of rain damage on KSPA Road Km 13/00 to 40/00 SH: C/O R/Wall at RD 18/070 to 18/075	498676/-	9973/-	350/-	Three month	C & D
40.	Restoration of rain damage on KSPA Road Km 13/00 to 40/00 SH: C/O R/Wall at RD 18/065 to 18/070	498677/-	9973/-	350/-	Three month	C & D

Certificate: - It is certified that the tenders of above works are exigency /emergent nature and in public interest.

Terms and conditions:-

1. The contractors shall produce their latest registration/ renewal of their registration/ Acknowledgement of up to date filed GST Return along with Certificate of GST Registration as per Condition No. 16(iii)/ EPF No. and earnest money should be accompanied with application. Application without earnest money will not be entertained.
2. Ambiguous/ telegraphic/Conditional tenders or tender by fax/ E- mail shall not be entertained/ considered and will summarily be rejected. Tender received after due date and time will be rejected. 3. The offer shall remain valid up to 75 days.
4. The contractor should not have more than two contracts within Division at a time tender. If the contractor has already two works in hand then the tender not excepted at the time of opening of tender and the same will be rejected technical evaluations.
5. If the contractors found lowest more than two works during the opening of bid then two works awarded to contractor at the one time and then opportunity will be given to next lowest bidder.
6. The contractor/bidder should quoted in percentage in words as well as in figures failing which XEN reserves the right to accept/ reject any or all tenders.
7. The contractor /bidders must inspect the site to ascertain /familiar the site conditions, accessibility etc. before quoting the bid/tender.
8. The tender documents shall be issued to only those contractors who does not have more the two works in hand in any HPPWD Circle/Division worth Rs. 1.00 Cr ore each.
9. That all your rates are inclusive of GST as such you will pay whole of it and you would not claim anything extra on this account from the Department.
10. The provisions of notification issued vide Additional Chief Secretary (PW) to the Govt. of HP. Shimla notification No. PBW (B) A (3)1/2018 dated 13.04.2021 shall also be applicable.

Provisions of the Addl. Chief Secretary (PW) to the Govt. of HP letter No. PBW(B)C(17)2/2012 dated 07.08.2018 are applicable.

The bidders are requested to submit their bid as per Notification issued by the Principal secretary PW to the Govt. of HP vide No.PBW(B)A(3)1/2020 dated 22.07.2020 & Govt. of HP vide No. PBW(B)A(3)1/2020-

I dated 07.10.2021 and Engineer-in-Chief HPPWD Shimla-2 letter No. PW/CTR/32-20/Genl. Inst. CPWD/2020-37996-38095 dated 13.03.2023.


Executive Engineer,
Bharmour Division,
HPPWD Bharmour

Dated:-

NO/PW/CB/GA/Tender/26-27-

Copy forwarded for information & necessary action to:-

1. The Engineer-in-Chief, HP.PWD, Shimla-2 please.
2. The Additional District Magistrate Bharmour Distt.-Chamba H.P.
2. The Chief Engineer (KZ) HPPWD Dharmshala-2 please.
3. The Deputy Commissioner Distt. Chamba please.
4. The Superintending Engineers 7th Circle HPPWD Dalhousie
5. The SDM/BDO, Bharmour please.
6. All the Assistant Engineers under this Division.
7. The Drawing Branch of this office.
8. Notice Board.


Executive Engineer,
Bharmour Division,
HPPWD Bharmour

SCHEDULE OF QUANTITY

ESTIMATED COST : Rs 69209.00
 EARNEST MONEY :- Rs 1384.18
 TIME LIMIT THREE MONTHS

NAME OF WORK :- Special repair of Chambers at ITDP Colony at Bharmour Tehsil Bharmour Distt Chamba

SUB-HEAD :- P/L brick chamber, P.V.C. pipe etc.

Sl. No.	Description of work	Quantity		RATES		Unit	Amount
				Fig	Words		
1	Dismantling of road gully chamber of various sizes including C.I. grating with frame including stacking of useful materials near the site and disposal of unserviceable materials with in 50 metres lead including refilling the excavated gap. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	2.00	Nos	404.30	Rupees two hundred thirty five and paise five only	Each	809.000
2	Cement mortar 1:4 (1 cement : 4 coarse sand) for sluice valve, with C.I. surface box 100mm top diameter, 160mm bottom diameter and 180 mm deep (inside) with chained lid and RCC top slab 1:2:4 mix (1 cement 2 coarse sand : 4 graded stone aggregate 20mm nominal size), U/C necessary excavation, foundation concrete 1:5:10 (1 cement : 5 sand : 10 graded stone aggregate 40mm nominal size) and inside plastering with cement mortar 1:3 (1 cement : 3 coarse sand) 12 mm thick, finished with a floating coat of nea. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3.00	Nos	7600.00	Six thousands nine hundred twenty two and paise ninety only	Each	22800.000
3	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor level in all shapes and sizes in. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	0.90	Cubic metres	9000.00	Rupees four hundred twenty six and paise seventy only	Per cubic metre	8100.000
4	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer-in-Charge. 100 mm nominal inner dia pipes. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	15.00	Rmt	2500.00	Rupees one thousand one hundred nine and paise sixty only	Per Running Metres	37500.000
Total :-							69209.00
% Above below							
Quoted Amount in Figures							
Quoted Amount in Words							


 Executive Engineer,
 Bharmour Division,
 JHPWD Bharmour

SCHEDULE OF QUANTITY

ESTIMATED COST : Rs 458877.00
EARNEST MONEY : Rs 9177.54
TIME LIMIT : One Month

NAME OF WORK : Construction of blance work Science block at Khani

SUB-HEAD : - P/L Kota stone flooring CC and gate.

Sl. No.	Description of work	Quantity		RATES		Unit	Amount
				Fig	Words		
1	Providing & laying 25 mm (twenty five millimetre) thick Kota stone single slab flooring in treads of steps or riser of 10 steps having semi/round nosing over 20 mm (twenty millimetre) (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, with base of cement mortar 1:4 (one cement four coarse sand) including rubbing and polishing complete as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	109.85	Cubic metres	1800.00	Rupees One Thousand Eight Hundred Only	Per Cubic metres	197730.00
2	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions With float glass panes of 5 mm thickness (weight not less than 12.50 kg/sqm) with EPDM rubber / neoprene gasket etc. Cost of aluminium snap beading shall be paid in basic complete as per the architectural drawings and within all leads, lifts of materials and other incidentals, as per approved drawing, design and as directed by the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	58.69	Cubic metres	1129.82	Rupees One Thousand One Hundred Twenty Nine And Paise Eighty Two Only	Per Cubic metres	66309.00
3	Providing and laying cement concrete 1:3:6 (One cement isto Three sand isto Six graded stone aggregate 20mm twenty millimetre) nominal size and curing complete excluding cost of form work in foundation and plinth complete as per architectural drawings including carriage of material within all leads, lifts and other incidentals, as per approved specifications drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	22.03	Cubic metres	7000.00	Rupees Seven Thousand Only	Per Cubic metres	154210.00

SCHEDULE OF QUANTITY

ESTIMATED CO Rs 498266.00
 EARNEST MON. Rs 10000.00
 TIME LIMIT THREE MONTHS

NAME OF WORK : C/O Andround to Gadyara road

SUB-HEAD :- Formation cutting from RD0/00 to 0/260

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Excavation in hilly area in all heights and depths and in all kind of soil by mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock, chiseling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required lines, grades, cutting and trimming of side slopes and level as shown in the drawing and as directed by engineer-in-charge at site according to the MORD technical specification clause 302, 304 and 1603 and sorting out useful materials and stacking the same in all leads, lifts in acquired width of road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to required width of the road or on approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour if required. Recovery of stone to the tune of 150.00 cubic metres quantity at the rate of 300/- (Rupees Three hundred) per cubic metre shall be effected from the contractor's running bills on pro-rata basis as per actual quantity executed. Any loss to the public, private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be compensated by him in all cases including carriage of materials within all leads, lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government. .	2212.55 Cubic metres			Per cubic metre	
Total :-						


 Executive Engineer,
 Bharmour Division,
 JHPWD Bharmour

SCHEDULE OF QUANTITY

Name of Work :- Restoration of rain damage on Various road under Rakh Sub Division						E/COST:-494460/-	
						E/MONEY:-10000/-	
Sh. :- Hiring of JCB for Removal of Slips at various Rd,s						TIME LIMIT:-2 MONTH	
S.No.	Description of Item	Quantity.		RATES		Unit	Amount (Rs.)
				Rate in Figure	Rate in Words		
1	Hiring of J.C.B./Excavator cum loader for cutting / widening of road and removal of slips in all kind of soil and disposal of all excavated earth un- serviceable material from the road surface up to all height and depths as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/ private property or any incident etcetera happened during the course of hiring period / executing shall be the absolute responsibility of the J.C.B /Excavator owner, which shall to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge	402.00	Per Hours			Per Hours	
						TOTAL AMOUNT=	494460.00




A. S. Rakh

Executive Engineer
Bharmour Division
HPPWD, Bharmour

SCHEDULE OF QUANTITY

Name of Work :- Restcration of rain damage on Various road under Rakh Sub Division

E/COST:-497700/-


E/MONEY:-1000)/-

TIME LIMIT:-1 MONTH

Sh. :- Hiring of Crawler for Removal of Slips at various Rd,s

S.No.	Description of Item	Quantity.		RATES		Unit	Amount (Rs.)
				Rate in Figure	Rate in Words		
1	Hiring of Crawler Excavator cum Pocklane or JS 210 or equipnment of slips debries and boulders clear from the roarl's surface upto all height's and cepths in a'll kind of soil including rocky portion and saturated soil and disposing of all excavated earth un-serviceable material from the road surface up to all heights and depths as per direction and entire satisfaction of Engineer-in-charge. The excavator at least 200 cum quantity for snow, Slips per hour. Any loss of public/ private property or any accident etc. happened during the course of hiring period / excavation shall be the absolute responsibility of the Excavator owner, which shall to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge	158.00	Per Hours			Per Hours	
TOTAL AMOUNT=							




A. Z. Rakh


Executive Engineer
Bharmour Division
HPPWD,Bharmour

DRAFT SCHEDULE OF QUANTITY

ESTIMATED COST **Rs** **489317.00**
EARNEST MONEY **Rs** **9786.00**
TIME LIMIT **THREE MONTHS**

NAME OF WORK : Restoration of rain damage on Daduma to Gareema road Km 0/00 to 6/00 (Under PDNA)

SUB-HEAD : - C/o R/Wall at RD 2/134 to 2/500 (Portion 0/680 to 0/691)

SL No.	Description of work	Quantity		RATES		Unit	Amount
				Fig	Words		
1	Excavation in earth work in all kinds of soil such as pick work jumper work blasting work (soft or hard rock) chess ling saturated soling upto all depths and disposal of all surplus material as directed by the Engineer-in-Charge including carriage of material within all leads and lift and as per the direction of the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	27.17	Cubic metres	350.10	Rupees Three Hundred Fifty And Paise Ten Only	Per cubic metre	9512.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical MORD specifications Clause 802, 803, 1202 & 1203 1:4:8 (One cement isto four sand isto eight graded/crushed stone aggregate 40mm (forty millimetres) nominal size) in road work as per the directions of the Engineer-in-Charge including carnage of materials within all leads, lifts. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	65.01	Cubic metres	6922.90	Rupees Six Thousand Nine Hundred Twenty Two And Paise Ninety Only	Per cubic metre	450058.00
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete in road structure as per drawing and MORD technical specifications clause 1604.7 and section 300 and as per direction of Engineer - in- Charge including carnage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	13.64	Cubic metres	1150.10	Rupees One Thousand One Hundred Fifty And Paise Ten Only	Per cubic metre	15687.00
4	Providing weep holes in brick/ stone / plain reinforced concrete abutment, wing wall, return walls with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1V: 20H towards drawing face complete as per drawing and technical specifications clauses 614, 709 and 1204 3.7 including carnage of material within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	37.00	Nos	380.00	Rupees Three Hundred Eighty Only	Each	14060.00
Total :-							489317.00


Executive Engineer,
Bharmour Division,
IIPPWD Bharmour

DRAFT SCHEDULE OF QUANTITY

ESTIMATED COST Rs 195536.00

EARNEST MONEY Rs 3910.72

TIME LIMIT THREE MONTHS

NAME OF WORK : Improvement of Hadsar to Manimahesh Mule road Km 0/00 to 13/00

SUB-HEAD :- Formation cutting Mule road at RD 2/110 to 2/260 & 7/300 to 7/340

Sl. No.	Description of work	Quantity		RATES		Unit	Amount
				Fig	Words		
1	Excavation in hilly area in all heights and depths and in all kind of soil by mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock, chiseling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required lines, grades, cutting and trimming of side slopes and level as shown in the drawing and as directed by engineer-in-charge at site according to the MORD technical specification section 300, 304 and 1600 and sorting out useful materials and stacking the same in all leads, lifts in acquired width of road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to required width of the road or on approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour if required. Any loss to the public, private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be compensated by him in all cases including carriage of materials within all leads, lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	361.10	Cubic metres	541.50	Rupees Five Hundred Forty One And Paise Fifty Only	Per cubic metre	195536.00
Total :-							195536.00


Executive Engineer,
Bharmour Division,
HPPWD Bharmour

SCHEDULE OF QUANTITY

ESTIMATED COST : Rs 474000.00
EARNEST MONEY : Rs 9480.00
TIME LIMIT : One Month

NAME OF WORK : Restoration of rain damage Under Holi Sub-Division (for Mansoon)

SUB-HEAD :- Hiring of Tipper for removal of slips at various Rd's

Sl. No.	Description of work	Quantity		RATES		Unit	Amount
				Fig	Words		
1	Hiring of Tipper 10Cum/18 tonne capacity for disposing and transporting of surplus excavated material and shifting of any type of construction material in all leads as per directions and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of owner of the machinery which shall have to be compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner at his own cost and repair & spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-charge. The rate including octroi, royalty, Malkana, toll tax sale tax, GST or other taxes imposed by the Government.	600.00	Hours	790.00	Rupees Seven Hundred Ninety Only	Per Hour	474000.00
		Total :-					474000.00
		%Above below					
		Quoted Amount in Figures					
		Quoted Amount in Words					


Executive Engineer,
Bharmour Division,
HPPWD Bharmour

SCHEDULE OF QUANTITY

ESTIMATED COST Rs 496920.00

EARNEST MONEY : Rs 9938.40

TIME LIMIT One Month

NAME OF WORK : Restoration of rain Damages on various road under Holi Sub. Division (For Monsoon)

SUB-HEAD :- Hiring of JCB for removal of slips at various Rd's

Sl. No.	Description of work	Quantity		RATES		Unit	Amount
				Fig	Words		
1	Hiring of J.C.B./Excavator cum loader for cutting/ widening of road and removal of slips in all kind of soil and disposal of all excavated earth un-serviceable material from the road surface up to all height and depths as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/ private property or any incident etcetera happened during the course of hiring period / executing shall be the absolute responsibility of the J.C.B./Excavator owner, which shall to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	404.00	Hours	1230.00	Rupees One Thousand Two Hundred Thirty Only	Per Hour	496920.00
	Total :-						496920.00
	% Above below						
	Quoted Amount in Figures						
	Quoted Amount in Words						


Executive Engineer,
Bharmour Division,
HPPWD Bharmour

SCHEDULE OF QUANTITY

ESTIMATED COST : Rs 495690.00


EARNEST MONEY : Rs 9913.80

TIME LIMIT : One Month

NAME OF WORK : Restoration of rain Damages on various road under Holi Sub. Division (For Monsoon)

SUB-HEAD :- Hiring of JCB for removal of slips at various Rd's

Sl. No.	Description of work	Quantity		RATES		Unit	Amount
				Fig	Words		
1	Hiring of J.C.B./Excavator cum loader for cutting/ widening of road and removal of slips in all kind of soil and disposal of all excavated earth un-serviceable material from the road surface up to all height and depths as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/ private property or any incident etcetera happened during the course of hiring period / executing shall be the absolute responsibility of the J.C.B./Excavator owner, which shall to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	403.00	Hours	1230.00	Rupees One Thousand Two Hundred Thirty Only	Per Hour	495690.00
	Total :-						495690.00
	%Above below						
	Quoted Amount in Figures						
	Quoted Amount in Words						


Executive Engineer,
Bharmour Division,
HPPWD Bharmour

SCHEDULE OF QUANTITY

ESTIMATED COST Rs 493230.00
EARNEST MONEY Rs 9864.60
TIME LIMIT One Month

NAME OF WORK : Restoration of rain Damages on various road under Rakh Sub. Division (For Mansoon)

SUB-HEAD : - Hiring of JCB for removal of slips at various Rd's

Sl. No.	Description of work	Quantity		RATES		Unit	Amount
				Fig	Words		
1	Hiring of J C B /Excavator cum loader for cutting/ widening of road and removal of slips in all kind of soil and disposal of all excavated earth un-serviceable material from the road surface up to all height and depths as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/ private property or any incident etcetera happened during the course of hiring period / executing shall be the absolute responsibility of the J C B/Excavator owner, which shall to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	401.00	Hours	1230.00	Rupees One Thousand Two Hundred Thirty Only	Per Hour	493230.00
	Total :-						493230.00
	% Above below						
	Quoted Amount in Figures						
	Quoted Amount in Words						


Executive Engineer,
Bharmour Division,
RPPWD Bharmour

SCHEDULE OF QUANTITY

ESTIMATED COST : Rs 496920.00
EARNEST MONEY : Rs 9938.40
TIME LIMIT : One Month

NAME OF WORK : Restoration of rain Damages on various road under Rakh Sub. Division (For Mansoon)

SUB-HEAD :- Hiring of JCB for removal of slips at various Rd's

Sl. No.	Description of work	Quantity		RATES		Unit	Amount
				Fig	Words		
1	Hiring of J.C.B./Excavator cum loader for cutting/ widening of road and removal of slips in all kind of soil and disposal of all excavated earth un-serviceable material from the road surface up to all height and depths as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/ private property or any incident etcetera happened during the course of hiring period / executing shall be the absolute responsibility of the J.C.B./Excavator owner, which shall to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	404.00	Hours	1230.00	Rupees One Thousand Two Hundred Thirty Only	Per Hour	496920.00
	Total :-						496920.00
	% Above below						
	Quoted Amount in Figures						
	Quoted Amount in Words						


Executive Engineer,
Bharmour Division,
HPPWD Bharmour

SCHEDULE OF QUANTITY

ESTIMATED COST : Rs 494460.00


EARNEST MONEY : Rs 9889.20

TIME LIMIT : One Month

NAME OF WORK : Restoration of rain Damages on various road under Rakh Sub. Division (For Mansoon)

SUB-HEAD :- Hiring of JCB for removal of slips at various Rd's

Sl. No.	Description of work	Quantity		RATES		Unit	Amount
				Fig	Words		
1	Hiring of J.C.B /Excavator cum loader for cutting/ widening of road and removal of slips in all kind of soil and disposal of all excavated earth un-serviceable material from the road surface up to all height and depths as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/ private property or any incident etcetera happened during the course of hiring period / executing shall be the absolute responsibility of the J.C.B/Excavator owner, which shall to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	402.00	Hours	1230 00	Rupees One Thousand Two Hundred Thirty Only	Per Hour	494460 00
	Total :-						494460.00
	%Above below						
	Quoted Amount in Figures						
	Quoted Amount in Words						


Executive Engineer,
Bharmour Division,
BPPWD Bharmour

SCHEDULE OF QUANTITY

ESTIMATED COST Rs **476000.00**


EARNEST MONEY : Rs **9520.00**

TIME LIMIT **One Month**

NAME OF WORK : Restoration of rain damage on various road under Rakh Sub-Division (For Mansoon)

SUB-HEAD : - Hiring of Tractor for shifting of material

Sl. No.	Description of work	Quantity		RATES		Unit	Amount
				Fig	Words		
1	Hiring charge of tractor for shifting of material un-dressed stone muck/debris Through mechanically from different reaches as per the direction Engineer in Charge with in all leads and lifts and other incidentals including all mechanical and operational charges. The rate including octroi, royalty, Malkhana, toll tax sale tax, GST or other taxes imposed by the Government. The rate including octroi, Malkhana, toll tax, GST or other taxes imposed by the Government.	680.00	Cubic metres	700.00	Rupees Seven Hundred Only	Per Cubic metres	476000.00
	Total:-						476000.00
	% Above below						
	Quoted Amount in Figures						
	Quoted Amount in Words						


Executive Engineer,
Bharmour Division,
HPPWD Bharmour

SCHEDULE OF QUANTITY

ESTIMATED COST : Rs 474000.00
EARNEST MONEY : Rs 9480.00
TIME LIMIT : One Month

NAME OF WORK : Restoration of rain damage Under Rakh Sub-Division (for Mansoon)

SUB-HEAD : - Hiring of Tipper for removal of slips at various Rd's

Sl. No.	Description of work	Quantity		RATES		Unit	Amount
				Fig	Words		
1	Hiring of Tipper 10Cum/18 tonne capacity for disposing and transporting of surplus excavated material and shifting of any type of construction material in all leads as per directions and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of owner of the machinery which shall have to be compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner at his own cost and repair & spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-charge. The rate including octroi, royalty, Malkana, toll tax sale tax, GST or other taxes imposed by the Government.	600.00	Hours	790.00	Rupees Seven Hundred Ninety Only	Per Hour	474000.00
		Total :-					474000.00
		%Above below					
		Quoted Amount in Figures					
		Quoted Amount in Words					


Executive Engineer,
Bharmour Division,
JPPWD Bharmour

SCHEDULE OF QUANTITY

ESTIMATED COST , Rs **498150.00**

EARNEST MONEY : Rs **9963.00**

TIME LIMIT **One Month**

NAME OF WORK : Restoration of rain Damages on various road under Garola Sub. Division (For Mansoon)

SUB-HEAD :- Hiring of JCB for removal of slips at various Rd's

Sl. No.	Description of work	Quantity		RATES		Unit	Amount
				Fig	Words		
1	Hiring of J.C.B./Excavator cum loader for cutting/ widening of road and removal of slips in all kind of soil and disposal of all excavated earth un-serviceable material from the road surface up to all height and depths as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/ private property or any incident etcetera happened during the course of hiring period / executing shall be the absolute responsibility of the J.C.B./Excavator owner, which shall to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	405.00	Hours	1230.00	Rupees One Thousand Two Hundred Thirty Only	Per Hour	498150.00
	Total :-						498150.00
	%Above below						
	Quoted Amount in Figures						
	Quoted Amount in Words						


Executive Engineer,
Bharmour Division,
HPPWD Bharmour

SCHEDULE OF QUANTITY

ESTIMATED COST : Rs 499380.00


EARNEST MONEY : Rs 9987.60

TIME LIMIT : One Month

NAME OF WORK : Restoration of rain Damages on various road under Garola Sub. Division (For Mansoon)

SUB-HEAD :- Hiring of JCB for removal of slips at various Rd's

Sl. No.	Description of work	Quantity		RATES		Unit	Amount
				Fig	Words		
1	Hiring of J.C.B./Excavator cum loader for cutting/ widening of road and removal of slips in all kind of soil and disposal of all excavated earth un-serviceable material from the road surface up to all height and depths as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/ private property or any incident etcetera happened during the course of hiring period / executing shall be the absolute responsibility of the J.C.B./Excavator owner, which shall to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	406.00	Hours	1230.00	Rupees One Thousand Two Hundred Thirty Only	Per Hour	499380.00
	Total :-						499380.00
	%Above below						
	Quoted Amount in Figures						
	Quoted Amount in Words						


Executive Engineer,
Bharmour Division,
HPPWD Bharmour

SCHEDULE OF QUANTITY

ESTIMATED COST : Rs 498150.00
EARNEST MONEY : Rs 9963.00
TIME LIMIT : One Month

NAME OF WORK : Restoration of rain Damages on various road under Garola Sub. Division (For Mansoon)

SUB-HEAD :- Hiring of JCB for removal of slips at various Rd's

SL. No.	Description of work	Quantity		RATES		Unit	Amount
				Fig	Words		
1	Hiring of J.C.B./Excavator cum loader for cutting/ widening of road and removal of slips in all kind of soil and disposal of all excavated earth un-serviceable material from the road surface up to all height and depths as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/ private property or any incident etcetera happened during the course of hiring period / executing shall be the absolute responsibility of the J.C.B./Excavator owner, which shall to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	405.00	Hours	1230.00	Rupees One Thousand Two Hundred Thirty Only	Per Hour	498150.00
	Total :-						498150.00
	%Above below						
	Quoted Amount in Figures						
	Quoted Amount in Words						


Executive Engineer,
Bharmour Division,
HPPWD Bharmour

SCHEDULE OF QUANTITY

ESTIMATED COST : Rs 476000.00
EARNEST MONEY : Rs 9520.00
TIME LIMIT : One Month

NAME OF WORK : Restoration of rain damage on various road under Garola Sub-Division (For Monsoon)

SUB-HEAD : - Hiring of Tractor for shifting of material

Sl. No.	Description of work	Quantity		RATES		Unit	Amount
				Fig	Words		
1	Hiring charge of tractor for shifting of material un-dressed stone muck/debris. Through mechanically from different reaches as per the direction Engineer in Charge with in all leads and lifts and other incidentals including all mechanical and operational charges The rate including octroi, royalty, Malkhana toll tax sale tax, GST or other taxes imposed by the Government. The rate including octroi, Malkhana toll tax, GST or other taxes imposed by the Government.	680.00	Cubic metres	700.00	Rupees Seven Hundred Only	Per Cubic metres	476000.00
Total:-							476000.00
%Above below							
Quoted Amount in Figures							
Quoted Amount in Words							


Executive Engineer,
Bharmour Division,
HPPWD Bharmour

SCHEDULE OF QUANTITY

ESTIMATED COST : Rs 474000.00

EARNEST MONEY : Rs 9480.00

TIME LIMIT : One Month

NAME OF WORK : Restoration of rain damage Under Garola Sub-Division (for Mansoon)

SUB-HEAD : - Hiring of Tipper for removal of slips at various Rd's

Sl. No.	Description of work	Quantity		RATES		Unit	Amount
				Fig	Words		
1	Hiring of Tipper 10Cum/18 tonne capacity for disposing and transporting of surplus excavated material and shifting of any type of construction material in all leads as per directions and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of owner of the machinery which shall have to be compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner at his own cost and repair & spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-charge. The rate including octroi, royalty, Malkana, toll tax sale tax, GST or other taxes imposed by the Government.	600.00	Hours	790.00	Rupees Seven Hundred Ninety Only	Per Hour	474000.00
Total :-							474000.00
% Above below							
Quoted Amount in Figures							
Quoted Amount in Words							


Executive Engineer,

Bharmour Division,

AIUPWD Bharmour

SCHEDULE OF QUANTITY

ESTIMATED COST : Rs 495690.00

EARNEST MONEY : Rs 9913.80

TIME LIMIT : One Month

NAME OF WORK : Restoration of rain Damages on various road under Garola Sub. Division (For Mansoon)

SUB-HEAD :- Hiring of JCB for removal of slips at various Rd's

Sl. No.	Description of work	Quantity		RATES		Unit	Amount
				Fig	Words		
1	Hiring of J.C.B./Excavator cum loader for cutting/ widening of road and removal of slips in all kind of soil and disposal of all excavated earth un-serviceable material from the road surface up to all height and depths as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/ private property or any incident etcetera happened during the course of hiring period / executing shall be the absolute responsibility of the J.C.B./Excavator owner, which shall to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	403.00	Hours	1230.00	Rupees One Thousand Two Hundred Thirty Only	Per Hour	495690.00
	Total :-						495690.00
	%Above below						
	Quoted Amount in Figures						
	Quoted Amount in Words						


Executive Engineer,
Bharmour Division,
HPPWD Bharmour


SCHEDULE OF QUANTITY

ESTIMATED COST : Rs 498150.00
EARNEST MONEY : Rs 9963.00
TIME LIMIT : One Month

NAME OF WORK : Restoration of rain Damages on various road under Bharmour Sub. Division

SUB-HEAD :- Hiring of JCB for removal of slips at various Rd's

Sl. No.	Description of work	Quantity		RATES		Unit	Amount
				Fig	Words		
1	Hiring of J.C.B/Excavator cum loader for cutting/ widening of road and removal of slips in all kind of soil and disposal of all excavated earth un-serviceable material from the road surface up to all height and depths as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/ private property or any incident etcetera happened during the course of hiring period / executing shall be the absolute responsibility of the J.C.B/Excavator owner, which shall to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	405.00	Hours	1230.00	Rupees One Thousand Two Hundred Thirty Only	Per Hour	498150.00
	Total :-						498150.00
	% Above below						
	Quoted Amount in Figures						
	Quoted Amount in Words						


Executive Engineer,
Bharmour Division,
HPPWD Bharmour

SCHEDULE OF QUANTITY

ESTIMATED COST	Rs	494460.00
EARNEST MONEY	Rs	9889.20
TIME LIMIT		One Month

NAME OF WORK : Restoration of rain Damages on various road under Bharmour Sub. Division (For Mansoon)

SUB-HEAD : - Hiring of JCB for removal of slips at various Rd's

Sl. No.	Description of work	Quantity		RATES		Unit	Amount
				Fig	Words		
1	Hiring of J.C.B./Excavator cum loader for cutting/ widening of road and removal of slips in all kind of soil and disposal of all excavated earth un-serviceable material from the road surface up to all height and depths as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/ private property or any incident etcetera happened during the course of hiring period / executing shall be the absolute responsibility of the J.C.B./Excavator owner, which shall to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	402.00	Hours	1230.00	Rupees One Thousand Two Hundred Thirty Only	Per Hour	494460.00
	Total :-						494460.00
	% Above below						
	Quoted Amount in Figures						
	Quoted Amount in Words						


Executive Engineer,
Bharmour Division,
HPPWD Bharmour

SCHEDULE OF QUANTITY

ESTIMATED COST : Rs 495690.00
EARNEST MONEY : Rs 9913.80
TIME LIMIT : One Month

NAME OF WORK : Restoration of rain Damages on various road under Bharmour Sub. Division (For Mansoon)

SUB-HEAD : - Hiring of JCB for removal of slips at various Rd's

Sl. No.	Description of work	Quantity		RATES		Unit	Amount
				Fig	Words		
1	Hiring of J.C.B./Excavator cum loader for cutting/ widening of road and removal of slips in all kind of soil and disposal of all excavated earth un-serviceable material from the road surface up to all height and depths as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/ private property or any incident etcetera happened during the course of hiring period / executing shall be the absolute responsibility of the J.C.B./Excavator owner, which shall to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	403.00	Hours	1230.00	Rupees One Thousand Two Hundred Thirty Only	Per Hour	495690.00
	Total :-						495690.00
	%Above below						
	Quoted Amount in Figures						
	Quoted Amount in Words						


Executive Engineer,
Bharmour Division,
HPPWD Bharmour

SCHEDULE OF QUANTITY

ESTIMATED COST : Rs 493230.00

EARNEST MONEY : Rs 9864.60

TIME LIMIT : One Month

NAME OF WORK : Restoration of rain Damages on various road under Bharmour Sub. Division (For Mansoon)

SUB-HEAD :- Hiring of JCB for removal of slips at various Rd's

Sl. No.	Description of work	Quantity		RATES		Unit	Amount
				Fig	Words		
1	Hiring of J.C.B./Excavator cum loader for cutting/ widening of road and removal of slips in all kind of soil and disposal of all excavated earth un-serviceable material from the road surface up to all height and depths as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/ private property or any incident etcetera happened during the course of hiring period / executing shall be the absolute responsibility of the J.C.B./Excavator owner, which shall to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	401.00	Hours	1230.00	Rupees One Thousand Two Hundred Thirty Only	Per Hour	493230.00
	Total :-						493230.00
	%Above below						
	Quoted Amount in Figures						
	Quoted Amount in Words						


Executive Engineer,
Bharmour Division,
HPPWD Bharmour

SCHEDULE OF QUANTITY

ESTIMATED COST : Rs 493230.00


EARNEST MONEY : Rs 9864.60

TIME LIMIT : One Month

NAME OF WORK : Restoration of rain Damages on various road under Bharmour Sub. Division (For Mansoon)

SUB-HEAD :- Hiring of JCB for removal of slips at various Rd's

Sl. No.	Description of work	Quantity		RATES		Unit	Amount
				Fig	Words		
1	Hiring of J.C.B./Excavator cum loader for cutting/ widening of road and removal of slips in all kind of soil and disposal of all excavated earth un-serviceable material from the road surface up to all height and depths as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/ private property or any incident etcetera happened during the course of hiring period / executing shall be the absolute responsibility of the J.C.B./Excavator owner, which shall to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	401.00	Hours	1230.00	Rupees One Thousand Two Hundred Thirty Only	Per Hour	493230.00
	Total :-						493230.00
	%Above below						
	Quoted Amount in Figures						
	Quoted Amount in Words						


Executive Engineer,

Bharmour Division,

HPPWD Bharmour

DRAFT SCHEDULE OF QUANTITY

ESTIMATED COST : Rs 498150.00

EARNEST MONEY : Rs 9963.00

TIME LIMIT : One Month

NAME OF WORK : Restoration of rain Damages on various road under Bharmour Sub. Division (For Mansoon)

SUB-HEAD :- Hiring of JCB for removal of slips at various Rd's

Sl. No.	Description of work	Quantity		RATES		Unit	Amount
				Fig	Words		
1	Hiring of J.C.B/Excavator cum loader for cutting/ widening of road and removal of slips in all kind of soil and disposal of all excavated earth un-serviceable material from the road surface up to all height and depths as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/ private property or any incident etcetera happened during the course of hiring period / executing shall be the absolute responsibility of the J.C.B/Excavator owner, which shall to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	405.00	Hours	1230.00	Rupees One Thousand Two Hundred Thirty Only	Per Hour	498150.00
	Total :-						498150.00
	%Above below						
	Quoted Amount in Figures						
	Quoted Amount in Words						


Executive Engineer,
Bharmour Division,
HPPWD Bharmour

DRAFT SCHEDULE OF QUANTITY

ESTIMATED COST Rs 448721.00
EARNEST MONEY Rs 8974.00
TIME LIMIT THREE MONTHS

NAME OF WORK : A/R & M/O on Nichli Kugti to Uper Kugti Road Km 0/00 to 2/00

SUB-HEAD :- C/o B/Wall at RD 0/575 to 0/582.50

Sl. No.	Description of work	Quantity		RATES		Unit	Amount
				Fig	Words		
1	Excavation in soil in Hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per Technical Specification Clause 16.1 (Soft rock) The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	40.73	Cubic metres	220.00	Rupees Two Hundred Twenty Only	Per cubic metre	8961.00
2	Excavation in earth work in all kinds of soil such as pick work jumper work blasting work (soft or hard rock) chess ling saturated soil upto all depths and disposal of all surplus material as directed by the Engineer-in-Charge including carriage of material within all leads and lift and as per the direction of the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	12.15	Cubic metres	350.10	Rupees Three Hundred Fifty And Paise Ten Only	Per cubic metre	4254.00
3	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical MORD specifications Clause 802, 803, 1202 & 1203 1.4.8 (One cement isto four sand isto eight graded/crushed stone aggregate 20mm (twenty five millimetres) nominal size) in road work as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	53.70	Cubic metres	6699.20	Rupees Six Thousand Six Hundred Ninety Nine And Paise Twenty Only	Per cubic metre	359747.00
4	Providing weep holes in brick/ stone / plain reinforced concrete abutment, wing wall, return walls with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1V: 20H towards drawing face complete as per drawing and technical specifications clauses 614, 709 and 1204.3.7 including carriage of material within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	45.00	Nos	380.00	Rupees Three Hundred Eighty Only	Each	17100.00
5	Providing and laying of boulder apron laid in wire crates with 4 mm (four millimetre) dia GI wire conforming to IS 280 and IS 4826 in 100 mm x 100 mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10 percent (ten percent) extra for laps and joints laid with stone boulders weighing not less than 40 kg (forty kilogramme) each as per drawing and MORD technical specifications section 1300 including carriage of material with in all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government.	23.37	Cubic metres	2510.00	Rupees Two Thousand Five Hundred Ten Only	Per cubic metre	58659.00
Total :-							448721.00
%Above below							
Quoted Amount in Figures							
Quoted Amount in Words							


Executive Engineer,
Bharmour Division,
HPPWD Bharmour

SCHEDULE OF QUANTITY

ESTIMATED COST	Rs	315986.00
EARNEST MONEY	Rs	6320.00
TIME LIMIT		THREE MONTHS

NAME OF WORK : A/R & M/O on Nichli Kugti to Uper Kugti road Km 0/00 to 2/00

SUB-HEAD : - C/o R/Wall at RD 0/476 to 0/481

Sl. No.	Description of work	Quantity		RATES		Unit	Amount
				Fig	Words		
1	Excavation in earth work in all kinds of soil such as pick work jumper work blasting work (soft or hard rock) chess ling saturated soling upto all depths and disposal of all surplus material as directed by the Engineer-in-Charge including carriage of material within all leads and lift and as per the direction of the Engineer-in-Charges. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	23.10	Cubic metres	350.10	Rupees Three Hundred Fifty And Paise Ten Only	Per cubic metre	8087.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical MORD specifications Clause 802, 803, 1202 & 1203 1.4.8 (One cement isto four sand isto eight graded/crushed stone aggregate 40mm (forty milimetres) nominal size) in road work as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	43.75	Cubic metres	6669.20	Rupees Six Thousand Six Hundred Sixty Nine And Paise Twenty Only	Per cubic metre	291778.00
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete in road structure as per drawing and MORD technical specifications clause 1604.7 and section 300 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.40	Nos	1150.10	Rupees One Thousand One Hundred Fifty And Paise Ten Only	Each	9661.00
4	Providing weep holes in brick stone / plain reinforced concrete abutment, wing wall, return walls with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1V: 20H towards drawing face complete as per drawing and technical specifications clauses 614, 709 and 1204 3.7 including carriage of material within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	17.00	Cubic metres	380.00	Rupees Three Hundred Eighty Only	Per cubic metre	6460.00
Total :-							315986.00
% Above below							
Quoted Amount in Figures							
Quoted Amount in Words							


Executive Engineer,
Bharmour Division,
HPPWD Bharmour

448175.00
8964.00
MONTHS

SCHEDULE OF QUANTITY

ESTIMATED COST Rs 315379.00
EARNEST MONEY Rs 6308.00
TIME LIMIT THREE MONTHS

NAME OF WORK : A/R & M/O on Nichli Kugti to Uper Kugti road Km 0/00 to 2/00
SUB-HEAD : - C/o R/Wall at RD 0/470 to 0/475

SL No.	Description of work	Quantity		RATES		Unit	Amount
				Fig	Words		
1	Excavation in earth work in all kinds of soil such as pick work jumper work blasting work (soft or hard rock) chess ling saturated soiling upto all depths and disposal of all surplus material as directed by the Engineer-in-Charge including carnage of material within all leads and lift and as per the direction of the Engineer-in-Charges. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	22.45	Cubic metres	350.10	Rupees Three Hundred Fifty And Paise Ten Only	Per cubic metre	7860.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical MORD specifications Clause 802, 803, 1202 & 1203 14.8 (One cement isto four sand isto eight graded/crushed stone aggregate 40mm (forty milimetres) nominal size) in road work as per the directions of the Engineer-in-Charge including carnage of materials within all leads, lifts. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	43.75	Cubic metres	6669.20	Rupees Six Thousand Six Hundred Sixty Nine And Paise Twenty Only	Per cubic metre	291778.00
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete in road structure as per drawing and M.O.R.D. technical specifications clause 1604.7 and section 300 and as per direction of Engineer - in- Charge including carnage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.40	Nos	1150.10	Rupees One Thousand One Hundred Fifty And Paise Ten Only	Each	9661.00
4	Providing weep holes in brick/ stone / plain reinforced concrete abutment, wing wall, return walls with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1V: 20H towards drawing face complete as per drawing and technical specifications clauses 614, 709 and 1204.3.7 including carnage of material within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	16.00	Cubic metres	380.00	Rupees Three Hundred Eighty Only	Per cubic metre	6080.00
Total :-							315379.00
%Above below							
Quoted Amount in Figures							
Quoted Amount in Words							

Executive Engineer,
Bharmour Division,
HPPWD Bharmour

SCHEDULE OF QUANTITY

ESTIMATED COST	Rs	448175.00
EARNEST MONEY	Rs	8964.00
TIME LIMIT		THREE MONTHS

NAME OF WORK : A/R & M/O on Nichli Kugti to Uper Kugti Road Km 0/00 to 2/00

SUB-HEAD : - C/o B/Wall at RD 0/583 to 0/590.50

Sl. No.	Description of work	Quantity		RATES		Unit	Amount
				Fig	Words		
1	Excavation in soil in Hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per Technical Specification Clause 16.1 (Soft rock) The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	38.25	Cubic metres	220.00	Rupees Two Hundred Twenty Only	Per cubic metre	8415.00
2	Excavation in earth work in all kinds of soil such as pick work jumper work blasting work (soft or hard rock) chess ling saturated soling upto all depths and disposal of all surplus material as directed by the Engineer-in-Charge including carriage of material within all leads and lift and as per the direction of the Engineer-in-Charges. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	12.15	Cubic metres	350.10	Rupees Three Hundred Fifty And Paise Ten Only	Per cubic metre	4254.00
3	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical MORD specifications Clause 802, 803, 1202 & 1203 1:4:8 (One cement isto four sand isto eight graded/crushed stone aggregate 20mm (twenty five millimetres) nominal size) in road work as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	53.70	Cubic metres	6699.20	Rupees Six Thousand Six Hundred Ninety Nine And Paise Twenty Only	Per cubic metre	359747.00
4	Providing weep holes in brick/ stone / plain reinforced concrete abutment, wing wall, return walls with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1V: 20H towards drawing face complete as per drawing and technical specifications clauses 614, 709 and 1204.3.7 including carriage of material within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	45.00	Nos	380.00	Rupees Three Hundred Eighty Only	Each	17100.00
5	Providing and laying of boulder apron laid in wire crates with 4 mm (four millimetre) dia GI wire conforming to IS 280 and IS 4826 in 100 mm x 100 mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10 percent (ten percent) extra for laps and joints laid with stone boulders weighing not less than 40 kg (forty kilogramme) each as per drawing and MORD technical specifications section 1300 including carriage of material with in all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government.	23.37	Cubic metres	2510.00	Rupees Two Thousand Five Hundred Ten Only	Per cubic metre	58659.00
Total :-							448175.00
%Above below							
Quoted Amount in Figures							
Quoted Amount in Words							


Executive Engineer,
Bharmour Division,
HPPWD Bharmour

SCHEDULE OF QUANTITY

ESTIMATED COST : Rs 276274.00
EARNEST MONEY : Rs 5525.00
TIME LIMIT : One Month

NAME OF WORK : Restoration of rain Damage on Galthan to massu road Km 0/00 to 4/500

SUB-HEAD : - Removal of slips & boulder at Various Rds

Sl. No.	Description of work	Quantity		RATES		Unit	Amount
				Fig	Words		
1	Removal of stand slide in hilly areas in ordinary rocks by mechanical means i.e. cutting (requiring blasting) and trimming of slope and disposal of excavated material upto all leads and lifts as per specification 302.3.5 and 1611 as per the direction of Engineer-in-Charge. The rate including octroi, Malkhana, toll tax, GST or other taxes imposed by the Government.	2631.18	Cubic metre	105.00	Rupees One Hundred Five Only	Per Cubic Metre	276274.00
Total :-							276274.00
%Above below							
Quoted Amount in Figures							
Quoted Amount in Words							


Executive Engineer,
Bharmour Division,
HPPWD Bharmour

SCHEDULE OF QUANTITY

ESTIMATED COST Rs 499845.00
EARNEST MONEY Rs 9997.00
TIME LIMIT **THREE MONTHS**

NAME OF WORK : C/o Batot to Almi road (Portion Batot to Gailu Kasrodi Km 0/00 to 2/500 (Under BASP)
SUB-HEAD : - C/o R/Wall from Rd 1/090 to 1/105

Sl. No.	Description of work	Quantity		RATES		Unit	Amount
				Fig	Words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and back filling in trenches with excavated suitable material. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	9.60	Cubic metres	276.14	Rupees Two Hundred Seventy Six And Paise Fourteen Only	Per cubic metre	2651.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical MORD specifications Clause 802, 803, 1202 & 1203 14.8 (One cement isto four sand isto eight graded/crushed stone aggregate 40mm (forty millimetres) nominal size) in road work as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	33.00	Cubic metres	5113.80	Rupees Five Thousand One Hundred Thirteen And Paise Eighty Only	Per cubic metre	168755.00
3	Random Rubble Masonry work in cement mortar 1:6 (one cement isto six sand) in foundation complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203 as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	45.48	Cubic metres	3298.60	Rupees Three Thousand Two Hundred Ninety Eight And Paise Sixty Only	Per cubic metre	150020.00
4	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	64.41	Cubic metres	1600.70	Rupees One Thousand Six Hundred And Paise Seventy Only	Per cubic metre	103101.00
5	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete in road structure as per drawing and MORD technical specifications clause 1604.7 and section 300 and as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	45.00	Cubic metres	1120.50	Rupees One Thousand One Hundred Twenty And Paise Fifty Only	Per cubic metre	50423.00
6	Steel reinforcement for R C C work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Mild steel and Medium Tensile steel bars. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	140.40	Kilogramme	96.80	Rupees Ninety Six And Paise Eighty Only	Per Kilogramme	13591.00

7	Construction of embankment with approved materials obtained from borrow pits with all leads and lifts, upto 150 m transporting to required slope and compacting to meet requirement of table 300.1 & 300.2 with lead upto 1000 m technical specification clause 501.5 with in all leads and lifts of materials and other incidentals, as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	120.00	Cubic metres	94.20	Rupees Ninety Four And Paise Twenty Only	Per cubic metre	11304.00
	Total :-						499845.00
	%Above below						
	Quoted Amount in Figures						
	Quoted Amount in Words						


 Executive Engineer,
 Bharmour Division,
 HPPWD Bharmour

SCHEDULE OF QUANTITY

ESTIMATED COST Rs 484939.00

EARNEST MONEY Rs 9699.00

TIME LIMIT THREE MONTHS

NAME OF WORK : C/o Batot to Almi road (Portion Batot to Gailu Kasrodi Km 0/00 to 2/500 (Under BASP)

SUB-HEAD : - C/o R/Wall from Rd 1/040 to 1/054 50

Sl. No.	Description of work	Quantity		RATES		Unit	Amount
				Fig	Words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and back filling in trenches with excavated suitable material. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	11.46	Cubic metres	276.14	Rupees Two Hundred Seventy Six And Paise Fourteen Only	Per cubic metre	3165.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 1.4.8 (One cement isto four sand isto eight graded/crushed stone aggregate 40mm (forty milimetres) nominal size) in road work as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	31.90	Cubic metres	5113.80	Rupees Five Thousand One Hundred Thirteen And Paise Eighty Only	Per cubic metre	163130.00
3	Random Rubble Masonry work in cement mortar 1:6 (one cement isto six sand) in foundation complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203 as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	44.64	Cubic metres	3298.60	Rupees Three Thousand Two Hundred Ninety Eight And Paise Sixty Only	Per cubic metre	147250.00
4	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	61.59	Cubic metres	1600.70	Rupees One Thousand Six Hundred And Paise Seventy Only	Per cubic metre	98587.00
5	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete in road structure as per drawing and M.O.R.D. technical specifications clause 1604.7 and section 300 and as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	43.50	Cubic metres	1120.50	Rupees One Thousand One Hundred Twenty And Paise Fifty Only	Per cubic metre	48742.00
6	Steel reinforcement for R.C.C work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Mild steel and Medium Tensile steel bars. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	135.72	Kilogramme	96.80	Rupees Ninety Six And Paise Eighty Only	Per Kilogramme	13138.00

7	Construction of embankment with approved materials obtained from borrow pits with all leads and lifts, upto 1.50 m transporting to required slope and compacting to meet requirement of table 300.1 & 300.2 with lead upto 1000 m technical specification clause 301.5 with in all leads and lifts of materials and other incidentals, as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	116.00	Cubic metres	94.20	Rupees Ninety Four And Paise Twenty Only	Per cubic metre	10927.00
	Total :-						484939.00
	% Above below						
	Quoted Amount in Figures						
	Quoted Amount in Words						


 Executive Engineer,
 Bharmour Division,
 HPPWD Bharmour

SCHEDULE OF QUANTITY

ESTIMATED COST : Rs 476000.00
 EARNEST MONEY : Rs 9520.00
 TIME LIMIT : One Month

NAME OF WORK : Restoration of rain damage on Kandi to Kuthed road Km 0/00 to 9/00

SUB-HEAD : - Hiring of Tipper for removal of slips at various Rd's

Sl. No.	Description of work	Quantity		RATES		Unit	Amount
		Fig	Words	Fig	Words		
1	Hiring of Tipper 10Cum/18 tonne capacity for disposing and transporting of surplus excavated material and shifting of any type of construction material in all leads as per directions and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of owner of the machinery which shall have to be compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner at his own cost and repair & spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-charge. The rate including octroi, royalty, Malkana, toll tax sale tax, GST or other taxes imposed by the Government.	560.00	Hours	850.00	Rupees Eight Hundred Fifty Only	Per Hour	476000.00
Total :-							476000.00
%Above below							
Quoted Amount in Figures							
Quoted Amount in Words							

(Signature)
 Executive Engineer,
 Bharmour Division,
 J.P.PWD Bharmour

SCHEDULE OF QUANTITY

ESTIMATED COST Rs 498779.00
 EARNEST MONEY Rs 9976.00
 TIME LIMIT THREE MONTHS

NAME OF WORK : Restoration of rain damage on Bharmour Badgram road Km 0/00 to 26/00

SUB-HEAD : - C/o R/Wall at RD 0/225 to 0/228.52

Sl. No.	Description of work	Quantity		RATES		Unit	Amount
				Fig	Words		
1	Excavation in earth work in all kinds of soil such as pick work jumper work blasting work (soft or hard rock) chess ling saturated soiling upto all depths and disposal of all surplus material as directed by the Engineer-in-Charge including carriage of material within all leads and lift and as per the direction of the Engineer-in-Charges. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	8.98	Cubic metres	350.10	Rupees Three Hundred Fifty And Paise Ten Only	Per cubic metre	3144.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical MORD specifications Clause 802, 803, 1202 & 1203 1:4:8 (One cement isto four sand isto eight graded/crushed stone aggregate 40mm (forty millimetres) nominal size) in road work as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	68.25	Cubic metres	6999.20	Rupees Six Thousand Nine Hundred Ninety Nine And Paise Twenty Only	Per cubic metre	477695.00
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete in road structure as per drawing and M.O.R.D technical specifications clause 1604.7 and section 300 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.66	Cubic metres	1150.10	Rupees One Thousand One Hundred Fifty And Paise Ten Only	Per cubic metre	9960.00
4	Providing weep holes in brick/ stone / plain reinforced concrete abutment, wing wall, return walls with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1V: 20H towards drawing face complete as per drawing and technical specifications clauses 614, 709 and 1204.3.7 including carriage of material within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	21.00	Nos	380.00	Rupees Three Hundred Eighty Only	Each	7980.00
Total :-							498779.00
%Above below							
Quoted Amount in Figures							
Quoted Amount in Words							

(Signature)
 Executive Engineer,
 Bharmour Division,
 HPPWD Bharmour

SCHEDULE OF QUANTITY

ESTIMATED COST Rs 498,399.00
EARNEST MONEY Rs 9968.00
TIME LIMIT THREE MONTHS

NAME OF WORK : Restoration of rain damage on Bharmour Badgram road Km 0/00 to 26/00
SUB-HEAD :- C/o R/Wall at RD 0/240 to 0/243.52

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Excavation in earth work in all kinds of soil such as pick work jumper work blasting work (soft or hard rock) chess ling saturated soling upto all depths and disposal of all surplus material as directed by the Engineer-in-Charge including carriage of material within all leads and lift and as per the direction of the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	8.98	Cubic metres	350 10 Rupees Three Hundred Fifty And Paise Ten Only	Per cubic metre	3144.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical MORD specifications Clause 802, 803, 1202 & 1203 1 & 8 (One cement isto four sand isto eight graded/crushed stone aggregate 40mm (forty millimetres) nominal size) in road work as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	68.25	Cubic metres	6999 20 Rupees Six Thousand Nine Hundred Ninety Nine And Paise Twenty Only	Per cubic metre	477695.00
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete in road structure as per drawing and MORD technical specifications clause 1604.7 and section 300 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.66	Cubic metres	1150 10 Rupees One Thousand One Hundred Fifty And Paise Ten Only	Per cubic metre	9960.00
4	Providing weep holes in brick/ stone / plain reinforced concrete abutment, wing wall, return walls with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1V: 20H towards drawing face complete as per drawing and technical specifications clauses 614, 709 and 1204 3.7 including carriage of material within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	20.00	Nos	380 00 Rupees Three Hundred Eighty Only	Each	7600.00
Total :-						498,399.00
% Above below						
Quoted Amount in Figures						
Quoted Amount in Words						

Executive Engineer,
Bharmour Division,
HPPWD Bharmour


SCHEDULE OF QUANTITY

ESTIMATED COST	Rs	498677.00
EARNEST MONEY	Rs	9973.54
TIME LIMIT		THREE MONTHS

NAME OF WORK : Restoration of Rain Damage on KSPA Road Km 13/00 to 40/00

SUB-HEAD : - C/o R/Wall at RD 18/070 to 18/075

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Excavation in earth work in all kinds of soil such as pick work jumper work blasting work (soft or hard rock) chese ling saturated soling unto all depths and disposal of all surplus material as directed by the Engineer-in-Charge including carriage of material within all leads and lift and as per the direction of the Engineer-in-Charges. The rate including octroi, royalty, Malkana, toll tax, GST, sale tax or other rexes imposed by the Government.	24.38	Cubic metres	350 10 Rupees Three Hundred Fifty And Paise Ten Only	Per cubic metre	8535 00
2	Providing and laying cement concrete 1:3:6 (1 cement four 3 and 6 graded crushed stone agg. 20 mm nominal size) and curing complete excluding cost of form work in R/wall B/wall etc with in all leads and lift and as per the direction of the Engineer-in-Charge. The rate including octroi, Malkhana, toll tax, GST or other taxes imposed by the Government.	53.40	Cubic metres	7450 00 Rupees Seven Thousand Four Hundred Fifty Only	Per cubic metre	397830 00
3	C/O Dry stone masonry in R/Wall and W/Wall and parapet etc. with in all leads and lift and as per the direction of the Engineer-in-Charge. The rate including octroi, Malkhana, toll tax, GST or other taxes imposed by the Government.	45.88	Cubic metres	1800 00 Rupees One Thousand Eight Hundred Only	Cubic metres	82584 00
4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia AC pipe extending through the full width of structure with slope of 1 (V): 20 (H) towards drawing face complete as per technical specification clause 614, 709, 1204 3.7 as per the direction of the Engineer-in-charge. The rate including octroi, royalty, Malkana, toll tax, GST, sale tax or other rexes imposed by the Government.	12.00	Nos	430 70 Rupees Four Hundred Thirty And Paise Seventy Only	Each	5168 00
5	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete in road structure as per drawing and M.O.R.D. technical specifications clause 1604.7 and section 300 and as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, GST, sale tax or other rexes imposed by the Government.	5.70	Cubic metres	800 00 Rupees Eight Hundred Only	Cubic metres	4560 00
Total :-						498677.00
% Above below						
Quoted Amount in Figures						
Quoted Amount in Words						


Executive Engineer,
Bharmour Division,
HPPWD Bharmour

SCHEDULE OF QUANTITY

ESTIMATED COST Rs 498677.00
 EARNEST MONEY Rs 9971.54
 TIME LIMIT THREE MONTHS

NAME OF WORK : Restoration of Rain Damage on KSPA Road Km 13/00 to 40/00
SUB-HEAD : - C/o R/Wall at RD 18/065 to 18/070

Sl. No.	Description of work	Quantity		RATES		Unit	Amount
				Fig	Words		
1	Excavation in earth work in all kinds of soil such as pick work jumper work blasting work (soft or hard rock) chess ling saturated soling unto all depths and disposal of all surplus material as directed by the Engineer-in-Charge including carriage of material within all leads and lift and as per the direction of the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	24.38	Cubic metres	350.10	Rupees Three Hundred Fifty And Paise Ten Only	Per cubic metre	8535.00
2	Providing and laying cement concrete 1:3:6 (1 cement four 3 and 6 graded crushed stone agg. 20 mm nominal size) and curing complete excluding cost of form work in R/Wall B/Wall etc with in all leads and lift and as per the direction of the Engineer-in-Charge. The rate including octroi, Malkana, toll tax, GST or other taxes imposed by the Government.	53.40	Cubic metres	7450.00	Rupees Seven Thousand Four Hundred Fifty Only	Per cubic metre	397830.00
3	C/O Dry stone masonry in R/Wall and W/Wall and parapet etc. with in all leads and lift and as per the direction of the Engineer-in-Charge. The rate including octroi, Malkana, toll tax, GST or other taxes imposed by the Government.	45.88	Cubic metres	1800.00	Rupees One Thousand Eight Hundred Only	Cubic metres	82584.00
4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia AC pipe extending through the full width of structure with slope of 1: (V) 20 (H) towards drawing face complete as per technical specification clause 614. 709, 1204 3.7 as per the direction of the Engineer-in-charge. The rate including octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	12.00	Nos	430.70	Rupees Four Hundred Thirty And Paise Seventy Only	Each	5168.00
5	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete in road structure as per drawing and M.O.R.D. technical specifications clause 1604.7 and section 300 and as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	5.70	Cubic metres	800.00	Rupees Eight Hundred Only	Cubic metres	4560.00
Total :-							498677.00
% Above below							
Quoted Amount in Figures							
Quoted Amount in Words							


 Executive Engineer,
 Bharmour Division,
 HPWD Bharmour