

NOTICE INVITING TENDER


Sealed percentage rate tenders on form 6 & 8 are invited by the Executive Engineer, Division, HP: PWD, Kangra on behalf of the Governor of Himachal Pradesh for the following work from the approved and eligible contractors/firms enlisted in HPPWD in the appropriate class for the work mentioned below on **15.07.2026 up to 11-00 A.M.** and will be opened on the same day at **11-30 A.M.** in the presence of intending contractors or their authorized representatives who may wish to be present. The tender forms can be obtained from this office on cash payment (non refundable) on **14.07.2026 up to 4.30 P.M.** The tender applications for issue of tender forms will be received in this office on **14.07.2026 up to 11.30 A.M.** The earnest money in shape FDR National Saving certificate/Saving Account/Time Deposit Account in any of the Post Office/National Bank in H.P. duly pledged in favour of Executive Engineer, HPPWD., Division, Kangra. The conditional tenders and the tenders received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 75 days.

Sr. No.	Name of work	Estimated cost	Earnest Money	Cost of tender form	Time Limit
1.	Special repair of HPPWD Rest House at Lunj(SH- C/O Septic Tank 20 users)	99797/-	2000/-	350/-	One Month
2.	Restoration of rain damages to GTLNS road km. 0/00 to 24/00(SH- C/O U-Shape drain from RD 24/600 to 24/638.50)	99368/-	2000/-	350/-	One Month
3.	Restoration of rain damages to GTLNS road km. 0/00 to 24/00(SH- C/O U-Shape drain from RD 24/640 to 24/678.50)	99368/-	2000/-	350/-	One Month
4.	Restoration of rain damages to GTLNS road km. 0/00 to 24/00(SH- C/O U-Shape drain from RD 24/680 to 24/703)	59207/-	1200/-	350/-	One Month
5.	Special Repair to HPPWD Rest House Building at Kangra Tehsil & Distt. Kangra(HP) (SH- Repair of wood work in Doors frames)	70377/-	1400/-	350/-	One Month
6.	Special Repair to existing building of Ayush Health and Wellness Centre (AHWC) at Purana Kangra Tehsil and Distt. Kangra(HP)(SH- Repair of G.I. Sheet Roofing)	77048/-	1550/-	350/-	One Month

Certified that tender of above works are being called of urgent nature in public interest.

TERMS & CONDITIONS:-

1. The contractors/firms should produce the attested copy of latest enlistment and renewal enlisted in HPPWD, GST No. and EPF No. with the application failing which their application will not be entertained.
2. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
3. The Earnest Money for the above works should be required at the time of sale of tender forms.
4. The contractor/firms should be quoted percentage rate in the tender both in figures and in words failing which tender is likely to be rejected.
5. The Executive Engineer reserves the right to accept/reject any tender/application or all tenders without assigning any reason


Executive Engineer,
HPPWD, Division, Kangra,
Distt. Kangra (H.P.)

(On behalf of Governor of Himachal Pradesh)


Dated:-

Endst:- No.PW/KD/CB/Tenders/2025-26-
Copy is forwarded to:-

3464-80

7/7/2026

1. The Computer Cell Office of the Chief Engineer (KZ),HPPWD., Dharamshala for uploading the NIT on the Department website.
2. The Superintending Engineer, 5th Circle, HPPWD., Palampur for information please.
3. All the Assistant Engineer's working under Kangra Division.
4. NIT Register.
5. All Head of Branches.
6. Notice Board.


Executive Engineer,
HPPWD, Division, Kangra,
Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

NAME OF WORK :-SPECIAL REPAIR OF HP.PWD REST HOUSE AT LUNJ (SH- CONSTRUCTION OF SEPTIC TANK 20 USERS)


Sr. No.	Description of work	Qty	Unit	Rates		AMOUNT
				In Figures	In Words	
				Time Limit:-		
						99797.00 2000.00 One Month
1	Excavation in foundation, trenches etcetra in earth work in all kind of classification of soil such as pick work, jumper work, pick jumper work, blasting work, soft and hard blasting and doing work in saturated soil, including chiselling or wedging out rocks where blasting work is prohibited or any other mixed variety of soil including shoring, strutting, de-watering and pumping or bailing out water (surface and sub soil water) upto any depths any quantum of water including slush which may arise during de-watering or removal of slush, lift upto any height stacking the excavated soil not more than 3 metres (Three metres) clear from the edge of excavation and then returning the stacked soil in 15cm (Fifteen centimetre) layers, when required into plinths, sides of foundation etcetra consolidating each deposited layer by ramming, watering and then disposing of all surplus excavated earth as per specification, approved drawing design as per the entire satisfaction and direction of the Engineer-in-Charge including carriage of material within leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, GST or any other taxes imposed by the Government.	30.04	Per Cubic metre	489.20	Rupees Four Hundred & Eighty Nine - Paise Twenty Only	14696.00
2	Providing form work with steel plates 3.15mm (Three decimal one five millimetre) thick welded with angle iron frame of 30x30x5mm., (Thirty into thirty into five millimetre) as to give a fair finish including centring, shuttering, strutting and propping etcetra with wooden battens and ballies complete upto all heights/ depth of propping and centering below supporting floor to ceiling for all height and removal of the same for insitu- reinforced concrete and plain concrete work in Flat surfaces such as soffits of suspended floors, roofs, landings and the like, as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, GST or any other taxes imposed by the Government.	5.25	per Square mtr	510.30	Rupees Five Hundred & Ten - Paise Thirty Only	2679.00
3	Providing form work with steel plates 3.15mm. (Three decimal one five millimetre) thick welded with angle iron frame of 30x30x5mm (Thirty millimetre into thirty millimetre into five millimetre) so as to give a fair finish including centering, shuttering, strutting and propping etcetra with wooden battens and ballies for all heights/depths of propping and centering below supporting floor to ceiling for all heights and removal of the same for in-situ reinforced concrete and plain concrete work in Edges of slab with slopping or stepped soffits excluding landing, as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, GST or any other taxes imposed by the Government.	10.80	per Running mtr	131.50	Rupees One Hundred & Thirty One - Paise Fifty Only	1420.00
4	providing and laying cement concrete 1:4:8 (One Cement isto four Sand isto eight graded crushed stone aggregate 40 mm (forty millimetre) nominal size mechanically mixed and curing complete excluding the cost of form work. in foundation and plinth, as per specifications, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, GST or any other taxes imposed by the Government.	0.89	Per Cubic metre	5474.55	Rupees Five Thousand Four Hundred & Seventy Four - Paise Fifty Five Only	4872.00

5	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand) : 3 graded stone aggregate (20 mm nominal size).	1.04	Per Cubic metre	7450.85	Rupees Seven Thousand Four Hundred & Fifty - Paise Eighty Five Only	7749.00
6	Providing and laying Tor steel of TATA/ SAIL/TISCO reinforcement for Reinforced cement concrete work including cutting, straightening, bending, binding and placing in position, including cost of binding wire complete for all floor level, as per specifications, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, GST or any other taxes imposed by the Government.	103.84	Per Kilogram	94.00	Rupees Ninety Four Only	9761.00
7	Random rubble masonry with hard stones of approved quality in foundation and plinth including raking out joints in cement mortar 1:6 (one cement is to six sand):12graded stone aggregate 20 mm nominal size in foundation and plinth) as per specifications, approved drawing, design, as per the entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, GST and all type of other taxes imposed by the Government.	6.05	Per Cubic metre	4950.00	Rupees Four Thousand Nine Hundred & Fifty Only	29948.00
8	Second class Brick masonry work in common burnt clay building bricks in super structure above plinth level to floor any level in cement mortar 1:6 (One Cement is to Six Sand), as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, GST or any other taxes imposed by the Government.	1.91	Per Cubic metre	7954.05	Rupees Seven Thousand Nine Hundred & Fifty Four - Paise Five Only	15192.00
9	Boulder filling dry hand packed tightly as in under floor The rate is inclusive for carriage of materials within all leads, lifts and other incidentals. as per the direction of the Engineer -in-Charge including carriage of material with in all leads, lifts and other incidentals. The rate including of octroi, royalty, Malikhana, toll tax, GST or other taxes imposed by the government.	1.62	Per Cubic metre	1428.00	Rupees One Thousand Four Hundred & Twenty Eight Only	2313.00
10	15 mm (Fifteen millimetre) thick cement plaster in single coat on fair side of brick/concrete/stone walls for interior plastering up to all floor level including arises, internal angles, chamfers and rounded angles any girth and finished even and smooth with cement mortar 1:6 (One cement is to Six sand), as per specifications, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, GST or any other taxes imposed by the Government.	17.60	per Square mtr	242.30	Rupees Two Hundred & Forty Two - Paise Thirty Only	4264.00
11	Providing and fixing in position pre-cast R.C.C. manhole cover and frame of required shape and approved quality rectangular shape 600x450mm internal dimensions complete as per specifications, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, GST or any other taxes imposed by the Government.	2.00	Each	980.00	Rupees Nine Hundred & Eighty Only	1960.00
12	Providing and fixing in trenches high pressure 110 mm (one hundred Ten millimetre) diameter conforming to BS NO.13592-92 (Thirteen thousand five hundred ninety two Ninety two) PVC (Poly Vinyl Chloride) Diplast pipe class B soil, waste and ventilating pipes fixing with adhesive mixture complete of supreme/Kishan/Astral/Finolex. as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, GST or any other taxes imposed by the Government.	5.00	per Running mtr	341.70	Rupees Three Hundred & Forty One - Paise Seventy Only	1709.00

13	Providing and fixing in trenches high pressure 150 mm (one hundred Fifty millimetre) diameter conforming to BS NO.13592-92 (Thirteen thousand five hundred ninety two Ninety two) PVC (Poly Vinyl Chloride) Diplost pipe class B soil , waste and venting pipes fixing with adhesive mixture complete of supreme/Kishan/Astral/Finolex. as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, GST or any other taxes imposed by the Government.	5.00	per Running mtr	437.65	Rupees Four Hundred & Thirty Seven - Paise Sixty Five Only	2188.00
14	Providing and fixing of PVC of supreme/Kishan/Astral/Finolex.s.c./c.i span fitting and accessories single equal branches of required degree plain 110 mm dia as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, GST or any other taxes imposed by the Government.	2.00	Nos	435.00	Rupees Four Hundred & Thirty Five Only	870.00
15	Providing and fixing PVC of supreme/Kishan/Astral/Finolex.cowl 110 mm nominal diameter as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, GST or any other taxes imposed by the Government.	1.00	No	176.00	Rupees One Hundred & Seventy Six Only	176.00
Total:						99797.00

EXCESS = _____ %

LESS = _____ %



 Executive Engineer,
 HPPWD Kangra
 Division Kangra.

SCHEDULE OF QUANTITY

NAME OF WORK:- RESTORATION OF RAIN DAMAGE TO GAGGAL TIARA LUNJ NAGROTA SURIAN ROAD KM. 0/00 TO 24/00(SUB HEAD:- CONSTRUCTION OF U-SHAPE DRAIN FROM RD 24/600 TO 24/638.50)		Estimated Cost:- Earnest Money:- Time Limit:-	99368.00 2000.00 One Month			
Sr. No.	Description of work	Qty	Unit	Rates		AMOUNT
				In Figures	In Words	
1	Earthwork in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks(where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- in-Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials up to any lead and up to any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) up to any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer -in charge including carriage of materials with in all leads and lifts and other incidental.The rate including of octroi, malikhana, tolltax, sale Tax or other taxes imposed by the government.	12.13	Per Cubic meters	489.20	Rupees Four Hundred & Eighty Nine - Paise Twenty Only	5934.00
2	Providing & laying mechanically mixed and vibrated for plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-Ten) nominal mix.1:3:6 (one cement: three sand: six graded crushed stone aggregate) 40mm(forty millimetre) nominal size with minimum cement contents 220 kg/cum (two hundred twenty kilogram per cubic metre) in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including the cost of form work as per drawings and MORD technical specifications section 800, 900, and 1200 as per the direction of the Engineer -in-Charge including carriage of material with in all leads, lifts and other incidental.The rate including of octroi, royalty, Malikhana, toll tax, GST or other taxes imposed by the government.	16.35	Per Cubic meters	5714.60	Rupees Five Thousand Seven Hundred & Fourteen - Paise Sixty Only	93434.00
Total:						99368.00

EXCESS = _____ %

LESS = _____ %


 EXECUTIVE ENGINEER
 KANGRA DIVISION
 HP.PWD KANGRA


2

SCHEDULE OF QUANTITY

NAME OF WORK:- RESTORATION OF RAIN DAMAGES TO GAGGAL TIARA LUNJ NAGROTA SURIAN ROAD KM. 0/00 TO 24/00(SUB HEAD:- CONSTRUCTION OF U-SHAPE DRAIN FROM RD 24/6-40 TO 24/678.50)		Estimated Cost:- Earnest Money:- Time Limit:-		99368.00 2000.00 One Month		
Sr. No.	Description of work	Qty	Unit	Rates		AMOUNT
				In Figures	In Words	
1	Earthwork in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks(where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer-in-Charge, including setting out, construction of shorting and bracing, removal of stumps and other deleterious materials and disposal of materials up to any lead and up to any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) up to any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-charge including carriage of materials with in all leads and lifts and other incidental.The rate including of octroi, malikhana, tolltax, sale Tax or other texes imposed by the government.	12.13	Per Cubic meters	489.20	Rupees Four Hundred & Eighty Nine - Paise Twenty Only	5934.00
2	Providing & laying mechanically mixed and vibrated for plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-Ten) nominal mix.1:3:6 (one cement: three sand: six graded crushed stone aggregate) 40mm(forty millimetre) nominal size with minimum cement contents 220 kg/cum (two hundred twenty kilogram per cubic metre) in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including the cost of form work as per drawings and MORD technical specifications section 800, 900, and 1200 as per the direction of the Engineer -in-Charge including carriage of material with in all leads, lifts and other incidental.The rate including of octroi,royalty,Malkhana, toll tax, GST or other taxes imposed by the government.	16.35	Per Cubic meters	5714.60	Rupees Five Thousand Seven Hundred & Fourteen - Paise Sixty Only	93434.00
Total:						99368.00

EXCESS = _____ %

LESS = _____ %


 EXECUTIVE ENGINEER
 KANGRA DIVISION
 HP PWD KANGRA

4

SCHEDULE OF QUANTITY

NAME OF WORK:- RESTORATION OF RAIN DAMAGE TO GAGGAL TIARA LUNJ NAGROTA SURIAN ROAD KM. 0/00 TO 24/00(SUB HEAD:- CONSTRUCTION OF U-SHAPE DRAIN FROM RD 24/680 TO 24/703)

Estimated Cost:- 59207.00
 Earnest Money:- 1200.00
 Time Limit:- One Month

Sr. No.	Description of work	Qty	Unit	Rates		AMOUNT
				In Figures	In Words	
1	Earthwork in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks(where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- in -Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials up to any lead and up to any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) up to any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer -in charge including carriage of materials with in all leads and lifts and other incidental.The rate including of octroi, malikhana, tolltax, sale Tax or other taxes imposed by the government.	7.25	Per Cubic metere	489.20	Rupees Four Hundred & Eighty Nine - Paise Twenty Only	3547.00
2	Providing & laying mechanically mixed and vibrated for plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-Ten) nominal mix.1:3:6 (one cement: three sand: six graded crushed stone aggregate) 40mm(forty millimetre) nominal size with minimum cement contents 220 kg/cum (two hundred twenty kilogram per cubic metre) in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including the cost of form work as per drawings and MORD technical specifications section 800, 900, and 1200 as per the direction of the Engineer -in-Charge including carriage of material with in all leads, lifts and other incidental.The rate including of octroi, royalty, Malikhana, toll tax, GST or other taxes imposed by the government.	9.74	Per Cubic metere	5714.60	Rupees Five Thousand Seven Hundred & Fourteen - Paise Sixty Only	55660.00
Total:						59207.00

EXCESS = %

LESS = %

EXECUTIVE ENGINEER
 KANGRA DIVISION
 H.P.W.D KANGRA.


SCHEDULE OF QUANTITY

Sr. No.		Description of work	Qty	Unit	Rates		Estimated Cost:- Earnest Money:- Time Limit:-	AMOUNT
					In Figures	In Words		
		NAME OF WORK :-SPECIAL REPAIR TO HP PWD REST HOUSE BUILDING AT KANGRA TEHSIL AND DISTRICT KANGRA(H.P)/SH:- REPAIR OF WOOD WORK IN DOORS FRAMES)						
1		Dismantling doors, windows and clerestory windows, ventilators etc. (wood or steel) shutters including chowkhats, architraves, hold fasts and other attachments etc. complete and stacking them within 20 metres lead. Of area 3 sq. metres and below as per specifications, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, GST or any other taxes imposed by the Government.	1.00	Each	215.00	Rupees Two Hundred & Fifteen Only	70377.00 1400.00	215.00
2		Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately). Sal wood as per specifications, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, GST or any other taxes imposed by the Government.	0.05	per Cubic Metre	2608.70	Rupees Two Thousand Six Hundred & Eight - Paise Seventy Only		130.00
3		Taking out existing wooden door shutter, repair by cutting, painting etc. and refixing of repaired doors/shutters to existing door frames, including replacement of hinges with screws, etc. as required, all complete as per specifications, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, GST or any other taxes imposed by the Government.	1.00	Each	218.50	Rupees Two Hundred & Eighteen - Paise Fifty Only		219.00
4		Providing and fixing factory made uPVC door frame made of uPVC extruded sections having an overall dimension as below (tolerance ± 1 mm), with wall thickness 2.0 mm (± 0.2 mm), corners of the door frame to be jointed with galvanized brackets and stainless steel screws, joints mitred and Plastic welded. The hinge side vertical of the frames reinforced by galvanized M.S. tube of size 19 X 19 mm and 1mm (± 0.1 mm) wall thickness and 3 nos. stainless steel hinges fixed to the frame complete as per manufacturer's specification and direction of Engineer-in-charge.Extruded section profile size 42x50 mm complete as per specifications, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, GST or any other taxes imposed by the Government.	10.10	per Running Metre	433.85	Rupees Four Hundred & Thirty Three - Paise Eighty Five Only		4382.00

5	<p>Providing and fixing to existing door frames, 24 mm thick factory made PVC door shutters made of styles and rails of a uPVC hollow section of size 59x24 mm and wall thickness 2 mm (± 0.2 mm) with inbuilt edging on both sides. The styles and rails mitred and joint at the corners by means of M.S. galvanised/ plastic brackets of size 75x220 mm having wall thickness 1.0 mm and stainless steel screws. The styles of the shutter reinforced by inserting galvanised M.S. tube of size 20x20 mm and 1 mm (± 0.1 mm) wall thickness. The lock rail made up of 'H' section, a uPVC hollow section of size 100x24 mm and 2 mm (± 0.2 mm) wall thickness, fixed to the shutter styles by means of plastic/galvanised M.S. 'U' cleats. The shutter frame filled with a uPVC multichambered single panel of size not less than 620 mm, having over all thickness of 20 mm and 1 mm (± 0.1 mm) wall thickness. The panels filled vertically and tie bar at two places by inserting horizontally 6 mm galvanised M.S. rod and fastened with nuts and washers, complete (for W.C. and bathroom door shutter), as per specifications, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, GST or any other taxes imposed by the Government.</p>	1.79 ✓	per Square Metre	1730.50 M. R.	Rupees One Thousand Seven Hundred & Thirty - Paise Fifty Only	3098.00 ✓
6	<p>Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately). Sal wood, as per specifications, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, GST or any other taxes imposed by the Government.</p>	0.02 ✓	per Cubic Metre	101763.05 M. R.	Rupees One Lakh One Thousand Seven Hundred & Sixty Three - Paise Five Only	2035.00 ✓
7	<p>Providing, supplying, transporting, and fixing a wooden table of overall size 1.20 m (L) x 0.75 m (W) x 0.45 m (H), fabricated from good quality seasoned hardwood/approved timber, complete with sturdy frame and top, finished with approved polish. The table shall be provided with a 6 mm thick decorative glass top, machine-cut to size with well-polished edges, fixed/placed as approved. The item shall include termite/moisture treatment, all necessary fittings, hardware, labour, transportation, and installation, complete in all respects as per approved drawings, specifications, and direction of the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, GST or any other taxes imposed by the Government.</p>	1.00 ✓	Each	23010.00 M. R.	Rupees Twenty Three Thousand & Ten Only	23010.00 ✓

7

8	Providing, supplying, transporting, and fixing a computer table of overall size 0.90 m (L) x 0.60 m (W) x 0.75 m (H), fabricated from good quality termite-resistant wood/engineered wood, complete with two storage racks, one of which shall be provided with a locking arrangement. The table shall be finished with approved decorative laminate on all exposed surfaces and shall be supplied along with one matching chair of approved design, size, and quality. The item shall include all necessary fittings, hardware, labour, transportation, and installation, complete in all respects as per approved drawings, specifications, and direction of the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malikhana, toll tax, GST or any other taxes imposed by the Government. The rate is inclusive of octroi, royalty, malikhana, toll tax, GST or any other taxes imposed by the Government.	1.00	Each	10030.00 M.R.	Rupees Ten Thousand & Thirty Only	10030.00
9	Providing, supplying, transporting, and fixing a bedside/nightstand table of overall size 0.40 m (L) x 0.35 m (W) x 0.45 m (H), fabricated from good quality termite-resistant wood/engineered wood, complete with two storage compartment/drawer as per approved design and finished with approved decorative laminate on all exposed surfaces. The item shall include all necessary fittings, hardware, labour, transportation, and installation, complete in all respects as per approved drawings, specifications, and direction of the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malikhana, toll tax, GST or any other taxes imposed by the Government.	1.00	Each	5310.00 M.R.	Rupees Five Thousand Three Hundred & Ten Only	5310.00
10	Providing, supplying, transporting, and placing premium-quality Orthocare mattresses of 150 mm thickness, each mattress manufactured with luxurious craftsmanship and designed to provide superior orthopedic support and sleeping comfort. The mattresses shall be made of high-quality materials with durable quilted fabric covering, adequate cushioning layers, and anti-sag construction, complete with all accessories, handling, transportation, unloading, and placement at site, in all respects, as per approved specifications and the directions of the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malikhana, toll tax, GST or any other taxes imposed by the Government.	1.00	Each	21948.00 M.R.	Rupees Twenty One Thousand Nine Hundred & Fourty Eight Only	21948.00
Total:						70377.00


Executive Engineer,
HPPWD Kangra
Division Kangra.

EXCESS = %


LESS = %

SCHEDULE OF QUANTITY

NAME OF WORK :-SPECIAL REPAIR TO EXISTING BUILDING OF AYUSH HEALTH AND WELLNESS CENTRE(AHWC) AT PURANA KANGRA TEHSIL AND DISTT KANGRA H.P.(SUB HEAD:- REPAIR OF G.I SHEET ROOFING)		Estimated Cost:- Earnest Money:- Time Limit:-		77048.00 1550.00 One Month	
Sr. No.	Description of work	Qty	Unit	Rates	
				In	In Words
1	Dismantling roofing including ridges,hips, valleys, gutters etc. stacking 5th serviceable materials and disposals of un-serviceable materials within 20 metres lead of G.I. sheet. as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, GST or any other taxes imposed by the Government.	41.64	per Square Metre	96.45	Rupees Ninety Six - Paise Fourty Five Only
2	Providing corrugated G.I sheet roofing fixed with galvanised iron J or L hooks bolts and nuts 8m diameter with bitumen and G.I limpet washers filled with white lead complete excluding the cost of purlins rafters and trusses. And including cutting to size and shape wherever required 0.63 mm thick with Zinc coating not less than 275gms/m ² as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, GST or any other taxes imposed by the Government.	44.83	per Square Metre	900.70	Rupees Nine Hundred - Paise Seventy Only
3	Providing ridge or hips 60cm overall in plain G.I sheet with galvanised iron J or L hooks bolts and nuts 8mm dia limpet and bitumen washer complete 0.63 mm thick with zinc coating not less than 275gms/m ² as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, GST or any other taxes imposed by the Government.	2.90	Per Running metre	621.00	Rupees Six Hundred & Twenty One Only
4	Steel work welded in built up sections of Tata in Trusses and trussed purlins in building, in beams joists channels, angles, tee-flats with connecting plates or angle cleats as in main and cross beams, hip and jack rafters, purlins connected to common rafters and the like. position and applying coat of approved steel primer using structural steel etc. as required and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malikana, toll tax, GST or other taxes imposed by the Government.	277.83	per kilo gram	111.05	Rupees One Hundred & Eleven - Paise Five Only
		Total:			77048.00

EXCESS = %

LESS = %


 Executive Engineer,
 Kangra Division
 HP.PWD.Kangra