



**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

Telephone No:-01782-240075  
e-mail:-ee-kum-hp@nic.in

No. PW-KMS-AB-NIT/2026-27- 2391-93

Dated: - 04/07/2026

To


✓  
The Executive Engineer (IT Cell),  
HP, PWD, Nirman Bhawan,  
Nigam Vihar Shimla-2

Subject: -

**Publication of Tender Notice**

Enclosed please find herewith the tender of works as given in the Notice Inviting tender for uploading on department website as per notification Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW(B)1/2020 dated 16.07.2021 as the works mentioned in the tender notice are urgent in nature and public instrest.

**Encl: - Notice Inviting tender &  
Schedule of Quantity and certificate.**

  
Executive Engineer,  
Kumarsain Division,  
HPPWD Kumarsain


Copy to the Supertntending Engineer, 11th Circle,  
HP.PWD., Rampur Bsr. for information please.

Copy to Drawing Branch in this office.

→  
Executive Engineer,  
Kumarsain Division,  
HPPWD Kumarsain

## CERTIFICATE

CERTIFIED THAT THE TENDERS OF WORKS, AS CALLED VIDE THIS OFFICE LETTER NO. PW-KMS-AB-NIT/ 2026-27-2340-90 DATED 04-07-2026 ARE URGENT NATURE AND PUBLIC INTEREST.

  
Executive Engineer,  
Kumarsain Division,  
HPPWD Kumarsain

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

**"NOTICE INVITING TENDER"**

Sealed item/percentage rate tenders are hereby invited by the Executive Engineer, Kumarsain Division, and HP.PWD. Kumarsain from the experienced contractors enlisted with PWD for B&R works, so as to reach in this office on or before **14.07.2026** up to **10:30 AM** and will be opened on same day at **11:00 AM**. in the presence of intending contractors or their authorized representatives who may wish to be present.


The application for issue of tender form shall be received on **13.07.2026** up to **1.00 PM**. The tender form can be had from his office against cash payment (Non-refundable) on **13.07.2026** upto **5.00 PM**.

The earnest money in the shape of National saving certificate/Time deposit receipt of any recognized Bank in H.P. duly pledged in the name of XEN must accompany with each application for obtaining the tender form. The Executive Engineer reserves the right to reject the tenders without assigning any reasons.

- 1. Name of work:** R/O R/D on link road to lower Jarol Km.0/000 to 2/400(SH:-C/O RR Masonry Retaining Wall at Rd.1/050 to 1/065, 1/067 to 1/081.40 and 1/081.50 to 1/087.15). Estimated Cost:-4,82,991/- Earnest Money: 9,700/- Time allowed: -One Month.
- 2. Name of work:** R/O R/D on link road from Kachoti Khad to Odi Nalla Km.0/000 to 2/453(SH:-Removal of slips between Rd.0/000 to 1/630). Estimated Cost:-4,99,309/- Earnest Money: 10,000/- Time allowed: -One Month.
- 3. Name of work:** R/O R/D on link road from Kuhal to Dildhar Km.0/000 to 1/135(SH:-C/O R.R. Masonry R/Wall at Rd.0/019 to 0/026). Estimated Cost:-4,98,630 Earnest Money: 10,000/- Time allowed: -One Month.
- 4. Name of work:** R/O R/D on link road from Kuhal to Dildhar Km.0/000 to 1/135(SH:-C/O R.R. Masonry R/Wall at Rd.0/011 to 0/018.50). Estimated Cost:-4,83,929/- Earnest Money: 9,700/- Time allowed: -One Month.
- 5. Name of work:** R/O R/D on link road from Kachoti Khad to Odi Nalla Km.0/000 to 2/453(SH:-Removal of slips between Rd.1/630 to 2/350). Estimated Cost:-2,89,089/- Earnest Money: 5,800/- Time allowed: -One Month.
- 6. Name of work:-**R/O R/D on link road to village Challan Km.0/000 to 1/180 (SH:- C/O PCC B/Wall at Rd.1/120 to 1/145.90).Estimated Cost:-4,97,766/- Earnest Money: 10000/- Time allowed: -One Month.
- 7. Name of work:-**R/O R/D on link road to Lower Jarol Km.0/000 to 2/400 (under PDNA) (SH:- C/O PCC V-Shape Side Drain in Km.0/000 to 1/000).Estimated Cost:-4,38,350/- Earnest Money: 8800/- Time allowed: -One Month.
- 8. Name of Work:-**R/O R/D on link road to village Shalota Km.0/000 to 3/000 (SH:- C/O PCC B/Wall at Rd.1/735 to 1/750).Estimated Cost:-1,95,967/- Earnest Money: 4,000/- Time allowed: -One Month.
- 9. Name of work:** (i) R/O R/D on Thanedhar Bhutti Banot Nallah road Km.0/000 to 9/375 (under PDNA) (SH: Removal of slips at Rd.2/900 to 2/990 & 3/930 to 4/000) (ii) R/O R/D on Lauga Badubagain Changadhar Dadesh Banot Nallah road Km.0/000 to 6/970 (under PDNA) (SH:- Removal of slips at Rd.0/120 to 0/200 & 2/030 to 2/090).Estimated Cost:-4,77,819/- Earnest Money: 9600/- Time allowed: -One Month.
- 10. Name of work:-**R/O R/D on Kumarsain Sharambal Camp road Km.0/000 to 2/400 (under PDNA)(SH:- C/O PCC V-Shape Side Drain at various Rds 0/120 to 0/390, 0/600 to 0/900, 1/200 to 1/360 & 1/800 to 2/200).Estimated Cost:-4,95,053/- Earnest Money: 9950/- Time allowed: -One Month.

**Terms and conditions:-**


1. The contractors shall produce their latest registration/renewal of their registration/GST No/EPF No./ PAN No. along with their application.
2. The single/conditional tender will be rejected.
3. The offer shall remain valid up to 75 days.
4. The amount should be within the 5% above.
5. The work should be started within fifteen days from the opening of tender.

  
Executive Engineer,  
Kumarsain Division  
HP.PWD, Kumarsain

No.PW-KMS-AB-N.I.T/2026-27- 2340-90

Dated:- 04/07/2026

Copy to the Engineer-in-Chief, HP.PWD., Shimla-2.  
Copy to the Deputy Commissioner Shimla, District Shimla (H.P)  
Copy to the Sub-Divisional Officer © Kumarsain, Distt. Shimla (H.P.)  
Copy to the Superintending Engineer, XIth Circle, HP.PWD., Rampur.  
Copy to Block Development office, Narkanda Distt. Shimla, (H.P.)  
Copy to all Assistant Engineers under this Division for information & n.a.  
Copy to various contractors for information.  
Copy to Notice Board of this office.

  
Executive Engineer,  
Kumarsain Division,  
HP.PWD. Kumarsain

6

**DRAFT SCHEDULE OF QUANTITY**

**Estimated cost:-Rs.482991/-**

**Earnest money:-Rs.9700/-**

**Time allowed:-One month.**

**Name of work:- Restoration of rain damages on link road to village Lower Jarol Km.0/000 to 2/400 (SH:-Construction of R.R. Masonry Retaining wall at RD.1/050 to 1/065 ,1/067 to 1/081.40 and 1/081.50 to 1/087.15).(PDNA)**

S. No.	Sub-Head/Items of work.	Quantity.	Rate.		Unit.	Amount.
			In fig.	In words.		
1	Excavation in soil in hill area by manual means/mechanical means including cutting and trimming of side slope and disposing of excavated earth with in all leads and lifts as per drawing and technical specification clause 1603.10 as per direction of the Engineer-in-charge.	21.38 m3	180.00	(Rupees one hundred eighty only).	Per cubic metre.	3848.00
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom backfilling in trenches with excavated suitable materials upto all leads and lifts as per directions of the Engineer-in-Charge.	35.75 m3	250.00	(Rupees two hundred fifty only).	Per cubic metre.	8938.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 P.C.C nominal mix 1:6:12(40mm aggregate) including entire carriage of materials in all leads and lifts.	12.62 m3	4300.00	(Rupees four thousand three hundred only).	Per cubic metre.	54266.00
4	Stone masonry in cement mortar for substructure complete as per drawing & technical specification Clauses 702,704,1202 and 1203 Random rubble masonry in cement mortar 1:6 including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	94.64 m3	4300.00	(Rupees four thousand three hundred only).	Per cubic metre.	406952.00
5	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8 Granular material including entire carriage of materials in all leads and lifts as per direction of the Engineer-in-Charge.	9.46 m3	950.00	(Rupees nine hundred fifty only).	Per cubic metre.	8987.00
<b>Total:-</b>						<b>482991.00</b>

**Draft schedule of quantity approved for  
Rs. 4,82,991/- only**

Executive Engineer,  
Kumarsain Division,  
H.P.PWD., Kumarsain.

(14)

**DRAFT SCHEDULE OF QUANTITY**

Estimated cost:-Rs.499309/-


Earnest money:-Rs.10000/-

Time allowed:-One Month.

Name of work:-Restoration of rain damages on link road Kachoti Khud to Odi Nalla Km.0/000 to 2/453 (SH:- Removal of slips between at RD. 0/000 to 1/630).

S. No	Sub-Head/Items of work.	Quantity.	Rate.(Including GST)		Unit.	Amount.
			In fig.	in words.		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 1611 including entire carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	3994.47 m <sup>3</sup>	125.00	(Rupees one hundred twenty five only).	Per cubic metre.	499309.00
	<b>Total:-</b>					<b>499309.00</b>

Draft schedule of quantity approved for  
~~Rs. 4,99,309/-~~ only

  
Executive Engineer,  
Kumarsain Division,  
HP.PWD., Kumarsain.

DRAFT SCHEDULE OF QUANTITY

Estimated cost:-Rs.498630/-

Earnest money:-Rs.10000/-

Time allowed:-One month.

Name of work:- Restoration of rain damages on link road Kulpit to Doldhar Km.0/000 to 1/135 (SH:-Construction of R.R. Masonry Retaining wall at RD. 0/019 to 0/026).

S. No.	Sub-Head/Items of work.	Quantity.	Rate.		Unit.	Amount.
			In fig.	In words.		
1	Excavation in soil in hill area by manual means/mechanical means including cutting and trimming of side slope and disposing of excavated earth with in all leads and lifts as per drawing and technical specification clause 1603.10 as per direction of the Engineer-in-charge.	18.62 m3	180.00	(Rupees one hundred eighty only).	Per cubic metre.	3352.00
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom backfilling in trenches with excavated suitable materials upto all leads and lifts as per directions of the Engineer-in-Charge.	51.52 m3	250.00	(Rupees two hundred fifty only).	Per cubic metre.	12880.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 P.C.C nominal mix 1:6:12(40mm aggregate) including entire carriage of materials in all leads and lifts.	6.72 m3	4300.00	(Rupees four thousand three hundred only).	Per cubic metre.	28896.00
4	Stone masonry in cement mortar for substructure complete as per drawing & technical specification Clauses 702,704,1202 and 1203 Random rubble masonry in cement mortar 1:6 including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	103.95 m3	4300.00	(Rupees four thousand three hundred only).	Per cubic metre.	446985.00
5	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8 Granular material including entire carriage of materials in all leads and lifts as per direction of the Engineer-in-Charge.	6.86 m3	950.00	(Rupees nine hundred fifty only).	Per cubic metre.	6517.00
<b>Total:-</b>						<b>498630.00</b>

Draft schedule of quantity approved for  
Rs. 4,98,630/- only

Executive Engineer,  
Kumarsain Division,  
H.P.W.D., Kumarsain.

**DRAFT SCHEDULE OF QUANTITY**

Estimated cost:-Rs.483929/-

Earnest money:-Rs.9700/-

Time allowed:-One month.

Name of work:- Restoration of rain damages on link road ~~Kulda~~ ~~Deldhar~~ Km.0/000 to 1/135 (SH:-Construction of R.R. Masonry Retaining wall at RD. 0/011 to 0/018.50).

S. No.	Sub-Head/Items of work.	Quantity.	Rate.		Unit.	Amount.
			In fig.	In words.		
1	Excavation in soil in hill area by manual means/mechanical means including cutting and trimming of side slope and disposing of excavated earth with in all leads and lifts as per drawing and technical specification clause 1603.10 as per direction of the Engineer-in-charge.	20.25 m <sup>3</sup>	180.00	(Rupees one hundred eighty only).	Per cubic metre.	3645.00
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom backfilling in trenches with excavated suitable materials upto all leads and lifts as per directions of the Engineer-in-Charge.	45.45 m <sup>3</sup>	250.00	(Rupees two hundred fifty only).	Per cubic metre.	11363.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 P.C.C nominal mix 1:6:12(40mm aggregate) including entire carriage of materials in all leads and lifts.	6.98 m <sup>3</sup>	4300.00	(Rupees four thousand three hundred only).	Per cubic metre.	30014.00
4	Stone masonry in cement mortar for substructure complete as per drawing & technical specification Clauses 702,704,1202 and 1203 Random rubble masonry in cement mortar 1:6 including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	100.58 m <sup>3</sup>	4300.00	(Rupees four thousand three hundred only).	Per cubic metre.	432494.00
5	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8 Granular material including entire carriage of materials in all leads and lifts as per direction of the Engineer-in-Charge.	6.75 m <sup>3</sup>	950.00	(Rupees nine hundred fifty only).	Per cubic metre.	6413.00
<b>Total:-</b>						<b>483929.00</b>

Draft schedule of quantity approved for  
Rs. ~~4,83,929/-~~ only

Executive Engineer,  
Kumarsain Division,  
HP.PWD., Kumarsain.

15

**DRAFT SCHEDULE OF QUANTITY**

Estimated cost:-Rs.289089/-


Earnest money:-Rs.5800/-

Time allowed:-One Month.

**Name of work:-Restoration of rain damages on link road Kachoti Khud to Odi Nalla Km.0/000 to 2/453 (SH:- Removal of slips between at RD. 1/630 to 2/350).**

S. No	Sub-Head/Items of work.	Quantity.	Rate.(Including GST)		Unit.	Amount.
			In fig.	in words.		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 1611 including entire carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	2312.71 m <sup>3</sup>	125.00	(Rupees one hundred twenty five only).	Per cubic metre.	289089.00
<b>Total:-</b>						<b>289089.00</b>

Draft schedule of quantity approved for  
~~Rs. 289089/- only~~

  
Executive Engineer,  
Kumarsain Division,  
HP PWD., Kumarsain.



## DRAFT SCHEDULE OF QUANTITY

**Estimated cost:-Rs.497766/-**

**Earnest money:-10000/-**

**Time allowed:-One month.**

**Name of work:-Restoration of rain damages on link road to village Challan Km.0/000 to 1/180 (SH:-Construction of P.C.C. Breast wall at RD.1/120 to 1/145.90).**

S. No.	Sub-Head/Items of work.	Quantity.	Rate.(Including GST)		Unit.	Amount.
			In fig.	In words.		
1	Excavation in soil in hill area by manual means/mechanical means including cutting and trimming of side slope and disposing of excavated earth with in all leads and lifts as per drawing and technical specification clause 1603.10 as per direction of the Engineer-in-charge.	12.43 m3	180.00	(Rupees one hundred eighty only).	Per cubic metre.	2237.00
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom backfilling in trenches with excavated suitable materials upto all leads and lifts as per directions of the Engineer-in-Charge.	5.70 m3	250.00	(Rupees two hundred fifty only).	Per cubic metre.	1425.00
3	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clauses 802,803,1202 and 1203 P.C.C. Grade M-10 Nominal mix 1:4:8 (1 Cement : 4 Sand : 8 Aggregate) 40mm size crushed stone aggregate complete including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	92.72 m3	5200.00	(Rupees five thousand two hundred only).	Per cubic metre.	482144.00
4	Providing weapholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	52 Nos.	230.00	(Rupees two hundred thirty only).	Each.	11960.00
<b>Total:-</b>						<b>497766.00</b>

Draft schedule of quantity approved for  
Rs. 4,97,766/- only

Executive Engineer,  
Kumarsain Division,  
HP.PWD., Kumarsain.

10

**DRAFT SCHEDULE OF QUANTITY**

Estimated cost:-Rs.438350/-

Earnest money:-Rs.8800/-

Time allowed:-One month.

**Name of work:-Restoration of rain damages on link road to Lower Jarol Km.0/000 to 2/400(SH:-Construction of P.C.C V-shape side drain in Km. 0/000 to 1/000).(PDNA)**

S. No	Sub-Head/Items of work.	Quantity.	Rate.(Including GST)		Unit.	Amount.
			In fig.	In words.		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom backfilling in trenches with excavated suitable materials upto all leads and lifts as per directions of the Engineer-in-Charge.	83.00 m3	250.00	(Rupees two hundred fifty only).	Per cubic metre.	20750.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803,1202 & 1203 P.C.C grade M 10 Nominal mix 1:3:6 including entire carriage of materials in all leads and lifts.	72.00 m3	5800.00	(Rupees five thousand eight hundred only).	Per cubic metre.	417600.00
<b>Total:-</b>						<b>438350.00</b>

Draft schedule of quantity approved for  
Rs. 4,38,350/- only.

Executive Engineer,  
Kumarsain Division,  
HP.PWD., Kumarsain.



**DRAFT SCHEDULE OF QUANTITY**

**Estimated cost:-Rs.195967/-**

**Earnest money:-4000/-**

**Time allowed:-One month.**

**Name of work:- Restoration of rain damages on link road to village Shalota Km.0/000 to 3/000 (SH:-Construction of P.C.C. Breast wall at RD. 1/735 to 1/750).**

S. No.	Sub-Head/Items of work.	Quantity.	Rate.(Including GST)		Unit.	Amount.
			In fig.	In words.		
1	Excavation in soil in hill area by manual means/mechanical means including cutting and trimming of side slope and disposing of excavated earth with in all leads and lifts as per drawing and technical specification clause 1603.10 as per direction of the Engineer-in-charge.	19.05 m3	180.00	(Rupees one hundred eighty only).	Per cubic metre.	3429.00
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom backfilling in trenches with excavated suitable materials upto all leads and lifts as per directions of the Engineer-in-Charge.	19.65 m3	250.00	(Rupees two hundred fifty only).	Per cubic metre.	4913.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203) P.C.C nominal mix 1:5:10 (40mm aggregates) including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	38.55 m3	4700.00	(Rupees four thousand seven hundred only).	Per cubic metre.	181185.00
4	Providing weapholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	28 Nos.	230.00	(Rupees two hundred thirty only).	Each.	6440.00
		<b>Total:-</b>				<b>195967.00</b>

Draft schedule of quantity approved for  
Rs. 1,95,967/- only

Executive Engineer,  
Kumarsain Division,  
HP.PWD., Kumarsain.



**DRAFT SCHEDULE OF QUANTITY**

Estimated cost:-Rs.477819/-

Earnest money:-Rs.9600/-

Time allowed:-One Month.

Name of work:-(1) Restoration of rain damages on Thanedhar Bhutti Banot Nalla road Km.0/000 to 9/375 (SH:- Removal of slips at RD. 2/900 to 2/990 & 3/930 to 4/000). (2) Restoration of rain damages on Link road Lauga Baddubagain Changadhar Dadesh Banot Nalla Km.0/000 to 6/970 (SH:- Removal of slips at RD. 0/120 to 0/200 & 2/030 to 2/090). (PDNA)

S. No	Sub-Head/Items of work.	Quantity.	Rate.(Including GST)		Unit.	Amount.
			In fig.	in words.		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 1611 including entire carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	3822.55 m3	125.00	(Rupees one hundred twenty five only).	Per cubic metre.	477819.00
	<b>Total:-</b>					<b>477819.00</b>

Draft schedule of quantity approved for  
Rs. 4,77,819/- only

Executive Engineer,  
Kumarsain Division,  
HP.PWD., Kumarsain.

9  
e

(13)

**DRAFT SCHEDULE OF QUANTITY**

Estimated cost:-Rs.495053/-


Earnest money:-Rs.9950/-

Time allowed:-One month.

Name of work:-Restoration of rain damages on Kumarsain Sharmbal Camp road Km.0/000 to 2/400 (SH:-C/O P.C.C V-shape drain at various RDs. 0/120 to 0/390, 0/600 to 0/900, 1/200 to 1/360 & 1/800 to 2/200). (PDNA)

S. No	Sub-Head/Items of work.	Quantity.	Rate.(Including GST)		Unit.	Amount.
			In fig.	In words.		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom backfilling in trenches with excavated suitable materials upto all leads and lifts as per directions of the Engineer-in-Charge.	92.66 m3	250.00	(Rupees two hundred fifty only).	Per cubic metre.	23165.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications clause 802,803,1202 & 1203 P.C.C. grade M 10 nominal mix 1:3:6 (20 mm aggregates) including entire carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	81.36 m3	5800.00	(Rupees five thousand eight hundred only).	Per cubic metre.	471888.00
<b>Total:-</b>						<b>495053.00</b>

Draft schedule of quantity approved to  
Rs. 4,95,053/- only

  
Executive Engineer,  
Kumarsain Division,  
HP.PWD., Kumarsain.