

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**

Sealed item rate / percentage rate tender are hereby invited on Form No. 6& 8 by the Executive Engineer, Bhoranj Division, HPPWD, Bhoranj on behalf of the Governor of Himachal Pradesh for the following works from the approved and eligible contractors/ firms of appropriate class enlisted in HPPWD (B&R) whose registration stood registered under the H.P. General Sales tax Act, 1968. As per latest instructions so as to reach and open in his office as per time schedule given below. The offer of the tender will be kept open for 20 days from the date of opening of the tenders. The undersigned reserves the right to reject any or all the tenders without assigning any reasons.

1. Date of receipt of Applications for tender form a/w requisite documents:- **21-07-2026 upto 10.00 AM to 11:00 AM.)**
2. Date of issue/Sale of tender forms against Cash payment (Non- refundable) **21-07-2026 (3:00 PM to 5.00 PM)**
3. Date of receipt of Tender:- **22-07-2026 at 10.30 AM.**
4. Date of opening of Tender:- **22-07-2026 at 11.30 AM.**

Sr. No.	Name of Road	Estimated Cost	Earnest Money	Time	Cost of Tender Form	Eligible class of Contractor
1	R/R damages of link road to RGDBS at Karah Km 0/00 to 0/400 (SH:- P/L WMM in km., 0/222 to 0/333 in approach road)	99900/-	2000/-	Two Months	Rs. 350/-	Class-D
2	C/O link Nagrota Palpal road km 0/00 to 1/600 (ii) link road to H.B Kakrot to Bhaur via Badehar (SH:- Providing & manufacture sign Board.)	98000/-	2000/-	Two Months	Rs. 350/-	Class-D
3	R/M of various roads in Bhareri Section under Bhoranj Sub Division (SH:- Removal of slips, maintenance of earthen shoulder & C/O unlined surface drain)	99224/-	2000/-	Two Months	Rs. 350/-	Class-D
4	R/R damages of link road to RGDBS at Karah Km 0/00 to 0/400 (SH:- P/L WMM in km., 0/333 to 0/400 in approach road)	90450/-	2000/-	Two Months	Rs. 350/-	Class-D
5	R/M of various roads in Bhareri Section under Bhoranj Sub Division (SH:- Removal of slips, maintenance of earthen shoulder & C/O unlined surface drain)	99171/-	2000/-	Two Months	Rs. 350/-	Class-D
6	R/R damages on Belag to Bhumplu Da Ghat at RD 0/00 to 1/500 (SH:- Providing & laying interlocking paver block at various RDs) PDNA	440103/-	9000/-	Two Months	Rs. 350/-	Class-D

The earnest money in the shape of National Saving Certificate/ Time Deposit/ saving account of any post office or FDR of Nationalized Bank duly pledged in the name of undersigned must be accompanied with each tender. The Conditional tender and tender not accompanying the earnest money in the proper mode of deposit with summarily be rejected.

The Tender documents to be sent should have invariably be waxed in sealed cover and in failure of that those will not be entertained.

The Copy of valid enlistment, GST Registration No. Income Tax PAN No. & EPF No. must be attached with application.

TERMS AND CONDITIONS:-

The tender form will be issued to those contractors who have relevant machinery and equipment, the list of which any be attached with their applications (The proof of ownership of machinery/ legal tie up arrangement).

The tender forms will not be issued to those contractors whose performance is not found satisfactory.

The tender form will not be issued to those contractors who have already two works in hand.

The earnest money for the above work should be submitted with the application for the purchase of the tender forms. The application received without earnest money shall summarily be rejected.

The conditional/ ambiguous/ telephonic tenders or tender by fax shall not entertain considered in any case.

(i) No Violation of social distancing.

(ii) Mandatorily wearing of face cover by everyone.

(iii) It is further added that any violation of the National directives & guidelines of containment of pandemic Covid-19 is liable for prosecution under section of IPC 1860.

Certified that the above work is of emergent nature in exigency of Public interest.

Executive Engineer
Bhoranj Division
HPPWD Bhoranj

For and on behalf of Governor of HP.
Dated:- 10-07-2026

No:-PW/BHD/TA/NIT/2025-

4748-88

Copy forwarded for information & necessary action to:-

1. The Engineer-in-Chief, Nirman Bhawan Nigam Vihar, HP PWD., Shimla.
2. The Chief Engineer (HZ) HPPWD., Hamirpur.
3. The Superintending Engineer, 8th Circle HPPWD, Hamirpur.
4. All the Superintending Engineers/ Executive Engineers in HP.PWD.
5. The Deputy Commissioner, Hamirpur.
6. The Tehsildar, Bhoranj.
7. The B. D. O. Bhoranj.
8. The Municipal Committee, Bhoranj.
9. All the Assistant Engineers working under this Division.
10. Accounts Branch/ Drawing Branch/ Notice Board.
11. LokMitra, Bhoranj.
12. Various Contractors/ Firms.

Executive Engineer,
Bhoranj Division,
HPPWD, Bhoranj.

SCHEDULE OF QUANTITY

NAME OF WORK:-R/R damages of link road RGDBS at Karah km 0/00 to 0/400 (SH:- P/L WMM in Km 0/222 to 0/333 in approach road).

Estimated Cost
Earnest Money
Time

Rs 99,900/-
Rs. 2,000/-
2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paverfinisher in sub- base / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achieve the desired density, complete as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	44.40	Per cubic Meter			
	Total					
	Terms and Condition:-					

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
H.P.W.D. Bhoranj



Schedule of Quantity

Estimated Cost :- 98000.00
Earnest Money:- 2000.00
Time: - 3 months

Name of Work:- C/O link Nagrota Palpal road Km. 0/00 to 1/600 (ii)C/O Link road to H.B. Kakrot to Bhour Via
Badehar (SH:-Providing & manufacturing sign Board)

Sr. No.	Description of items work	Qty	Unit	Rate In fig.	In words	Amount
1.	Providing and manufacturing steel fabrication of sign boards size following dia make of M.S sheet 1.60mm thickness with MS pipe 32mm dia. The height of board should not be less than 2430mm and size 4x3 including, welding, priming single coat complete in all respect and to the entire satisfaction of Engineer in Charge.	20	Each			

TERMS AND CONDITIONS:

1. The work will be carried out as per PWD specification and to the entire satisfaction of the Engineer in charge.
2. The rates shall be inclusive with all taxes and carriage of material in all leads and lifts.
3. Nothing will be paid for rejected work/material.
4. The material shall be used of ISI marked/reputed make.

SCHEDULE OF QUANTITY

NAME OF WORK:- R/M of Various roads in Bhareri section under Boranj Sub Division (SH:-Removal of Slips, Maintenance of earthen shoulders & C/O Unlined Surface drain).

Estimated Cost
Earnest Money
Time

Rs 99,224/-
Rs. 2000/-
2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregularity on shoulders to the design level by adding fresh approved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	813.65	Per square metre			
2	Construction of unlined surface drain of average cross sectional area 0.40 Sqm in soil to specified lines , grades, level and dimensions . Excavated material to be used in embankments with a lift up to 3 Mtr. and lead of 50 Mtr. (average lead 25 m) as per technical specification clause 307 as directed by the engineer in charge including entire carriage of material in all lead and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	420.00	Per Running Mtr.			
3	Removal of land slide in hilly area in ordinary rock not required blasting by mechanical means including cutting and trimming og slope and disposal of cut material with in lift upto 1.50 mtr. (one point five zero meter) and leads up to 1000 mtr (one thousand meter) as per technical specification 302.3.5 and 1611 and as per directon of Engineer-in-Charge including entire carriage of material in all lead and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	152.14	Per cubic metre			
Total						
Terms and Condition:-						

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
H.P.W.D Boranj



SCHEDULE OF QUANTITY

NAME OF WORK:- R/R damages of link road RGDBS at Karah km 0/00 to 0/400 (SH:- P/L WMM in Km 0/333 to 0/400 in approach road).

Estimated Cost
Earnest Money
Time

Rs 90,450/-
Rs. 2,000/-
2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paverfinisher in sub- base / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achieve the desired density, complete as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	40.20	Per cubic Meter			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.


 Executive Engineer
 Bhoranj Division
 H.P.W.D Bhoranj



SCHEDULE OF QUANTITY

NAME OF WORK:- R/M of Various roads in Bhareri section under Bhoranj Sub Division (SH:-Removal of Slips, Maintenance of earthen shoulders & C/O Unlined Surface drain).

			Estimated Cost Earnest Money Time	Rates in Words	Rs 99,171/- Rs. 2000/- 2 Months Amount
Sr No	Description of Items	Quantity	Unit	Rate	
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregularities on shoulders to the design level by adding fresh approved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	631.90	Per square metre		
2	Construction of unlined surface drain of average cross sectional area 0.40 Sqm in soil to specified lines , grades, level and dimensions . Excavated material to be used in embankments with a lift up to 3 Mtr. and lead of 50 Mtr. (average lead 25 m) as per technical specification clause 307 as directed by the engineer in charge including entire carriage of material in all lead and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	100.00	Per Running Mtr.		
3	Removal of land slide in hilly area in ordinary rock not required blasting by mechanical means including cutting and trimming of slope and disposal of cut material with in lift upto 1.50 mtr. (one point five zero meter) and leads up to 1000 mtr (one thousand meter) as per technical specification 302.3.5 and 1611 and as per direction of Engineer-in-Charge including entire carriage of material in all lead and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	348.25	Per cubic metre		
Total					
Terms and Condition:-					
1.Work shall be executed as per PWD specification.					

Executive Engineer
Bhoranj Division
P.W.D. Bhoranj



SCHEDULE OF QUANTITY

NAME OF WORK:-R/R Damages on Belag to Bhumplu Da Ghat at Rd 0/00 to 1/500 . (SH:- Providing & Laying interlocking paver Block at various RDs.) (PDNA)					Estimated Cost	Rs.4,40,103/-
					Earnest Money	Rs. 9000/-
					Time	2 month
Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structing and pumping and bailing out water (surface and sub sol water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	65.80	Per Cubic Meter			
2	Providing & Laying granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-ChargeWith material conforming to Grade-I (size range 75 mm to 0.075 mm) having CBR Value-30 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	20.56	Per cubic Meter			
3	Providing & laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paverfinisher in sub- base / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achieve the desired density, complete as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	20.56	Per Cubic Meter			
4	Providing concrete for plain/ reinforced concrete in P.C.C. grade M-10(M-ten)nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 20mm(twenty millimeters) nominal size in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lfts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	16.45	Per Cubic Meter			
5	Providing and laying heavy duty precast cement concrete interlocking paver blocks vibro compacted upto M-50(M-fifty) grade including border or kurb block grey or coloured over sub base of concrete with 25mm (twenty millimeters) thick average thickness of cement 1:4 (one cement: four sand) laid over and jointed with neat cement slurry mixed with pigment to match the shade of blocks including curing rubbing and polishing complete (sub base concrete) floor to be paid for 80mm(eighty millimeters) thick inter locking blocks (ISI approved), and as per direction of the Engineer-in-charge including entire carriage of materials within all leads and lifts including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government	164.50	Per Square Meter			
6	Providing and laying mechanically mixed cement concrete(M-20)(M-twenty) 1:2:4 one cement : two sand : four graded crushed stone aggregate) 20mm(twenty millimeters) for plain /reinforcement concrete in open foundation complete including cost of form work steel plate complete as per drawings and technical specification Clause 802, 803 1202 & 1204 including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	6.30	Per Cubic Meter			
Total						
Terms and Condition:-						

1.Work shall be executed as per PWD specification.


 Executive Engineer
 Bhoranj Division
 H.P.W.D Bhoranj

