


**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**


“CORRIGENDUM”

The Tenders invited vide this office NIT no 2337-51 dated 01.07.2026 to be opened on dated 10.07.2026 are hereby postponed due to Administrative/Technical reason. Now the application shall be received on 15.07.2026 upto 2.00 Noon and shall be sold on dated 15.07.2026 at 4:00 PM, The same shall be opened on dated 16.07.2026 at 11.00 AM.

All other items and condition shall remain unchanged.

No.PW/NBD/Tender/2025-26- **2423 - 37** Dated **06-07-2026**
Copy to the following for information and necessary action:-
1. The Chief Engineer (KZ), HPPWD, Dharamshala.
2. The Superintending Engineer, 5th Circle, HPPWD, Palampur.
3. The Executive Engineer IT Cell Shimla.
4. The Deputy Commissioner, Kangra at Dharamshala.
5. The Sub-Divisional Officer(C) Nagrota Bagwan.
6. All the S.E.s/E.E.s under North Zone.
7. All the Assistant Engineer under this Division.
8. The Drawing /Accounts Branch in this office.
9. Notice Board


Executive Engineer
HP PWD Division
Panda at N/Bagwan


Executive Engineer
HP PWD Division
Panda at N/Bagwan

HIMACHAL PRADESH
PUBLIC WORK DEPARTMENT

No. PW/DT/TA/ NIT /2025-26- 2336 Dated:- 01-07-2026


To,

The Executive Engineer
IT Cell Nirman Bhawan Nigam Vihar
HP PWD Shimla

Subject: _ Regarding NIT for uploading on HP PWD website .

Enclosed please find herewith the Notice inviting
tender Notice along with schedule of quantity for uploading on HP PWD website.
This is for your kind information and necessary action at your end please.

Encls:- 11 Nos copy of Schedule of quantity.


Executive Engineer
Tanda Division HP PWD
Lat Nagrota Bagwan


CERTIFICATE

Certified that the tenders of works, called vide

this office letter No. PW-DT-NIT-2026-27- 2237 -51

Dated:-01-07-2024

are urgent nature.


Executive Engineer
Tanda Division HP PWD
Bat Nagrota Bagwan

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Sealed item rate tender on form No. 6 & 8 are hereby invited by the **Executive Engineer, HP PWD Division Tanda at Nagrota Bagwan** on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HP PWD (B & R) whose registration stood renewed as per revised rules so as to fetch in his office on or before on **10.07.2026** up to **11:00 A.M.** And the same shall be opened on the same day at **04:00 P.M.** in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on **09.07.2026** up to **4:00 P.M.** and the application for issue of tender form shall be received on **08.07.2026** up to **12:00 noon.** The applications for issue of tender forms accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates/Saving Account of the Post Office /Time Deposit account/FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP PWD Division Tanda at Nagrota Bagwan.

The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 120 days.

Sr. No.	Name of work	Estimated Cost	Earnest Money	Time limit
1	Restoration of Damages on link road from Sera to chhanwar including bridge over Daroon Khad in G.P. Sera Thana in Distt. Kangra HP (SH: C/O Steel Railing etc).	98880.00	2000.00	One Months
2	Repair of Type-V Qtr. Block-B House No. 21 at Dr. R.P. Govt. Medical College Kangra at Tanda in Distt. Kangra HP deposit work (SH: Providing and laying tile work W.s. S.I work etc).	80220.00	1600.00	One Months
3	Restoration of rain damages on link road Paddar to Naihunda road km 0/00 to 4/800 (SH: Construction of retaining wall in km 2/590 to 2/595 and Protection work for Retaining wall in km 2/599 to 2/604).	99616.00	2000.00	Two Months
4	Repair of Indoor GYM at Dr. R.P. Govt. Medical College Tanda in Tehsil Nagrota Bagwan, Distt. Kangra H.P. Deposit work (SH: Providing form work, wall painting and providing and fixing Acrylic plate etc).	87684.00	1750.00	One Months
5	A.R. & M/O to 500 Bedded Hospital at Dr. R.P. Govt. Medical College Tanda in Tehsil Nagrota Bagwan, distt. Kangra HP (SH: Revised wages of labour w.e.f. 01-10-2025 to 31-03-2026.).	77576.00	1550.00	One Months
6	Repair of Internal Road at Dr. R.P. Govt. Medical College Tanda in Distt. Kangra HP Deposit Work (SH: P/L CC 1:3 to Right Side Block)	93000.00	1900.00	One Months
7	Repair of Internal Road at Dr. R.P. Govt. Medical College Tanda in Distt. Kangra HP Deposit Work (SH: P/L CC 1:3 to Left Block)	97743.00	1900.00	One Months
8	Construction of Packing and Shopping Complex at Nagrota Bagwan Under Contingency) (SH: Supplying of Primed Stationery Material).	93500.00	1870.00	One Months
9	Restoration of rain damages on various roads under HP PWD Division Tanda at Nagrota Bagwan in Distt. Kangra HP (SH: Bush Cutting and repair of berms under HP PWD Sub- Division Tanda).	98105.00	2000.00	One Months
10	Restoration of rain damages on various roads under HP PWD Division Tanda at Nagrota Bagwan in Distt. Kangra HP (SH: Hiring of JCB for removal of slips/ Clearing of drains under Sub- Division Baroh). Under SDF DC Deposit)	485000.00	10000.00	One Months
11	Restoration of rain damages on various roads under HP PWD Division Tanda at Nagrota Bagwan in Distt. Kangra HP (SH: Hiring of JCB for removal of slips/ Clearing of drains under Sub- Division Nagrota Bagwan). Under SDF DC Deposit)	490000.00	10000.00	One Months

Terms & Conditions:-

- The contractor/firm should be registered as or dealer GST No.
- The intending contractor / firm have to produce the copy of latest enlistment and renewal enlisted in HPPWD.
- If any of the date mentioned above happened to be Gazetted Holidays the same shall be processed on next working day.
- The Executive Engineer reserves the right to accept/reject any tender/application or all tenders without assigning any reason.
- The Contractor will have to submit affidavit along with application for issue of tender form.
- Next tender will be issued only after completion of previous works in hand.


HIMSUCHANA AVAM & JAN SAMPARK

(On behalf of Governor of Himachal Pradesh)

No.PW/NBD/TA/Tender/NIT/2026-27-2337-51 Dated/ 01-07-2026

Copy to the following for information and necessary action:-

- The Chief Engineer (KZ), HPPWD, Dharamshala.
- The Executive Engineer IT Cell Shimla HP PWD Shimla.
- The Superintending Engineer, 5th Circle, HPPWD, Palampur.
- The Deputy Commissioner, Kangra at Dharamshala.
- All the S.E.s/E.S. under North Zone.
- The Sub-Divisional Officer(C) Nagrota Bagwan.
- All the Assistant Engineer under this Division.
- The Drawing /Accounts Branch in this office.
- Notice Board.


Executive Engineer
H.P.P.W.D. Tanda Division
at Nagrota Bagwan


Executive Engineer
H.P.P.W.D. Tanda Division
at Nagrota Bagwan

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work:-Restoration of Damges on link road from Sera to Chhanwar including bridge over Daroon khad in G.P Sera					Estimate Cost:- 98,880.00/-	
Thana in Distt. Kangra (Himachal Pradesh).					Earnest Money:- 2,000.00/-	
Sub Head:-C/O Steel Railing etc.)					Time Limit :- One Month	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	920.24	Per Kilogram	107.45	#NAME?	98,880.00
Total :-						98,880.00
<i>Quoted rates percentage in figure</i>						
<i>Quoted rates percentage in words</i>						


Executive Engineer
HPPWD Division
Tanda at Nagrota Bagwan


Draft Schedule of Quantity

ESTIMATED COST: - ₹ 80220.00
EARNEST MONEY: - ₹ 1600.00
TIME LIMIT : ONE MONTH

Name of Work:- Repair of Type-V Qtr. Block-B House No. 21 at Dr. R.P. Govt. Medical College Kangra at Tanda in Distt. Kangra (H.P.) (Deposit Work)
Sub Head:- Providing and laying tile work, W.S. & S.I. work etc.

Sr. No	Description Of Item	Quantity		Rate		Unit	Amount
				In fig	In words		
1	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick bed of cement mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3 kg/ sq.m including pointing the joints with white cement and matching pigments etc., complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	9.00	Square metres	900.00	Rupees Nine hundred and paise Nil only	Per Square metre	8100.00
2	Providing and fixing 1st quality ceramic glazed floor tiles of size 300x450mm conforming to IS : 15622 (thickness to be specified by the manufacturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of steps and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with pigment of matching shade complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	32.76	Square metres	1050.00	Rupees One thousand fifty and paise Nil only	Per Square metre	34398.00
3	Providing and fixing white vitreous china pedestal type water closet (European type) with seat and lid, 10 litre low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I. brackets, 40 mm flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid plastic seat and lid complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	1	Numbers	5500.00	Rupees Five thousand five hundred and paise Nil only	Each	5500.00
4	Providing and fixing P.V.C. low level flushing cistern with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete. 10 litre capacity - White complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	1	Numbers	1100.00	Rupees One thousand one hundred and paise Nil only	Each	1100.00
5	Providing and fixing 15 mm nominal bore C.P. brass bib cock of approved quality conforming to IS:8931 : complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	5	Numbers	633.80	Rupees Six hundred thirty three and paise eighty only	Each	3169.00
6	Providing and fixing 110 mm diameter on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	40.00	Running metres	360.00	Rupees Three hundred sixty and paise Nil only	Per Running metre	14400.00
7	Providing and fixing Bend 87.5° 110 mm on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	6	Numbers	150.00	Rupees One hundred fifty and paise Nil only	Each	900.00
8	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	1000.00	Litres	8.50	Rupees Eight and paise fifty only	Per Litre	8500.00
9	Providing and fixing 15mm diameters brass angle valve without nuts as per approved drawing and design complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	5	Numbers	532.00	Rupees Five hundred thirty two and paise Nil only	Each	2660.00

Sr. No	Description Of Item	Quantity	Rate		Unit	Amount
			<i>In fig</i>	<i>In words</i>		
10	Providing and fixing 8 mm dia C.P. / S.S. Jet with flexible tube upto 1 metre long with S.S. triangular plate to European type W.C. of quality and make as approved complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	1 Numbers	492.80	Rupees Four hundred ninety two and paise eighty only	Each	493.00
11	Providing and fixing 100 mm inlet and 75 mm outlet trap of self cleansing design with screwed down or hinged grating with or without vent arm complete, including cost of cutting and making good the walls and floors : Hubless centrifugally cast (spun) iron epoxy coated inside & outside as per IS:15905 complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	2 Numbers	500.00	Rupees Five hundred and paise Nil only	Each	1000.00
Total:-						80220.00
<i>Quoted rates percentage in figure</i>						
<i>Quoted rates percentage in words</i>						



 Executive Engineer,
 HP PWD Division,
 Tanda at Nagrota Bagwan.

DRAFT SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 99616.00
 EARNEST MONEY: - ₹ 2000.00
 TIME LIMIT :- TWO MONTHS

NAME OF WORK:- Restoration of rain damages on link road Paddar to Niahunda road Km 0/000 to 4/800
 SUB HEAD: - Construction of Retaining wall in Km 2/590 to 2/595, Protection work for Retaining wall in Km 2/599 to 2/604 and 600mm dia Hume Pipe culvert at RD 2/594

Sr. No.	Description	Quantity	Rate		Unit	Amount
			In fig.	in words		
1	2	3	4	5	6	7
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within any lead including entire carriage of materials within all leads, lifts and other incidentals.	7.25 Cubic meters	320.00	Rupees Three hundred twenty and paise Nil only.	Per cubic metre	2320.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (One cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimetres nominal size) as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	19.46 Cubic metres	4000.00	Rupees Four thousand and paise Nil only.	Per cubic metre	77840.00
3	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 as directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals.	7.00 Running metres	320.00	Rupees Three hundred twenty and paise Nil only.	Per running metre	2240.00
4	Backfilling with granular material behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8, granular material as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	6.80 Cubic metres	750.00	Rupees Seven hundred fifty and paise Nil only.	Per cubic metre	5100.00
5	Filling available excavated earth (excluding rock) in trenches or embankment in layers (each layer should not exceed 15 cm), with intermediate layer of compacted earth (Soil density of 98%) after every four layers of compacted depth of fly ash, sides & top layer of filling shall be done with earth having total minimum compacted thickness 30 cm or as decided by Engineer-in-charge, including compacting each layer by rolling/ramming and watering, all complete as per drawing and direction of Engineer -in - charge.as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	9.75 Cubic metres	220.00	Rupees Two hundred twenty and paise Nil only.	Per cubic metre	2145.00
6	Providing and laying non-pressure NP3 class (Medium duty) R.C.C. hume pipes 600mm (Six hundred millimetre) dia with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (One cement : Two fine sand) including testing of joints etc; complete as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	2.50 Running metre	3988.50	Rupees Three thousand nine hundred eighty eight and paise fifty only.	Per running metre	9971.00
					TOTAL: -	99616.00
<i>Quoted rates percentage in figure</i>						
<i>Quoted rates percentage in words</i>						



 Executive Engineer,
 H.P.P.W.D. Division,
 Tanda at Nagrota Bagwan.

DRAFT SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 87684.00
 EARNEST MONEY :- ₹ 1750.00
 TIME LIMIT :- ONE MONTHS

NAME OF WORK :- Repair of Indoor Gym at Dr. R.P. Govt. Medical College Tanda in Tehsil Nagrota Bagwan, Distt. Kangra (H.P.)
SUB-HEAD :- Providing form work, wall painting and providing and fixing Acrylic plate etc.

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Wall painting two or more coats with acrylic emulsion paint of approved brand and manufacture to give an even shade complete and as per direction of Engineer- Incharge, including carriage of materials within all leads, lifts and other incidentals.	241.05 Square metres	82.00	Rupees Eighty two and paise Nil only	Per square metre	19766.00
2	Providing and Fixing Acrylic plate 75cm x 60cm (Seventy five centimetres into sixty centimetres) for inauguration including all fitting complete and as per direction of Engineer- Incharge, including carriage of materials within all leads, lifts and other incidentals.	1 Number	15000.00	Rupees fifteen thousand and paise Nil only	Each	15000.00
3	Centering and shuttering including strutting, propping etc. and removal of form for :Suspended floors, roofs, landings, balconies and access platform complete and as per direction of Engineer- Incharge, including carriage of materials within all leads, lifts and other incidentals.	113.00 Square metres	468.30	Rupees Four hundred sixty eight and paise thirty only	Per square metre	52918.00
					TOTAL :-	87684.00
<i>Quoted rates precentage in figure</i>						
<i>Quoted rates precentage in words</i>						



 Executive Engineer,
 H.P.P.W.D. Division,
 Tanda at Nagrota Bagwan.

DRAFT SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 77376.00
 EARNEST MONEY :- ₹ 1550.00
 TIME LIMIT :- ONE MONTH

NAME OF WORK :- A/R & M/O to 500 Bedded Hospital at Dr. R.P. Govt. Medical College Tanda in Tehsil Nagrota Bagwan, Distt. Kangra (H.P.)
SUB-HEAD :- Revised wages of labour w.e.f. 01.10.2025 to 31.03.2026..

S. No.	2	Quantity	Rate		Unit	Amount
			In fig	In words		
1	3	4	5	6	7	
1	Annual Repair and complete maintenance of all civil work the hospital including attending water supply storage tanks, checking and repair of bib tab, stop cock, pillar cock, mixtures, water pipes, cistern, wash basin, and flushing cistern etc; Checking and repair of internal sewerage, repair of doors, windows, ceiling, dismantling of floors, maintenance, checking and repair of all pipes with leakage etc; including all type of manpower involved but excluding material required complete and as per direction of Engineer-Incharge, including carriage of materials within all leads, lifts and other incidentals.	6 Months	12896.00	Rupees Twelve thousand eight hundred ninety six and paise Nil only	Per Month	77376.00
					TOTAL :-	77376.00
<i>Quoted rates percentage in figure</i>						
<i>Quoted rates percentage in words</i>						



 Executive Engineer,
 H.P.P.W.D., Division,
 Tanda at Nagrota Bagwan.

DRAFT SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 93000.00
EARNEST MONEY :- ₹ 1900.00
TIME LIMIT :- ONE MONTH

NAME OF WORK :- Repair of Internal Road at Dr. R.P. Govt. Medical College Tanda in Distt. Kangra (H.P.) (Deposit Work)
SUB-HEAD :- Providing and laying cement concrete 1:3:6 (Right side).

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering. All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm (Twenty millimetre) nominal size) complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	20.00 Cubic metres	4650.00	Rupees Four thousand six hundred fifty and paise Nil only	Per Cubic metre	93000.00
TOTAL :-						93000.00
<u>Quoted rates percentage in figure</u>						
<u>Quoted rates percentage in words</u>						



Executive Engineer,
H.P.P.W.D., Division,
Tanda at Nagrota Bagwan.

DRAFT SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 97743.00
 EARNEST MONEY :- ₹ 1900.00
 TIME LIMIT :- ONE MONTH

NAME OF WORK :- Repair of Internal Road at Dr. R.P. Govt. Medical College Tanda in Distt. Kangra (H.P.) (Deposit Work)
SUB-HEAD :- Providing and laying cement concrete 1:3:6 (Left side).

S. No.	Description of items	Quantity	Rate		Unit	Amount
			<i>In fig</i>	<i>In words</i>		
1	2	3	4	5	6	7
1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering. All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm (Twenty millimetre) nominal size) complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	21.02 Cubic metres	4650.00	Rupees Four thousand six hundred fifty and paise Nil only	Per Cubic metre	97743.00
					TOTAL :-	97743.00
<u>Quoted rates percentage in figure</u>						
<u>Quoted rates percentage in words</u>						


 Executive Engineer,
 H.P.P.W.D., Division,
 Tanda at Nagrota Bagwan.

Schedule of Quantity


ESTIMATED COST: - Rs. 93500-00
 EARNEST MONEY: - Rs. 1870-00
 TIME LIMIT: - One Month

NAME OF WORK: - Construction of Parking and Shopping Complex at Nagrota Bagwan. (**Under Contingency**)

SUB-HEAD: - Supplying of Printed stationery Material.

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1.	Providing and Supplying of Tender form No. 8 (1 Set of 146 pages) with cover and good quality paper complete in all respect including carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge.	550 Number	142.00	Rupees. One Hundred Forty Two only	Each	78100
2.	Providing and Supplying of Tender File Cover with Lamination and good quality complete in all respect including carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge.	550 Number	28.00	Rupees. Twenty Eight only	Each	15400.00
				Total =		93500.00
	Quoted rates percentage in figure (+ -)					
	Quoted rates percentage in word					

Bidder Name & Address



 Executive Engineer,
 HP PWD Division,
 Tanda at Nagrota Bagwan.

DRAFT SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 98105.00
EARNEST MONEY : - ₹ 2000.00
TIME LIMIT : ONE MONTH

NAME OF WORK : - Restoration of rain dmages on various roads under H.P.P.W.D. Division Tanda at Nagrota Bagwan in Distt. Kangra (H.P.).
SUB-HEAD : - Bush cutting and repair of berms under H.P.P.W.D. Sub-Division Tanda

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig.	In words		
1	2	3	4	5	6	7
1	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth upto 30 cm (Thirty centimetres) measured at a height of 1 metre above ground and removal of rubbish upto any distance of outside the periphery of the area cleared: as directed by the Engineer-in-Charge including entire carriage of materials within all leads, lifts and other incidentals.	8400.00 Square meters	9.20	Rupees Nine and paise twenty only.	Per square metre	77280.00
2	Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead (Maintenance of Earthen shoulder (filling with fresh selected soil) as per technical specification Clause 1903, as per directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals.	850.00 Square meters	24.50	Rupees Twenty four and paise fifty only	Per square metre	20825.00
TOTAL: -						98105.00
Quoted rates precentage in figure						
Quoted rates precentage in words						


Executive Engineer,
H.P.P.W.D., Division,
Tanda at Nagrota Bagwan.


Schedule of Quantity

ESTIMATED COST :- Rs 485000.00
EARNEST MONEY :- Rs 10000.00
TIME LIMIT :- ONE MONTH

NAME OF WORK : - Restoration of rain damages on various roads under HPPWD Division Tanda at Nagrota Bagwan in Distt. Kangra (H.P.)

SUB HEAD: - **Hiring of JCB for removal of slips/clearing of drains under Sub-Division Baroh.**

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig	In Words		
1	2	3	4	5	6	7
1	Hiring of hydraulic excavator with front end loader and 1.00 cum (One cubic metre) bucket capacity for formation cutting embankment/ removal of land slide slips in hilly area including cost of fuel, oil lubricants and wages of operating staff, any repair/breakage during operation will be carried out by the contractor/owner at his own risk. Shifting machinery from one place to other place will be absolute responsibility of the contractor only. Actual working hour will be accounted for the payment, earth cutting/removal of land slide slipes in all kind of soil including loading in tipper/truck and disposal of all excavated earth as per H.P.P.W.D. technical specifications, as directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals.	485.00 Hours	1000.00	Rupees One thousand and paise NIL only	Per Hour	485000.00
Total :-						485000.00
Quoted rates percentage in figure						
Quoted rates percentage in word						


Executive Engineer,
H.P.P.W.D., Division,
Tanda at Nagrota Bagwan.


Schedule of Quantity

ESTIMATED COST :- Rs 490000.00
EARNEST MONEY :- Rs 10000.00
TIME LIMIT :- ONE MONTH

NAME OF WORK :- Restoration of rain damages on various roads under HPPWD Division Tanda at Nagrota Bagwan in Distt. Kangra (H.P.)

SUB HEAD :- **Hiring of JCB for removal of slips/clearing of drains under Sub-Division Nagrota Bagwan.**

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig	In Words		
1	2	3	4	5	6	7
1	Hiring of hydraulic excavator with front end loader and 1.00 cum (One cubic metre) bucket capacity for formation cutting embankment/ removal of land slide slips in hilly area including cost of fuel, oil lubricants and wages of operating staff, any repair/breakage during operation will be carried out by the contractor/owner at his own risk. Shifting machinery from one place to other place will be absolute responsibility of the contractor only. Actual working hour will be accounted for the payment, earth cutting/removal of land slide slips in all kind of soil including loading in tipper/truck and disposal of all excavated earth as per H.P.P.W.D. technical specifications, as directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals.	490.00 Hours	1000.00	Rupees One thousand and paise NIL only	Per Hour	490000.00
Total :-						490000.00
Quoted rates percentage in figure						
Quoted rates percentage in word						


Executive Engineer,
H.P.P.W.D., Division,
Tanda at Nagrota Bagwan.